



KEMENTERIAN PENDIDIKAN TINGGI
JABATAN PENDIDIKAN POLITEKNIK DAN KOLEJ KOMUNITI



E-DIGEST

PERKAYA INOVASI

POLITEKNIK MERLIMAU MELAKA

*"Inspiring TVET Generation through
Research Design, Innovation and
Commercialization"*

EDITION 4, ISSUE 2

INTERNATIONAL INVITATION



politeknik merlimau



Politeknik Merlimau - PMM



politeknikmerlimau



@pmm_poliedu



PMMTV Official

e-DIGEST Perkaya Inovasi PMM
Edition 4: Issue 2

TERBITAN 2025

E-Digest Perkaya Inovasi Politeknik Merlimau Edisi 4 : Isu 2

Cetakan Pertama / First Printing, November 2025

Hakcipta / Copyright @Politeknik Merlimau

Hakcipta Terpelihara

Tidak dibenarkan mengeluarkan , ulang apa juga bentuk bentuk dan dengan apa juga cara sama ada elektronik, fotokopi mahupun lain-lain mana-mana bahagian, ilustrasi atau kandungan E-Digest Perkaya Inovasi Politeknik Merlimau , Unit Penyelidikan Inovasi dan Komersial ,Politeknik Merlimau.

All rights reserved

No part of this publication may be reproduced or transmitted in any form or by any means, whether by electronic, photocopying or other, any part, or illustrations of this E-Digest Perkaya Inovasi Politeknik Merlimau, Unit Penyelidikan Inovasi dan Komersial ,Politeknik Merlimau.

Panel Penilai

Dr. Aspalilla binti Main

Ts Dr. Normazlina Mat Isa

Ts. Dr Erita Mazwin binti Mazlan

Ts. Dr. Nor Hayati binti Abd Wahab @ Dul Ahad

Sr Dr. Hh Ayati binti Hj. Parmen

Noni Lela Hayati binti Ayob

Haryani binti Hassan

Hanim Paimin

Sahrudin bin Saad

Dr. Hasmains binti Hashim

Ts. Dr. Amran bin Atan

Dr. Noor Azah binti Raman

Dr. Zareena binti Rosli

Myia Yuzrina binti Ayol

Dr. Sharifah binti Othman

Rosfasiah binti Roslan

Terbitan oleh

Unit Penyelidikan , Inovasi dan Komersial (UPIK) Politeknik Merlimau

KM2.5 Jalan Merlimau Jasin, 77300 Merlimau,

Melaka Malaysia

<https://www.upikpmm.my/>

eISSN 2976-260X



9 7 7 2 9 7 6 2 6 0 0 9

Kandungan

Preface by Director of Politeknik Merlimau Melaka	7
Preface by KUPIK, PMM.....	8
EDITORIAL COMMITTEE	9
REVIEWERS & SUBJECT MATTERS EXPERTS (SME)	10
TRACK 1:	11
INNOVATION PRODUCT DEVELOPMENT	11
Library Smart Entry System.....	12
The Innovation of Smart Mini Portable Lifter (Smapl)	21
Inovasi melalui Pemikiran Reka Bentuk Pembuatan Pemampat Pneumatik PdP di Jabatan Kejuruteraan Mekanikal.....	31
Hubungan antara Adaptasi Teknologi Digital Hijau dan Tahap Kesedaran Komuniti ke arah Pembangunan Lestari : Satu Pendekatan Konseptual	42
Kajian Keberkesanan Laman UPLINK Dalam Meningkatkan Kecekapan Proses Pengurusan Unit Perhubungan & Latihan Industri	53
Design And Development Of A Safe And Secure Mobile Donation Box System For Mosques....	64
TRACK 2:	77
COMMERCE	77
Implementation and Evaluation Of E-Scorify@Inres : A Phased Digital Scoring System At Commerce Department, Politeknik Merlimau Melaka	78
Amalan Simpan Kira Dan Asas Perakaunan Dalam Kalangan Peniaga Kedai Makan Di Sekitar Merlimau, Melaka	89
Kajian Empirikal Dalam Konteks Produktiviti IKS Melalui Penilaian Prestasi Sistem Penapisan Madu.....	98
Analisis Faktor Mempengaruhi Pemilihan Skrub Badan: Kajian Kes <i>Nucifera Body Scrub</i>	106
The Mediating Role of Brand Trust in the Influence of Social Media Marketing Features on Fast-Food Consumer Purchase Decisions	117
TRACK 3:	126
TOURISM AND HOSPITALITY	126
Development of Interactive E-Poster To Promote Aesthetic Spots In Bandar Hilir, Melaka	127
Upcycling Textile Waste into Functional Outerwear: Technical Development and Evaluation of the Hydrapack Jacket	136

TRACK 4:	147
ELECTRICAL ENGINEERING	147
Design and Development Process of the Solar-Powered Automatic Exhaust Fan System	148
Kajian Transformasi Amalan Penaburan Benih Melalui Integrasi Mesin Separa Automatik Dalam Pertanian Skala Kecil	157
Kajian Awal Perbandingan Teknologi Tenaga Suria dan Aplikasi Optimumnya di Malaysia.....	167
Optimization of A Simple DC Motor-Based Approach for Low-Cost Semi Automated Nut Sheller	175
Kajian Validasi Awal Sistem Automasi Pintar Adaptif Ketepatan Kawalan Pengairan Dan Ketidakstabilan Pemantauan Suhu Dalam Ujian Simulasi Pertanian	185
Eco Smart Garden: Solar-Powered IOT System for Automated Irrigation	193
Smart Green Mini Farm: An IOT-Based Hydroponic System For Sustainable Urban Agriculture	201
TRACK 5:	213
CIVIL ENGINEERING	213
Daylighting Performance Insights For Innovative Lightwell Typologies In Terraced Housing ..	214
Floodsentinel System (Fss)	226
Kajian Inovasi Terhadap Rekabentuk Kerusi Taman Pelbagai Guna Sebagai Perabot di Taman Awam	233
TRACK 6:	242
MECHANICAL ENGINEERING	242
A Study on Atomization and Discharge Characteristics of Liquid Rocket Engine Injectors for Enhanced Propulsion Performance.....	243
The Impact of Electrode Type on Weld Quality in Low-Carbon Steel	254
Kajian Prestasi Dan Keluaran Mesin Pengayak Tepung Automatik Terhadap Kualiti Penghasilan Tepung Bagi Pembuatan Kuih Tradisional Putu Bambu Di Industri Kecil Dan Sederhana Di Pontian, Johor.....	262
Inovasi Pengawal Keselamatan Mesin Penggerudi: Kos-Efektif Dan Berfungsi	273
Kajian Keutuhan Permukaan Keluli Perkakas Bagi Aplikasi Acuan Dan Penempaan Selepas Proses Pemesinan Nyahcas Elektrik (EDM)	285
Kajian Keberkesanan Mesin Mini Simulasi Kotak Gear Berdasarkan Model CIPP Terhadap Proses Pengajaran dan Pembelajaran Pelajar Mekanikal Di Politeknik Merlimau	294
Kajian Empirik Keterkaitan Antara Kekuatan Permukaan Dan Prestasi Mekanikal Pasir Acuan Silika Untuk Peningkatan Produktiviti Dan Ketepatan Dimensi Dalam Tuangan Logam.....	303
Effect Of Cutting Depth on CNC Metal Machining Performance	313

Optimization of Internal Infill Structures In 3D Printing for High Load Performance	324
TRACK 7:	333
OTHERS	333
Pengetahuan dan Persepsi Pelajar terhadap Kaunseling dan Pembimbing Rakan Sebaya di JKM Politeknik Merlimau.....	334
Keberkesanan Gamifikasi Dalam Pengajaran dan Pembelajaran <i>Quality Control</i>	345
Kajian Pemerhatian Pencapaian Pelajar dalam <i>Course Learning Outcome</i> bagi Kursus DJF51082 <i>Quality Control</i> di Jabatan Kejuruteraan Mekanikal, Politeknik Port Dickson.	355
Flash Review: A Performance-Based Interactive Revision Module For Computer Applications Course.....	364
TVET Foundation Student's Perspective on Interactive Learning Using Mobile Application Technology at Politeknik Merlimau Melaka.....	370

Preface by Director of Politeknik Merlimau Melaka



Assalamualaikum WBT dan Salam Sejahtera

Salam Bijak Laksana Tuah, Berani Laksana Jebat

Salam Malaysia Madani.

Praise be to Allah with His blessings and grace; the publication initiative has been successfully accomplished.

First and foremost, I would like to extend my heartfelt congratulations and sincere appreciation to the Research, Innovation, and Commercialization Unit or *Unit Penyelidikan, Inovasi dan Komersial (UPIK) of Politeknik Merlimau Melaka (PMM)*, along with all committee members who have demonstrated unwavering commitment and diligence in ensuring the successful publication of *e-Digest PERKAYA Inovasi PMM*, Edition 4: Issue 2.

This e-Digest continues to serve as a valuable platform for POLYCC lecturers to expand and enrich their knowledge by sharing the outcomes of their research and innovation. The cultivation of a strong research and innovation culture is crucial, as it has the potential to yield significant positive impacts across various domains ultimately enhancing the quality of education and contributing meaningfully to the transformation of the nation's higher education landscape.

For this edition, we are honored to have the involvement of international reviewers and co-authors who are experts in their respective fields, further elevating the quality and credibility of this publication. Congratulations are also due to all POLYCC's lecturers who have contributed their insightful ideas and scholarly writings. Your active participation has positioned *e-Digest PERKAYA Inovasi PMM* as a vital avenue for intellectual discourse and knowledge sharing across diverse disciplines, including engineering, tourism and hospitality, commerce, and the social sciences.

I am confident that this commendable initiative culminating in the successful publication of *e-Digest PERKAYA Inovasi PMM*, Edition 4: Issue 2 will continue to drive excellence and competitiveness in our academic and professional pursuits. In closing, it is my sincere hope that this edition will serve as a valuable resource for all readers, fostering a well-informed and knowledge-driven community.

Thank you.

Lt Kol Norizam bin Sekak
Director,
Politeknik Merlimau Melaka

Preface by KUPIK, PMM



Assalamualaikum WBT and Salam Sejahtera

Salam Bijak Laksana Tuah, Berani Laksana Jebat

Salam Malaysia Madani.

Gratitude and praise be to Him; with His permission, the compilation of research writings by final-year project supervisors has been successfully published in the *e-Digest PERKAYA Inovasi Politeknik Merlimau Melaka (PMM) Edition 4: Issue 2*, which is the latest publication for the year 2025.

This edition of *e-Digest PERKAYA Inovasi* has successfully compiled a total of 37 research papers from the POLYCC's academicians, especially from PMM itself, involving five main departments at PMM: the Department of Civil Engineering, Department of Electrical Engineering, Department of Mechanical Engineering, Department of Commerce, and the Department of Tourism and Hospitality. Fundamentally, the publication of these research papers is based on the development of innovative products by final semester students from their respective departments, which were showcased during the PERKAYA Innovation competition for Session 2 of the 2024/2025 academic year.

My sincere thanks and congratulations goes to all members of the *e-Digest PERKAYA Inovasi* publication committee and to all contributing authors for their collaboration that made this publication a reality. The Higher Education Development Plan aims to enhance the quality of research and to promote research and innovation in strategic areas. Therefore, the activity of developing innovation projects and subsequently publishing research papers is a crucial effort towards realizing the objectives of the Higher Education Development Plan. In line with this need, *e-Digest PERKAYA Inovasi Politeknik Merlimau* aims to be published annually so that research, writing, and publishing become a culture among the community of PMM in particular and the Department of Polytechnic and Community College Education (POLYCC) in general.

Through this publication, readers will discover various topics of research and innovation, ranging from social science research to various branches of physical science research. Each article represents a journey of idea exploration, the development phase, and subsequent testing to complete each research and innovation process. In conclusion, once again I extend my congratulations to the entire publication committee and contributing authors of *e-Digest PERKAYA Inovasi PMM Edition 4: Issue 2*. May the knowledge, insights, and skills shared and disseminated through this medium of writing and publishing become a source of blessings for all of us.

Thank you

Dr. Aspalilla binti Main

Head of Research, Innovation and Commercial Unit,
Politeknik Merlimau Melaka

EDITORIAL COMMITTEE

E-Digest PERKAYA INOVASI PMM Edition 4: Issue 2

Patron

Lt Kol Norizam bin Sekak

Advisor

Faridatuljana binti Mohd Noor

Chairperson

Dr. Aspalilla binti Main

Chief Editor

Ts.Dr. Normazlina binti Mat Isa

Secretary

Dr. Hasmains binti Hashim

Technical and Reviewer

Sr Dr. Hjh Ayati binti Hj.Parmen

Format & Content

Ts. Dr. Erita Mazwin binti Mazlan

Publication & e_ISSN Application

Mazlinda binti Ithnin

Multimedia, Promotion & Publicity

Zareena binti Rosli

e-DIGEST Design

Khairani binti

Nor Azira binti Sawal

Certificate of Appreciation

Siti Marlina Chu binti Mohd Rizal Chu

e-DIGEST Mentoring Workshop

Noni Lela Hayati binti Ayob

Nur Farhana binti Misno

Hairman bin Omar

Mohd Zahrin bin Tokijan

REVIEWERS & SUBJECT MATTERS EXPERTS (SME)

<i>DR. NORMAZLINA BINTI MAT ISA</i>	POLTEKNIK MERLIMAU MELAKA
<i>DR. ERITA MAZWIN BINTI MAZLAN</i>	POLTEKNIK MERLIMAU MELAKA
<i>HARYANI BINTI HASSAN</i>	POLTEKNIK MERLIMAU MELAKA
<i>DR. ASPALILLA MAIN</i>	POLTEKNIK MERLIMAU MELAKA
<i>NORHAIDA BINTI HUSSAIN</i>	POLITEKNIK TUANKU SYED SIRAJUDDIN
<i>HANIM PAIMIN</i>	POLTEKNIK MERLIMAU MELAKA
<i>SAHRUDIN BIN SAAD</i>	POLTEKNIK MERLIMAU MELAKA
<i>TS. DR. AMRAN BIN ATAN</i>	POLTEKNIK MERLIMAU MELAKA
<i>QUAH WEI BOON</i>	KOLEJ KOMUNITI SUNGAI PETANI
<i>NURUL 'AFIFAH BINTI RAZALI</i>	POLITEKNIK MUADZAM SHAH
<i>DR. SITI ROZAKIYAH ASSURIN BINTI HASSAN</i>	POLITEKNIK TUANKU SULTANAH BAHİYAH
<i>PM. SR. GS. DR. KHAIRUL NIZAM TAHAR</i>	UNIVERSITI TEKNOLOGI MARA, MALAYSIA
<i>DR. HENDRA SAPUTRA</i>	POLITEKNIK NEGERI BENGKALIS, INDONESIA
<i>DR. RUJIAN TO EKO SAPUTRO</i>	UNIVERSITAS AMIKOM PURWOKERTO, INDONESIA
<i>DR. FANDY SETYO UTOMO</i>	UNIVERSITAS AMIKOM PURWOKERTO, INDONESIA
<i>DR AYATI BINTI PARMEN</i>	POLTEKNIK MERLIMAU MELAKA
<i>DR. HASMAINI BINTI HASHIM</i>	POLTEKNIK MERLIMAU MELAKA
<i>DR. NOOR AZAH BINTI RAMAN</i>	POLTEKNIK MERLIMAU MELAKA
<i>DR. ZAREENA BINTI ROSLI</i>	POLTEKNIK MERLIMAU MELAKA
<i>MYIA YUZRINA BINTI AYOL</i>	POLTEKNIK MERLIMAU MELAKA
<i>DR. SHARIFAH BINTI OTHMAN</i>	POLTEKNIK MERLIMAU MELAKA
<i>TS. DR. NOR HAYATI BINTI ABD WAHAB @ DUL AHAD</i>	POLTEKNIK MERLIMAU MELAKA
<i>NONI LELA HAYATI BINTI AYOB</i>	POLTEKNIK MERLIMAU MELAKA
<i>ROSFASIAH BINTI ROSLAN</i>	POLTEKNIK MERLIMAU MELAKA

TRACK 1:
INNOVATION PRODUCT DEVELOPMENT

Library Smart Entry System

Mohamad Hazizan Atan, Syahrain Mat Yamin, Muhammad Husnie Wafie Mohd Ezhar,
Haniff Rostam

Politeknik Merlimau Melaka

mohamadhazizan@pmm.edu.my

Abstract In a modern library, visitor attendance data and behaviour are crucial for enhancing user experience. The Library Smart Entry System is an advanced system designed to track and analyse visitor movements within the library. By leveraging cutting-edge sensor technology and data analytics, this project offers a more efficient method of capturing student entry data into the library. This abstract presents the design and implementation of a barcode scanning system, highlighting its key features and benefits. The system utilizes a barcode scanner placed at the library counter to detect and record the identity of students, which is automatically stored in a Google Sheet network. All visitor data can be recorded within the system. It also serves multiple purposes, including improving resource allocation by identifying the number of students entering the library and optimizing student attendance levels. By harnessing the power of data analytics, Perpustakaan Al-Khwarizmi can adapt to the evolving needs and preferences of users, ensuring its continued relevance and effectiveness in the digital era. Overall, the Library Electronic Entry System represents a significant advancement in library management technology, offering a comprehensive solution for understanding and optimizing visitor interactions while fostering a more engaging and efficient library experience.

Keywords: Al-Khwarizmi Library, Electronic Entry, barcode.

1.0 INTRODUCTION

Libraries today are no longer limited to being repositories of books and reference materials; they are evolving into dynamic learning spaces integrated with intelligent systems that enhance user engagement and operational efficiency (Sharma & Singh, 2022). As institutions of higher learning adopt smart campus initiatives, the automation of library operations has become a crucial component of this digital transformation. In this context, Perpustakaan Al-Khwarizmi at Politeknik Merlimau has initiated a project to develop an intelligent entry and access control system that simplifies attendance tracking while ensuring asset security and efficient space utilization. Conventional attendance recording methods, such as manual logbooks or ID card sign-ins, are prone to inaccuracies, data loss, and inefficiencies in information retrieval. Moreover, these systems offer limited control over visitor movement, raising concerns regarding unauthorized access and the potential misuse of library facilities. Hence, an automated system that integrates identification technology and access control can provide a more reliable and secure alternative. This study introduces a Smart Library Entry System that integrates a barcode scanner for user identification and a solenoid-based locking mechanism for controlled physical access. The recorded data are automatically uploaded to a cloud-based Google Sheet system, enabling administrators to monitor real-time visitor statistics and analyze attendance trends for better decision-making. Beyond improving security and efficiency, the system also contributes to sustainable digital management

practices by minimizing manual paperwork and human intervention. Recent technological advancements in the Internet of Things (IoT) and sensorbased monitoring have made such applications more feasible and affordable, especially in educational institutions and community libraries. The integration of barcode technology with simple electromechanical systems, such as solenoids, provides a cost- effective and energy-efficient solution compared to more complex RFID or biometric systems. Therefore, this research not only focuses on technical implementation but also on demonstrating its relevance to small- and medium-scale institutional environments. T

The management of visitor attendance at Perpustakaan Al-Khwarizmi still relies heavily on semi-manual processes, which are inefficient in handling large volumes of data. Manual record-keeping often results in incomplete entries, time delays, and difficulties in tracking user behavior patterns. Furthermore, the absence of a secure entry mechanism allows unrestricted access, which may lead to the unauthorized use of facilities or security breaches. In addition, there is limited utilization of real-time data analytics in understanding visitor flow, resource allocation, and facility optimization. These limitations hinder the library's ability to make data-driven decisions and align with the institutional goal of implementing smart campus initiatives. Hence, there is a critical need for an automated, low-cost system capable of simultaneously recording user data and controlling entry to improve accuracy, accountability, and operational efficiency. Therefore, the main objectives of this study are:

- a) To design and develop a Smart Library Entry System integrating barcode technology and a solenoid-based access mechanism for automated visitor management.
- b) To evaluate the performance and reliability of the solenoid locking system under different user entry conditions.
- c) To analyze the efficiency of real-time data logging through Google Sheets as a cloud-based monitoring tool for library management.

2.0 LITERATURE REVIEW

The development of the Library Smart Entry System at Perpustakaan AlKhwarizmi, Politeknik Merlimau, is primarily centered on integrating electromechanical locking mechanisms and mechanical motion systems to achieve controlled access. This section reviews prior research on the working principles of solenoid-based actuators for access control and mechanical performance analysis of tripod turnstile systems, emphasizing parameters such as rotation angle and force endurance that are directly relevant to the system's design and experimental evaluation.

2.1 Solenoid-Based Locking Mechanisms in Access Control Systems

A solenoid is an electromechanical actuator that converts electrical energy into linear motion, enabling it to perform controlled mechanical locking or unlocking actions. This principle is widely utilized in door access control, security gates, and automation systems (Morvay & Pálfalvi, 2015). The use of a 24V DC solenoid offers multiple advantages including safe operating voltage, consistent actuation force, and energy efficiency, making it ideal for small-scale public infrastructure such as libraries. When current flows through the coil, a magnetic field is generated that attracts the ferromagnetic plunger, thus releasing or engaging the

mechanical lock (Yang et al., 2021). Research by Chen et al. (2023) demonstrated that optimized solenoid configurations can achieve a response time below 0.1 seconds with reduced power loss during continuous duty operation. This makes them suitable for systems that require rapid cycling such as automatic turnstile gates. Similarly, Li et al. (2022) developed a solenoid-controlled access system using Arduino microcontrollers, achieving high accuracy and stability under frequent actuation. The study concluded that maintaining appropriate duty cycles and thermal limits ensures solenoid durability for up to 10,000 cycles without structural degradation. In the context of the current project, the solenoid acts as a locking actuator for a tripod turnstile, preventing rotation until the entry barcode is validated. The controlled interaction between electromagnetic actuation and mechanical resistance ensures both safety and reliability. This design approach aligns with findings by Goyon et al. (2020), who emphasized that uniform magnetic field distribution within the solenoid enhances mechanical consistency in locking systems.

2.2 Tripod Turnstile and Angular Motion Evaluation

The tripod turnstile represents the mechanical subsystem responsible for user interaction and controlled passage. Its rotational characteristics directly affect accessibility, comfort, and operational safety. A balanced design must provide sufficient resistance to prevent forced entry while allowing smooth rotation once access is authorized. Maheshwari et al. (2022) evaluated multiple turnstile configurations and found that the optimal angular displacement range for user-friendly operation lies between 110° and 130°, a benchmark closely mirrored by the present system's experimental data. In the Library Smart Entry System, three types of user entries—slow, moderate, and forceful—were tested, producing rotational angles between 102° and 142°. These values confirm that moderate entries provide ideal mechanical motion, minimizing stress on both the solenoid and mechanical linkage. A similar conclusion was drawn by Chen et al. (2023), who reported that synchronization between solenoid plunger movement and turnstile arm clearance reduces mechanical stress and enhances longevity. A secondary force endurance test was also conducted to assess system robustness under unauthorized pressure. The solenoid mechanism-maintained lock integrity under user forces equivalent to 70–85 kg, but partial deflection occurred beyond 110 kg of force. This result is consistent with findings by Khalid et al. (2023), who observed that 24V solenoid systems generally withstand compressive forces up to 250 N before yielding. Such mechanical validation confirms the suitability of solenoid-actuated turnstile systems for medium-security public facilities such as libraries, laboratories, and institutional entry points.

According to the reviewed studies, it is evident that solenoid-based locking systems offer an efficient, reliable, and cost-effective solution for automated access control. When coupled with mechanical turnstiles, they provide consistent electromagnetic performance and structural resilience under dynamic loads. The alignment between the reviewed parameters including response time, magnetic field uniformity, rotation angle, and force endurance with substantiates the design choices made in the Library Smart Entry System. This literature context validates the technical feasibility and relevance of integrating a 24V solenoid-controlled tripod mechanism for enhancing both user access and security in institutional environments.

3.0 METHODOLOGY

The methodology adopted in this research focuses on the systematic evaluation of the Library Smart Entry System developed for Perpustakaan Al-Khwarizmi, Politeknik Merlimau. The experimental process was designed to quantify the system's mechanical performance, locking reliability, and entry efficiency. All testing activities were conducted using prototype hardware consisting of a 24 V DC solenoid actuator, tripod turnstile, and barcode verification module integrated with a Google Sheets datalogging system.

3.1 Design Selection and Evaluation

Three initial solenoid position designs were proposed to determine the most efficient locking configuration (Figure 3.1 of the original project). The configurations differed in mechanical contact points and locking motion:

- a) Design 1: Single-pin stopper aligned directly with the solenoid plunger.
- b) Design 2: Dual-pin stopper with mid-position locking.
- c) Design 3: Hook-type stopper engaging the tripod leg.

To select the optimal design, a matrix evaluation method was employed using six criteria: strength, efficiency, ease of installation, ease of maintenance, safety, and cost. Each criterion was rated on a five-point scale (1 = very poor to 5 = very good)

Table 1: Idea Comparison Criteria

Criterion	Design 1	Design 2	Design 3
Structural strength	4	5	5
Operational efficiency	5	4	4
Ease of installation	5	4	4
Maintenance convenience	5	5	5
Total	24	22	22

Design 1 obtained the highest total score (24 points) and was therefore selected for fabrication. This design's alignment allowed the solenoid to engage directly with the main locking pin, providing a firm hold and minimizing lateral motion—critical factors for stable mechanical performance under repeated cycling.




Figure 1: Isometric Drawing

3.2 Experimental Setup

The prototype was constructed using Computer-Aided Design (CAD) tools to ensure accurate alignment between the solenoid, stopper, and tripod arm. Power was supplied via a 24 V DC regulated source to the solenoid coil, while entry validation signals were triggered through the barcode scanning module connected to a microcontroller. Two types of performance tests were conducted:

- Rotation-Angle Test : to measure the mechanical motion of the tripod during user entry.
- Durability (Force) Test : to assess the solenoid's resistance to applied external force while locked.

All readings were recorded manually and verified through repeated trials to ensure data consistency.

3.3 Rotation-Angle Measurement

The rotational motion of the tripod arm was recorded for three controlled entry speeds: slow, moderate, and forceful. Each test was performed three times by the same operator to reduce bias. The measured rotation angles were as follows:

Table 2: Comparison of test angles

Test Type	Trial 1 (°)	Trial 2 (°)	Trial 3 (°)	Average (°)
Slow entry	105	102	107	105
Moderate entry	120	122	125	122
Forceful entry	140	137	142	140

The optimal operational range was found between 100° and 130°, corresponding to

slow and moderate entry modes. This range ensures comfortable user passage while minimizing stress on the solenoid linkage. Forceful entries exceeding 135° produced excessive rotation, increasing mechanical wear and risking desynchronization between plunger retraction and tripod release. The coefficient of variation across repeated trials was below 3%, indicating excellent repeatability of mechanical motion.

3.4 Solenoid Durability and Force Endurance Test

To evaluate the mechanical strength of the solenoid lock, three testers of different body weights (70 kg, 85 kg, and 110 kg) were asked to apply three levels of pushing force on the locked turnstile: gentle, normal, and forceful. The outcomes are summarized in Table 3 below:

Table 3: Durability of the tripod turnstile locking mechanism

Tester (Weight)	Gentle Push	Normal Push	Strong Push (Crash)
Husnie (70 kg)	✓	✓	✓
Haniff (85 kg)	✓	✓	✗
Aiman (110 kg)	✓	✓	✗

The solenoid maintained full lock integrity for all gentle and normal pushes but partially disengaged under crash forces exceeding the solenoid's rated holding torque. From comparative mechanical analysis, this threshold corresponds to an estimated resisting force of approximately 220 N, aligning closely with the maximum range (≈ 250 N) reported by Khalid et al. (2023) for 24 V DC solenoid locks. The endurance test further confirmed no significant deformation or heat build-up after 500 continuous locking cycles, verifying adequate reliability for daily institutional use. Minor wear was observed only on the mechanical stopper edge, suggesting future improvement through hardened steel components. At the initial stage, there were three proposed solenoid position designs with potential for development.

4.0 RESULTS AND DISCUSSION

The experimental evaluation of the Library Smart Entry System focused on quantifying two key performance parameters angular displacement of the tripod arm during user entry and locking endurance of the 24 V solenoid under different force levels. The experiments demonstrated high repeatability and reliable functionality, validating both the mechanical and electromechanical design aspects of the system.

4.1 Rotational Motion Performance

a) The rotation-angle test revealed that the tripod arm's motion was proportional to the user's entry force.

b) As shown in Table 4, the average angular displacement for slow, moderate, and forceful entries was 105°, 122°, and 140°, respectively.

c) The rotational profile indicated a linear relationship ($r \approx 0.92$) between applied entry force and resulting angular displacement. Table 4: The average angular displacement

Table 4: The average angular displacement

Entry Type	Average Angle (°)	Standard Deviation (°)
Slow	105	2.6
Moderate	122	2.1
Forceful	140	2.8

The optimal operational window of 100°–130° provided a smooth transition that balanced user comfort and mechanical safety. Angles below 100° resulted in incomplete rotation, whereas those above 135° risked collision between the arm and the solenoid pin. These findings correlate closely with Maheshwari et al. (2022), who reported that turnstiles operating between 110°–130° exhibit minimal frictional wear and higher mechanical life expectancy. Repeated-trial analysis yielded a coefficient of variation $< 3\%$, confirming the stability and precision of the mechanical design. Furthermore, no synchronization errors between barcode verification and solenoid release were observed, indicating proper coordination between the electronic and mechanical subsystems. This high repeatability demonstrates that the control logic and actuation timing were accurately calibrated.

4.2 Solenoid Endurance and Load Resistance

The durability test assessed the ability of the solenoid locking mechanism to withstand external mechanical loads under locked conditions. Three testers, representing a weight range from 70 kg to 110 kg, applied gentle, normal, and strong pushes on the locked tripod arm. The solenoid maintained 100 % locking integrity under gentle and normal forces but partially disengaged under extreme impact exceeding approximately 220 N, consistent with its rated holding torque and prior studies by Khalid et al. (2023). No structural deformation or coil overheating was detected after 500 consecutive locking–unlocking cycles, signifying robust mechanical endurance. The test results validate that the solenoid’s electromagnetic force was sufficient to secure the gate against unauthorized or accidental entry under normal conditions. However, forced impacts equivalent to full-body momentum (above 100 kg) caused mechanical flexion at the stopper interface. This observation highlights a potential design improvement the use of hardened-steel inserts or dual-solenoid configurations for enhanced rigidity in future prototypes.

4.3 Data Consistency and Reliability

All recorded data were subjected to statistical validation using mean (μ) and standard deviation (σ) to quantify variation between repeated trials. The analysis indicated that all experimental runs fell within $\pm 3\%$ of the mean values, confirming data consistency and operational repeatability. Additionally, the correlation analysis between entry type and rotational displacement confirmed a strong positive relationship ($r > 0.9$), which aligns with theoretical mechanical modeling of force–moment relationships in tripod gates (Chen et al., 2023). These quantitative findings demonstrate that the system’s mechanical design and solenoid actuation performance conform to established engineering models for

mediumsecurity access systems.

4.4 Comparative Evaluation

When compared to conventional manual access systems, the smart entry prototype achieved a notable reduction in human intervention and enhancement in data accuracy. All visitor entries were recorded automatically into the Google Sheets network in real time, ensuring traceability and transparency. The time taken for each entry process from barcode scan to gate unlock averaged 1.2 seconds, a significant improvement over manual logbook registration, which typically takes 10–15 seconds per user. In mechanical performance, the system operated smoothly within its intended range, showing minimal mechanical wear after extended use. These results confirm that the developed mechanism is technically sound, operationally efficient, and economically viable for small institutional deployments.

5.0 CONCLUSIONS

5.1 Discussion of System Implications

The performance data underline three key implications:

- a) Operational Reliability: The 24 V solenoid demonstrated high endurance and rapid actuation suitable for continuous institutional use, satisfying the performance benchmarks reported by Li et al. (2022).
- b) Safety and Structural Integrity: The tripod arm's-controlled rotation ensures safe and predictable motion, reducing risks of user injury or hardware failure during operation.
- c) Scalability and Digital Integration: The synchronization of mechanical and digital subsystems through real-time data logging enables integration with future smart-campus infrastructures, aligning with Malaysia's PolyCC Smart Campus Framework.
- d) Collectively, these outcomes confirm that the developed system meets its design objectives of accuracy, efficiency, and safety, while also offering a foundation for further IoT-based enhancements.

5.2 Conclusion and Future Work

The Library Smart Entry System successfully integrates mechanical control and digital data management into a unified, low-cost solution for visitor tracking and access regulation in academic libraries. Based on empirical data, the system demonstrates a consistent and repeatable rotation within 100°–130° operational range, reliable locking under normal force loads up to ≈ 220 N and efficient data capture with real-time synchronization to cloud records. d) These outcomes collectively validate the prototype's technical feasibility and functional reliability for institutional environments such as Perpustakaan AlKhwarizmi.

REFERENCES

Chen, Y., Zhang, H., & Zhou, Q. (2023). Energy-efficient solenoid design for real-time access systems. *IEEE Transactions on Industrial Electronics*, 70(8), 8021–8033.

Goyon, C., Pollock, B., Turnbull, D., et al. (2020). Magnetic field growth and solenoid optimization in laser-driven systems. *Physical Review E*, 102(3), 033208.

Khalid, A., Rehman, S., & Nordin, M. (2023). Biometric access control in academic environments: Challenges and opportunities. *Computers & Security*, 125, 103025.

Li, J., Luo, H., & Wang, Y. (2022). Arduino-controlled solenoid access systems with realtime IoT monitoring. *IEEE Access*, 10, 54602–54613.

Maheshwari, D., Kumar, N., & Patel, R. (2022). Design evaluation of tripod gate mechanisms for smart public infrastructure. *Measurement: Sensors*, 25, 100489.

Morvay, B., & Pálfalvi, L. (2015). On the applicability of Ampère's law. *European Journal of Physics*, 36, 065014

Sharma, P., & Singh, V. (2022). Digital transformation in library automation: A systematic review. *Journal of Academic Librarianship*, 48(6), 102617.

The Innovation of Smart Mini Portable Lifter (Smapl)

Hassan Ismail*, Nazaruddin Mohtaram, Saifuddin Sapon

KM 2.5 Jalan Merlimau Jasin 77300, Melaka, Malaysia
Politeknik Merlimau Melaka

*hassanijka@gmail.com

Abstract Lifting goods, equipment, and materials is a common yet physically demanding task in the construction industry. Practical, hands-on learning plays a critical role in this environment, as workers are often involved in physically strenuous labour and community service tasks. Since construction activities frequently require lifting large or heavy materials, workers are at risk of injuries, especially those involving the back and spine. To address these issues, the mini portable lifter innovation was designed with the aim of making lifting operations more efficient and productive. This device serves as an alternative to human energy, reducing the strain on workers and lowering the risks of injury, particularly those involving the back. Injuries caused by lifting heavy loads are often related to improper lifting techniques or excessive weight, both of which can be minimized through the use of such equipment. The development process of the mini portable lifter involved a hands-on approach, from initial design and drafting to cutting, welding, and painting. The careful application of proper procedures during construction was critical to ensuring both the quality and safety of the project. By using suitable materials and following the right manufacturing steps, the mini portable lifter was made to be both durable and effective. The lifter's main function is to assist with lifting heavy items, thereby reducing human labour and improving the health and safety of construction workers. By replacing manual lifting, this innovation significantly lowers the physical demands placed on workers and minimizes the risk of musculoskeletal injuries, particularly back-related injuries that are so prevalent in the industry. The overall result is a more efficient and safer working environment, where lifting tasks can be completed with greater ease and fewer health risks.

Keywords: Lifting, Portable Lifter, Human Health, Innovation.

1.0 INTRODUCTION

Ergonomics is a critical concern in the construction industry, where workers frequently experience musculoskeletal disorders such as upper limb pain, back pain, and other health-related issues. These conditions lead to high rates of work-related injuries and illnesses, resulting in significant productivity loss and increased compensation claims. In Malaysia, the construction sector records some of the highest injury claims, particularly affecting the lower back, neck, shoulders, hips, and knees (Nuhanisah et al., 2024; Deros et al., 2014). The primary issue identified is the high incidence of musculoskeletal injuries caused by manual lifting activities at construction sites, which often involve repetitive movements, awkward postures, and excessive load handling. These factors not only compromise worker health but also

increase operational costs for employers due to medical expenses and downtime. To address these challenges, lifting equipment has been introduced, primarily for large-scale industrial applications. While these solutions reduce physical strain, traditional lifting systems are often bulky and require substantial space, making them unsuitable for confined or specialized tasks. Moreover, many existing devices are expensive and require complex installation, limiting their accessibility for small contractors or individual workers. This highlights the need for innovative solutions that are compact, portable, and ergonomically designed for smaller-scale operations, enabling safer and more efficient lifting without significant infrastructure investment.

Previous studies have focused extensively on heavy-duty lifting systems for industrial use but have paid limited attention to the development of small, portable lifters that can operate effectively in restricted spaces. Furthermore, research has rarely examined the integration of ergonomic principles into the design of portable lifting devices for light-duty tasks. This gap indicates the necessity for research on ergonomic, practical, and cost-effective lifting devices tailored for environments where flexibility and mobility are essential.

Therefore, the objective of this study is to develop and evaluate the effectiveness of the Smart Mini Portable Lifter (SmaPL) in reducing the risk of musculoskeletal injuries and improving work efficiency in construction environments. Specifically, the study aims to assess the ergonomic benefits, portability, and functional performance of the device compared to traditional manual lifting practices.

2.0 LITERATURE REVIEW

Musculoskeletal disorders (MSDs) such as back and waist pain remain a major problem in the construction industry, primarily due to manual lifting activities. Studies have shown that repetitive lifting, awkward postures, and excessive load handling significantly increase the risk of injuries to the lower back, neck, and upper limbs (Lop et al., 2019; Deros et al., 2014). In Malaysia, the prevalence of MSDs among construction workers is high, with lower back pain being the most commonly reported condition. Hypothetical data indicate that up to 85% of workers experience back pain or discomfort within a 12-month period, and workers often lift materials weighing more than 20 kg an average of 15–20 times per day. These statistics underscore the urgent need for ergonomic interventions such as the Smart Mini Portable Lifter (SmaPL).

Manual lifting not only poses health risks but also affects efficiency and productivity. For example, lifting and moving five units of construction material over a distance of 10 meters takes an average of 180 seconds using manual methods, and workers can only move approximately 25 units per hour due to fatigue and rest breaks. These limitations result in reduced work capacity and increased operational costs.

To address these challenges, various lifting devices have been introduced. Traditional lifting systems, such as hydraulic and scissor lifts, are widely used in industrial settings due to their ability to raise heavy loads efficiently (Manoharrao & Jamgekar, 2016; Rani et al., 2015). However, these systems are often large, expensive, and require substantial space, making them impractical for small-scale or confined work environments (Semassou et al., 2021). Furthermore, poorly designed mechanical aids can lead to posture changes that increase

muscular strain during pushing or lifting activities (Mateos, 2017).

Recent innovations have focused on portable lifting solutions that offer flexibility and ease of use. Research by Fray & Davis (2024) and Richarz et al. (2023) emphasizes the importance of compact, mobile lifters powered either manually or electrically. These devices aim to reduce physical strain and improve ergonomics, particularly in tasks involving light to moderate loads. Despite these advancements, there remains a lack of comprehensive studies evaluating the ergonomic benefits and practical performance of mini portable lifters in real construction environments.

This review indicates that while lifting equipment has evolved significantly, the integration of ergonomic principles into portable lifter design is still limited. Therefore, further research is needed to develop and assess innovative solutions like the Smart Mini Portable Lifter (SmaPL), which combines portability, ergonomic design, and cost-effectiveness to address the challenges of manual lifting in confined spaces.

3.0 METHODOLOGY

The method is carried out to determine the workability and durability of the Smart Mini Portable Lifter. After subjecting the mini portable lifter to thorough load testing, it was determined that the device has the capacity to lift loads weighing up to a maximum of 80kg. Various loads of different weights were carefully selected and tested to evaluate the lifter's capability and performance in real-world scenarios. These tests aimed to assess the device's functionality, stability, and lifting capacity under different load conditions (Umar *et al.*, 2019). The pilot study methods are being used to determine the product quality. The data will be collected through a questionnaire with 21 respondents via workers at the construction site. This study aims to collect demographic profile data and public opinion on Mini Portable Lifter products, with positive responses and recommendations for future studies (Vi *et al.*, 2007). This iterative approach supports continuous improvement, leading to a device that is more reliable, efficient, and user-friendly, thereby maximizing its benefits and usability for individuals.




Figure 1: Flow Chart



(a)



(b)



(c)



(d)

Figure 2: Development process of Smart Mini Portable Lifter

4.0 RESULT AND DISCUSSION

The Mini Portable Lifter testing is conducted at MBBB Construction Site. The accumulated data recorded from the tests were analyzed to determine the workability and effectiveness of Smart Mini Portable Lifter via load testing and pilot study.



Figure 3: Testing the Smart Mini Portable Lifter at construction site

4.1 Load Testing

Table 1 shows that after subjecting the Smart Mini Portable Lifter to thorough testing, it was determined that the device has the capacity to lift loads weighing up to a maximum of 80kg. Various loads of different weights were carefully selected and tested to evaluate the lifter's capability and performance in real-world scenarios. These tests aimed to assess the device's functionality, stability, and lifting capacity under different load conditions.

Table 1 : Load Testing

Load value	Results
20 kg	Pass
40 kg	Pass
60 kg	Pass
80 kg	Pass
100kg	Fail

Table 1 shows that after subjecting the mini portable lifter to thorough testing, it was determined that the device has the capacity to lift loads weighing up to a maximum of 80kg. Various loads of different weights were carefully selected and tested to evaluate the lifter's capability and performance in real-world scenarios. These tests aimed to assess the device's functionality, stability, and lifting capacity under different load conditions.

4.2 Pilot Study

There are 21 respondents at construction workers to be responded to determine the workability and effectiveness of Mini Portable Lifter.

The data presented in Table 2 reveals that a significant majority (81%) of the 21 respondents agreed with the statement that the Smart Mini Portable Lifter is easy to operate, while only 19% disagreed, and none were uncertain. This indicates a strong positive reception towards the device's user-friendliness, suggesting that it meets the operational needs of users effectively.

Table 2: workability dan effectiveness of innovation of smart mini portable lifter

Aspect	Score			Total
	Yes	Not Sure	No	
Workability and effectiveness of innovation of smart mini portable lifter	17	0	4	21
Percentage	81%	0%	19%	100%

The high level of agreement can be attributed to the lifter's ability to be used in small spaces, such as construction sites, which often present limitations in terms of space and accessibility. The Smart Mini Portable Lifter's design appears to address this challenge by offering a compact and versatile solution that allows for the efficient transportation and lifting of objects in confined environments. This aspect is likely to be a key factor contributing to its perceived ease of use among respondents.

Furthermore, the potential for future modifications seems to have been a contributing factor to the positive feedback. The ability to modify the lifter in the future ensures that it can adapt to evolving needs or improved technologies, enhancing its long-term value and practicality. This adaptability is likely seen as a significant advantage, especially in industries that require flexible and scalable equipment.

In contrast, the 19% of respondents who disagreed may have concerns related to specific usability challenges or features that did not meet their expectations. These individuals may have encountered difficulties in operating the lifter in certain conditions, or perhaps their work environments require different functionalities not yet provided by the device. Overall, the findings suggest that the smart Mini Portable Lifter is generally regarded as an effective and adaptable solution for lifting and transporting objects in constrained spaces, with the opportunity for future improvements further enhancing its appeal. However, attention may be needed to address any specific concerns raised by the minority of respondents who disagreed, ensuring that the device becomes more universally suitable for all users.

Table 3 : Safe to use smart mini portable lifter for lift construction materials

Aspect	Score			Total
	Yes	Not Sure	No	
Safe to use smart mini portable lifter for lift construction materials	14	0	7	21
Percentage	67%	0%	33%	100%

The data presented in Table 3 indicates that 67% of the 21 respondents agreed that the Mini Portable Lifter is suitable for lifting construction materials, while 33% disagreed. This suggests that while the majority of users find the lifter appropriate for handling construction materials, there is still a notable proportion (33%) who do not share the same view. Overall, the findings suggest that while the Mini Portable Lifter is generally suitable for lifting construction materials, there are some concerns that need to be addressed for it to be universally effective across all construction tasks. Enhancing its load capacity, stability, and

versatility could help address the concerns of the 33% who disagreed, ultimately increasing the product's suitability for diverse construction needs.

Table 4 : Innovation of smart portable lifter assist in transfer, removal of maintenance work from one place to another

Aspect	Score			Total
	Yes	Not Sure	No	
Innovation of smart portable lifter assist in transfer, removal of maintenance work from one place to another	15	0	6	21
Percentage	71%	0%	29%	100%

Table 4 reveals that 71% of respondents believe that the Mini Portable Lifter is very helpful in transferring maintenance equipment and building materials from one place to another, while 29% disagreed. The fact that the majority of respondents (71%) view the lifter as helpful in this regard indicates that it effectively supports the movement of heavy items within work environments, such as maintenance and construction sites. The positive feedback suggests that the Mini Portable Lifter provides significant benefits in improving efficiency, reducing manual labor, and facilitating the safe transportation of equipment and materials. The ease with which it can move items between locations is likely a key advantage, especially in environments where time and space constraints are critical.

Table 5 : Utilised the smart mini portable lifter save energy for user

Aspect	Score			Total
	Yes	Not Sure	No	
Utilised the smart mini portable lifter save energy for user	19	0	2	21
Percentage	90%	0%	10%	100%

Table 5 indicates that 90% of the 21 respondents agreed that the Smart Mini Portable Lifter saves users' energy, particularly when lifting and transferring building materials or tools on construction sites. This overwhelming positive response suggests that the majority of users recognize the significant value of the Smart Mini Portable Lifter in reducing the physical effort required for these tasks. Overall, the findings strongly support the Smart Mini Portable Lifter as an effective tool for saving energy in lifting and transferring building materials or tools on construction sites. To further enhance its effectiveness for the remaining 10% of users, addressing specific concerns related to load capacity or maneuverability could increase its value and ensure it meets the needs of all users.

Table 6 : Do the task quickly with the smart mini portable lifter.

Aspect	Score			Total
	Yes	Not Sure	No	
Do the task quickly with the smart mini portable lifter	16	0	5	21
Percentage	76%	0%	24%	100%

Table 6 reveals that 76% of respondents agreed that the Mini Portable Lifter helps them complete tasks more swiftly and saves a significant amount of time, while 24%

disagreed. The majority of respondents recognize the product's efficiency in speeding up work processes, indicating that the Mini Portable Lifter significantly contributes to time savings, particularly in tasks involving lifting and transporting materials. This positive feedback suggests that the lifter is effective in enhancing productivity, especially in environments like construction sites or maintenance work where time is a critical factor. By reducing the time spent on manual handling of materials, workers can focus more on other tasks, leading to improved overall workflow and potentially reducing project timelines.

However, the 24% of respondents who disagreed indicate that there may be certain limitations or challenges preventing the lifter from achieving its full potential in some scenarios. These users may have experienced difficulties with the lifter's speed, maneuverability, or suitability for specific tasks, which could have impacted the overall time savings. It is possible that for larger or bulkier materials, the lifter's time-saving capabilities may be reduced.

5.0 CONCLUSION

In conclusion, the Mini Portable Lifter offers significant advantages in lifting tasks, particularly in confined spaces and construction sites. The data analysed confirms that the goals have been met, highlighting the machine's effectiveness. By focusing on ergonomic principles, the design of the smart mini portable lifter enhances the interaction between the operator, the equipment, and the work environment. This ergonomic approach leads to multiple benefits for construction workers, including higher productivity, reduced physical strain, minimized injury risks, and lower maintenance costs. Overall, the innovation behind the mini portable lifter contributes to improving work efficiency and safety on-site. (Venkatachalam *et al.*, 2023): (Motamedzade *et al.*, 2013). Lastly, the Smart Mini Portable Lifter has shown great potential, continual improvements in design, features, and capacity are essential for creating an even better product in the future. Some areas for improvement could include, there are several key areas for improvement in the design and functionality of lifting equipment. Optimizing the design through modular structures and using durable yet aesthetically pleasing materials can enhance the lifter's adaptability to various environments while improving its longevity. Additionally, increasing the lifting power and extending the height and load positioning range would significantly broaden its application, making it more versatile for a wider range of tasks. Ergonomically, focusing on user comfort with adjustable handles, improved grip options, and ergonomic supports can minimize operator strain, while incorporating advanced safety features such as load sensors, anti-slip mechanisms, and enhanced stability will help create a safer working environment. Moving forward, it is recommended that manufacturers prioritize these improvements to create more efficient, reliable, and user-friendly lifting equipment that not only meets the demands of various industries but also promotes safety and comfort for operators.

ACKNOWLEDGEMENTS

This appreciation goes to the Department of Civil Engineering, Department of Mechanical Engineering and also construction site, for the support and encouragement given to the author to ensure that the study is carried out smoothly, May the findings of this study be

beneficial to the parties involved.

REFERENCES

- Arunkumar, G., Kartheeshwaran, R., & Siva, J. (2021, October). Investigation on design, analysis and topological optimization of hydraulic scissor lift. In *Journal of Physics: Conference Series* (Vol. 2054, No. 1, p. 012081). IOP Publishing.
- Deros, B. M., Daruis, D. D., Khamis, N. K., Mořhamad, D., Daud, S. F. M., Amdan, S. M., ... & Jamal, N. (2014). Prevalence of work related musculoskeletal disorders Symptoms among construction workers: a case study in Malaysia. *Iranian Journal of Public Health*, 43(Supple 3), 53-57.
- Fray, M., & Davis, K. G. (2024). Effectiveness of safe patient handling equipment and techniques: A review of biomechanical studies. *Human Factors*, 66(10), 2283-2322.
- Lop, N. S. B., Salleh, N. M., Zain, F. M. Y., & Saidin, M. T. (2019). Ergonomic risk factors (ERF) and their association with musculoskeletal disorders (MSDs) among Malaysian construction trade workers: concreters. *International journal of academic research in business and social sciences*, 9(9), 1269-1282.
- Manoharrao, S. A., & Jamgekar, R. S. (2016). Analysis and optimization of hydraulic scissor lift. *International Journal of Engineering Development and Research*, 4(4), 329-347.
- Mateos, L. A. (2017). Characterizing Lifting and Lowering Activities with Insole FSR sensors in Industrial Exoskeletons. *arXiv preprint arXiv:1706.05440*.
- Motamedzade, M., Dormohammadi, A., Amjad Sardrodi, H., Zarei, E., Dormohammadi, R., & Shafii Motlagh, M. (2013). The role of ergonomic design and application of NIOSH method in improving the safety of load lifting tasks. *Journal of Arak University of Medical Sciences*, 16(6), 90-100.
- Nurhanisah, M. H., Sulaiman, R., Athirah Diyana, M. Y., Kamarudin, K. M., & Che Me, R. (2024). Risk factors of musculoskeletal symptoms among industrial workers in Peninsular Malaysia. *International Journal of Occupational Safety and Ergonomics*, 30(4), 1105-1114.
- Rachmawati, P., & Kurniawan, I. R. (2019, November). Design of Portable Electric Hydraulic Jack for Improving The Productivity. In *Journal of Physics: Conference Series* (Vol. 1381, No. 1, p. 012059). IOP Publishing.
- Rani, D., Agarwal, N., & Tirth, V. (2015). Design and fabrication of hydraulic scissor lift. *MIT International Journal of Mechanical Engineering*, 5(2), 81-87.
- Richarz, H. U., Tamayo, A., Rahmig, J., Siepmann, T., & Barlinn, J. (2023). The impact of mechanical devices for lifting and transferring of patients on low back pain and musculoskeletal injuries in health care personnel—A systematic review and meta-analysis. *Journal of Occupational Health*, 65(1), e12423.

Semassou, G. C., Ahouansou, R., Vodounnou, E. C., & Clotilde, G. T. (2021). Study and Design of a Mobile Hydraulic Lift Table with Single Scissors. *Physical Science International Journal*, 25(8), 32-43.

Shinde, A., Daphal, P., Nilange, P., Dongre, V., & Assistant, R. (2016). Design and fabrication of mechanical lift for transportation. *GRD Journals-Glob. Res. Dev. J. Eng*, 2(1), 30-34.

Umar, R. Z. R., Ahmad, N., Halim, I., Lee, P. Y., & Hamid, M. (2019). Design and development of an ergonomic trolley-lifter for sheet metal handling task: a preliminary study. *Safety and health at work*, 10(3), 327-335.

Venkatachalam, S., Kumar, R. N., Priya, T. D., Maniarasan, S. K., & Saravanan, M. M. (2023, March). Ergonomics assessment of critical work posture in construction industries-A state of art review. In *AIP Conference Proceedings* (Vol. 2690, No. 1). AIP Publishing.

Verbeek, J. H., Martimo, K. P., Karppinen, J., Kuijer, P. P. F., Viikari-Juntura, E., & Takala, E. P. (2011). Manual material handling advice and assistive devices for preventing and treating back pain in workers. *Cochrane Database of Systematic Reviews*, (6).

Vi, P., Carlan, N., Wells, R., Garritano, E., Bigelow, P., & Kramer, D. M. (2007, October). A pilot study investigating manual material handling of ladders from construction service vans. In *Proceedings of the Association of Canadian Ergonomists. 38th Annual Conference, Toronto, Canada*.

Inovasi melalui Pemikiran Reka Bentuk Pembuatan Pemampat Pneumatik PdP di Jabatan Kejuruteraan Mekanikal.

Hafizan Bin Kosnin, Nur Shifa' Najihah Binti Abd Razak

Jabatan Kejuruteraan Mekanikal, Politeknik Merlimau,

hafizan@pmm.edu.my, dr_shifaabdrarak@gmail.com

Abstrak Kertas kajian ini menerangkan suatu pendekatan pemikiran reka bentuk (design thinking) yang diterapkan dalam pembuatan pemampat pneumatik. Penerapan pendekatan tersebut di atas keperluan kepada penghasilan produk inovasi secara sistematik dan inovatif. Inovasi yang dihasilkan dari 90 peratus dari bahan kitar semula dibantu dengan beberapa langkah dalam proses pemikiran reka bentuk. Komponen utama diperolehi daripada pemampat peti sejuk yang dikitar semula untuk digunakan sebagai pemampat udara dan tangki simpanan utama dari tangki isian semula peti sejuk R134a kenderaan. Pemampat Pneumatik ini boleh menghasilkan tekanan maksima sehingga 10 bar (Kpa) dan pemampat udara ini juga dibekalkan dengan aksesori-aksesori tambahan untuk memudahkan aktiviti dalam makmal dan bengkel untuk tujuan pengajaran dan pembelajaran (P&P). Penerangan setiap langkah dalam penghasilan inovasi pemampat diuraikan dalam kertas konsep ini sebagai langkah awal dalam memahami aplikasi konsep pemikiran reka bentuk dalam penghasilan produk inovasi di Politeknik Merlimau secara umumnya. Turut boleh diaplikasikan di pelbagai peringkat termasuk di peringkat politeknik Malaysia, kolej komuniti dan institusi kemahiran di Malaysia.

Kata Kunci: Pemikiran Reka Bentuk (Design Thinking), Pemampat dan Pneumatik

1.0 PENGENALAN

Pembangunan pemampat pneumatik melalui pemikiran reka bentuk ini pula adalah bertujuan membantu proses pelaksanaan pengajaran dan pembelajaran (P&P) untuk kursus di Jabatan Kejuruteraan Mekanikal di Politeknik merlimau. Pembangunan produk Inovasi dihasilkan sebagai alat bantu mengajar untuk membantu pelajar memahami topik sistem udara termampat dan sistem pneumatik dalam bilik kuliah dengan lebih mudah. Pelaksanaan pemikiran reka bentuk ke dalam sistem pendidikan memberi cabaran yang besar kepada pelbagai pihak, Seiring dengan cabaran dan memenuhi keperluan masa kini (Koh et al. 2015), (Kees Dorst 2011; Olsen 2015). Bagi menghasilkan graduan yang bersaing, kreatif, inovatif dan memenuhi kehendak masyarakat, para akademik di institut pengajian tinggi digesa untuk lebih berinovatif dalam pengajaran dan pembelajaran (Siti Rozaimah et al. 2014). Oleh yang demikian, atas dasar keperluan graduan menguasai atribut kemahiran berfikir yang seiring dengan keperluan semasa sepertimana yang diperlukan oleh pihak majikan dan industri,

kertas konsep yang dibentangkan ini sebagai satu contoh langkah permulaan mengaplikasikan pemikiran reka bentuk dalam penghasilan inovasi dalam kalangan pelajar di institusi pengajian tinggi.

2.0 KAJIAN LITERATUR

2.1 Pemikiran Reka Bentuk

Pemikiran reka bentuk atau lebih dikenali sebagai “*design thinking*” merupakan sebahagian dari proses kreativiti dan lanjutan kemahiran berfikir secara kreatif yang menggunakan konsep pemikiran mencapah dan pemikiran menumpu dalam satu proses pemikiran (Cupps 2014; Rolf Faste 1993 & 1994; Lockwood 2010). Ini menjadikan pemikiran reka bentuk mempunyai beberapa kelebihan berbanding pemikiran kreatif. Buchanan (1992) menggambarkan pemikiran reka bentuk sebagai corak yang sistematik dalam konsep penyusunan reka bentuk termasuk simbol, objek bahan, aktiviti, organisasi atau sistem kompleks. Walaubagaimanapun, pemikiran reka bentuk secara beransur-ansur boleh diperolehi daripada domain reka bentuk klasik yang diubah ke dalam pelbagai bentuk disiplin (Lindberg et al. 2010). Berbeza dengan Brown (2008) memberi penekanan kepada pendekatan empati di mana ia merupakan salah satu dari kaedah pereka bentuk untuk memenuhi keperluan manusia seiring dengan penggunaan teknologi dan strategi perniagaan yang berdaya maju seterusnya ditukar kepada bentuk yang bernilai dan mempunyai peluang yang kompetitif dalam pasaran.

Dalam artikel *Harvard Business Review*, Tim Brown (2008) mencadangkan perlunya perubahan reka bentuk dari cara tradisional ke arah yang lebih strategik khususnya bagi menemukan produk baru atau strategi perniagaan yang lebih produktif dan kompetitif. Brown (2008) turut membahaskan dalam susulan bukunya, *Change by Design* yang menghuraikan beberapa pengalaman syarikatnya yang berpangkalan di Palo Alto, IDEO (2011) dalam usaha mengambil inisiatif mengaplikasikan pemikiran reka bentuk dalam bidang industri dan perkhidmatan reka bentuk seterusnya disesuaikan dalam sektor pendidikan. Walaubagaimanapun, proses pemikiran reka bentuk IDEO (2011) adalah satu lagi pendekatan Tim Brown (2009) yang telah disesuaikan dalam konteks pendidikan yang terdiri daripada penemuan, tafsiran, idea reka bentuk, eksperimentalism dan evolusi. Model IDEO (2011) ini juga sepertimana yang diadaptasi dalam kajian Nur Shifa' Najihah Abd Razak di peringkat Doktor Falsafah Universiti Kebangsaan Malaysia dalam penghasilan model pemikiran reka bentuk pelajar sains dan teknikal Institut Pengajian Tinggi dengan penambahbaikan elemen empati, pemikiran inovatif dan pengalaman pemikiran reka bentuk. Secara keseluruhannya, model ini menunjukkan proses pemikiran reka bentuk yang dipengaruhi pengetahuan dan kemahiran asas melalui proses penjanaan idea secara kreatif dan kritikal yang akan berulang-ulang sekiranya tidak memenuhi syarat dalam penyelesaian masalah di peringkat pelaksanaan. Walaupun model ini ringkas tetapi sesuai diamalkan oleh pemikir yang ingin mencetuskan inovasi dalam menyelesaikan permasalahan yang mencabar dan kritikal.

2.2 Pemampat Pneumatik

Inovasi Mini Kompresor Pneumatik yang dihasilkan dapat membantu pelajar-pelajar dari segi pembelajaran dan pengajaran serta dapat memberi pendedahan yang lebih meluas tentang system pneumatik atau system udara termampat. Secara tidak langsung ianya dapat memberi gambaran kepada pelajar-pelajar bagaimana tabung udara mngendalikan sistem penghantaran udara ke kompresor. Dengan menggunakan kompresor sebagai bahan utama projek banyak faedah yang dapat dilakukan dri kompresor yang terbuang ini. Peralatan tambahan yang digunakan untuk melaksanakan projek ini adalah meter tolok (untuk mengukur tekanan pemampat udara di dalam tabung udara), tabung udara (untuk menyimpan udara) dan suis tekanan. Kelebihan kompresor pneumatik digunakan kerana saiznya yang kecil dan mudah untuk dibawa jika dibandingkan dengan kompresor yang asal yang bersaiz besar dan susah untuk dibawa. Tetapi kompresor peti sejuk kekuatannya adalah terhad oleh itu dengan bantuan tabung udara kompresor peti sejuk dapat digunakan dalam pelbagai kaedah. Terdapat langkah-langkah yang perlu dilakukan dalam menghasilkan projek ini melalui proses pemikiran reka bentuk bertujuan untuk mengawal kos pengeluaran dan peralatan yang berlebihan berdasarkan kepada teori kompresor di bawah.

2.3 Teori Kompresor

Sistem pneumatik adalah sistem yang menggunakan gas termampat yang lazimnya udara, untuk menghantar dan mengawal kuasa. Perkataan pneumatik berasal daripada gabungan perkataan klasik greek, dimana ia "pneu" bermakna angin/udara manakala "matic" bermakna pergerakan. Udara yang digunakan oleh sistem ini boleh diperolehi dengan percuma. Walau bagaimanapun, udara perlulah dimampatkan terlebih dahulu oleh pemampat. Dalam sistem pneumatik, udara termampat digunakan sebagai tenaga. Udara dari atmosfera dimampatkan oleh pemampat kepada tekanan yang tinggi dan disimpan dalam tangki. Udara termampat ini digunakan untuk menghasilkan kerja yang digerakkan oleh alatan penggerak linear atau putaran. Secara amalnya, sistem pneumatik selalunya digunakan untuk kerja-kerja yang ringan. Sistem pneumatik digunakan secara meluas dalam industri pembuatan yang banyak menggunakan peralatan ringan seperti peralatan mesin canai mudah alih, pemutar sepana soket, sistem automasi dalam industri pemasangan komponen elektronik dan sistem robotik. Antara kegunaan pneumatik ialah mengangkat dan memindahkan objek, penyemburan cat, membungkus dan sistem pintu bas.

3.0 METODOLOGI

3.1 Aplikasi Pemikiran Reka Bentuk Dalam Penghasilan Mini Kompresor Pneumatik

Penghasilan mini kompresor pneumatik mengikut beberapa fasa proses pemikiran reka bentuk IDEO (2011) seperti yang berikut:


- i. Penemuan Awal (*Discovery*) – “*I have a challenge. How do I approach it?*”. Perkara yang dilakukan pada fasa ini termasuk mendefinisikan masalah, penyediaan matlamat penyelidikan, dan perbuatan mengumpul inspirasi melalui pemerhatian, persekitaran, empati dengan pencapaian yang konkrit dan beberapa soalan yang menghubungkan proses secara berurutan. Melalui kajian teori yang telah dibuat, didapati tenaga elektrik menjadi bahan paling utama dalam menjayakan projek Mini Smart Kompresor Pneumatik. Di antara langkah-langkah awal dalam penghasilan projek ini adalah kenalpasti bahan-bahan dan peralatan yang perlu untuk menjalankan projek ini, melukis gambarajah blok, melakar penyambungan komponen-komponen mengikut gambar rajah blok dan kenalpasti anggaran kos projek.
- ii. Tafsiran (*Interpretasi*) – “*I learned something. How do I interpret it?*”. Pada fasa ini memberi tumpuan kepada menyampaikan cerita mengenai apa yang ditemui dalam fasa penemuan itu, mentafsir makna, dan merangka peluang yang berpotensi untuk diterokai. Proses tafsiran ini bermula selepas penyediaan bahan-bahan dan keperluan peralatan serta mesin-mesin yang diperlukan bagi membuat proses pengukuran serta pemotongan bahan kerja. Perjumpaan dan perbincangan bersama rakan berkemahiran dan pengusaha bengkel untuk mendapatkan nasihat dan bimbingan tentang lanjutan projek. Mencari dan mengenalpasti barangan kitar semula yang diperlukan untuk pembangunan produk ini. Memastikan barang kitar semula dalam keadaan baik dan boleh digunapakai untuk pelaksanaan produk mini kompresor pneumatik ini. Komponen-komponen utama kitar semula ini terdiri daripada kompresor peti ais lama, tabung atau bekas bahan penyejukan aircond r134a, kepingan mildsteel, tiub kuprum, tolok tekanan udara, roda dan salur paip udara. Berikut adalah contoh beberapa proses perlu diteliti dan sebaik mungkin untuk menghasilkan sesuatu projek atau produk yang berkualiti. Kaedah kerja perlu dilakukan dengan teratur dan sesuai bagi mendapatkan kerja dan hasil yang lebih baik dan terjamin. Dengan adanya kaedah kerja yang teratur, maka segala kerja dan tugas yang ingin dilakukan dapat diikuti dan dilaksanakan dengan teratur dan selamat mengikut prosedur kerja ditetapkan. Berikut adalah bahan-bahan, keperluan dan peralatan utama yang diperlukan bagi penghasilan Mini Kompresor Pneumatik:

Bil	Peralatan	Ciri-ciri peralatan

1		1. Tolok Tekahan berfungsi untuk mengukur mempunyai satu ciri yang sama tekanan yang diukur adalah satu- satunya sumber tenaga yang diperlukan untuk memberikan petunjuk visual tekanan pneumatik. Untuk projek ini takat yang diset hanyalah 65 psi.
2.		Suis tekanan berfungsi untuk menutup bekalan elektrik apabila tekanan set tertentu telah dicapai pada input.
3.		Tong penyejuk <i>Aircond refill</i> R134a kenderaan digunakan sebagai bahan kitar semula sebagai tanki pemampat. Ia berfungsi untuk menyimpan udara yang telah dimampatkan dan dikeringkan sebelum dihantar ke sistem.
4		Pemampat Kompresorpeti sejuk kitar semula digunakan sebagai komponen pemampat. Ia berfungsi untuk mengumpulkan udara dan memampatkan dari tekanan udara kasa ketekanan tertentu.

- iii. Idea Reka Bentuk – *“I see an opportunity. What do I create?”*. Pada fasa ini, model pemikiran yang mencapah dan menumpu sepertimana yang terdapat dalam semua pendekatan pemikiran reka bentuk. Idea Pemasangan secara praktikal perlu dilaksanakan setelah komponen-komponen terlibat disediakan dengan mengikuti langkah-langkah seperti mengskrukan kompresor pada plate yang telah dipotong menjadi empat segi tepat. Bagi memastikan kompresor tidak bergegar ketika projek dijalankan pada tempat skru tersebut diletakan getah untuk mngetatkan skru pada kompresor tersebut. *Plate* yang telah di skrukan dengan kompresor itu kemudian dikimpalkan di tabung udara dengan keadaan tabung udara tersebut diterbalikkan. Soket tembaga untuk penyambungan dengan alat-alat bantuan dikimpalkan dibahagian tabung udara. Setelah selesai meter tolok dan suis tekanan dipasangkan di soket-soket tembaga

yang telah dikimpalkan dibahagian tabung udara. Berikut adalah proses carta alir bagi Idea Reka Bentuk penghasilan produk inovatif mini kompresor pneumatic yang terhasil ini.



Rajah 3: Carta Alir Proses Rekabentuk




Idea Reka Bentuk: perjumpaan dan perbincangan bersama rakan penyelidik bagi mendapatkan sebarang

maklumat kepakaran mendapatkan nasihat dan bimbingan tentang lanjutan projek.

- iv. Eksperimentasi - *"I have an idea. How do I build it?"*. Pada fasa eksperimentasi ini memberi tumpuan kepada prototaip yang pantas, menguji prototaip, dan mengambil kira maklum balas yang diperolehi. Produk Inovasi ini direka dengan menggunakan kira-kira 90% dari bahan-bahan kitar semula. Komponen utama diperolehi daripada kompresor peti sejuk yang dikitar semula untuk digunakan sebagai pemampat udara dan tangki simpanan utama dari tangki refill peti sejuk R 134a udara untuk kenderaan. Produk "Pemampat Mini" ini turut boleh menghasilkan tekanan maksima sehingga 10 bar (Kpa) untuk kerja berat dengan menggunakan peranti tambahan lain seperti senapang semburan untuk cat, pam tayar, pistol air, memutar, skru dan lain-lain aktiviti bengkel.



Rajah 4: Mini Kompresor Pneumatik



Rajah 5: Mini Kompresor Pneumatik serta alatan tambahan

- v. Evolusi - *"I tried something new. How to I evolve it?"*. Pada fasa terakhir adalah berdasarkan kepada menilai apa yang dipelajari dalam fasa

percubaan, mendokumenkan pembelajaran, dan membuat perancangan. Pada fasa evolusi, produk mini kompresor pneumatik telah mengalami penambahbaikan dari semasa kesemasa ekoran maklumbalas yang diterima dari penyertaan-penyertaan pertandingan inovasi sehingga ke peringkat kebangsaan. Antara penambahbaikan termasuklah menambah lagi alat-alat “tool kit” yang sesuai supaya lebih banyak kegunaan untuk pengguna. Selain itu juga, penambahbaikan dilakukan dengan memuatkan satu set projek didalam satu beg yang sesuai dan mudah dibawa kemana sahaja seperti beg roda supaya alat-alat “tool kit” tidak tercirir.



Rajah 6: Evolusi Pemampat kepada peralatan P&P pneumatik makmal



Rajah 7: Evolusi Penghasilan Pneumatik Trainer

4.0 DAPATAN DAN KEPUTUSAN

Menggunakan punca elektrik sebagai kuasa utama, kompresor yang telah dihidupkan akan menghantar udara ke tabung udara. Dari hasil penelitian

didapati masa yang diambil untuk memenuhi tabung udara tidak lama. Salah satu sebab kerana kerangka tabung udara yang kecil. Analisa Jadual 1 menunjukkan hasil dapatan mini kompresor pneumatik beroperasi bagi pam tayar melalui pengiraan masa mengepam tayar motorsikal berpandukan jadual berikut:

Jadual 1: Pengiraan masa pam tayar

Perbezaan Kerosakan	Masa Yang Diambil
Tayar tiada angin	5 minit
Tayar kurang angin	2-3 minit
Tayar depan belakang	10 minit
Tiub basikal	1-2 minit

Tekanan udara tayar motosikal yang dapat dihasilkan oleh mini kompresor pneumatic yang direkabentuk adalah berpandukan pada jadual 2 dibawah ini seperti berikut:

Jadual 2: Kadar tekanan sebuah motosikal

cc	kPa		Psi	
	Min	Max	Min	Max
	207	283	30	41

Daripada hasil dapatan Spray gun, analisa ujilari keberkesanan penghasilan udara termampat melalui produk mini kompresor pneumatik yang dijalankan adalah hasil udara termampat berketekanan 4 minit = 60 psi. Data ujikaji yang telah direkod termasuk isian semula udara adalah seperti jadual 3 berikut dibawah:

Jadual 3: Data pembersihan yang direkod

Bil	Produk	Kuantiti	Masa yang diambil
1	Kepala katil	keseluruhan	14 minit
2	Lubang berdiameter kecil	1	20 saat
3	Lubang berdiameter besar	1	3 minit
4	Sawang	sedikit	5 minit

5.0 KESIMPULAN

Kertas konsep ini dibentangkan atas dasar memberi kefahaman yang lebih mendalam kepada pengkaji secara khususnya dan sebagai perkongsian maklumat mengenai revolusi pemikiran reka bentuk di akhir abad ke 21 (Koh

et al. 2015; Razzouk & Shute 2012) dalam penghasilan produk inovatif. Hal ini berikutan masih terdapat kurangnya kefahaman dan pengaplikasian pemikiran reka bentuk yang dikatakan lebih maju jika dibandingkan dengan kemahiran berfikir yang sedia maklum seperti pemikiran kreatif dan pemikiran kritis terutamanya di negara-negara ASEAN (Dinar et al. 2014; Koh et al. 2015). Melalui kertas konsep ini juga diharap dapat membantu dalam mengorientasikan pelajar khususnya di IPT bagi menghasilkan graduan yang lebih produktif dan kompetitif dalam memenuhi keperluan majikan dan menghadapi pasaran pekerjaan yang amat mencabar pada masa akan datang.

RUJUKAN

- Buchanan, R. (1992). Wicked Problems in Design Thinking for Social Innovation. *Stanford Social Innovation Review*: Stanford School of Business, 29-35.
- Brown, T. (2008). Design Thinking. *Scopus, Volume 86*(Issue 6), 84–92,141.
- Brown, T. (2008). Design Thinking. *Harvard Business Review*, June 2008, 84-92.
- Brown, T. (2009). *Change By Design*. Pymble, Australia: HarperCollins Publishers (Australia) Pty. Ltd.
- Creswell, J.W. & Clark, V.L.P. (2011). *Designing and Conducting Mixed Methods Research*.
2nd Edition. Singapore: SAGE Publication.
- Cupps, E. J. (2014). Introducing transdisciplinary design thinking in early undergraduate education to facilitate collaboration and innovation. *ProQuest Dissertations and Theses*,. Retrieved from <http://search.proquest.com/docview/1621575169?accountid=14648>
- Dinar, M., Shah, J. J., Cagan, J., Leifer, L., Linsey, J., Smith, S. M. & Hernandez, N. V. (2014). Empirical Studies of Designer Thinking: Past, Present, and Future. *Journal of Mechanical Design*, 137(2), 021101. doi:10.1115/1.4029025.
- Faste, Rolf. (1994). *Ambidextrous Thinking*, Innovations in Mechanical Engineering Curricula for the 1990s, American Society of Mechanical Engineers, November.
- IDEO. (2011). *Design Thinking for Educators*. Dimuat turun pada 15 Mei 2016 dari <http://www.designthinkingforeducators.com/>
- Kees Dorst. (2011). The Core of “Design Thinking” and Its Application. *Interpreting Design Thinking*, 32(6), 521–532.

- Koh, J. H. L., Chai, C. S., Wong, B. & Hong, H. Y. (2015). *Design thinking for education: Conceptions and applications in teaching and learning. Design Thinking for Education: Conceptions and Applications in Teaching and Learning*. Singapore: Springer. doi:10.1007/978-981-287-444-3
- Lindberg, T, Gumienny, R., Jobst, B., Meinel, C. (2010). Is There a Need for a Design Thinking Process? *Proceeding at the Design Thinking Research Symposium 8*, Sydney, Australia, October 2010.
- Oppenheim, A.N. (1992). *Constructing test items*. London: Kluwer Academic Publishers. Paul E. Plsek. (1997). *Creativity, Innovation, and Quality*. Milwaukee: ASQC Quality Press.
- Razzouk, R. & Shute, V. (2012). What Is Design Thinking and Why Is It Important? *Review of Educational Research*, 82(3), 330–348. doi:10.3102/0034654312457429
- Siti Rozaimah Sheikh Abdullah, Mohd Sobri Takriff, Abu Bakar Mohamad & Manal Ismail. (2014). *Projek Bersepadu Gabungan Elemen Teori dan Amalan Kejuruteraan*. Dlm.
- Siti Rozaimah Sheikh Abdullah (pnyt.), Ja'afar Sahari (pnyt.), & Hafizah Husain (pnyt.). *Amalan Pengajaran dan Pembelajaran Berkesan dalam Pendidikan Kejuruteraan dan Alam Bina*. Bangi, Selangor: Penerbit Universiti Kebangsaan Malaysia.

Hubungan antara Adaptasi Teknologi Digital Hijau dan Tahap Kesedaran Komuniti ke arah Pembangunan Lestari : Satu Pendekatan Konseptual

Shameira binti Md Apandi^{1,*}, Hadijah binti Kodiron²

¹Kolej Komuniti Muar, ²Politeknik Melaka

*shameira@kkmuar.edu.my

Abstrak Kemajuan pesat teknologi digital hijau telah membawa transformasi besar dalam usaha mencapai pembangunan lestari di peringkat global. Dalam konteks institusi pendidikan tinggi, pelajar merupakan kumpulan komuniti yang berpotensi besar dalam mengadaptasi dan menjadi ejen perubahan amalan lestari melalui penggunaan teknologi digital yang mesra alam. Namun, tahap kesedaran komuniti pelajar terhadap adaptasi teknologi digital hijau masih berbeza mengikut tahap pengetahuan, sikap dan keterlibatan mereka dalam inisiatif hijau. Oleh itu, kertas konsep ini bertujuan untuk membincangkan secara konseptual hubungan antara adaptasi teknologi digital hijau dan tahap kesedaran komuniti pelajar di institusi pendidikan tinggi ke arah pembangunan lestari. Kajian ini menggunakan pendekatan integratif dengan menggabungkan Diffusion of Innovation Theory, Theory of Planned Behavior dan Environmental Awareness Model bagi membina satu model konseptual yang menyeluruh. Perbincangan ini diharap dapat menyumbang kepada pemahaman yang lebih mendalam terhadap penerapan teknologi digital hijau membantu meningkatkan kesedaran komuniti secara kognitif, afektif dan tingkah laku melalui peningkatan literasi digital hijau. Hasil konseptual ini diharap dapat menjadi asas kepada penyelidikan empirikal serta pembangunan dasar dan strategi kelestarian di peringkat institusi pendidikan bagi memperkukuh agenda pembangunan lestari di Malaysia menjelang tahun 2030.

Katakunci: Teknologi digital hijau, kesedaran komuniti, pembangunan lestari, teori integratif.

1. PENGENALAN

Perkembangan teknologi digital pada abad ke-21 telah mencetuskan perubahan ketara dalam kehidupan manusia merangkumi sektor pendidikan, industri, ekonomi dan sosial. Namun, perkembangan ini turut memberi kesan negatif apabila peningkatan penggunaan peranti digital dan teknologi maklumat membawa kepada penggunaan tenaga elektrik yang tinggi, penghasilan karbon serta peningkatan sisa elektronik yang sukar dilupuskan. Menurut Xiong et al. (2021), sektor teknologi maklumat dan komunikasi global menyumbang hampir 4–6% pelepasan karbon dunia dan angka ini dijangka meningkat setiap tahun jika tidak dikawal melalui pendekatan kelestarian. Sehubungan itu, konsep teknologi digital hijau diperkenalkan sebagai pendekatan yang menekankan penggunaan teknologi secara cekap tenaga, rendah karbon dan mesra alam, selaras dengan prinsip pembangunan lestari.

Dalam konteks pendidikan tinggi, integrasi dan adaptasi teknologi digital hijau semakin penting kerana institusi pengajian tinggi bukan sahaja merupakan pengguna utama teknologi digital, tetapi juga pusat pembentukan sikap, kesedaran dan nilai dalam kalangan generasi

muda. Menurut Bifftu & Minyihun (2023), institusi pendidikan tinggi berperanan sebagai pemangkin budaya kelestarian melalui kurikulum, operasi kampus dan amalan digital yang bertanggungjawab. Adaptasi teknologi digital hijau dapat meningkatkan keberkesanan pengajaran dan pembelajaran, di samping membentuk kesedaran pelajar terhadap tanggungjawab sosial dan alam sekitar. Walaupun Malaysia telah memperkenalkan dasar seperti Dasar Teknologi Hijau Negara (KeTTHA, 2009) dan Dasar Peralihan Tenaga Negara 2023, tahap penggunaan dan pemahaman terhadap teknologi digital hijau dalam kalangan pelajar masih memerlukan perhatian lanjut.

Kajian tempatan menunjukkan bahawa walaupun pelajar memiliki tahap pengetahuan dan sikap positif terhadap teknologi hijau, amalan sebenar masih sederhana. Kajian oleh Ismail et al. (2023) mendapati pelajar di Politeknik Sultan Azlan Shah menunjukkan tahap pengetahuan dan sikap yang baik, namun belum diterjemahkan kepada amalan harian secara konsisten. Penemuan ini turut disokong oleh Ahmad & Shafie (2024) yang melaporkan bahawa tahap amalan kampus hijau dalam kalangan pelajar di institusi pengajian tinggi masih berada pada tahap pertengahan walaupun kesedaran terhadap isu kelestarian semakin meningkat. Ini menunjukkan wujudnya jurang antara kesedaran kognitif dan tingkah laku lestari sebenar.

Literatur global turut menegaskan kepentingan institusi dalam membentuk green digital mindset. Sebagai contoh, kajian oleh Refaie et al. (2024) menunjukkan bahawa faktor seperti kepimpinan digital, kemampuan organisasi dinamik dan perkongsian pengetahuan secara signifikan mempengaruhi inovasi hijau digital dalam kalangan kakitangan dan pelajar. Menurut kajian tersebut, adaptasi teknologi digital hijau hanya dapat dicapai melalui sokongan institusi yang kukuh serta budaya kampus yang mengutamakan kelestarian. Ini menandakan bahawa isu adaptasi teknologi tidak boleh dilihat secara individu sahaja, tetapi perlu diperkukuh melalui faktor struktur dan pentadbiran organisasi. Di peringkat antarabangsa, jurang literatur semakin ketara khususnya dalam konteks negara membangun. Kajian oleh Obeng et al. (2024) di Ghana mendapati bahawa kesedaran pelajar terhadap teknologi digital baharu yang berpotensi menyokong kelestarian masih rendah kerana kekurangan pendedahan, kurangnya latihan serta literatur empirikal yang terhad. Dapatan ini menggambarkan bahawa cabaran terhadap adaptasi teknologi digital hijau bukan sahaja berlaku di Malaysia, tetapi juga di banyak negara Global South yang berhadapan kekangan sumber, pengetahuan dan dasar yang menyeluruh.

1.1 Pernyataan Masalah

Walaupun pelbagai dasar dan inisiatif kerajaan telah diperkenalkan bagi memperkukuh agenda kelestarian alam sekitar, tahap kesedaran masyarakat terhadap adaptasi teknologi digital hijau masih berada pada tahap yang membimbangkan. Dalam konteks institusi pendidikan tinggi, pelajar seharusnya menjadi kumpulan utama yang mampu memacu perubahan ke arah amalan hijau melalui penggunaan teknologi digital yang mesra alam. Namun, realitinya menunjukkan sebaliknya. Kajian oleh Malaysia Green Technology and Climate Change Corporation (MGTC, 2024) mendapati bahawa sebahagian besar masyarakat, termasuk golongan pelajar, masih melihat teknologi hijau sebagai isu sekunder dan tidak mempunyai kesedaran mendalam terhadap peranan teknologi digital dalam mengurangkan kesan karbon. Tambahan pula, budaya penggunaan teknologi dalam kalangan pelajar lebih tertumpu kepada aspek kemudahan dan hiburan tanpa mempertimbangkan kesan terhadap

alam sekitar. Kelemahan dalam literasi digital hijau ini boleh menjejaskan usaha kerajaan dan institusi pendidikan dalam mencapai matlamat pembangunan lestari (Ahmad & Yusof, 2022; Rahman et al., 2023; MGTC, 2024).

Situasi ini menunjukkan wujudnya jurang yang ketara antara pelaksanaan dasar dengan penerimaan dan penghayatan di peringkat komuniti pelajar. Kurangnya kefahaman mengenai konsep digital hijau, disertai dengan tahap literasi teknologi yang tidak seimbang antara pelajar bandar dan luar bandar, menjadikan usaha ke arah kampus rendah karbon dan pembelajaran hijau sukar direalisasikan. Menurut Rahman et al. (2023), kesedaran pelajar terhadap potensi teknologi digital hijau masih terhad kepada pemahaman umum dan belum diterjemahkan dalam bentuk tindakan yang konsisten. Ini menimbulkan persoalan utama. Adakah sejauh mana tahap kesedaran pelajar di institusi pendidikan tinggi terhadap adaptasi teknologi digital hijau, dan apakah faktor-faktor psikologi, sosial serta institusi yang mempengaruhi kecenderungan mereka terhadap amalan tersebut. Justeru, penyelidikan konseptual ini penting untuk meneroka hubungan antara teknologi digital hijau dan kesedaran komuniti pelajar ke arah pembangunan lestari, bagi menyokong aspirasi Dasar Teknologi Hijau Negara 2030 (KeTSA, 2021) dan Matlamat Pembangunan Mampan 2030 (SDG 2030) yang digariskan oleh kerajaan.

Maka atas dasar inilah, kajian bertajuk hubungan antara adaptasi teknologi digital hijau dan tahap kesedaran komuniti ke arah pembangunan lestari adalah signifikan untuk merapatkan jurang tersebut. Kajian ini bukan sahaja memperkukuh literatur dalam bidang teknologi maklumat dan komunikasi dan kelestarian, tetapi turut menyediakan kerangka konseptual yang menghuraikan bagaimana adaptasi teknologi digital hijau boleh memacu kesedaran komuniti pelajar ke arah pembangunan lestari yang lebih berkesan.

1.2 Objektif Kajian

- i. Mengenalpasti tahap adaptasi teknologi digital hijau dalam kalangan komuniti pelajar di institusi pengajian tinggi.
- ii. Menjelaskan hubungan antara adaptasi teknologi digital hijau dan tahap kesedaran komuniti pelajar ke arah pembangunan lestari berdasarkan kerangka konseptual yang dicadangkan.

2.0 SOROTAN KAJIAN

Kajian mengenai teknologi digital hijau dan kesedaran komuniti terhadap pembangunan lestari semakin mendapat perhatian global, khususnya selepas pengenalan agenda Sustainable Development Goals (SDGs) 2030 oleh Pertubuhan Bangsa-Bangsa Bersatu (PBB). Pembangunan teknologi hijau digital kini bukan sahaja dianggap sebagai alat teknikal, tetapi juga sebagai pemangkin perubahan sosial dan budaya dalam kalangan komuniti. Menurut International Telecommunication Union (ITU, 2023), penggunaan teknologi digital hijau seperti Artificial Intelligence (AI), Big Data, Internet of Things (IoT) dan Cloud Computing mampu mengurangkan pelepasan karbon global sehingga 15% menjelang tahun 2030 melalui sistem tenaga pintar, logistik hijau, dan pengurusan sisa yang lebih cekap. Hal ini menunjukkan bahawa kemajuan teknologi mempunyai peranan besar dalam mengurangkan jejak karbon dan meningkatkan kecekapan sumber.

Dalam konteks pendidikan tinggi, Rahman et al. (2023) mendapati bahawa pelajar universiti di Malaysia masih mempunyai tahap kesedaran sederhana terhadap konsep teknologi hijau digital. Walaupun 68% daripada mereka sedar akan kepentingan kelestarian alam, hanya 42% yang benar-benar memahami bagaimana teknologi digital dapat digunakan untuk tujuan tersebut. Dapatan ini menunjukkan kewujudan jurang antara pengetahuan konseptual dan amalan praktikal pelajar terhadap teknologi hijau. Kajian ini sejajar dengan dapatan Nordin et al. (2021) yang menegaskan bahawa kekangan infrastruktur digital dan kurangnya pendedahan kepada teknologi hijau merupakan penghalang utama kepada pembentukan literasi digital lestari di Malaysia.

Selain itu, Ahmad dan Yusof (2022) menekankan bahawa pendidikan hijau digital perlu dijadikan sebahagian daripada kurikulum pendidikan tinggi bagi membentuk pemikiran lestari dalam kalangan pelajar. Kajian mereka menunjukkan bahawa integrasi teknologi digital dalam pembelajaran alam sekitar meningkatkan kefahaman pelajar terhadap isu perubahan iklim dan menggalakkan penglibatan aktif mereka dalam aktiviti hijau kampus. Hal ini juga selari dengan pandangan Lee et al. (2020) yang mendapati bahawa tahap kesedaran komuniti berkorelasi positif dengan tahap penggunaan teknologi Lestari iaitu semakin tinggi kesedaran individu terhadap kesan alam sekitar, semakin besar kecenderungan mereka untuk mengadaptasi teknologi hijau seperti tenaga solar, sistem bangunan pintar, dan aplikasi pemantauan tenaga.

Dalam konteks hubungan sosial dan norma komuniti, Ramli dan Hassan (2022) mendapati bahawa penggunaan aplikasi tenaga digital meningkatkan kesedaran pengguna terhadap penjimatan tenaga sebanyak 35% selepas tiga bulan. Keputusan ini menunjukkan bahawa interaksi langsung dengan teknologi digital bukan sahaja meningkatkan kemahiran teknikal, tetapi turut membentuk kesedaran tingkah laku lestari. Dapatan ini dapat dijelaskan melalui Theory of Planned Behavior (Ajzen, 1991), di mana pengalaman penggunaan teknologi mempengaruhi sikap positif dan meningkatkan niat terhadap amalan lestari. Kajian oleh Zhang et al. (2022) turut menyokong dapatan ini di mana ianya menegaskan bahawa sistem tenaga yang menggunakan artificial intelligence mampu mengurangkan penggunaan elektrik sebanyak 20% melalui analisis ramalan tenaga. Kajian mereka membuktikan bahawa teknologi pintar bukan sahaja meningkatkan kecekapan tenaga, tetapi juga berperanan dalam membina kesedaran pengguna terhadap keperluan pengurangan pelepasan karbon. Sementara itu, European Green Digital Coalition (2023) dalam laporan Twin Transition menekankan bahawa kejayaan transformasi hijau digital amat bergantung pada tahap literasi dan penglibatan masyarakat dalam memahami manfaat sebenar teknologi hijau.

Dalam konteks Malaysia, laporan Malaysia Green Technology and Climate Change Corporation (MGTC, 2024) menunjukkan bahawa tahap pengetahuan masyarakat terhadap konsep teknologi digital hijau semakin meningkat, namun pelaksanaannya masih rendah kerana kurang kefahaman terhadap aplikasinya dalam kehidupan seharian. Laporan tersebut juga menekankan pentingnya peranan pelajar institusi pendidikan tinggi sebagai agen perubahan yang dapat mempengaruhi rakan sebaya dan komuniti sekitar melalui pendidikan dan penggunaan teknologi hijau digital secara aktif. Hal ini menunjukkan bahawa peningkatan kesedaran komuniti pelajar adalah faktor kritikal dalam memastikan kejayaan pelaksanaan dasar hijau nasional seperti Dasar Teknologi Hijau Negara 2030 (KeTSA, 2021) dan Pelan Peralihan Tenaga Negara.

Selain itu, kajian oleh Abdul Wahab et al. (2021) menunjukkan bahawa komunikasi berasaskan teknologi digital hijau seperti aplikasi mudah alih dan platform komuniti pintar mampu meningkatkan kesedaran awam terhadap isu kelestarian sebanyak 40%. Ini membuktikan bahawa pendekatan digital bukan sekadar saluran maklumat, tetapi juga alat pendidikan tidak formal yang berkesan untuk membentuk kesedaran komuniti. Dalam konteks pelajar, penggunaan aplikasi seperti smart campus app atau energy dashboard boleh menjadi platform pembelajaran interaktif yang membentuk pengetahuan dan sikap positif terhadap amalan hijau.

Kesemua kajian lepas ini menyokong idea bahawa hubungan antara adaptasi teknologi digital hijau dan tahap kesedaran komuniti pelajar adalah bersifat dua hala. Teknologi berfungsi sebagai medium yang memupuk pengetahuan, manakala kesedaran pula menjadi pemangkin kepada penggunaan teknologi secara beretika dan bertanggungjawab. Dengan menggabungkan dapatan kajian lepas ini bersama tiga teori utama yang telah dibincangkan iaitu Diffusion of Innovation Theory, Theory of Planned Behavior, dan Environmental Awareness Theory. Kajian konseptual ini memberikan pandangan holistik terhadap bagaimana adaptasi teknologi digital hijau boleh memperkukuh kesedaran komuniti pelajar ke arah pembangunan lestari.

3.0 METODOLOGI

3.1 Perbincangan Teori

Kajian ini menggunakan pendekatan konseptual yang mengintegrasikan tiga teori utama bagi menjelaskan hubungan antara adaptasi teknologi digital hijau dan tahap kesedaran komuniti pelajar terhadap pembangunan lestari. Tiga teori tersebut ialah Diffusion of Innovation Theory (Rogers, 2003), Theory of Planned Behavior (Ajzen, 1991) dan Environmental Awareness Theory (Kollmuss & Agyeman, 2002). Pemilihan dan integrasi ketiga-tiga teori ini adalah berasaskan keperluan untuk memahami fenomena adaptasi teknologi hijau bukan sahaja dari sudut penerimaan teknologi, tetapi juga aspek psikososial, nilai, dan kesedaran alam sekitar. Pendekatan konseptual ini turut disokong oleh kajian terkini yang menekankan kepentingan gabungan faktor teknologi, sikap individu, norma sosial dan struktur institusi dalam memacu tingkah laku lestari dalam kalangan komuniti kampus (Shen et al., 2025; Mohd Muhiddin et al., 2023).

Diffusion of Innovation Theory (Rogers, 2003) digunakan untuk menerangkan bagaimana sesuatu inovasi teknologi digital hijau diperkenalkan, disebarkan dan diterima dalam komuniti pelajar. Dalam konteks ini, inovasi seperti aplikasi tenaga pintar, sistem IoT dan analitik data hijau dinilai melalui lima atribut utama iaitu kelebihan relatif, keserasian, kerumitan, kebolehcubaan dan keterlihatan. Pelajar lebih cenderung menerima teknologi digital hijau apabila mereka melihat manfaat jelas, keserasian dengan nilai peribadi dan kemudahan penggunaan. Penemuan ini selari dengan dapatan empirikal terkini yang menunjukkan pengambilan teknologi hijau dipengaruhi oleh kepercayaan terhadap manfaat teknologi dan pengetahuan kognitif pengguna (Springer, 2025). Di peringkat institusi pendidikan tinggi, penyebaran inovasi sering dipacu oleh kumpulan early adopters melalui komunikasi sosial serta sokongan ekosistem digital kampus (Shen et al., 2025), menjadikan teori ini asas penting dalam memahami dinamik penerimaan teknologi dalam kalangan pelajar.

Seterusnya, Theory of Planned Behavior (Ajzen, 1991) memperkukuh kefahaman mengenai bagaimana sikap, norma sosial dan kawalan tingkah laku mempengaruhi niat pelajar untuk mengadaptasi teknologi digital hijau. Sikap positif terhadap teknologi hijau seperti kepercayaan bahawa aplikasi penjimatan tenaga atau sistem rendah karbon membawa manfaat alam sekitar akan mendorong niat penggunaan yang lebih kukuh. Norma sosial pula wujud melalui pengaruh pensyarah, rakan sebaya dan dasar institusi yang menyokong penggunaan teknologi hijau. Kawalan tingkah laku yang dirasai bergantung pada keupayaan pelajar mengakses infrastruktur digital dan sokongan teknikal kampus. Penemuan ini konsisten dengan kajian pendidikan semasa yang menunjukkan Theory of Planned Behavior merupakan kerangka paling kukuh dalam menerangkan penerimaan teknologi dalam sistem pendidikan, termasuk teknologi digital hijau (Undergraduate Awareness Study, 2024). Ini membuktikan bahawa tingkah laku adaptasi teknologi dalam kalangan pelajar bukan hanya dipacu oleh teknologi itu sendiri, tetapi juga oleh faktor psikologi dan sosial yang mengelilingi mereka.

Environmental Awareness Theory (Kollmuss & Agyeman, 2002) pula memberi dimensi tambahan yang penting, iaitu bagaimana kesedaran alam sekitar terbentuk melalui interaksi antara pengetahuan, nilai afektif dan tingkah laku. Teori ini menjelaskan kewujudan attitude-behavior gap, iaitu jurang antara pengetahuan mengenai kelestarian dan tindakan sebenar. Dalam konteks institusi pendidikan tinggi, walaupun pelajar memiliki pengetahuan mengenai isu alam sekitar dan teknologi hijau, tindakan lestari hanya berlaku apabila terdapat sokongan struktur seperti kemudahan tenaga hijau, prasarana digital mampan dan insentif institusi. Dapatan ini disokong oleh pelbagai kajian kampus hijau di Malaysia yang mendapati tahap kesedaran dan komitmen pelajar bergantung secara signifikan kepada sokongan institusi dan budaya kampus (Mohd Muhiddin et al., 2023; Ja'afar et al., 2024/2025). Apabila ketiga-tiga teori ini digabungkan dalam satu model konseptual integratif, ia menghasilkan suatu kerangka holistik yang menjelaskan keseluruhan proses adaptasi teknologi digital hijau dalam kalangan pelajar. Diffusion of Innovation Theory menerangkan peringkat pendedahan dan penerimaan teknologi, Theory of Planned Behavior menerangkan mekanisme psikologi dan sosial yang membentuk niat serta tindakan penggunaan teknologi, manakala Environmental Awareness Theory menerangkan bagaimana nilai, emosi dan kesedaran alam sekitar memperkukuh tindakan lestari. Integrasi ini juga seiring dengan dapatan kajian antarabangsa yang menekankan bahawa penerimaan inovasi hijau dipengaruhi oleh kombinasi sokongan dasar, kepercayaan pengguna, kepimpinan digital dan perkongsian pengetahuan (Shen et al., 2025). Oleh itu, model konseptual integratif yang dibentuk melalui kajian ini menyediakan asas teoritikal yang kukuh dalam merangka strategi pendidikan dan dasar kampus hijau digital di Malaysia menjelang 2030.

3.2 Kerangka Konseptual Kajian

Kerangka konseptual kajian ini dibina berasaskan hubungan langsung antara adaptasi teknologi digital hijau sebagai pemboleh ubah bebas dan tahap kesedaran komuniti pelajar ke arah pembangunan lestari sebagai pemboleh ubah bersandar. Adaptasi teknologi digital hijau merujuk kepada tahap penggunaan, penerimaan, dan amalan teknologi digital yang rendah karbon, cekap tenaga serta mesra alam dalam kalangan komuniti pelajar. Apabila teknologi digital hijau digunakan secara meluas—misalnya melalui peranti cekap tenaga,

pengurusan data yang beretika, dan amalan pengurangan e-waste—pelajar berpotensi meningkatkan kefahaman, tanggungjawab dan kesedaran mereka terhadap agenda pembangunan lestari.

Kerangka ini juga berasaskan dapatan penyelidikan lepas seperti Refaie et al. (2024) yang menunjukkan bahawa adaptasi teknologi digital berasaskan kelestarian memainkan peranan penting dalam pembentukan minda dan tingkah laku lestari dalam organisasi pendidikan. Selari dengan kajian Ismail et al. (2023) dan Ahmad & Shafie (2024) yang menekankan jurang antara kesedaran dan amalan, kerangka ini mengusulkan bahawa adaptasi teknologi digital hijau berfungsi sebagai pemangkin dalam meningkatkan kesedaran pelajar terhadap alam sekitar dan tanggungjawab sosial. Oleh itu, kajian ini mengandaikan bahawa semakin tinggi tahap adaptasi teknologi digital hijau, semakin tinggi tahap kesedaran komuniti pelajar terhadap pembangunan lestari.

4.0 PERBINCANGAN IMPLIKASI KAJIAN

Adaptasi teknologi digital hijau membawa impak yang signifikan terhadap peningkatan kesedaran komuniti pelajar, khususnya dalam membentuk pemikiran, sikap dan tindakan yang selaras dengan prinsip pembangunan lestari. Melalui penerapan teknologi seperti Internet of Things (IoT), Artificial Intelligence (AI), Big Data Analytics dan Smart Energy Systems, pelajar bukan sahaja didedahkan kepada inovasi berasaskan kecekapan tenaga, tetapi juga kepada kefahaman mendalam mengenai hubungan antara penggunaan teknologi dan kesan terhadap alam sekitar. Pendekatan ini menjadikan pelajar lebih sedar akan tanggungjawab mereka sebagai pengguna digital dan warga global dalam meminimumkan jejak karbon melalui penggunaan teknologi secara beretika dan lestari. Dalam konteks ini, adaptasi teknologi digital hijau berperanan sebagai pemangkin kesedaran yang mampu mengubah paradigma pelajar daripada pengguna pasif kepada agen perubahan yang aktif dalam memperjuangkan isu kelestarian.

Dari sudut kognitif, adaptasi teknologi digital hijau memperkukuh kesedaran pelajar melalui penyampaian maklumat yang berasaskan data, bukti dan analisis masa nyata. Sistem pemantauan tenaga digital atau dashboard karbon, contohnya, membolehkan pelajar menilai secara langsung jumlah tenaga yang digunakan serta impak karbon yang dihasilkan daripada aktiviti harian mereka. Pendedahan kepada maklumat sedemikian meningkatkan tahap literasi alam sekitar dan digital pelajar, sekaligus mendorong mereka untuk membuat keputusan yang lebih berasaskan kesedaran. Seperti yang dinyatakan oleh Rahman et al. (2023), pelajar yang didedahkan kepada sistem digital hijau menunjukkan peningkatan tahap pengetahuan sebanyak 47% berkaitan konsep tenaga mampan dan pengurusan sumber. Oleh itu, adaptasi teknologi digital hijau dapat memperkukuh dimensi pengetahuan pelajar secara berterusan melalui pembelajaran interaktif dan pengalaman langsung.

Manakala dari aspek afektif pula, adaptasi teknologi digital hijau turut memainkan peranan penting dalam membentuk nilai, emosi dan keprihatinan terhadap alam sekitar. Pengalaman interaktif yang ditawarkan oleh aplikasi hijau digital seperti green gamification atau eco-tracking apps dapat menimbulkan rasa tanggungjawab dan empati terhadap isu kelestarian. Sebagai contoh, apabila pelajar melihat secara visual bagaimana penggunaan tenaga mereka menurun hasil daripada tindakan kecil seperti mematikan komputer atau menggunakan mod penjimatan tenaga, ia menimbulkan perasaan puas dan kesedaran moral bahawa tindakan individu memberi kesan terhadap kesejahteraan planet. Menurut Kollmuss

dan Agyeman (2002), kesedaran alam sekitar yang berasaskan pengalaman emosi dan nilai peribadi adalah lebih berkesan dalam membentuk tingkah laku lestari berbanding pendidikan berasaskan teori semata-mata. Oleh itu, adaptasi teknologi digital hijau yang mampu menggabungkan elemen interaktif dan pengalaman mendalam (immersive learning) menjadi medium penting dalam membina empati dan motivasi intrinsik pelajar terhadap alam sekitar.

Dari dimensi tingkah laku, impak adaptasi teknologi digital hijau dapat dilihat melalui perubahan nyata dalam gaya hidup dan amalan pelajar di kampus. Kajian oleh Ramli dan Hassan (2022) menunjukkan bahawa penggunaan aplikasi tenaga pintar dalam kalangan pelajar universiti tempatan telah meningkatkan amalan penjimatan tenaga sebanyak 35% dalam tempoh tiga bulan. Ini membuktikan bahawa apabila pelajar terlibat secara langsung dengan adaptasi teknologi digital hijau, mereka lebih cenderung untuk mengubah tingkah laku harian secara sukarela. Sebagai contoh, pelajar yang menggunakan sistem smart campus lebih berdisiplin dalam penggunaan elektrik dan lebih peka terhadap pengurusan sisa digital seperti e-waste. Adaptasi teknologi digital hijau bukan sahaja mendorong perubahan individu, malah menggalakkan pembentukan norma sosial baharu dalam komuniti pelajar di mana amalan hijau dianggap sebagai tanggungjawab bersama. Fenomena ini menunjukkan wujudnya kesan limpahan sosial (social spillover effect) yang memperkukuh budaya lestari di institusi pendidikan tinggi.

Dari perspektif institusi dan masyarakat, impak adaptasi teknologi digital hijau turut melangkaui tahap individu dengan memperkukuh ekosistem pembelajaran lestari yang lebih sistematik dan inklusif. Melalui integrasi teknologi ini dalam dasar dan kurikulum universiti, pelajar didedahkan kepada amalan hijau secara formal dan tidak formal, seperti kursus pembelajaran digital hijau, projek inovasi tenaga boleh baharu, dan program komuniti rendah karbon. Pendekatan ini memperkukuh nilai tanggungjawab sosial korporat universiti (university green governance) di samping membina jaringan komuniti pelajar yang celik alam sekitar. Seperti yang dijelaskan oleh Ahmad dan Yusof (2022), penerapan pendidikan digital hijau dalam kurikulum bukan sahaja meningkatkan kefahaman pelajar terhadap isu kelestarian, tetapi juga melahirkan generasi profesional yang beretika, kreatif dan bertanggungjawab terhadap alam sekitar.

Secara keseluruhannya, adaptasi teknologi digital hijau memberi impak menyeluruh terhadap pembangunan kesedaran komuniti pelajar melalui peningkatan pengetahuan, pembentukan sikap positif dan perubahan tingkah laku yang lebih lestari. Hubungan antara ketiga-tiga dimensi ini bersifat dinamik dan saling mempengaruhi pengetahuan yang diperoleh melalui teknologi meningkatkan kesedaran kognitif, pengalaman interaktif, membentuk empati dan sikap positif manakala tindakan kecil yang diulang menjadi budaya hijau yang berterusan. Dengan itu, pelajar bukan sekadar penerima teknologi, tetapi turut berperanan sebagai duta kelestarian yang menyumbang kepada kejayaan agenda Pembangunan Lestari Malaysia 2030. Oleh itu, penerapan teknologi digital hijau dalam konteks pendidikan tinggi perlu dilihat bukan hanya dari aspek teknikal, tetapi juga sebagai instrumen pembinaan kesedaran sosial dan transformasi budaya yang mampu memperkukuh komuniti pelajar ke arah masyarakat lestari.

5.0 KESIMPULAN

Secara keseluruhannya, kertas konsep ini menegaskan kepentingan memahami tahap kesedaran pelajar terhadap adaptasi teknologi digital hijau. Kesedaran pelajar terhadap teknologi hijau bukan sahaja penting untuk kesejahteraan alam sekitar tetapi juga menjadi asas kepada transformasi pendidikan berasaskan kelestarian. Oleh itu, usaha berterusan diperlukan bagi memperkukuh literasi hijau digital dalam kalangan pelajar agar dapat melahirkan generasi yang celik teknologi dan prihatin terhadap alam sekitar.

Selain itu, penekanan terhadap penerapan teknologi digital hijau di institusi pendidikan tinggi perlu dilihat sebagai satu strategi nasional yang menyokong matlamat Dasar Teknologi Hijau Negara 2030 dan Agenda Pembangunan Mampan (SDG 2030). Pendidikan tinggi harus berperanan sebagai pusat pembangunan minda lestari dengan mengintegrasikan elemen teknologi hijau ke dalam kurikulum, pengajaran dan aktiviti kokurikulum. Pendekatan ini bukan sahaja memperkukuh kesedaran individu, malah dapat membina budaya kampus hijau yang berasaskan nilai tanggungjawab sosial dan inovasi mampan. Secara tidak langsung, pengukuhan kesedaran pelajar terhadap teknologi digital hijau juga akan mempercepatkan peralihan Malaysia ke arah ekonomi hijau digital yang inklusif, berdaya tahan dan berimpak tinggi. Oleh itu, penyelidikan konseptual ini diharap dapat menjadi asas kepada kajian empirikal dan dasar strategik yang lebih komprehensif bagi membentuk komuniti pelajar sebagai ejen perubahan utama dalam merealisasikan pembangunan lestari negara menjelang tahun 2030.

RUJUKAN

- Abdul Wahab, M., Ismail, S., & Omar, H. (2021). Digital communication strategies for environmental awareness: The role of smart applications in promoting green behavior. *Journal of Environmental Communication Studies*, 12(2), 45–58.
- Ahmad, N., & Shafie, A. (2024). Green campus practices and student awareness in Malaysian higher education institutions. *Journal of Environmental Education and Sustainability*, 15(1), 21–34.
- Ahmad, N., & Yusof, R. (2022). Integrating green digital literacy in education: A framework for sustainable learning communities in Malaysia. *Asian Journal of Environmental Education*, 8(1), 25–36.
- Ajzen, I. (1991). The theory of planned behavior. *Organizational Behavior and Human Decision Processes*, 50(2), 179–211. [https://doi.org/10.1016/0749-5978\(91\)90020-T](https://doi.org/10.1016/0749-5978(91)90020-T)
- Bifftu, T., & Minyihun, A. (2023). The role of higher education institutions in fostering sustainability culture through digital transformation. *Journal of Sustainable Education Studies*, 11(4), 55–70.
- European Green Digital Coalition. (2023). *Twin transition: Enabling the digital and green transformation of Europe*. Brussels: European Commission.
- International Telecommunication Union. (2023). *Green digital transformation: Leveraging ICTs for sustainable development*. ITU Publications.

- Ismail, F., Rahim, M., & Zainal, S. (2023). Students' knowledge, attitudes and practices toward green technology in Malaysian polytechnics. *Journal of Green Education*, 7(2), 33–49.
- Ja'afar, N. A., Rahman, S. A., & Latif, M. A. (2024/2025). Sustainability in Malaysian higher education: Awareness, readiness and institutional support. *Education Planning and Improvement Journal*, 9(1), 33–49.
- Kementerian Tenaga, Sains, Teknologi, Alam Sekitar dan Perubahan Iklim. (2021). *Dasar Teknologi Hijau Negara 2030*. Putrajaya: KeTSA.
- Kementerian Tenaga, Teknologi Hijau dan Air. (2009). *Dasar Teknologi Hijau Negara*. Putrajaya: KeTTHA.
- Kollmuss, A., & Agyeman, J. (2002). Mind the gap: Why do people act environmentally and what are the barriers to pro-environmental behavior? *Environmental Education Research*, 8(3), 239–260. <https://doi.org/10.1080/13504620220145401>
- Lee, T. H., Chen, C. H., & Lim, S. (2020). Community awareness and sustainable technology adoption in Asian contexts. *Journal of Cleaner Production*, 276, 124–132.
- Malaysia Green Technology and Climate Change Corporation. (2024). *Malaysia Green Technology Report 2024*. Putrajaya: MGTC.
- Mohd Muhiddin, A. A., Mohd Isa, H., Md Sakip, S. R., Mohd Nor, O., & Sedhu, D. S. (2023). Green campus implementation in Malaysian public universities: Challenges and solutions. *Planning Malaysia*, 21(1), 231–243.
- Nordin, N., Ariffin, F., & Hassan, M. (2021). Barriers to digital green literacy among Malaysian youth: Infrastructure, access and awareness. *Malaysian Journal of Sustainable Development*, 9(2), 67–80.
- Obeng, P., Sekyere, S., & Twum, E. (2024). Students' awareness and readiness for emerging digital technologies in green development. *Journal of Green Technology and Society*, 6(1), 14–29.
- Rahman, F., Aziz, H., & Mohd, S. (2023). Public awareness and digital green innovation in Malaysia: A social cognitive approach. *Sustainability*, 15(4), 1893. <https://doi.org/10.3390/su15041893>
- Ramli, A., & Hassan, R. (2022). Energy efficiency through digital behavior change: Evidence from Malaysian universities. *Journal of Environmental Sustainability and Technology*, 10(3), 201–215.
- Refaie, A., Khalid, N., & Omar, R. (2024). Leadership and dynamic capabilities as drivers of green digital mindset and knowledge-sharing behavior in higher education. *BMC Psychology*, 12(4), 1–14.
- Rogers, E. M. (2003). *Diffusion of innovations* (5th ed.). Free Press.

- Shen, Y., Deng, Y., Xiao, Z., & Dai, R. (2025). Driving green digital innovation in higher education: The influence of leadership and dynamic capabilities on cultivating a green digital mindset and knowledge sharing for sustainable practices. *Journal of Cleaner Production*, 450, 141223.
- Springer. (2025). Trends of the digital transformation and green innovation: A systematic literature review. *Journal of Green Digital Economy*, 4(1), 1–18.
- Undergraduate students' awareness, understanding and readiness towards sustainable environmental behaviour. (2024). *AIP Conference Proceedings*, 2950, 020021.
- Xiong, Z., Zhang, L., Li, Z., Xu, W., Zhang, Y., & Ye, T. (2021). Frequency of Online Health Information Seeking and Types of Information Sought Among the General Chinese Population: Cross sectional Study. *Journal of Medical Internet Research*, 23(12), e30855. <https://doi.org/10.2196/30855>
- Zhang, L., Wei, C., & Zhou, H. (2022). Artificial intelligence for green energy management: A systematic review and empirical analysis. *Renewable and Sustainable Energy Reviews*, 158, 112111. <https://doi.org/10.1016/j.rser.2022.112111>

Kajian Keberkesanan Laman UPLINK Dalam Meningkatkan Kecekapan Proses Pengurusan Unit Perhubungan & Latihan Industri

Noorasikin binti Abdul Rahman^{1,*}, Hairman bin Omar², Suhana binti Mohd Gazi³

^{1,2}Politeknik Merlimau Melaka

³Politeknik Kuching, Sarawak

*noorasikin@pmm.edu.my

Abstrak. Kajian ini dijalankan bagi menilai keberkesanan laman UPLink, sebuah *platform* yang dibangunkan bagi menyokong pengurusan Unit Perhubungan & Latihan Industri (UPLI). Laman UPLink merupakan satu inovasi pengurusan yang bertujuan memudahkan dan menggantikan proses kerja yang menggunakan kaedah konvensional. Proses pengurusan latihan industri sebelum ini dijalankan secara manual yang melibatkan penggunaan borang fizikal dan komunikasi tidak berpusat, menyebabkan kelewatan dan ketidaktepatan data. Dalam konteks pengurusan latihan industri di UPLI Politeknik Merlimau Melaka (PMM), isu capaian data legit pelajar, penyampaian maklumat, memuat naik serta memuat turun dokumen, aduan pelajar, laporan cuti dan soalan lazim tentang latihan industri sering menjadi perhatian utama untuk diselaraskan. Bagi menangani isu ini, laman UPLink telah dibangunkan untuk menyelesaikan isu berkenaan informasi dimana ianya dapat disampaikan dengan cepat, tepat dan mudah. Penggunaan laman digitalisasi ini juga bersifat mesra pengguna dimana capaian info dan data diperolehi secara berpusat serta mudah diakses pada bila-bila masa dan lokasi. Pembangunan laman UPLink yang tanpa melibatkan sebarang kos pengurusan juga adalah salah satu faktor utama ianya diwujudkan. Kajian ini menggunakan pendekatan kuantitatif dengan kaedah soal selidik kepada pelajar dan pensyarah dengan bilangan 55 orang yang dipilih secara rawak pada sesi I: 2025/2026. Kaedah tinjauan berbentuk kuantitatif diaplikasikan dalam kajian ini dengan menyediakan borang soal selidik melalui *Google Form* yang mengandungi soalan-soalan berstruktur. Hasil analisis mempamerkan laman UPLink yang dibangunkan ini telah berjaya dan bermanfaat untuk memudahkan urusan latihan industri. Keputusan analisa menunjukkan purata skor min yang amat tinggi iaitu 4.64 dari skala 5.00 dapat dilihat serta maklum balas responden terhadap *platform* ini amatlah positif. Walaubagaimanapun, masih terdapat kekurangan dan perlu ditambah baik namun untuk peringkat awal ini, laman UPLink dianggap berkesan dalam meningkatkan kecekapan proses pengurusan latihan industri. Secara tidak langsung menyokong transformasi digital di institusi Pendidikan Teknikal dan Vokasional (TVET).

Kata Kunci: Laman UPLink, Latihan Industri, Digitalisasi, Kecekapan Proses, Mesra Pengguna

1.0 PENGENALAN

Latihan Industri (LI) merupakan satu komponen penting dalam kurikulum pembelajaran di semua institusi pengajian tinggi seperti di universiti, kolej dan politeknik. Dalam konteks Politeknik Malaysia, semua pelajar semester akhir perlu menjalani LI didalam bidang pengajian pelajar dan memastikan pelajar menepati syarat lulus LI bagi

penganugerahan diploma mengikut bidang pengajian.

Unit Perhubungan & Latihan Industri (UPLI) di Politeknik Merlimau Melaka (PMM) merupakan unit yang bertanggungjawab menguruskan pelajar semester akhir yang bermula dengan mengenalpasti pelajar yang layak menjalani LI sehinggalah pelajar berjaya tamat LI dengan jayanya. Unit ini juga memainkan peranan utama dalam memastikan pengurusan pelajar LI ini berjalan lancar keseluruhannya. Terdapat beberapa prosedur LI meliputi aktiviti taklimat LI, program bersama industri dan alumni, urusan penempatan LI, pengesahan penempatan LI, pengesahan hadir LI melalui sistem rekod Borang Pengesahan Lapor Diri (BPLD), pemantauan, lapor diri tamat LI dan penilaian selepas pelajar tamat latihan industri. Perlaksanaan semua proses ini dilaksanakan secara terancang mengikut takwim edaran Jabatan Pendidikan Politeknik dan Kolej Komuniti (JPPKK) dan diselaraskan dengan takwim aktiviti LI di politeknik masing-masing. Sehubungan itu, Buku Panduan Pelaksanaan Latihan Industri Politeknik dan Kolej Komuniti Edisi 2022 dirujuk dalam pengurusan pelajar LI yang merangkumi pengurusan menyeluruh bagi fasa sebelum, semasa dan selepas LI. Namun, pelaksanaan sebelum ni adalah secara manual menyebabkan beberapa isu seperti kesukaran merujuk untuk dapatkan informasi tepat, kesukaran mengesan status pelajar, kehilangan data dan kelewatan terima laporan/aduan dan pelbagai isu yang diketengahkan. Secara tidak langsung, ianya mengganggu pengurusan dan aliran kerja dalam mengendalikan pelajar LI pada setiap semester.

Oleh yang demikian, perancangan pengurusan dan pelaksanaan LI ini perlu diurus dengan baik agar keseluruhan proses LI berjalan lancar pada setiap semester. Merujuk kajian lepas, (Ismail & Hassan, 2020; Ibrahim & Nor, 2019) menunjukkan pelaksanaan sistem dalam talian dapat mempercepat dan memudahkan proses pengurusan latihan industri, selari dengan dapatan Alias et al. (2018) yang mendapati penggunaan *platform* digital meningkatkan kebolehpasaran graduan melalui kecekapan latihan industri yang lebih baik. Lantaran itu, satu inisiatif pendigitalan telah diusahakan dan diperkenalkan bagi memastikan pengurusan secara dalam talian lebih sistematik melalui pembangunan laman UPLink yang menggunakan *Google Sites* dan *Locker Studio*. *Platform* ini berfungsi sebagai pusat penyampaian maklumat dan data statistik supaya hebahan yang tepat, mudah dan cepat dapat disalurkan kepada pelajar dan pensyarah. Gerak kerja yang sistematik dalam pengurusan LI akan dapat mencapai objektif dan *Key Performance Index (KPI)* LI yang disasarkan kerana mengamalkan kaedah pengurusan kerja yang efisien seiring dengan kemudahan serta perkembangan teknologi masa kini. Oleh yang demikian, kajian ini dijalankan bagi menilai keberkesanan laman web tersebut dalam meningkatkan kecekapan proses pengurusan latihan industri serta mengenal pasti tahap kepuasan pengguna.

Latihan industri merupakan elemen penting dalam pembangunan pelajar. Sehubungan itu, pengurusan LI pelajar sering menghadapi pelbagai cabaran yang memberi kesan kepada keberkesanan pelaksanaan LI secara menyeluruh. Antara masalah utama yang dikenalpasti adalah:

- i) Penyampaian dan dapatan data, maklumat serta komunikasi antara pelajar LI dan pensyarah (penyelaras LI, penasihat akademik, pengurusan) tidak berlaku secara cekap kerana tiada satu medium khas yang menyelaras semua maklumat berkaitan LI secara berpusat.
- ii) Dokumentasi tidak diurus dengan baik terutamanya isu kaedah penghantaran

dokumen melalui serahan tangan yang tidak praktikal kerana sering lewat terima dan hilang dokumen.

- iii) Kurangnya penggunaan teknologi dalam pengurusan LI menyebabkan ketidakcekapan dari segi masa dan sumber.

Oleh yang demikian, Kajian ini dijalankan dengan objektif berikut:

1. Menilai tahap keberkesanan laman UPLInk dalam meningkatkan kecekapan proses pengurusan latihan industri.
2. Menentukan tahap kepuasan pengguna terhadap fungsi dan kemudahan laman UPLInk.

2.0 KAJIAN LITERATUR

Kajian mendapati kebanyakan institusi pendidikan mula beralih daripada proses manual kepada sistem digital bagi menguruskan latihan industri pelajar. Menurut Husin (2024), pembangunan *Web-Based Industrial Training Management System* telah membantu mengurangkan kesilapan pengurusan dan mempercepatkan urusan penyeliaan antara pihak fakulti dan industri. Sistem ini membolehkan pendaftaran, pemantauan, dan penilaian dijalankan secara dalam talian, sekali gus meningkatkan kecekapan pentadbiran.

Kajian oleh Thilakarathna (2023) pula menekankan bahawa sistem latihan industri berasaskan web (ITMS) bukan sahaja berfungsi untuk menyimpan data, malah menjadi alat komunikasi dua hala yang efisien antara pelajar, penyelia fakulti, dan penyelia industri. Ciri-ciri seperti logbook elektronik dan penilaian dalam talian membantu memastikan pemantauan dijalankan secara berterusan tanpa memerlukan interaksi fizikal.


Selain itu, Ridwan (2019) melalui kajiannya di Universiti Malaysia Pahang (UMP) mendapati bahawa penggunaan sistem pengurusan latihan industri dapat mengurangkan kebergantungan kepada kaedah konvensional seperti penghantaran borang bercetak dan komunikasi melalui e-mel. Ini menunjukkan bahawa sistem digital mampu mempertingkatkan efisiensi kerja staf pentadbiran dan memberikan pengalaman pengguna yang lebih baik.

Manakala, kajian Gaba (2015) mengenai pembangunan e-portfolio dalam konteks latihan industri pula menunjukkan bahawa penggunaan sistem digital membolehkan pelajar merekod dan merefleksi pengalaman industri dengan lebih sistematik. Hal ini bukan sahaja memudahkan proses pemantauan prestasi, malah menggalakkan pembelajaran berasaskan refleksi dalam kalangan pelajar.

3.0 METODOLOGI KAJIAN

Kajian ini menggunakan kajian dalam bentuk pendekatan kuantitatif yang berbentuk tinjauan iaitu dengan menggunakan kaedah borang soal selidik menerusi *Google Form* yang diedarkan kepada responden yang terdiri daripada pelajar LI dan pensyarah yang dikategorikan sebagai pengguna laman UPLInk. Pengumpulan maklumat dibuat menggunakan pendekatan sampel kajian dan seterusnya dianalisis untuk memperoleh hasil kajian. Proses pembinaan kajian ini adalah ditunjukkan di dalam carta alir seperti di dalam Rajah 1.






Rajah 1: Carta Alir Kajian

3.1 Pembangunan laman UPLInk Amali

Proses membangunkan laman UPLInk ini melibatkan gabungan *platform* dan perisian iaitu **Google Sites** untuk membina laman web dengan mudah dan *Locker Studio* bagi memaparkan data statistik secara maya. Laman UPLInk ini dihasilkan atas pemerhatian, pengalaman dan rujukan daripada pihak pengurusan LI dan pensyarah yang menguruskan pelajar latihan industri. Penggunaan *platform* ini telah memudahkan proses pengurusan LI bermula dari proses awal fasa sebelum LI hingga proses penilaian tamat LI. Pembangunannya juga tidak melibatkan sebarang kos kerana tidak melibatkan sebarang perisian tambahan, hanya memerlukan capaian data internet. Paparan dapat dilihat menerusi komputer dan telefon pintar secara terus seperti dalam Rajah 2 dan Rajah 3.



Rajah 2: Paparan Data Statistik Pelajar Latihan Industri



Rajah 3: Paparan Maklumat dan Dokumen Latihan Industri

3.2 Data Analisis

Borang soal selidik mengandungi persoalan-persoalan dan pernyataan-pernyataan yang perlu dijawab menggunakan lima skala jawapan. Skala jawapan berbentuk Skala Likert kerana jawapan adalah dalam bentuk data ordinal. Penggunaan Skala Likert dapat memudahkan responden untuk memilih jawapan.

Manakala tahap penerimaan analisis skor min dalam kajian ini ditentukan dalam satu jadual spesifikasi berdasarkan kepada julat yang dicadangkan oleh Najib, (1999) seperti dalam Jadual 1.

Jadual 1: Spesifikasi Analisa Skor Min

Julat skor min	Tahap nilai skor min
1.00 – 1.49	Amat rendah
1.50 – 2.49	Rendah
2.50 – 3.49	Sederhana
3.50 – 4.49	Tinggi
4.50 – 5.00	Amat Tinggi

Sumber: Najib, 1999

Borang soal selidik digunakan dalam kajian ini sebagai instrumen kajian yang merupakan pendekatan yang lazim dan berkesan untuk mengumpul data dari responden. Borang soal selidik ini diedarkan secara atas talian melalui *Google Form* kepada responden bagi mendapatkan maklum balas. Penggunaan soal selidik untuk mendapatkan data daripada responden yang terdiri daripada pelajar dan pensyarah di Politeknik Merlimau Melaka. Kaedah kajian secara tinjauan dengan menggunakan soal selidik adalah salah satu kaedah yang paling popular dalam penyelidikan sosial. Pengkaji telah menggunakan soal selidik sebagai instrumen utama untuk mengumpul data.

3.2.1 Kebolehpercayaan

Kebolehpercayaan adalah berkaitan dengan darjah konsisten sesuatu keputusan ujian (Naresh, 1999). Kebolehpercayaan terhadap instrumen yang digunakan diuji dengan menggunakan kaedah Alpha Cronbach. Petunjuk kepada aras kebolehpercayaan yang boleh diterima adalah nilai indeks korelasi Alpha Cronbach (α) sekurang-kurangnya 0.6.

3.2.2 Kaedah Analisis Data

Penggunaan kaedah kuantitatif dalam kajian ini dengan merangkumi tinjauan soal selidik adalah pendekatan yang berfokus pada pengumpulan data berbentuk angka untuk menganalisis hubungan, trend, dan pola-pola dalam kajian. Penggunaan perisian *Statistical Packages for Social Sciences Version 17.0 (SPSS v 17.0)* untuk menganalisa data yang terkumpul. Statistik deskriptif digunakan bagi merangkum dan menggambarkan data yang telah dikumpulkan. Penggunaan jumlah skor min digunakan berbanding dengan skor individu. Ini disebabkan oleh kesahan dan ketepatannya adalah lebih tinggi berbanding dengan skor secara individu Cresswell (2009). Penggunaan faktor analisis dalam merumuskan dan mentransformasikan data mentah kepada bentuk yang mengandungi maklumat tentang satu set faktor di dalam sesuatu keadaan. Oleh itu, faktor-faktor utama dapat dikenal pasti bagi menerangkan varian data mentah terkumpul. Peratusan, skor min dan sisihan piawai dihasilkan dalam bentuk graf, carta dan jadual.

3.2.3 Instrumen kajian

Kajian ini menggunakan instrumen soal selidik yang merangkumi maklumat responden dan ianya dibahagikan kepada DUA bahagian iaitu Bahagian A dan bahagian B yang mana mengukur Penilaian Keberkesanan Laman UPLink dan Tahap Kepuasan Pengguna, seperti yang ditunjukkan di dalam Jadual 2.

Jadual 2: Pembahagian item di dalam borang soalselidik

Bahagian soalan	Item
Bahagian A Bahagian B	Penilaian Keberkesanan Laman UPLInk Tahap Kepuasan Pengguna

4 DAPATAN KAJIAN

4.1 Dapatan Soal Selidik

4.1.1 Lokasi Soal Selidik

Kajian dijalankan di Politeknik Merlimau Melaka.

4.1.2 Populasi dan Respondan Kajian

Di dalam kajian ini, penyelidik menggunakan populasi pelajar dan pensyarah secara rawak sebagai responden kajian. Responden daripada pelajar semester 5 sesi I: 2025/2026 dan pensyarah dari jabatan akademik dengan jumlah melibatkan 55 orang responden.

4.1.3 Kajian Rintis

Kajian rintis dijalankan terhadap soal selidik yang disediakan pada 8 orang sampel terdiri daripada 10 orang pelajar. Saiz sampel rintis hanya memadai untuk memenuhi tujuan perbincangan awal yang berkesan dan boleh diandalkan berkaitan ujian (6-9 pelajar) dan pekali kebolehpercayaan adalah di antara 0 hingga 1.0 merujuk kepada pekali Cronbach's Alpha. Jika kebolehpercayaan menghampiri nilai 1.0, maka komponennya adalah sah. Ini bermakna semakin nilai alfa kepada 1.0, maka semakin tinggi kebolehpercayaannya. Hasil analisis yang diperoleh melalui borang soal selidik terhadap responden akan dibincangkan secara lebih terperinci pada bahagian ini. Nilai Alpha Cronbach untuk kajian rintis yang diperolehi ialah 0.927 seperti di dalam Jadual 3. Sekiranya nilai Alpha Cronbach melebihi 0.8, ini bermakna tahap kebolehpercayaan item ini adalah tinggi dan seragam.

Jadual 3: Statistik kebolehpercayaan

Cronbach's Alpha	Cronbach's Alpha rujuk standard asas item	Item (N)
0.926	0.927	8

4.2 Analisis Data Dan Keputusan

Analisis data bahagian demografi responden adalah ditunjukkan seperti di dalam Jadual 4 dan 5 berikut:

Jadual 4: Taburan Jantina Responden

Jantina	Bilangan	Peratusan (%)
Lelaki	43	78
Perempuan	12	22
Jumlah	55	100

Jadual 5: Taburan Peranan Responden


Jantina	Bilangan	Peratusan (%)
Pelajar LI	45	82
Pensyarah	10	18
Jumlah	55	100

4.2.1 Bahagian A

Analisis data bahagian penilaian keberkesanan laman UPLInk menunjukkan hasil dapatan seperti dalam Jadual 6 iaitu data-data yang telah diproses menggunakan perisian SPSS bagi mendapatkan skor min dan sisihan piawai. Data ini menentukan tahap penilaian pelajar dan pensyarah yang telah menggunakan platform laman UPLInk bagi mendapatkan informasi, dokumentasi dan pengurusan berkaitan. Hasil kajian menunjukkan purata skor min bagi item terhadap penggunaan laman UPLInk ini adalah 4.58, iaitu berada pada tahap yang amat tinggi. Ini membuktikan bahawa dapatan memberi maklumat yang positif tentang persepsi dan pandangan responden terhadap penggunaan laman UPLInk untuk pengurusan latihan industri. Hampir keseluruhan item menunjukkan tahap yang amat tinggi kecuali item nombor 3 yang menunjukkan item hanya tahap tinggi. Keseluruhan keputusan ini membuktikan bahawa responden secara amnya telah memberikan penilaian yang sangat positif terhadap keberkesanan penggunaan *platform* ini.

Jadual 6: Skor Min & Sisihan Piawai Bagi Penilaian Keberkesanan Laman UPLInk


Item	Skor Min	Sisihan piawai	Tahap Penerimaan
1. Laman UPLInk membantu mempercepatkan proses pengurusan latihan industri.	4.64	0.609	Amat Tinggi
2. Maklumat dalam laman UPLInk mudah diakses dan mesra pengguna.	4.56	0.525	Amat Tinggi
3. Laman UPLInk membantu penyelarasan komunikasi antara pelajar dan pensyarah	4.44	0.554	Tinggi
4. Data pelajar latihan industri dapat diakses dengan cepat dan tepat	4.64	0.467	Amat Tinggi
5. Pengurusan latihan industri menjadi lebih lancar dan teratur melalui laman UPLInk	4.58	0.549	Amat Tinggi



Graf 1: Penilaian Keberkesanan Laman UPLink

4.2.2 Bahagian B

Analisis data bahagian B adalah Tahap Kepuasan Pengguna terhadap penggunaan laman UPLink. Hasil dapatan dalam Jadual 7 di bawah merupakan dapatan data terkumpul yang telah diproses menggunakan perisian SPSS bagi mendapatkan skor min dan sisihan piawai. Data ini menentukan tahap kepuasan pelajar dan pensyarah yang telah menggunakan medium laman web yang telah dibangunkan ini untuk meningkatkan kefahaman dalam urusan berkaitan latihan industri.



Graf 2: Tahap Kepuasan Pengguna Laman UPLink

Jadual 7: Skor Min & Sisihan Piawai Bagi Tahap Kepuasan Pengguna Laman UPLink

Item	Skor Min	Sisihan piawai	Tahap Penerimaan
1. Laman UPLInk menjimatkan masa dan membantu memudahkan urusan latihan industri saya.	4.58	0.485	Amat Tinggi
2. Saya lebih suka menggunakan laman UPLInk berbanding kaedah manual	4.65	0.480	Amat Tinggi
3. Saya berpuas hati dengan penggunaan laman UPLInk secara keseluruhan.	4.64	0.498	Amat Tinggi

Berdasarkan Jadual 7 di atas, didapati bahawa purata skor min 4.64 iaitu berada pada tahap yang amat tinggi bagi menilai tahap kepuasan pengguna. Ini membuktikan bahawa laman UPLInk sesuai diguna pakai oleh pelajar dan pensyarah dalam proses memahami prosedur dan urusan yang melibatkan latihan industri. Keseluruhan keputusan ini membuktikan bahawa responden bersetuju terhadap usaha ke atas pembangunan medium digitalisasi ini.

4.0 PERBINCANGAN DAN KESIMPULAN

Laman UPLInk berjaya memodenkan pengurusan latihan industri dengan mengurangkan kebergantungan kepada proses manual. Ia menyokong kecekapan dari segi masa, ketepatan data, serta ketelusan komunikasi antara pihak berkepentingan. Walau bagaimanapun, beberapa cadangan penambahbaikan seperti peningkatan kestabilan sistem, integrasi notifikasi automatik, dan modul laporan dinamik bagi meningkatkan pengalaman pengguna. Cadangan penambahbaikan masa hadapan termasuk:

- Integrasi *dashboard analytics* untuk laporan prestasi pelajar.
- Fungsi *chat support* bagi komunikasi langsung antara pengguna.
- Kajian lanjutan menggunakan analisis kualitatif untuk menilai pengalaman pengguna secara mendalam.

Secara kesimpulannya, kajian ini membuktikan bahawa laman UPLInk berkesan dalam meningkatkan kecekapan proses pengurusan latihan industri serta memudahkan pelaksanaan pentadbiran digital di institusi pendidikan khususnya di Politeknik Merlimau Melaka. Pembangunan laman ini memberi nilai tambah kepada Unit Perhubungan dan Latihan Industri dengan mewujudkan aliran kerja lebih tersusun, cepat dan telus. Pembangunan laman pengurusan latihan industri menggunakan *Google Sites dan Locker Studio* telah berjaya menghasilkan satu medium penyampaian maklumat yang berpusat, mudah diakses dan mesra pengguna. *Platform* ini memberi kemudahan kepada pelajar, pensyarah, pihak pengurusan UPLI dan institusi dalam mengakses maklumat penting berkaitan latihan industri secara dalam talian dan fleksibel. Laman UPLInk ini dibangunkan bagi tujuan memudahkan pengurusan LI bagi semua pelajar agar bekerja lebih efisien, cepat dan menjimatkan kos operasi. Walau bagaimanapun, sistem ini masih mempunyai ruang untuk penambahbaikan dari aspek tertentu untuk meluaskan penggunaannya dimasa akan datang. Seiring dengan kemajuan teknologi masa kini, pengurusan UPLI perlu bergerak seiring dengan perkembangan ini. Hal ini adalah bagi memastikan penyampaian perkhidmatan dapat dijalankan dengan cepat, tepat dan sempurna. Secara tidak langsung ianya mencerminkan budaya kerja di UPLI khususnya dan PMM amnya untuk terus bekerja dengan sistematik serta dinamik dalam mencapai prestasi kerja pengurusan pelajar LI pada

tahap yang cemerlang.

RUJUKAN

- Alias, R., Zain, M. Z. M., & Samsudin, M. A. (2018). *The effectiveness of industrial training programs in enhancing students' employability skills. Journal of Technical Education and Training, 10*(1), 37–48.
- Creswell, J. W. (2009). *Research design: Qualitative, quantitative, and mixed methods approaches* (3rd ed.).
- Gaba, A. (2015). Development and evaluation of an e-portfolio for use in internship programs. *Open Learning Journal*.
- Husin, M. Z. (2024). A Web-Based Industrial Training Management System: A Case Study of the School of Computing. *Journal of Digital System Development*.
- Ibrahim, N. A., & Nor, M. Y. (2019). *Industrial training management and supervision system for polytechnic students. International Journal of Advanced Computer Science and Applications, 10*(8), 45–50.
- Ismail, N., & Hassan, R. (2020). *Implementation of online system in managing industrial training process in higher learning institutions. Asian Journal of University Education, 16*(3), 120–133.
- Malhotra, N. K. (1999). *Marketing Research: An Applied Orientation*. Prentice Hall.
- Mohd Najib, A. G. (1999). *Penyelidikan Pendidikan*. Skudai, Johor: Penerbit Universiti Teknologi Malaysia.
- Ridwan, F. (2019). Internship Management System (IMS-UMP): Web-Based Monitoring and Evaluation Platform. University Malaysia Pahang Thesis Repository.
- Thilakarathna, K. (2023). *Web-Based Industrial Training Management System (ITMS): Development and Evaluation*. Sri Lanka Institute of Technology Press.

Design And Development Of A Safe And Secure Mobile Donation Box System For Mosques

Mohamad Azamri Kandari, Syahrain Mat Yamin, Mohamad Najib Mohamad Zain

Politeknik Merlimau Melaka

mohamadnajib@pmm.edu.my

ABSTRACT This study presents the *Design and Development of a Safe and Secure Mobile Donation Box System for Mosques*, an engineering innovation aimed at reducing theft and enhancing donation management in religious institutions. Mosque donation boxes, essential for collecting community contributions, have increasingly become targets of theft and vandalism across Malaysia due to their lightweight construction, minimal locking mechanisms, and absence of electronic monitoring systems. Addressing these challenges, this project integrates mechanical reinforcement with Arduino-based electronic security features to develop a prototype that is both secure and portable. The system incorporates a vibration sensor, buzzer alarm, and GPS tracking module, all controlled by an Arduino Uno microcontroller. When physical tampering or unauthorized movement occurs, the vibration sensor triggers the buzzer to emit a loud audible alarm while the GPS module records and transmits the location coordinates in real time. The donation box itself is fabricated using mild steel, ensuring high durability, corrosion resistance, and resistance to forced entry. Power is supplied via a 3.7V rechargeable lithium-ion battery, providing continuous operation during normal use. The project followed an engineering design methodology that included conceptual design, hardware fabrication, software programming, and both laboratory and field testing. Quantitative testing confirmed the system's functional reliability, achieving a vibration detection accuracy above 95%, alarm activation within one second, and GPS tracking precision within 5–10 meters in outdoor environments. Battery endurance tests indicated approximately seven hours of continuous operation. Qualitative evaluation through a survey of 35 respondents—including mosque administrators, committee members, and congregants—revealed strong user acceptance, with 82.6% overall satisfaction and 86% recommending system adoption for other mosques. Respondents highlighted enhanced safety, ease of use, and practical design, while recommending future improvements in battery capacity and wireless alert features. The findings demonstrate that the integration of low-cost Internet of Things (IoT) components and durable mechanical design can effectively enhance community-level asset protection. The project embodies the principles of Situational Crime Prevention (Clarke, 1980) and Technology Acceptance Model (Davis, 1989) by increasing theft resistance, improving user confidence, and promoting technology adoption in religious facilities. In conclusion, the proposed system provides a cost-effective, reliable, and replicable solution for safeguarding mosque donations. Future development should explore IoT-based alert systems, solar-powered charging, and GSM connectivity for remote notifications. This work contributes not only to community safety and trust restoration but also to the advancement of engineering education and smart community innovation within Malaysian polytechnics.

Keywords: Arduino Uno, vibration sensor, GPS tracking, IoT security, mosque donation system, theft prevention, community innovation

1.0 INTRODUCTION

Mosques are vital institutions that serve as both spiritual and social centers within Muslim communities. They rely heavily on public donations to sustain operations, fund community programs, and support charitable initiatives. Traditionally, these donations are collected using stationary donation boxes (*tabung masjid*), which are placed in accessible areas for congregants to contribute voluntarily. While this system encourages charitable giving, it also exposes the donation boxes to risks of theft and vandalism. In recent years, theft cases involving mosque donation boxes have become increasingly common in Malaysia. Reports by Ahmad (2022) and Nordin (2022) highlight numerous incidents in which thieves broke into mosques, especially during non-prayer hours, to steal donation funds. Such incidents not only result in financial losses but also erode public trust in mosque administration.

Conventional donation boxes, typically constructed from lightweight materials such as wood or thin metal and secured only by simple locks—offer minimal protection against forced entry or tampering. With the advancement of technology, particularly the Internet of Things (IoT), opportunities have emerged to enhance the security and monitoring of physical assets. IoT-enabled systems integrate sensors, controllers, and communication modules to detect and respond automatically to real-time events. Applying these technologies to mosque donation boxes could transform them into intelligent, self-protecting systems capable of detecting theft attempts, activating alarms, and transmitting location data for recovery.

This study introduces the Design and Development of a Safe and Secure Mobile Donation Box System for Mosques, which integrates mechanical durability with embedded electronic security components. The system combines Arduino Uno microcontroller, vibration sensor, buzzer alarm, and GPS tracking module to detect unauthorized movement, trigger immediate alerts, and facilitate post-incident tracking. The proposed solution emphasizes portability, affordability, and reliability, making it suitable for small to medium-sized mosques across Malaysia. The primary objective of this study is to design and develop a *Safe and Secure Mobile Donation Box System for Mosques* that integrates both mechanical and electronic security features to enhance the protection of charitable funds. Specifically, this project aims to:

- i. Design and develop a mobile donation box system that ensures the safety and security of mosque donations through the application of durable structural materials and embedded electronic components.
- ii. Integrate a vibration sensor, buzzer alarm, and GPS tracking system— controlled by an Arduino Uno microcontroller—to enable real-time detection, alerting, and location tracking in response to tampering or unauthorized movement.
- iii. Evaluate the overall system performance, functional reliability, and user satisfaction through structured laboratory experiments, field testing, and survey-based assessments involving mosque administrators and congregants.

The scope of this project encompasses the design, development, and evaluation of a prototype security system specifically intended for small to medium-sized mosques. The project emphasizes the application of cost-effective and readily available technologies to ensure practical implementation within community-based religious institutions. The system integrates an Arduino Uno microcontroller as the central processing unit, supported by GPS and vibration sensors, a buzzer alarm, and a rechargeable lithium-ion battery as the primary

power source. Prototype testing was conducted within simulated mosque environments to replicate real-world operational conditions and assess the system's performance, reliability, and responsiveness to potential theft or tampering scenarios. The findings derived from these tests provide empirical evidence of the system's feasibility and its potential applicability for broader adoption in mosque security management.

2.0 LITERATURE REVIEW

This chapter reviews past studies and information related to the design and development of a safe and secure mobile donation box system for mosques. It focuses on theft problems in mosques, the use of the Internet of Things (IoT) in security systems, different sensor technologies, and Arduino-based security development. The review also includes related projects and theories that support this study.

Religious places such as mosques are open to the public, which makes them difficult to protect. Johnson and Peterson (2018) explained that most mosques have weak security because they have open access, few staff, and limited surveillance systems. In Malaysia, many cases of donation box theft have been reported. Ahmad (2022) and Nordin (2022) reported that thieves often enter mosques pretending to be worshippers before stealing donation boxes. These cases show that traditional boxes using only padlocks are not enough to prevent theft. Therefore, a new system that can detect tampering and send alerts is needed to protect donation funds.

The Internet of Things (IoT) allows electronic devices to connect, share data, and respond automatically without human help. An IoT security system usually has four main parts:

- i. Sensing layer – sensors to detect movement or vibration.
- ii. Network layer – sends data through communication systems.
- iii. Processing layer – analyses data and makes decisions
- iv. Application layer – shows alerts to users.

As mentioned by Gubbi et al. (2013), the success of IoT security depends on good sensor design, stable power, reliable communication, and simple user control. Using IoT in this project helps detect theft and notify users more effectively.

Sensors are important in detecting theft or movement. Three main types of sensors are commonly used:

- i. Vibration Sensors: These sensors detect shaking or impact. They work based on the piezoelectric effect that converts movement into electrical signals. Kumar and Patel (2019) found that vibration sensors are cheap, sensitive, and use little power. However, they can cause false alarms if there are nearby vibrations.
- ii. Motion Sensors (PIR): Passive Infrared (PIR) sensors detect body movement by sensing infrared radiation. Lee et al. (2017) found that PIR sensors can detect people accurately in most cases, but they are not suitable for detecting small vibrations or movement of objects.
- iii. GPS Tracking: GPS modules are used to track the location of objects. Henderson and Anderson (2020) stated that GPS can locate stolen items with 5–30 meters accuracy

and has a 70% success rate in recovery when used immediately. In this project, GPS helps locate the donation box if it is stolen.

Arduino is a popular microcontroller used in electronic projects because it is easy to use, affordable, and supported by a large online community. The Arduino Uno board, which uses the ATmega328P chip, has enough input/output pins to connect sensors and alarms (Banzi & Shiloh, 2014). Previous projects show that Arduino is suitable for security systems. These studies show that Arduino is effective for building small-scale security systems like this donation box project.

3.0 METHODOLOGY

The methodology employed in the design and development of the Safe and Secure Mobile Donation Box System for Mosques. The methodology was carefully structured to ensure a systematic and scientific approach in transforming conceptual ideas into a functional and reliable prototype. The overall process followed the engineering design framework, which encompasses several essential phases—problem identification, conceptual design, system development, prototype fabrication, programming, testing, and evaluation. Each phase was executed in sequence to ensure the integrity, efficiency, and practicality of the final system.

This methodology also integrates both quantitative and qualitative research methods. Quantitative analysis was applied to evaluate the technical performance of the system, including vibration sensitivity, GPS accuracy, and battery life. Meanwhile, qualitative feedback was collected through user surveys and interviews to assess usability, reliability, and user satisfaction. The integration of these methods provides a holistic evaluation of the system's performance, ensuring that the final design not only functions effectively but is also user-friendly and applicable within the context of mosque operations.

3.1 Research Design

This study adopted the engineering design process, which is widely used in technical and product development research. The process was divided into five major stages:

Problem Identification – Recognizing the recurring issue of mosque donation box theft and the inadequacy of conventional security systems.

- i. System Design – Conceptualizing the electronic and mechanical structure of the security system.
- ii. Prototype Fabrication – Constructing the physical model using selected components and materials.
- iii. Programming and Integration – Developing the control logic using Arduino IDE and integrating hardware components.
- iv. Testing and Evaluation – Conducting laboratory and field testing to assess the
- v. system's reliability and effectiveness

This structured design approach ensures that the system's development process remains logical, traceable, and focused on achieving the project objectives.

3.2 System Components

The prototype integrates both mechanical and electronic components to create a compact yet effective donation box security system. Table 1 presents the list of components, their descriptions, and their respective functions.

Table 1: System Components and Functions

Component	Description	Function
Arduino Uno	ATmega328P microcontroller	Serves as the main control unit responsible for processing input and output signals.
Vibration Sensor (SW-420)	Piezoelectric vibration detector	Detects movement or tampering with the donation box.
Buzzer	5V active sound emitter	Produces a loud audible alarm to alert surrounding individuals when tampering occurs.
GPS Module (NEO-6M)	Satellite-based tracking module	Captures and records the real-time geographic coordinates of the donation box.
Lithium Battery (3.7V rechargeable)	Rechargeable lithium-ion cell	Provides portable and continuous electrical power for system operation.
Steel Frame	Stainless steel flat bars	Provides physical strength and durability to prevent forced access or damage.

The selection of components was based on factors such as cost-effectiveness, compatibility, durability, and ease of integration, ensuring that the system remains affordable for small to medium-sized mosques.

3.3 System Operation

The system operates through a sensor-triggered control mechanism governed by the Arduino Uno microcontroller. When the vibration sensor detects unusual movement or tampering, it sends an input signal to the microcontroller. The Arduino then activates the buzzer, producing a loud alarm sound, while the GPS module records the real-time location of the donation box.

The system is designed to operate independently (offline), eliminating the need for internet connectivity. This approach reduces operational costs and simplifies maintenance while ensuring continuous functionality even in remote or rural mosque locations. The integration of audible alerts and GPS tracking provides dual-layer protection-detering theft through immediate noise generation and enabling asset recovery through location monitoring.

3.4 Prototype Fabrication

The fabrication process involved both mechanical construction and electronic integration. The structural design of the donation box was created using CAD software (Autodesk

Inventor), allowing for precise dimensioning and optimization of internal space for component placement. The box was fabricated using mild steel flat bars, selected for their strength, affordability, and resistance to tampering. The fabrication stages included cutting, welding, drilling, and assembly. After structural completion, the box was painted with an anti-corrosion coating to enhance durability and aesthetics.

Electronic components were installed within the box. The Arduino Uno, vibration sensor, GPS module, buzzer, and battery were interconnected using jumper wires, ensuring secure connections and compact arrangement. The wiring was carefully organized using cable ties to prevent short circuits and overheating. Finally, the assembled prototype was calibrated and tested for electrical continuity, sensor responsiveness, and power stability before moving to full system testing.

3.5 Testing Procedures

To verify the functionality, reliability, and usability of the system, a series of testing procedures were conducted. The tests were divided into two main categories: technical performance evaluation and user-based assessment.

3.6 Technical Performance Evaluation

The following tests were performed in a controlled environment to measure the system's operational efficiency:

- i. Vibration Sensitivity Test: Evaluated the sensor's ability to detect various levels of physical disturbance.
- ii. Alarm Response Time Test: Measured the time between detection and buzzer activation to ensure immediate response.
- iii. GPS Accuracy Test: Determined the positional accuracy in both indoor and outdoor environments.
- iv. Battery Endurance Test: Measured the system's operating duration on a single full charge under normal use.

3.7 User Evaluation and Feedback

After technical verification, user testing was conducted involving mosque committee members and congregants. A structured questionnaire was distributed to assess perceptions of the system's ease of use, reliability, design practicality, and security effectiveness. Quantitative data were analyzed using descriptive statistics, while qualitative comments were examined through thematic analysis to identify patterns and areas for future improvement. In conclusion, the methodology used in this project ensures that the development of the mosque donation box security system is carried out in a planned, systematic, and practical engineering-based approach. Through the combination of mechanical, electronic, and software aspects, this system is capable of enhancing the security level of the donation box and adding value to mosque management in terms of safety and operational efficiency.

4.0 RESULTS AND DISCUSSION

This section presents the results obtained from both hardware testing and user

evaluation of the developed Safe and Secure Mobile Donation Box System for Mosques. The findings are analyzed and discussed in relation to the project's objectives, which were to (i) design and develop a secure donation box system, (ii) integrate vibration, alarm, and GPS tracking features, and (iii) evaluate the performance and usability of the prototype.

The evaluation process consisted of two main phases:

- a. Technical Testing – conducted under controlled conditions to measure the system's operational performance.
- a. User Evaluation – performed through a structured survey involving mosque committees and congregants to assess user satisfaction and acceptance

The results are presented in Tables 2 , followed by analytical discussion highlighting the system's strengths, limitations, and areas for improvement.

4.1 Hardware Testing Results

Hardware testing focused on validating the core functional components—namely, the vibration sensor, buzzer alarm, GPS module and power supply system. Each component was tested individually and in integrated mode to ensure proper functionality.

4.2 Vibration Detection Performance

The vibration detection function was tested by applying controlled disturbances to the donation box at different intensity levels. The sensor demonstrated consistent responsiveness, activating the alarm within less than one second after detection. Table 2 summarizes the results of the vibration sensitivity test.

Table 2: Vibration Sensor Performance Test

Test Condition	Sensor Response	Buzzer Activation	Response Time (s)
Light vibration	Detected	Activated	0.95
Moderate vibration	Detected	Activated	0.89
Strong vibration	Detected	Activated	0.82

The results indicate that the vibration sensor effectively detected tampering or movement under all test conditions, with an average response time of 0.89 seconds, meeting the system's design target of under two seconds.

4.3 Alarm Activation Performance

Upon detection of vibration, the buzzer alarm produced an immediate and continuous audible signal. The sound intensity was measured using a digital sound level meter and averaged 90 dB, which is sufficient to alert individuals within the mosque vicinity. The alarm stopped automatically once the system was reset, confirming correct logic operation. This performance validates the real-time response capability of the system, achieving its goal of deterring theft through immediate auditory feedback.

4.4 GPS Tracking Accuracy

The GPS module was tested in both open-air and indoor environments to evaluate positional accuracy and signal reliability. Table 3 shows the recorded accuracy data.

Table 3: GPS Module Accuracy Results

Environment	Average Accuracy (m)	Signal Delay (s)	Remarks
Open area	5–8	1.5	Stable and accurate
Semi-covered area	10–15	2.0	Slight delay due to partial obstruction
Indoor (enclosed)	20–30	3.5	Occasional signal loss; recovered after short delay

The GPS system achieved 5–10 meters accuracy in open areas, aligning with standard GPS module performance. Accuracy decreased in enclosed areas due to signal attenuation, a known limitation of GPS technology. Nevertheless, the system maintained functional tracking capability after a short recovery period.

4.5 Power Supply Endurance

The system used a 3.7V rechargeable lithium-ion battery. Continuous operation tests were conducted under two conditions:

- Normal Monitoring Mode (no alarm activation)
- Active Mode (frequent vibration and alarm triggers)

Table 4: Battery Endurance Test

Operating Mode	Average Duration (hours)	System Status
Normal Monitoring	7.0	Stable operation
Active Alarm Mode	5.0	Reduced due to power draw from buzzer and GPS

The results indicate that the system can operate continuously for 5–7 hours per charge. Although sufficient for short-term deployment, future versions could incorporate solar charging or higher-capacity batteries to enhance endurance.

4.6 Prototype Field Testing

Field testing was conducted at a local mosque in Merlimau to simulate a real operational environment. During testing, the donation box was placed in its typical location within the prayer hall. The box was subjected to controlled shaking, movement, and simulated theft attempts. The vibration sensor accurately detected each disturbance and triggered the buzzer alarm instantly. Simultaneously, the GPS coordinates were transmitted to the serial monitor, confirming system synchronization and reliability.



Figure 1: Field Testing Setup of the Donation Box Prototype

The prototype successfully demonstrated practical functionality and robustness, fulfilling its intended operational objectives.

a. User Evaluation Survey

A total of 35 respondents participated in the post-project evaluation survey, including mosque committee members, regular congregants, and community representatives. The survey employed a five-point Likert scale ranging from 1 (*Strongly Disagree*) to 5 (*Strongly Agree*), assessing usability, security effectiveness, design, and perceived usefulness.

b. Respondent Demographics

Table 5: Summary of Respondent Demographics

Category	Number	Percentage (%)
Gender		
Male	26	74.3
Female	9	25.7
Age Group		
< 20 years old	3	8.6
21–30 years old	13	37.1
31–40 years old	14	40.0
> 40 years old	5	14.3
Respondent Role		
Mosque Committee Member	12	34.3
Mosque Congregant	15	42.9
General Public	8	22.8
Have Seen/Tested the System		
Yes	30	85.7
No	5	14.3

The findings show that the majority of respondents consist of mosque congregants and committee members aged between 21 and 40 years. This indicates that the respondent group has experience and understanding of the donation box security requirements.

c. Mean Score Analysis

The survey used a **1–5 Likert scale** to assess the level of agreement with ten (10) main statements related to the design and function of the donation box security system. The mean value (average) for each statement is summarised in Table 6.

Table 6: Mean Analysis of Likert Scale (Q1–Q10)

No	Evaluation Item	Mean
Q1	The box design is sturdy and attractive	4.09
Q2	Easy to move and suitable for portable use	4.37
Q3	The security system functions well	4.26
Q4	The vibration sensor detects movement accurately	4.14
Q5	The buzzer gives a clear and fast warning	3.86
Q6	The GPS functions well in tracking the box location	3.34
Q7	The system is easy for users to understand	4.20
Q8	The box structure is durable	4.17
Q9	The system enhances the security of the donation box	4.36
Q10	Suitable for use in mosques/surau (prayer rooms)	4.26

Overall Average: 4.10

Percentage of Positive Responses (≥ 4): 82.6%

Overall, respondents rated the system positively, particularly in terms of ease of use, safety, and reliability. The lower score for battery duration suggests an area requiring technical enhancement.

d. User Satisfaction and Recommendation

Over 82.6% of respondents indicated satisfaction with the prototype's overall performance. Furthermore, 86% stated they would recommend the system for implementation in other mosques or public institutions.

e. Qualitative Feedback and Discussion

In addition to numerical survey data, open-ended feedback was collected to capture deeper insights into user perceptions. Common themes that emerged include:

- **Enhanced Security Awareness:** Users acknowledged that the system increased vigilance among congregants and committee members.
- **Design Improvements Suggested:** Respondents recommended adding GSM-based SMS alerts and solar-powered charging to extend system autonomy.
- **Ease of Use:** Participants reported that the system was easy to operate but suggested providing basic training for mosque staff.
- **Aesthetic and Portability:** Users appreciated the compact, mobile design and the strong structural construction of the box.

The overall qualitative findings support the conclusion that the prototype not only meets its technical objectives but also aligns with user expectations for practicality and convenience. The results show that the average score for the design aspect (Q1 and Q8) is 4.09 and 4.17, respectively, indicating that respondents find the produced box structure to be sturdy, durable, and attractive. The use of mild steel material also instils confidence regarding the aspect of physical security. For the security system function, the mean value for Q3 (overall function) is 4.26, while Q4 (vibration sensor) records 4.14. This shows that the system successfully detects any movement effectively. However, the GPS performance (Q6) obtained a mean of 3.34, which is slightly lower compared to other items. This suggests that the location tracking function still needs improvement, possibly due to signal coverage factors or data processing time.

The system's usability (Q7) received a high score of 4.20, indicating that the system's interface and operation are easy to understand for ordinary users. Respondents also provided positive feedback on the system's effectiveness (Q9 = 4.34) and its suitability for use in mosques/surau (Q10 = 4.26). Respondents also provided several suggestions for improvement, such as:

- a. Adding GSM/SMS connectivity for immediate notification to the mosque administration.
- b. Increasing battery capacity or adding a solar panel for operational longevity.
- c. Improving the physical locking mechanism on the box structure.
- d. Providing a waterproof cover for outdoor use.

General comments from respondents indicate that the system is considered practical, innovative, and provides confidence in protecting mosque donation collections. Overall, the survey results indicate that the developed portable donation box security system received positive user acceptance with an overall average score of 4.10. The system is proven to enhance security, is easy to use and is suitable for application in mosques or surau. Although the GPS performance needs improvement, the system as a whole has achieved the project objectives and has the potential to be developed towards an integrated IoT system with automatic notifications and sustainable energy through solar panels.

5.0 CONCLUSIONS AND RECOMMENDATIONS

This project successfully achieved its main objective of designing and developing a Safe and Secure Mobile Donation Box System for Mosques. The system integrates both mechanical strength and electronic intelligence, providing an innovative solution to the recurring issue of mosque donation box theft. By combining durable steel construction with Arduino-based automation, the prototype effectively enhances safety, reliability, and user confidence in donation collection systems within religious facilities. The implementation of the Arduino Uno microcontroller, vibration sensor, buzzer alarm, and GPS tracking module created a dual-layer protection mechanism that enables immediate local response and location monitoring.

The system's operational testing demonstrated high reliability, with vibration detection accuracy exceeding 95%, buzzer response time below one second, and GPS tracking precision of 5–10 meters in open environments. These results confirm that the integration of

low-cost embedded components can provide practical, efficient, and replicable security solutions. User evaluation involving 35 respondents comprising mosque committee members, congregants, and community representatives showed strong acceptance and satisfaction, with over 82% rating the system positively and 86% recommending it for adoption in other mosques. Respondents commended the system for its enhanced safety, simple operation, and compact design. Constructive feedback highlighted opportunities to further improve battery capacity, introduce solar charging, and integrate GSM-based notification systems for real-time alerts. From an academic perspective, this project reinforces the relevance of engineering design methodology and IoT-based innovation in addressing real-world community challenges. It also aligns with the principles of the Situational Crime Prevention Theory (Clarke, 1980) and the Technology Acceptance Model (Davis, 1989), which emphasize practical deterrence measures and user confidence in adopting technology-driven solutions.

In conclusion, the *Safe and Secure Mobile Donation Box System for Mosques* represents a valuable advancement in community safety engineering. It demonstrates how affordable, modular technology can significantly reduce theft risk, improve public trust, and enhance the operational efficiency of religious institutions. The project's outcomes not only contribute to community welfare but also provide an educational framework for future smart security systems within polytechnic engineering programs.

5.1 Recommendations for Future Work

While the current prototype has proven its effectiveness, several enhancements are recommended to improve system performance and sustainability:

- a. Integration of GSM/IoT Notification System Implement GSM or Wi-Fi modules to send real-time alerts to mosque administrators via SMS or mobile application.
- b. Solar-Powered Charging System Incorporate a compact solar panel to ensure continuous operation and reduce dependence on manual battery charging.
- c. Increased Battery Capacity and Power Management Use higher-capacity rechargeable batteries with efficient power regulation to extend operational duration.
- d. Autonomous Line-Tracking Mechanism Introduce line-tracking sensors to allow autonomous movement of donation boxes between collection points within the mosque.
- e. Data Logging and Analytics Develop a data recording feature to log vibration events and location history for analysis of theft attempts or misuse.
- f. Enhanced Enclosure Design Explore advanced materials such as aluminum alloy or composite panels for improved strength-to-weight ratio.

By implementing these recommendations, the system can evolve into a more comprehensive, autonomous, and sustainable solution suitable for mass adoption across religious and public institutions.

REFERENCES

Ahmad, H. F. (2022). *Dua lelaki terlibat kes pecah rumah, curi tabung masjid diberkas. Utusan Malaysia*. <https://www.utusan.com.my>

- Alimin, N. A. (2022). *Remaja curi tabung masjid: Hukuman jel, denda diketepikan*. *Sinar Harian*. <https://www.sinarharian.com.my>
- Azhar, A. (2022). *Tabung masjid pintar [Smart mosque donation box]*. Final Year Project Report, Politeknik Malaysia.
- Banzi, M., & Shiloh, M. (2014). *Getting started with Arduino*. Maker Media, Inc.
- Clarke, R. V. (1980). *Situational crime prevention: Theory and practice*. *British Journal of Criminology*, 20(2), 136–147.
- Davis, F. D. (1989). *Perceived usefulness, perceived ease of use, and user acceptance of information technology*. *MIS Quarterly*, 13(3), 319–340.
- Gubbi, J., Buyya, R., Marusic, S., & Palaniswami, M. (2013). *Internet of Things (IoT): A vision, architectural elements, and future directions*. *Future Generation Computer Systems*, 29(7), 1645–1660.
- Henderson, M., & Anderson, K. (2020). *GPS tracking technology and stolen asset recovery rates*. *Journal of Security Studies*, 15(3), 234–248.
- Kumar, A., & Patel, S. (2019). *Piezoelectric vibration sensors for security applications: Performance evaluation*. *IEEE Sensors Journal*, 19(12), 4523–4531.
- Nordin, A. H. (2022). *Pura-pura musafir sebelum pecah tabung masjid*. *Harian Metro*. <https://www.hmetro.com.my>
- Rosli, W. N. W. (2010). *Wireless based home security with automation system*. Final Year Project Report, Universiti Malaysia Pahang.

TRACK 2: COMMERCE

Implementation and Evaluation Of E-Scorify@Inres : A Phased Digital Scoring System At Commerce Department, Politeknik Merlimau Melaka

Suzana Binti Baharudin¹, Maria Binti Mohd Yatim¹, Fakrul Nur Aiman Bin Raman²

¹Jabatan Perdagangan, Politeknik Merlimau Melaka
77300 Merlimau, Malacca

²Fakulti Teknologi Kejuruteraan, Universiti Tun Hussein Onn Malaysia
Hab Pendidikan Tinggi Pagoh, Km 1 Jalan Panchor, 84600 Pagoh, Muar, Johor

*Corresponding author : suzana@pmm.edu.my

Abstract This study presents the development and implementation of e-Scorify@InRes, a digital scoring system aimed at improving efficiency, transparency, and accuracy in evaluating participants of the InRes competition, a research and innovation event for diploma students at the Commerce Department, Politeknik Merlimau Melaka. The primary objective was to address limitations of manual scoring, which is often time-consuming and susceptible to calculation errors. The development followed a two-phase methodology. Phase 1 involved designing an Excel-based scoring system to validate the competition's scoring framework. This system automated calculations for weighted criteria across three categories: Innovation, Research, and Poster & Booth. A pilot test conducted during an internal competition showed notable improvements in processing speed and reduced errors compared to manual tabulation methods. Phase 2 advanced the system into a web-based solution by integrating Google Forms, Google Sheets, Power BI, and Google Sites. Google Forms was used for score collection, while Google Sheets handled automated computations. Power BI provided real-time analytics and visual dashboards, which were then published on Google Sites for centralized access. This integration enabled live ranking updates, transparent score displays, and minimized administrative workload during the event. User feedback indicated high satisfaction, emphasizing ease of use, real-time access to data, and improved reliability as key benefits. Overall, the findings demonstrate that e-Scorify@InRes successfully enhanced the scoring process, offering a scalable and adaptable solution for academic competitions seeking efficient and transparent evaluation systems.

Keywords: Digital Scoring; Student Innovation; Assessment System; Real-Time Scoring; User Satisfaction

1. INTRODUCTION

Academic competitions play a crucial role in fostering innovation, critical thinking, and problem-solving skills among students. These competitions often rely on accurate, transparent, and fair evaluation mechanisms to ensure credibility and participant satisfaction. Traditionally, the Innovation and Research (InRes) competition at Politeknik Merlimau Melaka employed manual scoring methods, which, while straightforward, introduced several operational challenges (Lee & Penyelidikan, n.d.). These included prolonged processing times, susceptibility to human calculation errors, and delays in result announcements. Furthermore, the absence of automated checks limited transparency and

occasionally led to disputes regarding scoring accuracy (“Assessment of Learning in Online Academic Programs from the Digital Transformation Impelled by Covid-19,” 2023).

The increasing demand for efficiency and fairness in academic evaluations has driven the adoption of digital scoring systems in various educational settings (Islami et al., 2024). However, small- and medium-scale academic events often face resource constraints, resulting in continued reliance on semi-manual or spreadsheet-based solutions that lack real-time interactivity and scalability (Slade et al., 2024). To overcome these limitations, e-Scorify@InRes was conceptualized and developed as a structured, phased digital scoring solution. The primary objectives of this system are to automate score computation, enable real-time result visualization, and standardize evaluation criteria to ensure fairness and accuracy (Gaftandzhieva et al., 2024).

This paper outlines the development and implementation of e-Scorify@InRes in two phases: Phase 1, which involved an Excel-based validation of scoring logic and automation; and Phase 2, which transitioned the system into a cloud-based environment integrating Google Sites, Google Forms, Google Sheets, and Power BI for real-time analytics and dashboards. Additionally, the study evaluates the system’s impact on performance, focusing on key metrics such as efficiency, transparency, and usability, while highlighting its potential for broader application in academic and institutional competitions (De La Torre et al., 2022).

2. LITERATURE REVIEW

Digital scoring solutions have increasingly become an essential component in educational and competitive settings due to their ability to enhance efficiency, accuracy, and transparency in the evaluation process (He et al., 2024). Automated scoring systems minimize the likelihood of human error by eliminating manual calculations and standardizing evaluation criteria across all participants (Hadzhikoleva et al., 2025). This not only improves fairness but also reduces administrative workload during high-stakes events. Furthermore, the incorporation of cloud-based technologies and advanced analytics tools, such as Power BI, strengthens these systems by enabling real-time data visualization, interactive dashboards, and automated reporting (Panduro-Ramírez et al., 2021). Such features foster transparency and allow stakeholders—including participants, evaluators, and organizers—to monitor progress dynamically (Santos et al., 2024).

Before the adoption of modern digital scoring systems, many institutions relied heavily on traditional manual scoring methods, including paper-based evaluation sheets, manual tallying, and verbal communication between evaluators. These conventional approaches often resulted in delays, inconsistencies, and a higher probability of human error, especially in competitions involving multiple categories or large numbers of participants (Rahman et al., 2020). Manual documentation also posed challenges in terms of data retrieval and archival, making it difficult for organizers to verify scores, track performance trends, or prepare post-event reports efficiently. Additionally, the absence of automated validation mechanisms increased the likelihood of miscalculations and subjective interpretation of scoring rubrics, which could undermine the fairness and credibility of the event (Kumar & Idris, 2022). As events grew more complex, these manual methods struggled to keep pace, highlighting the need for streamlined and scalable digital solutions.

In recent years, semi-digital tools such as Excel-based scoring templates, forms, and locally

stored spreadsheets have emerged as transitional alternatives, appreciated for their accessibility and cost-effectiveness (Fernandez et al., 2020; Meletiadou, 2023). However, many smaller-scale academic events, particularly at institutional levels, continue to depend on these semi-digital tools (Nurbekova et al., 2023; Wahyuni & Haeruddin, 2025). While they provide basic automation and easier data organization, these systems have notable limitations, including limited multi-user interactivity, lack of real-time updates, and reduced scalability for integration with advanced analytics platforms (Isaias et al., 2023). They also rely heavily on manual consolidation and are susceptible to version-control issues when multiple evaluators input scores simultaneously.

The development of e-Scorify@InRes addresses these limitations by implementing a structured, scalable, and cloud-integrated scoring platform tailored to academic competitions. Unlike conventional manual or semi-digital methods, this system combines the accessibility of Google Forms and Google Sheets with the visualization capabilities of Power BI, providing an integrated solution for real-time scoring, transparency, and data-driven decision-making (Rodríguez-Rad et al., 2023).

3. METHODOLOGY

The development of e-Scorify@InRes was conducted using a two-phase methodology, designed to ensure accuracy, usability, and scalability. The methodology also includes a structured scoring framework that aligns with the competition objectives. Both phases are detailed as follows:

Phase 1: Excel-Based Scoring System

The first phase focused on validating the scoring structure through the development of an Excel-based scoring system. This phase began with defining the evaluation framework, which consisted of three main categories: Innovation, Research, and Poster & Booth. Each category included specific evaluation criteria with assigned weightage to ensure fair and comprehensive assessment. For instance, the Innovation category focused on creativity, practicality, and commercialization potential; the Research category emphasized originality, methodological rigor, and contribution to knowledge; while Poster & Booth assessed visual presentation quality, clarity of content, and engagement level.

Once the scoring framework was finalized, an automated Excel template was designed to calculate scores based on weighted criteria. Automated formulas were implemented to minimize manual calculation errors and speed up the tabulation process. The workflow for this phase included four key steps:

1. Criteria Selection and Weight Distribution – Establishing the evaluation components and assigning proportional weights.
2. Template Development – Creating an Excel sheet with embedded formulas for score computation.
3. Pilot Testing – Using sample data to validate the system's accuracy and reliability.
4. Performance Evaluation – Comparing results with manual methods to ensure improvements in efficiency and error reduction.

The pilot test demonstrated significant improvements in processing speed and a substantial reduction in human errors compared to traditional manual scoring approaches. This validation confirmed that the scoring framework was robust enough for implementation in a web-based system.

Phase 2: Web-Based Scoring and Visualization Using Google Sites, Google Forms, and Power BI

Building on the validated framework, the second phase focused on creating a cloud-based scoring and visualization system that was user-friendly and accessible on multiple devices. This phase utilized Google Sites as the main platform, integrated with Google Forms for data input and Power BI for real-time visualization. The process began by designing a Google Form where evaluators could submit scores for all categories, with required fields and automated validation to prevent errors. Responses were linked to Google Sheets, which served as a central database for scoring data. To enhance real-time analytics and transparency, a Power BI dashboard was developed and connected to the Google Sheet, generating dynamic visualizations such as team rankings, category-based breakdowns, and score distributions. This dashboard was embedded into Google Sites, creating a centralized portal where evaluators could access the scoring form, view live rankings, and refer to competition guidelines.

The workflow of this phase ensured seamless data integration and real-time updates. When evaluators submitted scores via Google Forms, the data automatically populated in Google Sheets, which was then processed by Power BI to update dashboards instantly on Google Sites. Multiple testing iterations were conducted to validate data synchronization, ensuring accurate and immediate score computation. This approach significantly enhanced the efficiency, accuracy, and transparency of the scoring process compared to traditional methods. Additionally, it eliminated the need for complex local installations and provided a scalable solution that could be accessed from any internet-enabled device.

4. RESULT AND DISCUSSION

This section presents the outcomes of the development and implementation of the scoring system in two phases: Phase 1 (Excel-Based System) and Phase 2 (Google Sites Integration with Google Forms and Power BI). The results highlight improvements in efficiency, transparency, and evaluator satisfaction, supported by pilot testing data and user feedback.

4.1 Validation Of Scoring Framework

The scoring framework was designed to ensure fairness and alignment with competition objectives. Table 1, Table 2 and Table 3 illustrate the weightage distribution for each evaluation category and its associated criteria. Innovation emphasized creativity and feasibility, Research focused on originality and methodology, while Poster & Booth prioritized presentation and engagement.

Table 1: Scoring Distribution for Best Poster Award

Criteria	Weightage (%)
Theme	2
Creativity and Physical Appeal	3
Information Availability and Quality	4
Visual Impact/Overall Impression	4
Presentation	2
Effective use of any Promotional Materials	2
Professionalism	3

Table 2: Scoring Distribution for Best Innovation Award

Criteria	Weightage (%)
Project Functionality	20
Complexity and Quality	15
Sustainability, Social and Environment Impact	25
Marketability or Ready to Be Commercialized	25
Appearances & Professionalism	5
Effective Presentation	5
Ability to Answer Question	5

Table 3: Scoring Distribution for Best Research Award

Criteria	Weightage (%)
Abstract	10
Introduction	10
Problem Statement	10
Objective and Significant	10
Literature Review	10
Methodology	10
Result	10
Discussion	10
Conclusion	5
Appearances & Professionalism	5
Effective Presentation	5
Ability to answer question	5

The structured weightage ensured balanced consideration of technical and presentation aspects, as agreed upon by the organizing committee.

4.2 Phase 1: Excel – Based Scoring Results

The first phase focused on developing an Excel-based automated scoring system to replace traditional manual scoring. The main goal was to reduce human errors, improve efficiency, and ensure consistency in score calculation during competitions. The system utilized predefined formulas and weighting mechanisms to automatically compute final scores based on evaluator input, minimizing the need for manual intervention.

4.2.1 Scoring layout comparison: manual vs. Excel – based scoring layout

Before the introduction of the automated Excel-based system, the manual scoring method relied on paper-based forms and manual tabulation, which was time-consuming and prone to calculation errors. Scores were recorded by hand, and final rankings required multiple cross-checks to ensure accuracy.

In contrast, the Excel-based scoring layout streamlined the process by centralizing all inputs and calculations in a single digital sheet. The layout featured predefined formulas for weighted scores, automated ranking, and conditional formatting to highlight top-performing teams. This eliminated the need for manual computation and significantly improved scoring efficiency.

Figure 1 illustrates the comparison between the manual scoring layout as in Figure 1(a) and the Excel-based scoring layout as shown in Figure 1(b). The manual layout consisted of static tables for score entry, requiring manual addition and verification, whereas the Excel template included automated score computation, ranking columns, and a summary dashboard. This comparison highlights the significant improvement in usability, efficiency, and transparency achieved through the digital approach.




Figure 1: Comparison of Manual vs. Excel – Based Scoring Layout

4.2.2 Performance comparison: manual vs. Excel – based system

One of the primary objectives of Phase 1 was to reduce scoring time and eliminate errors through automation. Table 4 compares the manual scoring process with the Excel-based scoring system in terms of average time per submission and error rate.

reduced by over 65%, and immediate leaderboard generation improved transparency for participants and evaluators. Feedback collected after both events highlighted increased satisfaction among judges, who appreciated the system's speed and error-free computation. Participants also expressed confidence in the scoring process due to real-time updates and structured evaluation criteria.

4.2.5 Evaluator Feedback On Phase 1

Evaluator feedback was collected to assess usability and satisfaction with the Excel-based system. Table 5 summarizes the percentage of positive responses for key aspects such as ease of use, speed, transparency and also time management.

Table 5: Evaluator Feedback on Excel – Based System

Criteria	Positive Response (%)
Ease of Use	92
Speed	95
Transparency	88
Time Management	95

4.3 Phase 2: Google Sites Integration With Google Forms And Power BI

In Phase 2, the scoring process was transitioned to a web-based environment for greater accessibility and real-time visualization. The system integrated Google Forms for score input, Google Sheets for automated calculations, Power BI for analytics, and Google Sites as a central hub for publishing dashboards and competition updates. Table 6 outlines the integration workflow.

Table 6: Phase 2 Integration Workflow

Criteria	Function
Google Form	Collect Evaluator Score
Google Sheets	Store Responses and Calculate weighted scores
Power BI	Visualize real-time scoring and rankings
Google Sites	Display dashboard and Competition updates

4.4 Comparison of Phase 1 vs. Phase 2

The evaluation of the scoring systems across different phases highlights significant improvements in accessibility, real-time functionality, automation, and transparency.

In Phase 1, the Excel-based system provided a local solution that improved calculation accuracy compared to manual scoring. However, accessibility was limited to individual devices, and real-time updates were not possible since data consolidation still required manual intervention. Automation in this phase was partial, focusing primarily on weighted

score computation, while visualization and summary reporting remained manual. Transparency was moderate, as results could only be shared after processing, which delayed stakeholder visibility.

Conversely, Phase 2 introduced a Google Sites-integrated solution, which was fully web-based and accessible from any location, ensuring greater convenience for judges and organizers. Real-time updates became a core feature, allowing immediate score aggregation and live result visualization. The automation level was significantly enhanced, covering both calculations and dashboard integration through tools like Google Sheets and Power BI. This eliminated human error and streamlined data handling. Transparency reached its peak, as all stakeholders could monitor live scoring dashboards, promoting trust and fairness in the competition process. Table 6 illustrate the comparison of the phase 1 and phase 2.

Table 7: Comparison of Phase 1 and Phase 2

Criteria	Phase 1: Excel - Based System	Phase 2: Google Sites Integration
Accessibility	Local (PC-based)	Web-based, accessible anywhere
Real-Time Updates	No	Yes
Automation Level	Medium (calculations)	High (calculations + visualization)
Transparency	Limited	High (live dashboards)

5. CONCLUSION

The development and implementation of e-Scorify@InRes successfully addressed the limitations of manual scoring systems. Phase 1 validated the scoring framework and demonstrated efficiency improvements using Excel automation, while Phase 2 introduced a fully integrated, cloud-based solution with Google Sites, Google Forms, and Power BI, enabling real-time updates, transparency, and scalability. User satisfaction was exceptionally high, reinforcing the system's reliability and usability.

Future work includes integrating advanced analytics, AI-driven scoring recommendations, and mobile app support to further enhance functionality. The success of e-Scorify@InRes highlights the potential for digital transformation in academic assessments, setting a model for adoption in other educational institutions.

ACKNOWLEDGMENT

The authors would like to thank all individuals and institutions who supported and contributed to this study. Appreciation is also extended to colleagues and family for their encouragement throughout the research.

REFERENCES

Assessment of learning in online academic programs from the digital transformation impelled by Covid-19. (2023). *Revista de Ciencias Sociales*.

<https://doi.org/10.31876/rcs.v29i1.39761>

- De La Torre, E. M., Perez-Encinas, A., & Gomez-Mediavilla, G. (2022). Fostering Sustainability through Mobility Knowledge, Skills, and Attitudes. *Sustainability*, 14(3), 1349. <https://doi.org/10.3390/su14031349>
- Fernandez, K., Ruderman, M., & Clerkin, C. (2020). Building Leadership resilience: The CORE Framework. <https://doi.org/10.35613/ccl.2020.2043>
- Gaftandzhieva, S., Docheva, M., Doneva, R., Pashev, G., & Totkov, G. (2024). Assessing the Digital Level in Educational Institutions: Formal Model and Software Prototype. *TEM Journal*, 1303–1318. <https://doi.org/10.18421/TEM132-45>
- Hadzhikoleva, S., Hadzhikolev, E., Gaftandzhieva, S., & Pashev, G. (2025). A conceptual framework for multi-component summative assessment in an e-learning management system. *Frontiers in Education*, 10. <https://doi.org/10.3389/feduc.2025.1656092>
- He, L., Dongyang, H., Wan Feng, Y., Zhuo, Z., & Yuyang, Z. (2024). Research on the Digital Transformation and Innovative Pathways of Education Management and Evaluation Systems in the Information Age. *Modern Management Science & Engineering*, 6(3), p82. <https://doi.org/10.22158/mmse.v6n3p82>
- Isaias, P., Miranda, P., & Pifano, S. (2023). E-Assessment Systems: An Evaluation Framework from the Perspective of Higher Education Experts. 2023 International Symposium on Computers in Education (SIIE), 1–6. <https://doi.org/10.1109/SIIE59826.2023.10423677>
- Islami, S., Ambiyar, A., Sukardi, S., Zaus, A. A., Zaus, A. A., & Zaus, M. A. (2024). Innovative Tech-Savvy Education: Designing a Smart Assessment System. *Journal of Applied Engineering and Technological Science (JAETS)*, 6(1), 537–549. <https://doi.org/10.37385/jaets.v6i1.5861>
- Meletiadou, E. (2023). Leadership for Sustainability in Higher Education Amidst the COVID-19 Crisis (pp. 1–23). <https://doi.org/10.4018/978-1-6684-6172-3.ch001>
- Nurbekova, Z., Aimicheva, G., Baigusheva, K., Sembayev, T., & Mukametkali, M. (2023). A Decision-Making Platform for Educational Content Assessment Within a Stakeholder-Driven Digital Educational Ecosystem. *International Journal of Engineering Pedagogy (IJEP)*, 13(7), 4–23. <https://doi.org/10.3991/ijep.v13i7.41689>
- Panduro-Ramírez, J., Alanya-Beltrán, J., Soto-Hidalgo, C., & Ruiz-Salazar, J. (2021). Student Assessment in the Digital Age: A Systematic Review in Latin America. *Espirales Revista Multidisciplinaria de Investigación*, 5(36), 48–66. <https://doi.org/10.31876/er.v5i36.779>
- Rodríguez-Rad, C. J., Revilla-Camacho, M.-Á., & Sánchez-del-Río-Vázquez, M.-E. (2023). Exploring the Intention to Adopt Sustainable Mobility Modes of Transport among Young University Students. *International Journal of Environmental Research and Public*

- Health, 20(4), 3196. <https://doi.org/10.3390/ijerph20043196>
- Santos, J. V., Ramos, L., & Mallari, M. (2024). Assessment of Facility Management Performance: A Basis for Digitalizing Reporting Systems in Educational Institutions. *Journal of Interdisciplinary Perspectives*, 3(2). <https://doi.org/10.69569/jip.2024.0651>
- Slade, C., Mahon, K., Lynagh, J., McGrath, D., Sheppard, K., Ahsan, S. Q. M., & Benson, K. (2024). A pedagogical evaluation of an institution's digital assessment platform (DAP): Integrating pedagogical, technical and contextual factors. *Australasian Journal of Educational Technology*. <https://doi.org/10.14742/ajet.9448>
- Wahyuni, N. G. A. P. E. S., & Haeruddin. (2025). Pengembangan Digital Assessment untuk Pemahaman Konsep Dasar IPAS di SD Kota Palu. *Jurnal Ilmiah Profesi Guru (JIPG)*, 6(1), 63–72. <https://doi.org/10.30738/jipg.vol6.no1.a18681>

Amalan Simpan Kira Dan Asas Perakaunan Dalam Kalangan Peniaga Kedai Makan Di Sekitar Merlimau, Melaka

***Norhayah binti Sabtu, Nur Iman Batrisyia binti Faizulhizam, Nurul Nabila binti Omar, Noraida Mohd Faizal, Nurul Aqilah binti Abdul Rashid**

Politeknik Merlimau Melaka
KM2.5, Jalan Merlimau-Jasin
77300 Merlimau, Melaka

[*norhayah@pmm.edu.my](mailto:norhayah@pmm.edu.my)

Abstrak Kajian ini bertujuan untuk menilai tahap amalan simpan kira dan asas perakaunan dalam kalangan peniaga kedai makan di sekitar Merlimau, Melaka. Pengurusan kewangan yang baik melalui rekod simpan kira yang sistematik merupakan faktor penting dalam menjamin kelangsungan dan perkembangan sesebuah perniagaan kecil. Namun, masih terdapat peniaga yang tidak mengamalkan sistem perakaunan yang betul akibat kekangan pengetahuan dan kemahiran asas perakaunan. Kajian ini menggunakan kaedah kuantitatif dengan mengedarkan soal selidik kepada 65 orang responden yang terdiri daripada peniaga kedai makan di kawasan Merlimau. Data dianalisis menggunakan perisian SPSS bagi mendapatkan analisis deskriptif dan inferensi. Dapatan menunjukkan bahawa majoriti responden mempunyai tahap kesedaran sederhana terhadap kepentingan simpan kira, tetapi tahap pengamalan sebenar masih rendah. Faktor utama yang dikenal pasti ialah kekurangan pengetahuan asas perakaunan dan kebergantungan kepada kaedah tradisional. Hasil kajian ini diharapkan dapat menjadi panduan kepada agensi kerajaan dan institusi latihan untuk merangka program bimbingan dalam meningkatkan kecekapan pengurusan kewangan usahawan kecil.

Kata Kunci: Simpan kira, asas perakaunan, peniaga kecil, pengurusan kewangan, kedai makan

1.0 PENGENALAN

Amalan simpan kira dan asas perakaunan merupakan elemen penting dalam memastikan kelangsungan dan kejayaan sesebuah perniagaan, terutamanya bagi perniagaan kecil seperti kedai makan. Dalam konteks perniagaan mikro, pengurusan kewangan yang sistematik bukan sahaja membantu peniaga mengurus hasil dan perbelanjaan dengan lebih teratur, malah turut menjadi asas kepada proses membuat keputusan yang berkesan. Menurut Heng Seai Kie (2013), simpan kira ialah proses mengelas, merekod dan merumuskan transaksi perniagaan, manakala perakaunan pula melibatkan penganalisan serta tafsiran maklumat kewangan untuk tujuan pelaporan dan keputusan pengurusan.

Dalam era globalisasi dan kemajuan teknologi hari ini, pengurusan kewangan yang efisien menjadi keperluan utama bagi memastikan perniagaan terus kompetitif. Walau bagaimanapun, kebanyakan peniaga kecil di Malaysia, khususnya di kawasan luar bandar seperti Merlimau, Melaka, masih berdepan cabaran dalam melaksanakan sistem simpan kira

yang teratur. Ramai antara mereka tidak mempunyai latihan formal dalam bidang perakaunan, dan hanya bergantung kepada kaedah manual seperti catatan dalam buku nota atau ingatan peribadi untuk merekod transaksi harian. Keadaan ini mengakibatkan kekeliruan dalam mengenal pasti keuntungan sebenar, kesukaran mengawal aliran tunai, dan kegagalan merancang strategi perniagaan dengan berkesan.

Sektor perniagaan kecil dan sederhana (PKS) memainkan peranan penting dalam menyumbang kepada pertumbuhan ekonomi Malaysia. Namun, laporan oleh Jabatan Perangkaan Malaysia (2023) menunjukkan bahawa antara punca utama kegagalan perniagaan kecil adalah kelemahan dalam pengurusan kewangan, terutamanya dalam aspek penyimpanan rekod dan perakaunan asas. Situasi ini turut berlaku dalam kalangan peniaga kedai makan di Merlimau yang kebanyakannya menjalankan operasi secara milikan tunggal dan bergantung kepada pendapatan harian tanpa sistem pemantauan kewangan yang formal. Pengurusan kewangan yang lemah boleh menjejaskan daya saing peniaga kecil dan menyukarkan mereka berkembang dalam pasaran yang semakin mencabar. Oleh itu, pengetahuan asas perakaunan amat penting agar peniaga dapat memantau kedudukan kewangan mereka secara lebih terancang. Kajian oleh Nurainsah Sepeai (2019) menegaskan bahawa pengurusan perbelanjaan yang berhemah dan efisien merupakan tunjang utama kepada kelangsungan sesebuah perniagaan kecil.

Kajian ini dijalankan bagi mengenal pasti tahap amalan simpan kira dan asas perakaunan dalam kalangan peniaga kedai makan di sekitar Merlimau, Melaka. Penyelidikan ini turut meneliti tahap kesedaran peniaga terhadap kepentingan amalan perakaunan yang betul serta faktor yang mempengaruhi pelaksanaannya. Diharapkan, melalui kajian ini, pihak-pihak berkepentingan seperti agensi kerajaan, institusi pendidikan, dan badan keusahawanan dapat mengenal pasti keperluan sebenar peniaga kecil dan merangka strategi yang sesuai untuk meningkatkan tahap literasi kewangan mereka. Secara keseluruhannya, hasil kajian ini bukan sahaja memberikan gambaran tentang keadaan sebenar amalan perakaunan dalam kalangan peniaga kedai makan di Merlimau, malah diharap dapat menjadi rujukan kepada usaha memperkukuh daya saing perniagaan kecil melalui pengurusan kewangan yang lebih sistematik dan profesional.

2.0 SOROTAN KAJIAN DAN PEMBINAAN HIPOTESIS

a) Definisi dan Kepentingan Amalan Simpan Kira

Menurut Weygandt et al. (2015), simpan kira merupakan proses merekod, menyusun dan menyimpan maklumat kewangan sesebuah perniagaan untuk tujuan pelaporan kewangan yang tepat dan boleh dipercayai. Melody Corporate House (2025) pula menekankan bahawa rekod kewangan yang baik membolehkan peniaga kecil mengesan jumlah wang masuk dan keluar, mengelakkan masalah kewangan, dan merancang perbelanjaan dengan lebih berhemah. Amalan simpan kira yang sistematik membantu dalam penyediaan laporan kewangan seperti penyata pendapatan, imbalan duga, dan penyata aliran tunai, yang merupakan asas kepada keputusan perniagaan yang lebih tepat dan berkesan.

Kajian oleh MyBizCore (2024) menunjukkan bahawa penyimpanan rekod kewangan yang baik bukan sahaja membantu dalam pengurusan dalaman, tetapi juga memudahkan

urusan percukaian dan pinjaman perniagaan. Namun begitu, ramai peniaga kecil di Malaysia masih menganggap aktiviti simpan kira sebagai tugas tambahan yang tidak penting selagi perniagaan berjalan dengan lancar (Yahya et al., 2017).

b) Tahap Literasi Kewangan dan Pengetahuan Perakaunan

Kajian oleh Mohd Abdullah Jusoh dan Nur Atiqah Abd Talib (2018) mendapati bahawa tahap literasi kewangan yang sederhana dalam kalangan usahawan mikro memberi kesan kepada tingkah laku kewangan mereka, termasuk kemahiran dalam membuat belanjawan, simpanan, serta kawalan kewangan. Ahmad et al. (2014) pula menunjukkan bahawa usahawan yang mempunyai latar belakang pendidikan dalam bidang perakaunan lebih cenderung mengamalkan sistem simpan kira yang sistematik berbanding mereka yang tidak mempunyai pendedahan formal. Kekurangan latihan dan ilmu asas ini menyebabkan ramai peniaga menjalankan operasi secara tidak teratur dan bergantung kepada ingatan atau catatan manual.

c) Cabaran Dalam Pelaksanaan Simpan Kira

Walaupun kepentingan amalan simpan kira diakui secara meluas, banyak perniagaan kecil masih gagal melaksanakannya secara berkesan. Ogoun dan Ayaundu (2020) mendapati bahawa perniagaan mikro di negara membangun sering mengabaikan rekod kewangan akibat kekangan masa, kekurangan tenaga kerja, dan persepsi bahawa sistem formal hanya sesuai untuk syarikat besar. Kajian oleh SBS Accounting (2023) turut menegaskan bahawa kaedah manual meningkatkan risiko kesilapan dalam rekod kewangan, manakala penggunaan sistem perakaunan digital boleh mengurangkan kesilapan tersebut dengan ketara.

Selain itu, Zainol dan Wan Norhayate (2016) mendapati bahawa banyak usahawan hanya mencatat transaksi apabila diperlukan, seperti semasa permohonan pinjaman atau audit cukai, menunjukkan sikap reaktif terhadap amalan simpan kira.

d) Peranan Teknologi Dalam Pengurusan Kewangan

Peralihan daripada kaedah simpan kira manual kepada sistem digital berasaskan awan seperti Xero, Wave Accounting, atau QuickBooks memberikan kelebihan dari segi masa, keselamatan data, dan kebolehcapaian (Chong, 2020). Kajian beliau mendapati penggunaan sistem perakaunan digital dapat menjimatkan masa pengurusan rekod sehingga 35% serta meningkatkan ketepatan maklumat kewangan. Namun, kekangan kos dan kurang pengetahuan teknologi menyebabkan ramai peniaga kecil tidak memanfaatkan sepenuhnya sistem ini.

3.0 METODOLOGI KAJIAN

Kajian ini dijalankan menggunakan pendekatan kuantitatif melalui kaedah tinjauan (survey) bagi mendapatkan data daripada peniaga kedai makan yang menjadi responden. Pendekatan ini dipilih kerana ia sesuai untuk mengukur tahap amalan, pengetahuan dan kesedaran responden terhadap aspek simpan kira dan asas perakaunan menggunakan instrumen berbentuk soal selidik yang dianalisis secara statistik.

3.1 Pembinaan Hipotesis Kajian

Berdasarkan sorotan kajian terdahulu dan objektif penyelidikan ini, beberapa hipotesis telah dibina untuk diuji secara empirikal:

Hipotesis 1 (H1):

Terdapat hubungan yang signifikan antara tahap pengetahuan asas perakaunan dengan amalan simpan kira dalam kalangan peniaga kedai makan di sekitar Merlimau, Melaka. (Asas: Ahmad et al., 2014; Mohd Abdullah Jusoh & Nur Atiqah Abd Talib, 2018)

Hipotesis 2 (H2):

Terdapat hubungan yang signifikan antara tahap kesedaran terhadap kepentingan rekod kewangan dengan tahap pengurusan dokumen perniagaan. (Asas: MyBizCore, 2024; Weygandt et al., 2015)

Hipotesis 3 (H3):

Terdapat hubungan yang signifikan antara penggunaan sistem perakaunan digital dengan keberkesanan pengurusan aliran tunai peniaga kedai makan. (Asas: Chong, 2020; SBS Accounting, 2023)

Kajian lepas menunjukkan bahawa pengurusan rekod kewangan yang baik membantu perniagaan meningkatkan daya saing dan kelestarian jangka panjang. Menurut Ahmad et al. (2019), keupayaan peniaga kecil dalam mengurus simpan kira secara sistematik memberi kesan positif terhadap prestasi kewangan.

3.2 Reka Bentuk Kajian

Kajian ini menggunakan reka bentuk deskriptif kuantitatif. Pendekatan ini digunakan bagi mendapatkan gambaran umum dan mengenal pasti tahap amalan simpan kira serta kefahaman asas perakaunan dalam kalangan peniaga kedai makan di sekitar Merlimau. Kaedah soal selidik digunakan sebagai instrumen utama bagi mengumpul data kerana ia lebih praktikal, menjimatkan masa, dan membolehkan pengumpulan maklumat yang seragam daripada semua responden. Soal selidik dibahagikan kepada tiga bahagian: profil responden, tahap pengetahuan asas perakaunan, dan tahap amalan simpan kira.

3.3 Populasi dan Sampel Kajian

Populasi kajian terdiri daripada peniaga kedai makan di sekitar kawasan Merlimau, Melaka yang mempunyai premis berdaftar di bawah Majlis Perbandaran Jasin (MPJ). Berdasarkan data MPJ, terdapat sebanyak 77 buah premis kedai makan yang beroperasi di kawasan tersebut. Bagi menentukan saiz sampel, pengkaji menggunakan Jadual Krejcie dan Morgan (1970). Berdasarkan jadual tersebut, bagi populasi 77 orang, saiz sampel yang sesuai ialah 65 responden. Walaupun populasi sebenar lebih besar, sebahagian peniaga tidak dapat memberikan kerjasama sepenuhnya semasa pengedaran soal selidik dijalankan. Oleh itu, sebanyak 65 peniaga kedai makan dipilih sebagai responden kajian ini.

3.4 Instrumen Kajian

Instrumen utama kajian ini ialah borang soal selidik berstruktur, yang direka berdasarkan objektif kajian dan telah disahkan oleh pakar dalam bidang perakaunan serta keusahawanan. Soal selidik ini terbahagi kepada lima (5) bahagian utama dengan tujuan seperti berikut:

Bahagian A (Data Demografi Responden): Untuk mengenal pasti latar belakang responden, termasuk jantina, umur, kelayakan akademik, jenis perniagaan, dan tempoh operasi.

Bahagian B (Maklumat Perniagaan): Bertujuan mendapatkan gambaran umum mengenai bentuk dan sumber kewangan perniagaan.

Bahagian C (Asas Perakaunan): Untuk menilai tahap kefahaman dan pengetahuan responden terhadap prinsip asas perakaunan.

Bahagian D (Pengurusan Dokumen Perniagaan): Untuk mengukur sejauh mana peniaga mengurus dan menyimpan dokumen berkaitan transaksi.

Bahagian E (Pengurusan Aliran Tunai): Untuk menilai tahap kecekapan peniaga dalam menguruskan aliran tunai perniagaan harian.

Soalan dalam Bahagian C, D, dan E menggunakan Skala Likert lima mata (1 = Sangat Tidak Setuju hingga 5 = Sangat Setuju) bagi mengukur tahap persetujuan responden terhadap setiap pernyataan.

4: KEPUTUSAN KAJIAN DAN ANALISIS

Kajian deskriptif kuantitatif ini bertujuan untuk menilai tahap amalan simpan kira dan asas perakaunan dalam kalangan 65 orang peniaga kedai makan di Merlimau, Melaka. Hasil analisis profil responden mendedahkan bahawa majoriti pengusaha adalah lelaki (67.7%) dan tergolong dalam kumpulan umur muda, iaitu 20 hingga 30 tahun (72.3%). Kebanyakan mereka memiliki kelayakan akademik pada peringkat SPM (72.31%), menjalankan perniagaan secara Milikan Tunggal (73.85%), dan telah beroperasi antara 6 hingga 10 tahun (64.62%). Analisis menunjukkan bahawa majoriti peniaga tidak pernah mendapat latihan formal sebelum memulakan perniagaan (67.44%) dan tidak mempunyai sistem simpan kira formal (65.12%). Kekurangan pengetahuan mengenai simpan kira dikenal pasti sebagai cabaran utama dalam perekodan (41.86%), walaupun majoriti responden sedar tentang kewujudan sistem perakaunan berkomputer (67.44%) dan majoriti pernah mengalami masalah kewangan (72.09%).

Dapatan kajian menunjukkan wujudnya jurang antara tahap kesedaran dan amalan sebenar dalam pengurusan kewangan. Dari segi Asas Perakaunan, peniaga menunjukkan tahap kefahaman yang tinggi, di mana mereka yakin rekod kewangan yang baik membantu perniagaan berkembang (Min 4.09) dan sedar akan kepentingan penyediaan laporan kewangan. Walau bagaimanapun, aspek pelaksanaan adalah lemah, terutamanya dalam aspek penyediaan lejar akaun, dengan skor min paling rendah direkodkan pada item Siapa

menyediakan lebar akaun dan penyata kewangan perniagaan (Min 1.95), mencerminkan kebergantungan kepada pihak luar atau pengabaian amalan formal.

Dalam Pengurusan Dokumen Perniagaan, peniaga mengamalkan penyimpanan resit yang baik (Min 4.07) dan memastikan urusan niaga direkodkan. Namun, konsistensi rekod urusan niaga adalah rendah (Min 2.37), menyokong pandangan bahawa usahawan mikro sering berdepan kekangan masa, tenaga, dan kemahiran untuk memastikan dokumentasi dilakukan secara sistematik. Begitu juga dalam Pengurusan Aliran Tunai, kesedaran adalah tinggi di mana mereka sentiasa memastikan wang perniagaan tidak digunakan untuk tujuan peribadi (Min 4.21). Sebaliknya, item Ke kerap an memasukkan tunai ke dalam akaun bank mencatatkan min paling rendah (Min 2.26), menunjukkan bahawa amalan pengurusan tunai yang formal masih tidak sistematik dan terdapat kebergantungan kepada budaya penggunaan tunai

Hipotesis 1 (H1) yang menyatakan terdapat hubungan yang signifikan antara tahap pengetahuan asas perakaunan dengan amalan simpan kira dalam kalangan peniaga kedai makan di sekitar Merlimau, Melaka, telah diterima. Analisis menggunakan ujian korelasi Pearson menunjukkan terdapat hubungan positif yang signifikan antara kedua-dua pemboleh ubah ini ($r = 0.62$, $p < 0.05$). Keputusan ini secara empirikal membuktikan bahawa peningkatan dalam pengetahuan asas perakaunan peniaga adalah berkait secara langsung dengan peningkatan dalam tahap pengamalan simpan kira yang sistematik. Walaupun peniaga mempunyai tahap kesedaran sederhana terhadap kepentingan simpan kira, tahap pengamalan sebenar masih rendah. Justeru, penemuan ini mengukuhkan dapatan bahawa kekurangan pengetahuan asas perakaunan merupakan faktor utama kelemahan dalam amalan simpan kira, dan selaras dengan kajian lepas yang menunjukkan usahawan dengan latar belakang pendidikan perakaunan cenderung mengamalkan sistem simpan kira yang lebih teratur.

Hipotesis 2 (H2), yang mengandaikan terdapat hubungan yang signifikan antara tahap kesedaran terhadap kepentingan rekod kewangan dengan tahap pengurusan dokumen perniagaan, disokong secara implisit oleh dapatan kajian. Walaupun ujian korelasi spesifik bagi hipotesis ini tidak dipersembahkan, data deskriptif menunjukkan bahawa peniaga mempunyai tahap persetujuan yang tinggi terhadap kepentingan rekod kewangan yang baik. Kesedaran ini diterjemahkan kepada amalan yang baik dalam pengurusan dokumen perniagaan, di mana min tertinggi dalam bahagian ini adalah untuk item Saya menyimpan semua resit dalam dokumen kewangan dengan baik (Min 4.07). Penemuan ini menyokong asas hipotesis bahawa apabila peniaga menyedari kepentingan rekod yang sistematik, mereka cenderung untuk menguruskan dan menyimpan dokumen perniagaan mereka dengan lebih teratur. Namun demikian, walaupun kesedaran adalah tinggi, isu konsistensi dalam merekod urusan niaga harian (Ke kerap an rekod urusan niaga perniagaan dibuat: Min 2.37) menunjukkan bahawa faktor kekangan masa dan kemahiran masih menghalang kesedaran daripada diterjemahkan kepada amalan pengurusan dokumen yang sepenuhnya sistematik

Hipotesis 3 (H3), yang mengandaikan terdapat hubungan yang signifikan antara penggunaan sistem perakaunan digital dengan keberkesanan pengurusan aliran tunai peniaga kedai makan, disokong secara kuat berdasarkan keperluan dan teori kajian. Analisis deskriptif menunjukkan kelemahan ketara dalam pengurusan aliran tunai formal, terutamanya dalam aspek ke kerap an memasukkan tunai ke dalam akaun bank (Min 2.26).

Kelemahan ini dapat diperbaiki dengan sistem digital, yang menurut kajian literatur, dapat mengurangkan kesilapan dan meningkatkan ketepatan rekod, sekali gus menyumbang kepada keberkesanan aliran tunai. Walau bagaimanapun, majoriti responden masih tidak menggunakan sistem digital secara meluas disebabkan oleh kekangan kos dan kurang pengetahuan teknologi. Oleh itu, penemuan ini menekankan keperluan untuk memperkenalkan sistem perakaunan digital yang mudah diakses dan murah, , bagi memastikan peniaga dapat merekod transaksi secara automatik dan meningkatkan keberkesanan pengurusan aliran tunai.

5.0 KESIMPULAN

Kajian ini telah berjaya mencapai dua objektif utama yang ditetapkan, iaitu untuk mengenalpasti tahap amalan simpan kira dan asas perakaunan yang diamalkan, dan untuk menilai tahap kesedaran peniaga kedai makan di sekitar Merlimau, Melaka. Secara keseluruhan, dapatan menunjukkan bahawa tahap amalan dan pengetahuan adalah pada tahap yang sederhana. Walau bagaimanapun, peniaga mempamerkan tahap kesedaran yang tinggi tentang kepentingan merekod kewangan, malah meyakini bahawa rekod kewangan yang baik dapat membantu perniagaan mereka berkembang (Min 4.09).

Namun, analisis membuktikan wujudnya jurang yang signifikan antara kesedaran peniaga dengan pelaksanaan praktikal. Hipotesis 1 (H1), yang menguji hubungan antara pengetahuan asas perakaunan dan amalan simpan kira, telah diterima melalui korelasi positif yang signifikan ($r = 0.62$, $p < 0.05$). Penemuan ini menegaskan bahawa kekurangan pengetahuan asas perakaunan merupakan kekangan utama dalam pelaksanaan amalan yang sistematik, yang mana ini dibuktikan dengan skor min yang sangat rendah dalam aspek penyediaan lejar akaun sendiri (Min 1.95). Di samping itu, Hipotesis 2 (H2) disokong, di mana kesedaran tinggi peniaga kepada amalan pengurusan dokumen yang baik, terutamanya dalam penyimpanan resit (Min 4.07). Walaupun begitu, amalan ini terjejas oleh isu ketekalan dalam merekod urus niaga harian. Selanjutnya, Hipotesis 3 (H3) disokong secara teori, meskipun peniaga menunjukkan integriti kewangan yang baik dengan memisahkan wang perniagaan dan peribadi (Min 4.21), pengurusan aliran tunai formal adalah lemah, terutamanya dalam aspek kekerapan memasukkan tunai ke dalam akaun bank (Min 2.26). Kekurangan pendedahan kepada sistem digital dan isu kos kekal menjadi penghalang utama kepada pengamalan sistem perakaunan moden. Hasil kajian ini diharapkan dapat menjadi panduan kepada agensi kerajaan, institusi pendidikan dan pihak berkepentingan dalam merangka program pembangunan keusahawanan yang menekankan literasi kewangan dan kemahiran simpan kira bagi memperkukuh daya saing peniaga kecil di Malaysia. Kajian lanjutan boleh dijalankan dengan melibatkan sampel lebih besar dan pelbagai sektor perniagaan bagi membandingkan tahap amalan simpan kira antara industri. Kajian kualitatif juga boleh dijalankan bagi menilai faktor dalaman seperti sikap, motivasi dan persepsi terhadap amalan perakaunan.

PENGHARGAAN

Para penyelidik memanjatkan setinggi-tinggi rasa syukur dan merakamkan penghargaan tulus ikhlas kepada Allah S.W.T atas segala rahmat, kekuatan, dan petunjuk yang telah memudahkan usaha penyelidikan ini, yang bertajuk "Amalan Simpan Kira Dan Asas Perakaunan Dalam Kalangan Peniaga Kedai Makan Di Sekitar Merlimau, Melaka", dapat disempurnakan dengan jayanya. Penghargaan yang amat mendalam dan istimewa ditujukan kepada penyelia utama kami, Puan Norhayah binti Sabtu , yang merupakan tenaga pengajar

di Jabatan Perdagangan, Politeknik Merlimau Melaka. Kami amat menghargai kepakaran, bimbingan akademik yang tidak pernah putus, nasihat profesional yang berharga, dan semangat yang telah dicurahkan dalam membimbing kami sejak dari peringkat perancangan, pengumpulan data, sehingga proses penganalisan dan penulisan laporan akhir. Ucapan terima kasih yang tidak terhingga juga diberikan kepada rakan-rakan sepasukan yang gigih, iaitu Nur Iman Batrisyia binti Faizulhizam, Nurul Nabila binti Omar, Noraida Mohd Faizal, dan Nurul Aqilah binti Abdul Rashid. Dedikasi, kerjasama erat, dan semangat setiakawan yang kukuh dalam menghadapi pelbagai cabaran di lapangan semasa pengumpulan data daripada 65 orang responden adalah kunci utama kepada kejayaan penyelesaian kajian ini dalam tempoh masa yang ditetapkan. Kami juga ingin merakamkan ucapan terima kasih kepada Politeknik Merlimau Melaka atas penyediaan kemudahan akademik dan logistik yang sangat membantu. Terima kasih juga ditujukan kepada semua peniaga kedai makan di Merlimau yang sudi bekerjasama dan memberikan input jujur tentang amalan simpan kira mereka, yang menjadi inti pati kepada dapatan kajian ini.

RUJUKAN

- Ahmad, R., Mohd Nor, N., & Salleh, M. (2014). *Amalan simpan kira dalam kalangan usahawan PKS di Malaysia* (Tesis sarjana muda, Universiti Teknologi MARA).
- Accounting Standards Board. (2021). *Financial reporting standards and concepts*. London: ASB Publications.
- Abdullah, M., Ismail, R., & Mahmud, R. (2017). Kegagalan perniagaan kecil akibat kelemahan simpan kira. *Jurnal Keusahawanan Malaysia*, 9(2), 13–22.
- Burke Johnson, R., & Christensen, L. (2012). *Educational research: Quantitative, qualitative, and mixed approaches* (4th ed.). SAGE Publications.
- Chong, C. L. (2020). Benefits of adopting cloud-based accounting systems among SMEs. *Asian Journal of Business and Accounting*, 13(1), 87–104.
- Fatoki, O. (2012). The impact of poor financial management on small businesses in South Africa. *Journal of Small Business and Enterprise Development*, 19(3), 404–420.
- Hassan, M. S. (2020). Integrating financial literacy in entrepreneurship programs: A government initiative. *Journal of Social Enterprise*, 15(1), 23–35.
- Heng, S. K. (2013). *Asas perakaunan untuk perniagaan kecil*. Kuala Lumpur: PTS Publications.
- Ismail, M., & King, R. (2023). Financial literacy and record keeping among food vendors in Malaysia. *Malaysian Journal of Entrepreneurship and Business*, 11(1), 33–45.
- Ismail, M., & Othman, S. (2017). *Kekangan simpan kira dalam kalangan usahawan mikro luar bandar*. Universiti Malaysia Kelantan.
- Jabatan Perangkaan Malaysia. (2023). *Laporan tahunan perusahaan makanan kecil 2023*. Putrajaya: DOSM.

- Jumaat, A. M., Norazlina, M. H., & Faridah, S. (2012). Kelemahan rekod kewangan dalam perniagaan kecil. *Jurnal Pengurusan PKS*, 3(2), 19–27.
- Melody Corporate House. (2025). Why record keeping matters for small businesses. Retrieved from <https://www.melodycorporate.com/articles/record-keeping>
- Mohamad Najib Abdul Ghafar. (2003). *Kaedah penyelidikan pendidikan*. Skudai: Universiti Teknologi Malaysia Press.
- Mohd Abdullah Jusoh, & Nur Atiqah Abd Talib. (2018). Literasi kewangan usahawan mikro di Malaysia. *Jurnal Pengurusan Kewangan*, 6(1), 1–10.
- Mohd Shukri, N. A., Ahmad, H., & Syamsul, M. (2020). Pengurusan aliran tunai usahawan mikro. *Jurnal Ekonomi & Kewangan Islam*, 12(2), 41–50.
- Mohd Zulkifli, M. A., Ahmad, N., & Rahim, N. (2015). Analisis tahap simpan kira dalam kalangan usahawan kecil. *Jurnal Keusahawanan Malaysia*, 8(1), 56–66.
- Maseko, N., & Manyani, O. (2011). Accounting practices of SMEs in Zimbabwe. *Journal of Accounting and Taxation*, 3(8), 171–181.
- Noor Dina Ibrahim. (2022). Applying the theory of planned behavior in small business record keeping. *International Journal of SME Studies*, 5(2), 20–34.

Kajian Empirikal Dalam Konteks Produktiviti IKS Melalui Penilaian Prestasi Sistem Penapisan Madu

Nor Zuliana Abdul Latif¹, Mohd Fauzi Hassan², Mohamad Shahril Ibrahim³

Politeknik Kuching Sarawak

norzuliana@poliku.edu.my, mfauzi@poliku.edu.my, hb150009@gmail.com

Abstrak Kajian ini dijalankan secara empirikal bagi menilai prestasi sistem penapisan madu dalam konteks peningkatan produktiviti pengusaha Industri Kecil dan Sederhana (IKS) di Malaysia. Kajian ini memberi fokus kepada perbandingan keberkesanan tiga kaedah utama yang lazim digunakan dalam industri penapisan madu lebah, iaitu kaedah manual, mesin separuh automatik, dan sistem automatik sepenuhnya. Ujian eksperimen dijalankan dengan menapis madu lebah sebanyak 1500 mililiter bagi setiap kaedah, dan purata masa penapisan direkodkan sebagai penunjuk prestasi utama. Hasil kajian menunjukkan bahawa sistem automatik mencatatkan masa purata 4.6 minit, berbanding 7.7 minit bagi mesin manual dan 17.3 minit bagi kaedah manual menggunakan tangan. Dapatan ini membuktikan bahawa pelaksanaan sistem automatik mampu memberikan penjimatan masa melebihi 70% berbanding kaedah konvensional. Pengurangan masa ini secara langsung memberi impak kepada peningkatan kapasiti pengeluaran madu serta pengurangan kebergantungan terhadap tenaga buruh. Selain daripada aspek masa, sistem automatik turut menawarkan kelebihan dari segi konsistensi proses, kebersihan produk akhir dan pengurangan keletihan operator. Secara keseluruhannya, kajian ini menyimpulkan bahawa pelaksanaan sistem penapisan automatik berupaya memberikan nilai tambah yang signifikan kepada pengusaha IKS dan wajar dipertimbangkan sebagai strategi pemodenan proses industri madu di peringkat nasional.

Kata kunci: Sistem penapisan madu automatik, Industri Kecil dan Sederhana (IKS), automasi proses, kecekapan masa, produktiviti pengeluaran, teknologi pemprosesan madu

1.0 PENGENALAN

Pengeluaran madu lebah secara komersial bukan sahaja memerlukan kaedah penternakan yang sistematik, tetapi turut bergantung kepada keberkesanan proses pascatuai, khususnya proses penapisan. Proses penapisan yang cekap dan bersih adalah penting bagi memastikan kualiti, ketulenan dan kebersihan madu memenuhi keperluan pengguna serta spesifikasi standard seperti piawaian Malaysia MS 2683:2017. Walau bagaimanapun, pengusaha madu di Malaysia terutamanya dalam kalangan Industri Kecil dan Sederhana (IKS) masih banyak bergantung pada kaedah penapisan manual dan separuh automatik. Kaedah ini memerlukan masa pemprosesan yang lebih panjang (antara 15–20 minit bagi setiap liter mengikut pemerhatian awal lapangan) dan melibatkan pengendalian fizikal yang berulang, seterusnya meningkatkan risiko pencemaran silang.

Dalam konteks pengeluaran berskala kecil dan sederhana, kaedah konvensional ini memberikan impak langsung terhadap produktiviti harian dan kapasiti pemprosesan. Berdasarkan tinjauan terhadap dua pengusaha kecil di daerah Melaka Tengah dan Jasin pada tahun 2024, purata jumlah madu yang mampu diproses secara manual tidak melebihi 8–10

liter sehari, menyebabkan pengusaha sukar memenuhi peningkatan permintaan pasaran domestik. Situasi ini menimbulkan keperluan mendesak terhadap sistem penapisan madu yang lebih sistematik, konsisten, dan menjimatkan masa untuk meningkatkan daya saing IKS dalam rantai bekalan madu tempatan.

Sehubungan itu, kajian ini dijalankan bagi menilai keberkesanan tiga kaedah penapisan utama manual, separuh automatik dan automatik sepenuhnya menggunakan pendekatan empirikal di daerah Jasin, Melaka. Penilaian dilakukan dalam tempoh empat minggu pada tahun 2024 menggunakan sampel madu *multiflora* tempatan sebanyak 1500 ml bagi setiap kaedah. Prestasi operasi ditaksir berdasarkan dua indikator terukur, iaitu masa penapisan (minit) dan isipadu bersih yang berjaya ditapis (ml) dalam tempoh yang ditetapkan. Melalui perbandingan ini, kajian ini bertujuan memberikan gambaran yang lebih jelas tentang impak penggunaan teknologi terhadap produktiviti sebenar pengusaha IKS, sekali gus menyediakan asas saintifik untuk menyokong pemodenan proses penapisan madu di peringkat akar umbi.

Dalam landskap pengeluaran madu tempatan, kebanyakan pengusaha Industri Kecil dan Sederhana (IKS) masih bergantung kepada kaedah penapisan secara manual atau penggunaan mesin separuh automatik yang memerlukan campur tangan manusia secara intensif. Kebergantungan kepada kaedah konvensional ini bukan sahaja menjejaskan kecekapan operasi, malah menimbulkan pelbagai isu berkaitan produktiviti, konsistensi kualiti produk dan ketahanan jangka panjang tenaga kerja yang terlibat. Masalah ini lebih ketara apabila pengeluaran perlu dipertingkatkan bagi memenuhi permintaan pasaran yang semakin kompetitif. Kaedah yang sedia ada didapati tidak mampu menyokong peningkatan kapasiti pengeluaran secara efektif, di samping mengekalkan piawaian kebersihan dan kecekapan proses. Di samping itu, kekurangan maklumat empirik yang menyeluruh berkaitan prestasi sebenar kaedah penapisan yang digunakan menyukarkan pengusaha membuat keputusan tepat dalam pemilihan sistem yang paling sesuai untuk diaplikasikan.

Kajian ini dijalankan bagi merungkai permasalahan tersebut dengan menilai dan membandingkan keberkesanan pelbagai sistem penapisan madu yang diguna pakai dalam sektor IKS. Penemuan daripada kajian ini diharapkan dapat memberikan panduan berasaskan bukti kepada pengusaha serta pihak berkepentingan dalam merangka strategi peningkatan produktiviti dan kecekapan operasi industri madu lebah secara menyeluruh. Kajian ini dijalankan untuk menangani cabaran keberkesanan sistem penapisan madu yang masih meluas penggunaannya dalam kalangan pengusaha Industri Kecil dan Sederhana (IKS). Berdasarkan permasalahan yang telah dikenal pasti, objektif kajian ini dirangka seperti berikut:

- i. Meneliti keterbatasan dan keperluan semasa pengusaha IKS berkaitan penggunaan sistem penapisan madu yang tidak efisien.
- ii. Menilai prestasi relatif tiga pendekatan sistem penapisan dari sudut operasi iaitu manual, separuh automatik dan automatik melalui pemerhatian dan pengalaman pengguna.

Skop kajian ini ditentukan berdasarkan objektif untuk memahami dan menilai sistem penapisan madu dalam persekitaran pengeluaran IKS, serta membandingkan keberkesanannya dalam konteks operasi harian. Had kajian ini adalah seperti berikut:

Kajian memberi tumpuan kepada penggunaan sistem penapisan madu dalam kalangan pengusaha kecil dan sederhana di peringkat tempatan. Penilaian melibatkan analisis operasi dan pengalaman penggunaan tiga pendekatan utama: sistem manual, sistem separuh automatik, dan sistem automatik.

2.0 KAJIAN LITERATUR

Kajian berkaitan keberkesanan sistem penapisan madu dalam konteks pengeluaran berskala kecil semakin mendapat perhatian dalam beberapa tahun kebelakangan ini. Menurut Alarifi et al. (2019), proses penapisan memainkan peranan penting dalam menentukan mutu akhir madu, khususnya dari segi ketulenan, kebersihan, dan kestabilan semasa penyimpanan. Kajian mereka menunjukkan bahawa sistem penapisan yang direka bentuk dengan baik dapat mengurangkan keperluan pemprosesan tambahan dan memelihara kandungan enzim dalam madu. Jagadeesh et al. (2020) pula menekankan kepentingan integrasi automasi dalam sistem penapisan untuk meningkatkan kecekapan proses dalam perusahaan kecil. Mereka mendapati bahawa pengaplikasian motor berkuasa rendah dalam reka bentuk penapisan automatik memberikan keseimbangan antara kecekapan dan kos operasi bagi pengusaha mikro dan kecil.

Sementara itu, kajian oleh Ramesh & Devi (2021) mendapati bahawa pengusaha IKS lebih cenderung menggunakan sistem penapisan manual disebabkan kos permulaan automasi yang tinggi. Namun begitu, kajian tersebut turut menunjukkan bahawa pengusaha yang beralih kepada sistem automatik mencatatkan peningkatan produktiviti sehingga 60%, dengan pengurangan masa operasi dan kebergantungan kepada tenaga kerja. Li et al. (2022) pula mencadangkan pendekatan modular dalam pembangunan mesin penapisan makanan termasuk madu, bagi memudahkan penyesuaian skala dan keperluan pengeluaran. Mereka menekankan bahawa reka bentuk perlu disokong oleh data prestasi lapangan untuk memastikan keberkesanan dalam pelbagai konteks penggunaan. Akhir sekali, Hassan et al. (2023) menyatakan bahawa kekangan utama dalam kalangan pengusaha IKS bukanlah teknologi semata-mata, tetapi kekurangan maklumat dan data empirik yang dapat menyokong keputusan peralihan kepada sistem baharu. Oleh itu, mereka menyeru agar kajian-kajian tempatan dijalankan secara sistematik bagi menilai prestasi sebenar sistem penapisan di peringkat akar umbi. Sorotan ini memperlihatkan bahawa wujud keperluan mendesak untuk kajian empirikal yang memberi fokus kepada pengalaman pengguna dan keberkesanan operasi sistem penapisan madu dalam kalangan pengusaha IKS. Kajian ini diharap dapat mengisi jurang tersebut dan menyumbang kepada pembangunan teknologi yang lebih bersifat aplikatif serta lestari dalam konteks pengeluaran tempatan.

3.0 METODOLOGI

Bagi memenuhi objektif kajian ini, iaitu menilai prestasi relatif tiga pendekatan sistem penapisan madu (manual, separuh automatik dan automatik) dari sudut operasi, kajian ini menggunakan pendekatan empirikal yang melibatkan pemerhatian langsung, pengukuran kuantitatif, serta maklum balas pengalaman pengguna semasa menjalankan proses penapisan sebenar.

3.1 Reka Bentuk Kajian

Reka bentuk kajian adalah perbandingan eksperimental deskriptif, di mana setiap sistem diuji dalam situasi yang sama untuk tujuan analisis prestasi. Kajian ini tidak tertumpu kepada kawalan makmal, tetapi dilakukan dalam konteks sebenar operasi IKS bagi memastikan kesahan luaran yang tinggi. Metodologi ini direka untuk menghasilkan dapatan yang tepat, praktikal dan berasaskan pengalaman sebenar pengguna sistem penapisan madu dalam sektor IKS.

3.2 Lokasi dan Subjek Kajian

Tiga sistem penapisan madu yang berbeza diuji oleh pengusaha madu tempatan secara bersilang (*cross-testing*). Pemilihan pengusaha dilakukan secara bertujuan, berdasarkan pengalaman mereka dalam menggunakan dua atau lebih sistem penapisan. Lokasi ujian adalah premis pengeluaran sebenar milik pengusaha IKS.

3.3 Prosedur Pengumpulan Data

Untuk setiap sistem penapisan, data dikumpulkan berdasarkan komponen berikut:

- i. Masa operasi (dari mula hingga selesai penapisan untuk isipadu tetap)
- ii. Isipadu hasil ditapis
- iii. Kemudahan penggunaan (dinilai melalui borang soal selidik pengguna)
- iv. Tahap keletihan dan ergonomik (diterjemah kepada persepsi pengguna)
- v. Proses ini diulang bagi memastikan kebolehpercayaan (*reliability*) dan ketekalan (*consistency*) data.

3.4 Instrumen Pengukuran

- i. Jam randik digital untuk masa operasi
- ii. Bikar volumetrik untuk ukur isipadu hasil
- iii. Soal selidik 5 skala Likert untuk persepsi pengguna
- iv. Senarai semak kendalian mesin (untuk konsistensi pelaksanaan ujian)

3.5 Teknik Analisis

- i. Data dianalisis menggunakan kaedah berikut:
- ii. Purata masa operasi
- iii. Perbandingan min antara tiga kaedah
- iv. Analisis kandungan terbuka untuk cadangan dan ulasan pengguna
- v. Visualisasi graf bar bagi menunjukkan trend perbandingan

4.0 DAPATAN DAN PERBINCANGAN

Dapatan kajian ini membandingkan prestasi tiga sistem penapisan madu yang biasa digunakan oleh pengusaha Industri Kecil dan Sederhana (IKS): kaedah manual, separuh automatik, dan automatik. Penilaian dilakukan berdasarkan masa operasi sebenar bagi isipadu tetap 1500 ml madu dan pemerhatian terhadap kemudahan penggunaan serta tahap penyelesaian pengendali. Dapatan ini dianalisis untuk menentukan keberkesanan sistem dari segi kecekapan dan kebolehgunaan dalam konteks pengeluaran kecil dan sederhana.


4.1 Masa Operasi dan Kecekapan Proses

Jadual 1 dan Rajah 1 berikut menunjukkan perbandingan masa operasi purata bagi ketiga-tiga kaedah penapisan madu yang diuji.

Jadual 1 : Perbandingan Masa Operasi Purata

Bilangan Uji Kaji (Minit) / Isipadu Madu (ml)									
Bil.	Alat	Bilangan Uji Kaji (Minit) / Isipadu Madu (ml)						Purata Masa (min)	
		1		2		3			
1.	Menpis Menggunakan Tangan	15	1500ml	17	1500ml	20	1500ml	17.3	
2.	Menapis Menggunakan Mesin Manual	8	1500ml	7	1500ml	8	1500ml	7.7	
3.	Menapis Menggunakan Mesin Automatik	4	1500ml	5	1500ml	5	1500ml	4.6	

Perbandingan Purata Masa Operasi Tiga Kaedah Penapisan Madu



Rajah 1 : Graf Perbandingan Masa Operasi Purata

Berdasarkan tiga siri uji kaji, kaedah manual mencatatkan purata masa 17.3 minit, menjadikannya paling lambat dalam kalangan kaedah yang diuji. Sistem separuh automatik mengambil purata masa 7.7 minit, manakala sistem automatik hanya mengambil masa 4.6 minit untuk menapis jumlah madu yang sama. Ini menunjukkan bahawa sistem automatik menjimatkan hampir 73% masa berbanding manual dan 40% berbanding separuh automatik. Perbezaan masa ini memberi impak langsung terhadap keupayaan pengusaha meningkatkan kadar pengeluaran harian. Di samping itu, sistem automatik juga menunjukkan kestabilan masa operasi antara setiap sesi, manakala kaedah manual menunjukkan variasi ketara disebabkan keletihan dan ketidakkonsistenan manusia.

4.2 Kemudahan Kendalian dan Ergonomik

Melalui pemerhatian dan maklum balas lisan daripada pengguna, sistem automatik dinilai paling mudah dikendalikan kerana hanya memerlukan pengaktifan awal dan

pemantauan minimum. Sistem ini tidak memerlukan pergerakan fizikal yang berulang, dan pengendali hanya perlu menunggu proses selesai tanpa gangguan. Sistem separuh automatik pula memerlukan campur tangan berkala, manakala kaedah manual menuntut pengendalian sepenuhnya dengan pergerakan tangan secara berterusan.

Kaedah manual juga dilihat paling terdedah kepada kesilapan kendalian dan memerlukan koordinasi tangan-mata yang tinggi, khususnya semasa pemindahan dan pengawalan aliran madu. Situasi ini bukan sahaja meningkatkan beban fizikal, malah boleh menyebabkan ketidakseragaman hasil penapisan.

4.3 Pengalaman Pengguna dan Tahap Keletihan

Pengendali sistem manual melaporkan tahap keletihan tinggi terutama di bahagian lengan, bahu dan pergelangan tangan. Proses yang berulang-ulang dan berpanjangan menyumbang kepada keletihan fizikal yang mengganggu kelancaran kerja. Sebaliknya, pengguna sistem automatik menyatakan pengalaman kerja yang lebih selesa dan lancar, serta kurang tekanan fizikal sepanjang sesi penapisan.

Sistem separuh automatik dilaporkan lebih baik sedikit berbanding manual, namun masih memerlukan tenaga fizikal yang tidak dapat dielakkan, terutamanya bagi proses kawalan aliran dan pemantauan putaran.

4.4 Perbincangan Keseluruhan

Dapatan kajian ini secara langsung menjawab Objektif (a), iaitu meneliti keterbatasan dan keperluan semasa pengusaha IKS dalam penggunaan sistem penapisan madu yang tidak efisien. Hasil pemerhatian menunjukkan bahawa kaedah manual, yang masih meluas digunakan dalam kalangan pengusaha kecil, mempunyai beberapa kekangan ketara seperti masa penapisan yang panjang, ketidakseragaman aliran penapisan, serta risiko pencemaran silang akibat pengendalian berulang. Kekangan ini menyebabkan pengusaha IKS sukar meningkatkan kapasiti harian dan terpaksa bergantung pada tenaga kerja tambahan untuk memenuhi permintaan pasaran. Kaedah separuh automatik pula mengurangkan sedikit beban kerja, namun masih tidak menyelesaikan isu utama seperti konsistensi hasil dan kebergantungan kepada operasi fizikal, sekali gus membuktikan bahawa keperluan terhadap sistem yang lebih efisien dan stabil adalah nyata.

Berkaitan Objektif (b), iaitu menilai prestasi relatif tiga pendekatan penapisan melalui pemerhatian dan pengalaman pengguna, analisis menunjukkan bahawa sistem automatik memberikan prestasi operasi terbaik dalam hampir semua aspek yang diuji. Sistem automatik mencatatkan masa penapisan paling singkat dan isipadu bersih paling konsisten, sekaligus menunjukkan tahap kecekapan tertinggi berbanding kaedah separuh automatik dan manual. Pengguna juga melaporkan pengalaman operasi yang lebih mudah dan kurang memenatkan, kerana proses penapisan dapat dijalankan tanpa pemantauan berterusan. Ini berbeza dengan sistem manual yang memerlukan perhatian penuh sepanjang proses dan menyebabkan keletihan, manakala sistem separuh automatik masih menuntut penyelarasan *operator* untuk mengekalkan kelancaran aliran. Secara keseluruhan, dapatan kajian ini menunjukkan bahawa sistem automatik bukan sahaja mengatasi keterbatasan yang dikenal pasti dalam Objektif (a), tetapi juga memenuhi keperluan efisiensi dan kebersihan yang diperlukan oleh pengusaha IKS. Pada masa yang sama, perbandingan prestasi yang dilakukan dalam Objektif (b) jelas menegaskan bahawa sistem automatik memberikan nilai tambah

paling besar dari sudut operasi, kebolehskalaan dan konsistensi hasil menjadikannya pilihan paling praktikal untuk pemodenan proses penapisan madu di peringkat IKS.

5.0 KESIMPULAN DAN CADANGAN

Kajian ini telah berjaya memenuhi objektif untuk menilai prestasi tiga pendekatan sistem penapisan madu manual, separuh automatik dan automatik dalam konteks pengeluaran oleh pengusaha Industri Kecil dan Sederhana (IKS). Berdasarkan analisis masa operasi, kemudahan penggunaan dan pengalaman kerja, didapati bahawa sistem automatik memberikan kelebihan paling signifikan dari segi kecekapan masa, kestabilan proses dan pengurangan beban fizikal ke atas pengguna.

Kaedah manual, walaupun masih digunakan secara meluas kerana kosnya yang rendah dan reka bentuk yang mudah, didapati tidak lagi efisien dalam memenuhi keperluan pengeluaran semasa yang semakin meningkat. Sistem separuh automatik menunjukkan peningkatan kecekapan berbanding manual, namun masih tidak dapat menandingi kemudahan dan prestasi sistem automatik sepenuhnya.

Berdasarkan dapatan kajian, beberapa cadangan praktikal dikemukakan:

- i. Galakan penggunaan sistem automatik dalam kalangan pengusaha IKS melalui program subsidi atau insentif peralatan yang memfokuskan kepada peningkatan produktiviti dan kecekapan kerja.
- ii. Pembangunan sistem automatik berskala kecil yang lebih kos efektif dan mudah digunakan, agar sesuai dengan keupayaan pengusaha kecil yang memiliki sumber terhad.
- iii. Latihan dan sokongan teknikal perlu disediakan kepada pengusaha yang beralih kepada sistem automatik, agar mereka dapat mengendalikan peralatan dengan selamat dan optimum.
- iv. Penyelidikan susulan dicadangkan untuk menilai aspek ekonomi seperti kos pelaksanaan, pulangan pelaburan (*ROI*), dan impak jangka panjang terhadap keuntungan pengusaha.
- v. Kerjasama antara institusi teknikal, koperasi dan agensi kerajaan perlu digerakkan bagi membolehkan pemindahan teknologi secara menyeluruh dan lestari dalam industri madu tempatan.

Keseluruhannya, dapatan kajian ini memberikan sokongan empirikal terhadap keperluan pemodenan proses penapisan madu di peringkat akar umbi. Pemilihan sistem penapisan yang bersesuaian bukan sahaja memberi kesan kepada *output* pengeluaran, tetapi juga terhadap kebajikan pengusaha, kestabilan hasil dan kualiti produk akhir.

RUJUKAN

- Alarifi, S., et al. (2019). Honey Quality Assessment Based on Filtration Methods. *Journal of Food Processing*, 21(3), 204–210.
- Jagadeesh, K., Sharma, R., & Mehta, P. (2020). Design of Low-Cost Automatic Filtration Systems for Rural Food Processing Units. *International Journal of Agro-Engineering*, 12(1), 54–61.

- Ramesh, K., & Devi, A. (2021). Challenges in Adopting Automation in Small-Scale Agro Industries: A Case Study on Honey Processors. *South Asian Journal of Technology*, 8(4), 199–207.
- Li, X., Wang, J., & Xu, Y. (2022). Modular Design Framework for Honey Processing Equipment in SMEs. *Journal of Food Engineering and Automation*, 14(2), 112–120.
- Hassan, R., Norazman, F., & Khalid, S. (2023). Adoption of Filtration Technology Among Malaysian Agropreneurs: Gaps and Opportunities. *Malaysian Journal of Agri-Technology*, 17(1), 33–41.

Analisis Faktor Mempengaruhi Pemilihan Skrub Badan: Kajian Kes *Nucifera Body Scrub*

Hanim binti Paimin¹, Halizah binti Alwi², Norwidayati bt Ahmad@ Nasiman³

^{1,2}Politeknik Merlimau Melaka

³Kolej Komuniti Selandar

*hanim@pmm.edu.my

Abstrak. Produk skrub badan Nucifera adalah produk baharu yang akan menembusi pasaran tempatan menggunakan bahan bersifat mesra alam, hampas kelapa sebagai bahan utama. Tanpa kajian yang sistematik mengenalpasti ciri produk pilihan pengguna, pengeluar berisiko merancang strategi pemasaran dan pengkomersialan yang berkesan. Sehubungan itu terdapat keperluan untuk mendapatkan maklumat ciri produk yang boleh diterima pengguna. Oleh itu kajian ini bertujuan untuk mengenal pasti faktor estetika dan faktor fizikal yang menjadi pilihan pengguna dalam pemilihan produk skrub badan. Kajian dijalankan menggunakan pendekatan kuantitatif deskriptif melalui soal selidik berstruktur dengan nilai Cronbach's Alpha merentasi keseluruhan instrumen berada pada julat 0.89 hingga 0.94, seramai 289 responden dari sejumlah 351 sampel dipilih secara rawak mudah telah memberi maklumbalas. Dapatan kajian faktor estetika menunjukkan warna produk yang cerah, bau semula jadi dan harum menjadi pilihan utama pengguna. Manakala penggunaan bahan semula jadi hampas kelapa berstruktur halus, bahan yang selamat dan berbentuk bulat menjadi pilihan faktor fizikal produk. Maka penghasilan produk perlu menitikberatkan elemen estetika dan fizikal untuk membolehkan bersaing dan menembusi pasaran kosmetik di Malaysia. Implementasi pilihan pengguna, kerjasama antara institusi dan media pengiklanan akan membantu pengkomersialan yang berkesan bagi produk Nucifera Body Scrub.

Kata Kunci: *skrub badan, hampas kelapa, pengkomersialan.*

1. PENGENALAN

Dalam usaha mencapai proses pengkomersialan yang berkesan, pengeluar mempunyai peranan dan tanggungjawab mengumpul, menganalisis dan menentukan ciri-ciri produk yang menjadi pilihan pengguna. Dewasa ini pelbagai produk muncul bak cendawan selepas hujan dengan pelbagai jenis kandungan, warna, fungsi serta pilihan harga yang kompetitif. Pilihan pengguna terhadap produk kosmetik telah berkembang pesat dipacu oleh faktor-faktor seperti keselamatan bahan, keberkesanan multifungsi, estetika, kepercayaan jenama, dan inovasi teknologi. Dalam pada itu kesedaran pengguna terhadap kesihatan dan alam sekitar telah berubah, minat pengguna terhadap kosmetik semula jadi turut meningkat. Dapatan kajian di Malaysia menekankan bagaimana gaya hidup sihat menyokong permintaan untuk bahan semula jadi dalam produk kecantikan (Ainunnazlee & Aini, 2012).

Kesedaran pengguna terhadap keselamatan dan kesihatan yang tinggi mendorong pengeluar memberikan penekanan kepada penghasilan kosmetik yang mempunyai konsep kosmetik hijau. Landskap baharu penggunaan produk masakini lebih menekankan kepada kandungan bahan kosmetik mempunyai nilai mesra alam dan bersifat semulajadi (Anggi & Adaviah, 2023). Sehubungan itu dalam usaha mendapatkan maklumat yang relevan perlu bagi memastikan penghasilan produk baharu dapat diterima baik serta berpeluang dikomersialkan dengan berkesan, setiap produk yang dihasilkan mesti memenuhi citarasa dan mempunyai ciri yang menjadi tarikan kepada pembelian. Ini dibuktikan berdasarkan dapatan kajian di Putrajaya menunjukkan kualiti sesuatu produk kosmetik perapi badan adalah faktor penting yang mempengaruhi dan signifikan dalam pembuatan keputusan pembelian dalam kalangan wanita Melayu (Ilya Syahirah, etl 2023). Dalam pada itu, di kalangan remaja, penggunaan produk penjagaan diri, terutamanya skrub badan, semakin mendapat perhatian. Jenama-jenama yang menumpukan pada nilai dan keunikan visual telah menjadi faktor penting dalam membuat keputusan pembelian oleh remaja pada masa sekarang.

Seiring dengan perkembangan permintaan semasa dan landskap pembelian yang positif ini, pelbagai pihak dan agensi termasuk Kementerian Pendidikan Tinggi (KPT) memberi peluang kepada institusi untuk mengkomersialkan produk yang mempunyai potensi tinggi untuk menembusi pasaran melalui pemberian *TVET Applied Commercialization Grant Scheme* (T-ACGS) di bawah Trans Tech 4-TVET. Ini menunjukkan sokongan langsung kerajaan terhadap usaha komersial penyelidikan dan pembangunan produk teknikal atau inovatif serta meningkatkan potensi pembangunan dan menambah nilai ekonomi negara melalui kerjasama industri (Dr Riam Chau, 2024). T-ACGS lebih memberi tumpuan kepada pemasaran dan pengkomersialan produk dengan kesediaan teknologi. Keberhasilan projek *Nucifera Body Scrub* memperoleh geran pengkomersialan TVET adalah melalui cadangan penggunaan inovatif hampas kelapa dijadikan bahan utama untuk menghasilkan skrub badan selaras dengan *Sustainable Development Goals* (SDGs) 12 dengan matlamat pembangunan mampan mensasarkan pengeluaran dan penggunaan sumber secara bertanggungjawab bermotifkan mengurangkan penajanaan sisa dengan ketara (audit.utem.edu.my, 2025). Ini termasuk strategi pengurangan sisa melalui kaedah *reduce, reuse, recycle*. Selain itu ia juga menjurus kepada konteks kitaran ekonomi, pemulihan dan penambahnilaian sisa pertanian.

Untuk memastikan proses pengkomersialan dapat dilaksanakan dengan berkesan dan mencapai sasaran pasaran pembuatan skrub badan daripada hampas kelapa menuntut perhatian khusus terhadap penentuan ciri produk yang menjadi pilihan pengguna. Kajian oleh Nur Ain Shakila & Noorsyalina (2024) mendapati bahawa pengguna Malaysia semakin berminat dengan kosmetik hijau. Namun, persepsi harga yang tinggi dan jurang antara niat dan tindakan pembelian (*intention-behavior gap*) masih wujud. Sebagai pengeluar produk baharu mahupun pengkaji adalah menjadi satau perkara penting untuk mengenalpasti dan menentukan ciri-ciri produk yang dapat diterima di pasaran seterusnya bersaing dengan produk sedia ada. Sehubungan dengan itu bagi produk baharu ini seseorang pereka atau pengeluar yang merupakan pemegang geran perlu mengenalpasti elemen produk yang boleh mendorong keputusan pembelian produk berasaskan hampas kelapa ini. Pengeluar memerlukan input dan maklumat yang relavan di pasaran untuk menghasilkan produk yang memenuhi citarasa pengguna. Kajian sistematik tentang pengaruh faktor estetika dan fizikal sangat signifikan dalam memenuhi citarasa pengguna. (Ai Qin, Faren, & Guanhua, 2021). Oleh

yang demikian satu kajian pasaran perlu dilaksanakan untuk mendapatkan maklumat yang penting tentang ciri dan sifat produk yang menjadi pilihan pengguna terutama bagi produk yang menggunakan bahan terbuang iaitu hampas kelapa sebagai bahan utama.

Oleh yang demikian objektif kajian ini bertujuan untuk mengenalpasti faktor estetika dan faktor fizikal selain menganalisis pilihan pengguna terhadap bau, bentuk, dan warna produk skrub badan yang mempengaruhi pemilihan pengguna terhadap produk *Nucifera Body*. Ini bagi memastikan produk baharu ini, yang menggunakan bahan alam semula jadi, hampas kelapa mampu diterima oleh pengguna dan menembusi pasaran tempatan secara komersial serta menjadi pesaing kompetitif kepada produk kosmetik sedia ada. Kajian ini mempunyai kepentingannya yang tersendiri terutama kepada penyelidik atau pengeluar. Informasi yang diperolehi dari data primer membantu pengeluar mencipta produk yang bukan sahaja berfungsi tetapi juga meningkatkan niat beli pembelian produk kosmetik (Norashikin & Hanisah, 2023) berasaskan bahan alami selaras dengan matlamat utama iaitu pengkomersialan produk secara meluas. Selain itu, nilai *invisible* yang baik membina reputasi sebagai pengeluar yang teliti dan berkualiti, mewujudkan kepercayaan pengguna, dan menambah nilai imej jenama yang profesional. Disamping itu kajian ini memberikan satu pandangan baharu dalam penghasilan produk perapihan badan dengan menggunakan bahan terbuang menjadikan sesuatu yang bernilai iaitu *from waste to wealth*.

2. SOROTAN KAJIAN

Kajian oleh Nur Ain Shakila, Noorsyalina, & Sharkawi (2024) mendapati bahawa pengguna Malaysia semakin berminat dengan kosmetik hijau. Selain itu kajian oleh Sakinah (2023) di Lembah Klang menunjukkan bahawa kepercayaan pengguna meningkat apabila jenama memberi maklumat terperinci mengenai bahan, kurang bahan berbahaya , dan memiliki pensijilan seperti *cruelty-free* atau organik dalam produk kosmetik. Ketelusan dan kesahihan bahan meningkatkan kredibiliti jenama sesuatu produk dan boleh diterima di pasaran dengan lebih baik. Dalam pada itu Menurut kajian Allied Market Research (2022), pasaran produk kosmetik semula jadi global dijangka berkembang pada kadar pertumbuhan tahunan sebanyak 5.2% dari 2021 hingga 2030. Peningkatan ini didorong oleh perubahan gaya hidup sihat dan peningkatan kesedaran alam sekitar. Kajian tesis oleh Azmi (2022) di UKM menunjukkan bahawa faktor seperti keselamatan dan kesihatan, identiti agama, serta sikap pengguna adalah penentu penting dalam niat pembelian produk kosmetik halal—lebih penting daripada pengetahuan atau logo halal sendiri. Pengeluar seharusnya menekankan aspek ini dalam strategi para pengeluar. Dalam pada itu dalam kajian ini juga menunjukkan seiring dengan peningkatan tahap kesedaran pengguna mengenai isu kesihatan dan alam sekitar, industri kosmetik telah mengalami satu metamorfosis ke arah budaya pengeluaran dan permintaan terhadap produk-produk berasaskan organik dan semula jadi. Anjakan ini membayangkan tren global yang semakin mengutamakan kelestarian dalam landskap sektor kecantikan dan penjagaan diri.

Dalam pada itu juga kajian terhadap pelajar di Malaysia oleh Nurulhayah (2019) mendapati bahawa sikap dan pengetahuan merupakan faktor utama mempengaruhi pembelian kosmetik tiruan, manakala imej jenama kurang berkesan mempengaruhi keputusan tersebut. Pengeluar perlu membina sikap positif dan memperkukuh pendidikan pengguna dalam amalan keselamatan produk. Dalam pada itu kajian dalam bidang aromaterapi dan psikologi sensori menunjukkan bahawa wangian (seperti bunga ros, buah-

buah, atau eucalyptus) dalam produk penjagaan diri boleh mempengaruhi mood dan persepsi keberkesanan produk, menjadikan penggunaannya lebih menyeronokkan dan terasa seperti spa. Selain itu haruman lavender menjadi pilihan pengguna kerana dipercayai mengurangkan tekanan psikologi serta bersifat menenangkan (Zhang, 2025). Namun, persepsi harga yang tinggi dan jurang antara niat dan tindakan pembelian (*intention-behavior gap*) masih wujud. Pengeluar perlu menyesuaikan produk dengan maklumat jelas dan promosi harga untuk memenuhi harapan pasaran. Kajian lepas menunjukkan faktor estetika, harga, jenama, dan kandungan semula jadi mempengaruhi keputusan pembelian produk kosmetik dalam kalangan pengguna muda (Chen & KIm, 2021)

3. METODOLOGI KAJIAN

3.1 Rekabentuk Kajian

Kajian ini menggunakan pendekatan rekabentuk kajian ini menggunakan pendekatan kuantitatif deskriptif. Menurut Creswell (2014), pendekatan kuantitatif sesuai untuk mengkaji hubungan antara pemboleh ubah dan membuat generalisasi berdasarkan data numerikal. Data dalam kajian ini diperoleh dan dikumpulkan melalui dua sumber utama iaitu data primer dan data sekunder. Instrumen utama data primer adalah data yang diperoleh secara terus dari responden dengan menggunakan instrumen soal selidik yang diedarkan menggunakan *Google Form*. Instrumen terdiri daripada soal selidik berstruktur yang dibahagikan kepada tujuh bahagian iaitu Bahagian A: Soalan Demografik dan Bahagian B-F: Fokus kepada Menilai faktor estetika dan fizikal produk yang mengandungi 25 item dengan penggunaan 5 skala Likert bertujuan mendapatkan maklumat secara langsung. Selain itu sumber data juga menggunakan kajian lepas seperti pembacaan jurnal, kajian keperpustakaan, majalah, dokumen dan laporan di laman sesawang selain laporan akhbar untuk menyokong perbincangan.


3.2 Teknik Persampelan Dan Ujian Keboleh Percayaan

Populasi sasaran bagi kajian ini ialah seramai 4286 responden yang terdiri dari kalangan pelajar Politeknik Merlimau Melaka yang mendaftar pengajian sepenuh masa bagi Sesi 2 2024/2025. Jumlah sampel ditentukan menggunakan Jadual Krejcie & Morgan (1975). Jumlah sampel yang ditetapkan ialah sepatutnya sekitar 351 orang. Jumlah maklumbalas yang lengkap yang diperoleh ialah seramai 289 orang. Responden dipilih melalui pensampelan rawak, sesuai untuk kajian kuantitatif deskriptif yang membolehkan semua sampel mendapat peluang yang sama.

Ujian rintis telah dijalankan ke atas 30 responden untuk memeriksa kebolehpercayaan instrumen. Nilai *Cronbach's Alpha* merentasi keseluruhan instrumen berada pada julat 0.89 hingga 0.94, menandakan kebolehpercayaan yang tinggi. Data yang dikumpul dianalisis menggunakan SPSS versi 26 dengan fokus kepada analisis deskriptif kekerapan, peratusan, min serta pengesahan kebolehpercayaan instrumen melalui Cronbach's Alpha. Penggunaan SPSS sebagai alat analisis adalah konsisten dengan amalan penyelidikan kontemporari dalam kajian kuantitatif di Malaysia (Pawitra Ramu, 2023)


4. KEPUTUSAN KAJIAN DAN ANALISIS

4.1 Analisis Demografi




Rajah 1 : Bilangan responden mengikut jantina

Rajah 1 menunjukkan bilangan responden majoriti adalah perempuan seramai 165 orang , manakala seramai 124 lagi adalah responden lelaki.



Rajah 2 : Bilangan responden mengikut Semester

Rajah 2 menunjukkan bilangan responden dari semester 4 adalah dominan seramai 45%, disusuli responden dari semester 2 sebanyak 17.3%, semester 1 sebanyak 14.9% dan semester 3 hanya sejumlah 8.3%. Responden semester 5 dan 6 sebanyak 10.4% dan 4.2%.



Rajah 3 : Bilangan responden mengikut jabatan

Data pada Rajah 3 menunjukkan Jabatan Perdagangan adalah penyumbang responden terbesar dengan seramai 72% dari sejumlah 289 orang responden. Manakala Jabatan Kejuruteraan Elektrik sejumlah 14.5% dan Jabatan Kejuruteraan Mekanikal sebanyak 7.6% responden telah memberi maklumbalas yang lengkap.

4.2 Analisis Faktor

4.2.1 Analisis Faktor Estetika

Jadual 1 : Analisis Estetika Ke Atas Produk Nucifera

Bil	Item	Sangat Tidak Setuju	Tidak Setuju	Setuju	Sangat Setuju	Min	Tahap
1	Warna scrub badan yang menarik mempengaruhi pilihan saya.	2 0.7%	19 6.6%	114 39.4%	154 53.3%	3.45	Tinggi
2	Saya lebih suka scrub badan dengan warna semula jadi.	1 0.3%	16 5.5%	127 43.9%	145 50.2%	3.49	Tinggi
3	Warna yang cerah pada scrub badan membuatkan produk nampak lebih menarik.	2 0.7%	12 4.2%	128 44.3%	147 50.9%	3.45	Tinggi
4	Saya menganggap warna produk mencerminkan kualiti scrub badan.	8 2.8%	16 5.5%	123 42.6%	142 49.1%	3.38	Tinggi
5	Bau scrub badan mempengaruhi keputusan pembelian saya	2 0.7%	4 1.4%	93 32.2%	190 65.7%	3.63	Tinggi
6	Saya lebih suka scrub badan yang berbau harum dan menyegarkan.	0 0%	8 2.8%	91 31.5%	190 65.7%	3.39	Tinggi
7	Saya mengelak daripada membeli scrub badan yang berbau terlalu kuat.	4 1.4%	25 8.7%	115 39.8%	145 50.2%	3.45	Tinggi
8	Scrub badan dengan bau semula jadi lebih menarik perhatian saya	2 0.7%	22 7.6%	108 37.4%	157 54.3%	3.44	Tinggi
9	Reka bentuk produk berasaskan hampas kelapa menarik minat saya untuk mencuba	2 0.7%	18 6.2%	119 41.2%	150 51.9%	3.44	Tinggi
	Purata Skor Min Keseluruhan					3.46	Tinggi

Berdasarkan jadual 1 menunjukkan semua item menunjukkan skor purata antara 3.38 hingga 3.63, yang secara konsisten dan di kategorikan sebagai tinggi. Keseluruhan skor min adalah pada tahap tinggi iaitu 3.46. Ini membuktikan bahawa elemen estetika seperti warna menarik, warna semula jadi, dan bau harum diterima baik dan memberi pengaruh kuat dalam pilihan pengguna terhadap produk *Nucifera Body Scrub*. Analisis . Item 5 –Bau scrub badan mempengaruhi keputusan pembelian saya mencatat min 3.63, tertinggi dalam senarai. Manakala Item 4 – Saya menganggap warna produk mencerminkan kualiti scrub badan mencatat skor min 3.38, berada dalam kategori tinggi walaupun terendah berbanding item

lain. Ini menjelaskan bahawa faktor bau sebenarnya mempunyai kuasa *success* yang melebihi faktor visual seperti warna. Skor min kedua tertinggi 3.49 ialah bagi item 2 iaitu Saya lebih suka skrub badan dengan warna semula jadi . Ini menunjukkan bahawa bahawa bau yang menarik sesuatu produk terutama bauan semula jadi akan menjadi tarikan pengguna dalam pemilihan produk. Manakala item 1: Warna skrub badan yang menarik mempengaruhi pilihan saya., 3 : Warna yang cerah pada skrub badan membuatkan produk nampak lebih menarik dan item 7: Saya mengelak daripada membeli skrub badan yang berbau terlalu kuat memberikan nilai skor min yang sama iaitu 3.45. Keseluruhan maklumbalas adalah pada tahap tinggi melebihi 3.30.

4.2.2 Analisis Faktor Fizikal


Jadual 2 : Analisis Fizikal ke atas produk Nucifera

Bil	Item	Sangat Tidak Setuju	Tidak Setuju	Setuju	Sangat Setuju	Min	Tahap
1	Saya lebih suka skrub badan yang mempunyai tekstur halus.	4 1.4%	18 6.2%	105 36.3%	162 56.1%	3.47	Tinggi
2	Saya suka skrub badan yang mempunyai butiran kasar untuk pengelupasan kulit.	16 5.5%	53 18.3%	114 39.4%	106 36.7%	3.07	Tinggi
3	Saiz butiran skrub badan mempengaruhi keputusan pembelian saya.	5 1.7%	21 7.3%	125 43.3%	138 47.8%	3.37	Tinggi
4	Saya lebih suka skrub badan yang diperbuat daripada bahan semula jadi seperti hampas kelapa badan.	4 1.4%	18 6.2%	120 41.5%	147 50.9%	3.41	Tinggi
5	Skrub badan berasaskan hampas kelapa lebih lembut pada kulit.	4 1.4%	13 4.5%	130 45%	142 49.1%	3.42	Tinggi
6	Saya percaya skrub badan daripada hampas kelapa lebih selamat digunakan.	3 1.0%	14 4.8%	121 41.9%	151 52.2%	3.45	Tinggi
7	Skrub badan dengan tekstur sederhana lebih selesa digunakan.	3 1.0%	17 5.9%	122 42.2%	147 50.9%	3.43	Tinggi
	Purata Skor Min Keseluruhan					3.37	Tinggi

Berdasarkan Jadual 2 diatas menunjukkan secara keseluruhan skor min adalah pada tahap tinggi iaitu 3.37. Skor min tertinggi di tunjukan oleh item 1 iaitu Saya lebih suka skrub badan yang mempunyai tekstur halus. Item 6 iaitu Saya percaya skrub badan daripada hampas kelapa lebih selamat digunakan memberikan skor min 3.45, skor min kedua tertinggi. Manakala item yang menunjukkan skor min terendah, namun masih dalam kategori tinggi ialah item 2 iaitu Saya suka skrub badan yang mempunyai butiran kasar untuk pengelupasan


kulit. Skor min ke dua terendah ialah pada item 3: Saiz butiran scrub badan mempengaruhi keputusan pembelian saya iaitu 3.37.

4.2.3 Analisis Pilihan bauan, bentuk dan warna scrub badan




Rajah 4: Pilihan bauan

Data dari rajah 4 menunjukkan pengguna paling menggemari bauan lavender sebanyak 63% disusuli bauan leman 54.5% dan Vanila sebanyak 45.30% memilih bauan tersebut yang sesuai untuk scrub badan. Manakala dapatan kajian untuk pilihan bentuk scrub badan yang menjadi pilihan adalah bentuk bulat seramai 163 responden memilihnya, bunga menjadi pilihan bentuk kedua tertinggi dengan seramai 117 responden, dan segi empat tepat majoriti menjadikan sebagai pilihan ketiga. Dapatan ini seperti dalam rajah 5 dibawah.



Rajah 5: Pilihan bentuk Scrub badan

Dapatan analisis bagi pilihan warna scrub badan di tunjukkan seperti dalam Rajah 6 di bawah. Warna cerah biru laut menjadi pilihan utama responden seramai 174 orang. Warna merah jambu menjadi pilihan warna kedua dengan seramai 160 responden memilihnya, diikuti putih adalah pilihan warna ketiga paling digemari.



Rajah 6: Pilihan warna Scrub badan

5. PERBINCANGAN DAN KESIMPULAN

Berdasarkan analisis faktor estetika dan fizikal, dapat disimpulkan bahawa faktor estetika terutama warna dan bau merupakan elemen kritikal yang mempengaruhi pilihan pengguna terhadap produk *Nucifera Body Scrub*. Bau bunga lavender adalah faktor paling dominan, diikuti oleh warna semula jadi. Ini selari dengan kajian oleh Zhang (2025) bahawa bau yang menyegarkan dari lavender sentiasa menjadi pilihan pengguna kerana mempunyai kesan psikologi kepada pengguna selaras dengan skor min **3.63**. Ini menjelaskan bahawa faktor bau sebenarnya mempunyai signifikan yang melebihi faktor visual seperti warna untuk mempengaruhi pembelian oleh pengguna. Dapatan ini selari dengan kajian (Justina, Caroline, & Carlo, 2015) menunjukkan pendedahan bau meningkatkan niat beli melalui perubahan dalam sikap, persepsi, ingatan, dan tingkah laku. Ini juga disokong kajian oleh Dahlia & Douglas (2020) secara eksperimen menunjukkan bahawa estetika memberi impak besar kepada persepsi kegunaan, namun pengaruhnya mungkin menurun dari masa ke masa setelah penggunaan berulang. Dapatan ini juga selari dengan dengan kajian oleh Chen (2021).

Manakala bagi analisis faktor fizikal seperti tekstur, saiz butiran, dan bahan juga diambil kira oleh pengguna dalam kajian pasaran pemilihan produk *Nucifera Body Scrub*. Pengguna lebih mengutamakan tekstur halus, bahan semula jadi, dan saiz butiran yang sesuai. Produk *Nucifera* berasaskan hampas kelapa mempunyai daya tarikan yang kuat dari segi estetika dan fizikal, yang menyumbang kepada penerimaan tinggi dalam kalangan pengguna, dengan fungsi menanggalkan sel kulit mati dengan penggunaan bahan alami dan selamat. Ini kerana pengguna pada masa kini amat mementingkan penggunaan bahan yang selamat dan bersifat semulajadi. Selari dengan kajian Azmi Abd Azizi (2022) keselamatan dan kesihatan, adalah penentu penting dalam niat pembelian produk kosmetik halal. Pengguna kurang berminat kepada produk yang memiliki tekstur yang kasar. Bentuk bulat pula menjadi pilihan utama pengguna bagi produk *Nucifera Body Scrub*.

Oleh yang demikian, produk scrub badan Nucifera perlu memberi tumpuan dan fokus pada penghasilan produk yang berbau harum, menyegarkan, dan semula jadi, memandangkan ia adalah faktor utama yang mempengaruhi keputusan pembelian. Selain itu

elakkan bahan yang terlalu kuat atau tiruan, kerana ia boleh menjejaskan minat pembeli. Dalam pada itu juga scrub badan yang perlu dihasilkan perlu menggunakan warna semula jadi untuk mengekalkan daya tarikan dan keyakinan pengguna yang berpunca dari signifikan dorongan faktor estetika. Oleh yang demikian penggunaan bahan - bahan semula jadi daripada hampas kelapa sebagai satu kelebihan dalam strategi pemasaran dan pengkomersialan untuk menarik lebih ramai pengguna. Dengan mengenalpasti semua elemen dapatan kajian seterusnya mengimplimentasikan ciri tersebut dalam penghasilan Nucifera Body Scrub , akan membolehkan produk baharu ini dikomersialan dengan berkesan dan memenuhi matlamat geran TACGS tersebut.

PENGHARGAAN

Setinggi penghargaan dan ucapan terima kasih kepada semua penyelidik TACGS Nucifera Body Scrub yang terdiri daripada Halizah Alwi, Norwidayati, Nurol Aleyzan, Norhazma dan Maria yang memberi sumbangan secara langsung penghasilan kajian ini. Selain itu kepada semua pihak termasuk UPIK , PMM yang memberikan sumbangan langsung atau tidak langsung untuk mejayakan geran TACGS dan penyelidikan ini.

RUJUKAN

- Anggi, R. M., & Adaviah, M. (2023). Understanding factors shaping green cosmetic purchase intentions: Insights from attitudes, norms, and perceived behavioral control. *International Journal of Academic Research in Business and Social Sciences*, 13(11), 1487–1496.
- Ainunnazlee, M. A., & Aini, M. S. (2012). Factors influencing consumers in choosing natural cosmetics products. *Jurnal Pengguna Malaysia*, 17–34. eISSN:3030-8799
- Azmi, A. A. (2022). *Faktor-faktor untuk memilih barangan kosmetik halal di Malaysia* [Tesis Ijazah Doktor Falsafah, Universiti Kebangsaan Malaysia]. Bangi.
- Chen, L., & Smith, A. (2021). Consumer behavior in natural cosmetic products. *Journal of Cosmetic Science*, 45(2), 123–135.
- Dr Riam Chau. (2024, Julai). Trans Tech 4TVET bangunkan ekonomi negara. *Sinar Harian*. <https://www.sinarharian.com.my>
- Ilya Syahirah, I., Syed Ashrene, S. O., Azurin, Ahmad Shazeer, M. T., & Sharifah Fazirah, S. A. (2023). Factors influencing purchase intention towards international cosmetic products among Malay women. *Information Management and Business Review*, 15(4), 502–507.
- Justina, R., Caroline, M., & Carlo, S. F. (2015). The effect of scent on consumer behaviour. *International Journal of Consumer Studies*, 39(1), 24–34. <https://doi.org/10.1111/ijcs.12152>
- Norashikin, A., & Hanisah, A. (2023). Faktor-faktor yang mempengaruhi pelajar terapi kecantikan dan spa di Kolej Komuniti Sungai Petani dalam pembelian produk

- kosmetik halal. *Public Health and Safety International Journal*, 3(1), 61–72.
- Pawitra, R., Mei, O., Hui-Hwa, Y., & Yu-Jie, L. (2023). Trends in natural cosmetic usage among Malaysian youth. *Malaysian Journal of Consumer Studies*, 15(3), 45–62.
- Research, A. M. (2022). *Natural cosmetics market global report*. AMR Publishing.
- Sari, A., Hu, F., & He, G. (2021). Effects of design aesthetics on the perceived value of a product. *Frontiers in Psychology*, 12, Article 699260. <https://doi.org/10.3389/fpsyg.2021.699260>
- StrategyH.com. (2025). <https://strategyh.com>
- Unit Audit Universiti Teknikal Malaysia Melaka (UTeM) (2025). <https://audit.utem.edu.my>
- Zhang, N. (2025). Effect of plant aromas on stress recovery and brain activity in university students. *ScienceDirect*. <https://www.sciencedirect.com/>

The Mediating Role of Brand Trust in the Influence of Social Media Marketing Features on Fast-Food Consumer Purchase Decisions

Muhammad Raslah Aiman bin Mohamad*, Khairulazam bin Annuar

Politeknik Merlimau, Melaka.

*Corresponding author: khairulazam_a@pmm.edu.my

Abstract This study investigates the influence of Social Media Marketing Features (SMMF) on Consumer Purchase Decisions (PD) within the Malaysian fast-food restaurant (FFR) industry, specifically examining the mediating role of Brand Trust (BT). Given the FFR sector's high reliance on dynamic digital engagement, understanding the psychological mechanism linking brand content to consumer action is vital. A quantitative approach was employed, collecting data from active FFR consumers in Malaysia. Data were analyzed using Multiple Regression Analysis via SPSS. The results confirmed that SMMF significantly influence PD indirectly through BT, alongside a significant direct effect, supporting the finding of Partial Mediation. The model revealed that the majority of SMMF's efficacy is channeled through building confidence. The findings underscore that successful social media strategies for FFR brands must prioritize establishing consumer confidence and reliability (trust) before influencing final purchase intent. This research offers significant theoretical contributions to the marketing and hospitality literature and provides clear practical implications for FFR marketers seeking to optimize their digital presence.

Keywords: Social Media Marketing Features, Brand Trust, Purchase Decision, Fast-Food Restaurants.

1.0 INTRODUCTION

The fast-food restaurant (FFR) industry operates in an aggressively competitive environment, where the adoption of digital technologies is no longer optional but mandatory for survival and growth. Social media platforms have become the primary arena for customer attention (Sajin, 2023), serving as rich communication channels where FFR brands arrange Social Media Marketing Features (SMMF). These features encompass everything from interactive polls, engaging video content, personalized advertisements, and responsive customer service through direct messaging. Social Media Marketing stands out from traditional methods due to its attributes like interactivity, personalization, and user-generated content, which are key in engaging consumers and building brands (Dabbous & Barakat 2020). These platforms allow real-time interactions, fostering personalized experiences that enhance brand loyalty and drive sales. Additionally, factors such as food quality, price, convenience, and brand image significantly influence consumer behavior in the fast-food market, making it essential for industry stakeholders to understand these elements to influence consumer purchase decisions effectively.

The fast-food industry operates under distinct dynamics that differ from other sectors. The need for quick, effective communication, impulsive purchasing behavior, and the high

frequency of consumer interactions makes this sector unique in terms of social media marketing. Social media platforms provide fast-food chains with the opportunity to directly interact with consumers through features like interactivity, entertainment, and perceived relevance (Hanaysha, 2022a; Jamil et al., 2022). Previous research has demonstrated the significant role of these elements in shaping consumer preferences and purchase decisions in the food and beverage sector (Gad, 2023). Despite extensive studies on SMMF and Purchase Decisions, the psychological mechanism that bridges this relationship, particularly within the fast-paced, impulsive context of the fast-food industry, remains under-specified and empirically underexplored. Specifically, the role of Brand Trust (BT) as a critical psychological middle is often assumed but rarely tested in Malaysian FFR contexts. This study addresses this gap by integrating BT as a mediator to provide a more detail understanding of the SMMF-PD relationship.

This study suggests that Brand Trust (BT)—the consumer's willingness to rely on a brand's competence and compassion—serves as the necessary psychological intermediary. By integrating BT as a mediator, this research aims to provide a slighter difference understanding of the SMMF-PD relationship within the context of Malaysian FFRs.

1.1 Research Objectives and Hypotheses

The primary objective is to investigate the direct and indirect influence of SMMF on PD, mediated by BT.

Based on the theoretical integration of the Source Credibility and Stimulus-Organism Response (S-O-R) frameworks, the following hypotheses were tested:

H1: Social Media Marketing Features (SMMF) have a positive and significant influence on Consumer Purchase Decisions (PD).

H2: Social Media Marketing Features (SMMF) have a positive and significant influence on Brand Trust (BT).

H3: Brand Trust (BT) has a positive and significant influence on Consumer Purchase Decisions (PD).

H4: Brand Trust (BT) mediates the relationship between Social Media Marketing Features (SMMF) and Consumer Purchase Decisions (PD).

2.0 LITERATURE REVIEW

2.1 Purchase Decision

In previous research, the purchase decision has been defined as an individual's choice of a specific product or service offered by a company over those presented by its competitors. This decision-making process can be influenced by internal and external marketing factors. Internal factors encompass beliefs, attitudes, knowledge, personality traits, perceptions, lifestyle, roles, and status (Wardhana et al., 2023). Conversely, external factors encompass cultural influences, membership in certain groups, and social class. With the proliferation of diverse product/service offerings and multiple alternatives available to consumers, service providers have acknowledged the difficulty in attracting and retaining key customers, which is crucial for sustained growth and market presence (Borg & Schoonover, 2020). Marketing

practitioners have observed a shift in consumer behaviors, noting their increased comfort in using internet channels and social media platforms to connect with others. Consequently, many service providers have established their own social network pages to engage with customers online and cultivate positive brand perceptions (Wang & Lee, 2020)

2.2 SMMF, Brand Trust, and Purchase Decision

Social Media Marketing Features (SMMF): In earlier literature, researchers have explored diverse components of social media marketing to ascertain their influence on consumer purchasing behavior (Alalwan., 2018 & Jamil et al., 2022). Effective SMMF are critical for cutting through the digital noise and establishing brand salience.

Brand Trust (BT): Conceptualized as a consumer's feeling of security based on the belief that a brand is reliable and will meet their expectations. In the FFR context, this relates to faith in product quality, accurate service delivery, and ethical operations. As outlined in earlier literature, brand trust denotes consumers' inclination to rely on a brand to deliver on its explicitly or implicitly stated commitments (Cardoso et al., 2022)

Purchase Decision (PD): Refers to the consumer's behavioral intent and following action to choose a specific FFR brand and purchase its offerings. The literature review supports the proposed direct links: SMMF are necessary to capture attention and provide information that aids in PD (H1). More importantly, the transparency and consistent engagement delivered via SMMF are seen as signals of reliability, which directly contribute to the build-up of BT (H2). Once established, Brand Trust acts as a powerful assurance mechanism, mitigating perceived risk and strongly driving the ultimate PD (H3).

2.3 The Mediating Hypothesis

The central argument of H4 is that SMMF are primarily effective in driving sales because they first foster trust. When consumers encounter a brand's quality social content (SMMF), they develop a sense of reliability (BT). This reliability then becomes the key factor that differentiates the FFR brand from competitors, simplifying the purchase choice and reducing cognitive load during the decision process. Therefore, the effect of SMMF on PD is not just direct but significantly channeled through the establishment of Brand Trust.

3.0 METHODOLOGY

3.1 Research Design and Sampling

A quantitative research design utilizing a cross-sectional survey was employed. The target population comprised Malaysian consumers aged 18 and above who actively follow or interact with FFR brands on social media platforms (such as Facebook, Instagram, and TikTok). Due to the specific focus on individuals who are active users of social media marketing features (SMMF) related to FFRs, a non-probability convenience sampling technique was employed. This approach was supposed the most practical and efficient method for reaching this specialized, non-general population of highly engaged consumers within the research timeframe and resource limitations. This allowed the study to gather

relevant data directly from those whose behavior is most likely influenced by SMMF, aligning just with the research objectives.

Table 1: Demographic table

Code	Items	Measures	Sources
A1	Gender	Male Female	
A2	Age	18 - 25 years 26 - 33 years 34 - 41 years 42 - 49 years 50 - 60 years	
A3	Educational level	Primary or Secondary school Diploma or equivalent Bachelor's Degree Master Degree Doctorate Degree	
A4	State of Origin	Terengganu, Pahang, Kedah, Selangor, Perak, Melaka, Negeri Sembilan, Johor, Kelantan, Pulau Pinang, Sabah, Sarawak, Wilayah Persekutuan, Perlis, Wilayah Persekutuan Putrajaya, Wilayah Persekutuan Labuan.	

3.2 Instrumentation and Measurement

The measurement scales for all latent constructs were adapted from rigorous existing literature and assessed using a five-point Likert scale (1 = Strongly Disagree to 5 = Strongly Agree). The constructs were operationalized as follows:

- Social Media Marketing Features (SMMF): Measured by items focusing on perceived quality of content, interactivity, and perceived entertainment value.
- Brand Trust (BT): Measured through items assessing the brand's reliability, honesty, and intention to fulfill customer needs.
- Purchase Decision (PD): Measured by items capturing repurchase intention, recommendation intention, and preference over competitors.

3.3 Data Analysis

Data analysis was conducted using SPSS (Statistical Package for the Social Sciences, version 26.0 or higher). The procedure involved three main steps:

- Descriptive and Reliability Analysis: Descriptive statistics were used to summarize the sample demographics. Internal consistency for all scales was verified using Cronbach's Alpha.

- ii. Hypothesis Testing (H1, H2, H3): Standard Simple Linear Regression Analysis was employed to test the direct relationships. This involved regression models where BT and PD served as dependent variables, respectively.
- iii. Mediation Testing (H4): The mediation effect was tested using the Baron and Kenny (1986) four-step approach to determine the existence of mediation, and the significance of the indirect effect was statistically confirmed using the Sobel Test.

4.0 RESULTS

4.1 Reliability and Validity Assessment

The internal consistency of all measurement instruments was confirmed through Cronbach's Alpha, with all constructs exceeding the acceptance threshold of 0.70, as tabulated in Table 2.

Table 2: Measurement Instruments

Construct	Cronbach's Alpha (α)	Number of Items
SMMF	0.968	15
BT	0.939	10
PD	0.959	8

The cross-sectional nature of the data collection, where all constructs were measured using self-reported questionnaires at a single point in time, suggests a potential susceptibility to Common Method Bias (CMB). To minimize this risk, several procedural techniques were implemented during the survey design and data collection process:

- i. Anonymity: Respondents were assured that their identity would not be revealed, and all answers would be kept private. This helped reduce the chance of them giving answers just to look good.
- ii. Clear Instructions: The questions were written in an easy and clear way, and the answer scales were placed neatly and separately in the questionnaire.

4.2 Simple Linear Regression Analysis and Hypothesis Testing

The regression models demonstrated good fit and predictive power. The model predicting Brand Trust explained $R^2 = 0.42$ of the variances, and the final model predicting Purchase Decision explained $R^2 = 0.58$ of the variances.

Table 3 presents the results of the Multiple Regression analysis for the paths, where β refers to the standardized regression coefficient:

Table 3: Multiple Regression analysis

Hypothesis	Path	B	t-Value	Standardized Beta (β)	Finding
H1	SMMF to PD	.737	11.818***	0.757	Supported
H2	SMMF to BT	.780	12.400	0.766	Supported
H3	BT to PD	.804	16.332	0.844	Supported

All direct hypotheses (H1, H2, and H3) were strongly supported, indicating significant positive relationships between all primary constructs in the model. The strongest direct influence was observed from SMMF to BT (H2).

4.3 Mediation Analysis (H4)

The mediation effect was tested following the steps necessary to establish mediation. The analysis confirmed:

- i. SMMF significantly predicted PD (H1 supported, Path c).
- ii. SMMF significantly predicted BT (H2 supported, Path a).
- iii. BT significantly predicted PD when SMMF was also in the model (H3 supported, Path b).

Crucially, when both SMMF and BT were included in the final regression model predicting PD, the coefficient for the direct effect of SMMF on PD decreased significantly but remained statistically significant. This finding confirms that Brand Trust partially mediates the relationship between Social Media Marketing Features and Consumer Purchase Decisions (H4 supported).

The indirect effect was confirmed as significant by the Sobel Test ($z = 5.21, p < 0.001$). The magnitude of the indirect effect (approx. 0.325) compared to the total effect (approx. 0.535) confirms that BT accounts for approximately 60.7% of the total influence, underscoring its key role.

5.0 DISCUSSION AND CONCLUSION

5.1 Discussion

The findings provide compelling empirical evidence for the established conceptual framework. The significant results across all tested hypotheses confirm that SMMF, BT, and PD are strongly interconnected in the FFR consumer context.

5.1.1 Interpretation of Key Findings

Three main element of finding are discussed as the following:

- i. SMMF and Brand Trust is Primary (H2 Supported)

The path from SMMF to BT exhibited the strongest coefficient ($\beta=0.648$). This suggests that the primary function of effective social media marketing in the FFR industry is not instant conversion, but the consistent, long-term building of **trust**. Consumers interpret interactive, transparent, and responsive SMMF as signals of brand competence and benevolence, aligning perfectly with the core tenets of Source Credibility Theory.

- ii. Trust as the Purchase Engine (H3 Supported):

The strong positive effect of BT on PD ($\beta=0.501$) is crucial. In a market saturated with

options, FFR consumers rely on existing trust to simplify their decisions. When trust is established, the perceived risk of a poor meal, hygiene issues, or delivery failure is minimized, leading to a higher willingness to purchase.

iii. Partial Mediation Confirmed (H4 Supported):

The partial mediation result is the most significant finding. It indicates that the 60.7% of the total influence SMMF has on PD is channeled through Brand Trust. While a well-designed promotional post (SMMF) may directly trigger a purchase (H1), the *sustained* impact and repeat business are fundamentally driven by the confidence that social media activities have instilled. This highlights a strategic imperative: FFR brands must treat their social channels as trust repositories, not just advertising platforms.

5.1.2 Theoretical and Practical Implications

This study successfully validates the S-O-R framework in the context of digital consumer behavior in the hospitality sector. It empirically confirms BT as a necessary Organism state that transforms external digital stimuli (SMMF) into behavioral responses (PD), resolving ambiguity found in earlier models that only tested the direct SMMF-PD link. The findings are a notable contribution to the literature on digital marketing and consumer psychology within the FFR industry, particularly from the underrepresented Malaysian market perspective.

Practical Implications:

- i. For FFR marketers, the findings necessitate a strategic shift:
- ii. Focus on Trust Content: Prioritize SMMF content that showcases operational transparency, food quality, and ethical sourcing
- iii. Enhance Responsiveness: Treat social media customer service as a high-priority function, as rapid and helpful responses directly build confidence and signal brand care, thereby reinforcing BT.
- iv. Measure BT, Not Just Engagement: Marketing KPIs should expand beyond simple likes and shares to include metrics that track brand trust and perceived reliability, as these are the true long-term drivers of sales.

5.2 Conclusion

This research confirms the pivotal role of Social Media Marketing Features in influencing Consumer Purchase Decisions, establishing that Brand Trust acts as a critical partial mediator in this relationship. The partial mediation finding highlights that FFR brands must deploy SMMF not just to persuade, but to consistently build and maintain a strong foundation of consumer trust. For long-term viability, success in the digital fast-food market is inextricably linked to perceived reliability, honesty, and competence fostered through quality social media engagement.

This study utilized a cross-sectional design, which captures relationships at a single point in time and limits the ability to infer complex causality or temporal dynamics. Future research directions should include:

- a. Longitudinal Studies: Implementing a time-lagged design to observe how changes in SMMF strategies over six to twelve months affect the evolution of Brand Trust and subsequent Purchase Decisions.
- b. Dimensional Analysis: Disaggregating the SMMF construct into specific sub-dimensions (e.g., hedonic content, informative content, interactivity) to identify which specific features are the most powerful antecedents of Brand Trust.
- c. Multi-Brand Comparative Study: Comparing the mediation strength of Brand Trust across different FFR brand categories (e.g., premium vs. budget chains) or international markets.

REFERENCES

- Alalwan, A. A. (2018). Investigating the impact of social media advertising features on customer purchase intention. *International journal of information management*, 42, 65-77.
- Baron, R. M., & Kenny, D. A. (1986). The moderator-mediator variable distinction in social psychological research: Conceptual, strategic, and statistical considerations. *Journal of Personality and Social Psychology*, 51(6), 1173–1182. (New Citation for SPSS Mediation)
- Borg, D., Mont, O., & Schoonover, H. (2020). Consumer acceptance and value in use-oriented product-service systems: lessons from Swedish consumer goods companies. *Sustainability*, 12(19), 8079.
- Dabbous, A., & Barakat, K. (2020). Bridging the online offline gap: Assessing the impact of brands' social network content quality on brand awareness and purchase intention. *Journal of Retailing and Consumer Services*, 53, 101966. <https://doi.org/10.1016/j.jretconser.2019.101966>.
- Gad, K. (2023). The Impact of Social Media Marketing on Purchase Decision through Customer Experience: An Empirical Study on Skin and Hair Care Products in Egypt. *Arab Journal of Administration*, 46(1).
- Hanaysha, J. R. (2022a). Exploring the Impact of Social Media Marketing Features on Purchase Intention in the Fast-Food Industry. *Metamorphosis*, 21(2), 75-85.
- Jamil, K., Liu, D., Gul, R., Shehzad, M., Gillani, S., & Awan, F. (2022). Role of Social Media Marketing Activities in Influencing Customer Intentions: A Perspective of a New Emerging Era. *Frontiers in Psychology*, 12. <https://doi.org/10.3389/fpsyg.2021.808525>.
- Sajin, V. (2023). Social media marketing and digital marketing. Culegere de lucrari stiintifice: Simpozion stiintific al tinerilor cercetatori, vol 2. <https://doi.org/10.53486/9789975359030.37>.

- Wang, T., & Lee, F. Y. (2020). Examining customer engagement and brand intimacy in social media context. *Journal of retailing and consumer services*, 54, 102035.
- Wardhana, A., Pradana, M., Syarifuddin, S., Alves, A., & Firmansyah, I. (2023, April). Marketing mix analysis of an Internet service provider in Indonesia. In *International Conference on Mathematical and Statistical Physics, Computational Science, Education, and Communication (ICMSCE 2022)* (Vol. 12616, pp. 75-79). SPIE.
- Cardoso, A., Gabriel, M., Figueiredo, J., Oliveira, I., Rêgo, R., Silva, R., Oliveira, M., & Meirinhos, G. (2022). Trust and Loyalty in Building the Brand Relationship with the Customer: Empirical Analysis in a Retail Chain in Northern Brazil. *Journal of Open Innovation: Technology, Market, and Complexity*. <https://doi.org/10.3390/joitmc8030109>.

**TRACK 3:
TOURISM AND HOSPITALITY**

Development of Interactive E-Poster To Promote Aesthetic Spots In Bandar Hilir, Melaka

Zuraida Yaacob*, Faizah Yusof, Nadzirah Bt Sulaiman, Siti Azieyatul Elliya Bt Azian, Nurul Hasyareena Bt Roszaima

Department of Tourism and Hospitality, Politeknik Merlimau Melaka,
KM2.5 Jalan Merlimau Jasin, 77300 Merlimau, Melaka

*zuraida@pmm.edu.my

Abstract This study aimed to identify key aesthetic spots in Bandar Hilir, Melaka and to develop an interactive e-poster to promote these locations among tourists. A quantitative research design was employed, using a structured questionnaire distributed to 30 local visitors. Demographic analysis revealed that 83% of respondents were aged 18–25 and 66% were female, with Instagram and Twitter being the most preferred social media platforms (51%). Based on respondents' feedback, six locations were identified as the most visually appealing. These were featured in the e-poster, which included QR codes, GPS links and pose suggestions to enhance the user experience. Evaluation results showed high satisfaction across all design aspects, with the highest-rated feature being technological integration with mean score 4.70, followed by font type readability and willingness to share the poster (both mean score 4.63). The lowest-rated item visibility on social media still received a moderate score with 4.17 mean, indicating potential for improvement in outreach strategy. The findings affirm that a visually driven, interactive digital tool like an e-poster can significantly enhance tourist engagement, navigation and aesthetic appreciation in heritage destinations like Bandar Hilir.

Keywords: Aesthetic spots, Bandar Hilir, Digital marketing, E-poster, Tourist attraction

1.0 INTRODUCTION

Tourism plays a central role in economic development, cultural preservation, and destination branding (Ismarizal, & Kusumah, 2023). As global travel behavior evolves, destination attractiveness is increasingly influenced by visual qualities and experiential value rather than traditional historical narratives alone (Stylidis, 2018; Wang et al., 2020). Digital technologies have heightened this shift, with modern visitors—particularly those of younger demographics—seeking visually appealing and “Instagrammable” spaces (Gretzel & Jamal, 2022). Bandar Hilir, located within Melaka’s UNESCO World Heritage Site, exhibits distinctive architectural, cultural, and aesthetic features. However, existing promotional materials remain largely static and informational, relying on brochures, signage, and conventional tour guiding (Sigala, 2018). Studies indicate that heritage destinations that fail to provide visually engaging digital content risk reduced visibility and weaker tourist engagement (Xiang et al., 2022; Mariani & Borghi, 2021).

Currently, Bandar Hilir lacks a thematic, visually focused digital platform that highlights aesthetic spots relevant to contemporary tourists who prioritize photography,

content creation, and seamless navigation (Lim & Ramli, 2023). The absence of such tools results in fragmented visitor experiences and underutilization of visually appealing micro-destinations. The absence of thematic, aesthetic-focused visual guides in Bandar Hilir has contributed to a fragmented visitor experience, especially for tourists who rely on photography and content creation as central elements of their journey. Current promotional materials emphasize general historical facts or directions without offering experiential or visual context. This lack of cohesive visual information not only diminishes satisfaction but also discourages deeper exploration of the city's hidden gems. A centralized, interactive solution that maps out aesthetic attractions while offering photography tips and navigation support is thus essential for meeting the expectations of modern travelers and enriching the tourism experience (Xiang & Gretzel, 2022).

To address this gap, this study introduces the development of an interactive e-poster that integrates QR codes, navigation links and pose suggestions. This digital tool serves as both an aesthetic guide and a visual marketing medium to promote the most scenic locations in Bandar Hilir. This aligns with Malaysia's National Tourism Policy (MOTAC, 2022), which prioritizes smart tourism tools and digital innovation. The main objectives of this study are to identify key aesthetic spots in Bandar Hilir based on visitors' perceptions and to develop an interactive e-poster that promotes these locations digitally.

2.0 LITERATURE REVIEW

Tourism aesthetics have evolved from passive observation to participatory and experiential engagement. Modern visitors expect immersive and shareable moments that align with digital storytelling trends (Wang et al., 2020; Hunter, 2021). Visual representation and aesthetic identity play significant roles in shaping destination image and emotional attachment. Destination image research has expanded from cognitive-affective models (Echtner & Ritchie, 2003) to incorporate digital visibility and aesthetic immersion (Brito et al., 2021). Recent studies emphasize the role of visually curated spaces in shaping emotional resonance, especially in heritage contexts where authenticity and aesthetics intersect (Tussyadiah, 2020; Koo et al., 2023). The prominence of aesthetic experiences is further amplified by mobile photography and real-time content sharing (Hunter, 2021)

The rise of visually driven platforms such as Instagram, TikTok, and YouTube has transformed how tourists discover, interpret, and share spatial experiences (Li & Lee, 2023). User-generated content is now more influential than official tourism promotions (Gretzel et al., 2021). Younger travelers, in particular, gravitate towards authentic, relatable visuals over polished marketing imagery (Ayeh, 2020; Lim et al., 2021). Smart tourism technologies including QR codes, e-posters, augmented reality, and digital maps have become essential tools for enhancing visitor engagement (Jung & tom Dieck, 2017; Koo et al., 2023). These interactive media improve accessibility, personalization, and navigational ease (Mariani & Borghi, 2021; Xiang et al., 2022). Recent studies confirm that mobile-friendly, visually engaging tools significantly increase tourists' motivation to explore new spaces (Castanho, et.al, 2023). Heritage destinations face unique challenges in balancing authenticity with digital innovation (Stylidis et al., 2022). Many heritage cities still rely on outdated promotional materials that lack interactivity (Lim & Ramli, 2023). Integrating digital aesthetics through tools like interactive e-posters can help attract tech-savvy tourists without compromising cultural identity (Rahim et al., 2022).

3.0 METHODOLOGY

This study employed a quantitative research design supported by descriptive statistics. Guided by Creswell's (2014) methodological framework, a structured approach was implemented to ensure systematic data collection, product development, and evaluation. Data were gathered using a structured questionnaire, which enabled the researchers to obtain specific and measurable insights into tourists' behaviours, preferences, and perceptions of visual aesthetics. The instrument was designed to (i) identify the most aesthetically appealing locations in Bandar Hilir, (ii) assess tourists' expectations for a digital navigational aid, and (iii) evaluate the usability and design effectiveness of the developed interactive e-poster. The questionnaire comprised three sections which is

- i. Section A focused on demographic information (age, gender, and preferred social media platforms).
- ii. Section B examined respondents' perceptions of aesthetic value across selected locations in Bandar Hilir
- iii. Section C evaluated the usability and visual appeal of the interactive e-poster using a 5-point Likert scale.

A random sampling method was employed to target individuals who had recently visited Bandar Hilir. A total of 30 respondents, consisting of local tourists within the area, participated in the study. Although the sample size is relatively small, it represents a relevant group of tech-literate users who actively engage with digital and visual content on social media.

The development of the interactive e-poster followed several key stages, including conceptualisation, design drafting, multimedia integration, and user testing. This systematic process ensured that the final product was visually cohesive, functional, and aligned with contemporary digital tourism expectations.

Step 1: Design Draft for Media Tools

- Initial sketches were developed based on site observations and visual aesthetics. Each location included in the e-poster was assigned a dedicated segment with visual thumbnails, short descriptions, and a QR code leading to digital content.

Step 2: QR Code and Map Integration

- Using the Linktree platform, the team generated unique links for each location. QR codes were embedded into the e-poster that, when scanned, led users to two key features:
- Google Map route to the location.
- A tutorial or visual guide for capturing the best photographic angles.

Step 3: Multimedia and Visual Design

- Design software such as Canva, Adobe Photoshop, and ibisPaint X were used to produce a visually consistent and engaging digital poster. Attention was given to visual hierarchy, color harmony, and typography, aligning with contemporary aesthetic design standards (Delve, 2017).

Step 4: Publication and Distribution

- The final product was distributed digitally via social media platforms (Instagram, Facebook, Twitter), chosen based on respondents' usage trends from the survey. The e-poster was formatted for mobile- friendly display and optimized for sharing.

The following tools were employed throughout the research and production process:

- Design Applications: Canva (for layout), Adobe Photoshop (for image enhancement), ibisPaint X (for illustration).
- QR Code Generator: Linktree, used to house multiple links per location.
- Photography Equipment: Nikon DSLR and mobile smartphones were used to capture original images of aesthetic spots.
- Data Collection: Google Forms was used for distributing questionnaires.
- Statistical Analysis: SPSS (Statistical Package for the Social Sciences) was employed to analyze survey results, including mean scores and frequency distributions.
- These tools were selected for their accessibility, reliability, and ability to integrate across platforms, ensuring seamless workflow from data gathering to design execution.

Once the data was collected through Google Forms, it was exported into SPSS for analysis. The data analysis focused on descriptive statistics. Mean Scores calculated for each item in the Likert-scale section to determine the overall satisfaction with the e-poster.

4.0 FINDINGS & DISCUSSION

The demographic data presented in Table 1 reveals insightful trends that are strongly aligned with the project's objectives and the literature underpinning visual and digital tourism behavior.

Table 1 : Demographic distribution

Category	Percentage (%)
Age Group	
Age 18–25	83.0%
Age 26–33	11.0%
Age 42 and above	6.0%
Gender	
Female Respondents	66.0%
Male Respondents	34.0%
Preferred Social Media Platforms	
Instagram & Twitter	51.0%
Twitter (alone)	24.0%
Facebook	20.0%
Pinterest	5.0%

The results confirm that young, digitally fluent visitors dominate tourist behaviour in Bandar Hilir, supporting literature on visual-centric tourism (Stylidis, 2018; Hunter, 2021).

Table 2: Locations were most frequently selected

Aesthetic Spot	Percentage of Respondents
Jalan Laksamana	16.7%
Jalan Tukang Besi	13.3%
Kiehl's Heritage Murals	13.3%
Heeren House	13.3%
Nomaps	10.0%
Dutch Harbour Café	10.0%
Clock Tower	3.3%

The data presented in Table 2 identifies the six most frequently selected aesthetic locations in Bandar Hilir, based on respondents' perceptions. These results serve as a direct input for the content design of the interactive e-poster, aligning with the study's objective of promoting visually appealing tourist spots. The most popular aesthetic spot, Jalan Laksamana (16.7%), is known for its colonial-era charm and vibrant pedestrian life, making it an ideal backdrop for photography. This is followed closely by Jalan Tukang Besi (13.3%), Kiehl's Heritage Murals (13.3%), and Heeren House (13.3%), all of which possess distinct visual elements such as murals, vintage architecture, and curated façades that appeal to tourists seeking "Instagrammable" scenes. These selections reflect Fitzmaurice's (2001) argument that tourists are drawn to locations offering novel aesthetic experiences that stand out from their everyday environment.

Interestingly, Nomaps (10.0%) and Dutch Harbour Café (10.0%) also made the list, showing that hospitality-based locations such as themed cafés and boutique accommodations can function as dual-purpose destinations, offering both service and scenic value. This supports Breiby's (2014) observation that the tourism aesthetic is increasingly multidimensional, integrating elements of lifestyle, ambiance, and setting. On the other hand, Clock Tower, a traditionally recognized landmark, was rated the lowest (3.3%).

This suggests a shift in tourist preferences toward less conventional, more personalized visual environments, rather than iconic but overexposed landmarks. As suggested by Zhang, Zhao, and Xu (2015), contemporary tourism trends are shaped by social media "micro-trends," where smaller, niche spots gain popularity through digital sharing rather than institutional promotion. The findings reveal alignment with current trends where niche, visually distinctive spaces outperform iconic landmarks in digital popularity (Zhang et al., 2015).

The results in Table 3 present a comprehensive evaluation of the interactive e-poster, based on user perceptions of design, usability, functionality, and content relevance. The evaluation utilized a 5- point Likert scale show mean. Overall, the evaluation indicates a high level of satisfaction across all 16 items, with mean scores ranging from 4.17 to 4.70 positive agreement across the board. These findings validate the usability and appeal of the interactive e-poster as an innovative tourism promotion tool. The evaluation of the interactive e-poster revealed several important insights regarding its design, functionality and user acceptance.

Among the highest-rated features was its alignment with modern technological expectations (Mean = 4.70), indicating that users strongly valued the inclusion of digital elements such as QR codes, mobile responsiveness, and interactive links characteristics essential for contemporary tourism tools, as highlighted by Masters et al. (2015). Similarly, features like font type readability and the likelihood of sharing the poster (both Mean = 4.63) underscore the significance of user-friendly design and viral potential. These findings reflect Yasmin et al.'s (2015) emphasis on clarity and shareability as crucial components in digital marketing effectiveness.

Table 3: E-Poster Evaluation Summary

Item	Mean
Interesting features	4.47
Color palette	4.47
Graphic selection	4.57
Font type	4.63
Font size	4.40
In line with technology	4.70
Ease of use	4.60
Ease of QR code	4.53
GPS link accessible	4.43
Pose suggestions	4.57
Easily found on social media	4.17
Locate aesthetic spots easily	4.40
Easy to share	4.43
Likely to share with friends/family	4.63
Meets information needs	4.57
Easy to understand	4.53

Further supporting this perspective, the poster's ease of use (4.60) and clarity of content (4.53) affirm its accessibility to a broad range of users, reinforcing the importance of intuitive layout and concise information delivery in visual communication. Visually, the poster also performed strongly; graphic selection and pose suggestion guides each scored 4.57, demonstrating that the aesthetic presentation of information met user expectations and encouraged social media interaction echoing notion that tourists are drawn to locations and tools offering visually enriching experiences. From a functionality standpoint, embedded navigational features such as QR code usability (4.53) and GPS link accessibility (4.43) were also well-received. These elements enhance the poster's practicality by enabling tourists to independently access, locate, and explore aesthetic spots, aligning with Delve's (2017) observations on the growing importance of interactive media in destination promotion.

Nonetheless, a few areas were noted for improvement. The item "easily found on social media" received the lowest score (4.17), highlighting a visibility gap that may stem from insufficient promotion or suboptimal tagging strategies. Additionally, items such as font size (4.40) and ease of locating aesthetic spots (4.40), while still rated highly, suggest opportunities for minor refinements in visual hierarchy and directional clarity. Overall, all poster features received mean scores above 4.0, signifying consistent satisfaction and confirming that the interactive e-poster is a well-rounded, engaging, and effective digital tool.

It demonstrates strong potential for real-world application in tourism promotion, particularly among younger, visually oriented travelers who depend on mobile-based guidance and visual stimuli when exploring destinations.

The findings confirm that the interactive e-poster effectively meets its intended objectives: it identifies and visually promotes aesthetic locations in Bandar Hilir, and it is well-received by users in terms of design and functionality. The mean scores indicate a high level of satisfaction, particularly with the poster's aesthetics, ease of use, and relevance to modern technology. However, some areas, such as distribution visibility on social media, present opportunities for enhancement.

5.0 DISCUSSION AND CONCLUSION

The study successfully achieved its objectives of identifying aesthetic spots in Bandar Hilir and developing an interactive e-poster to promote them. Through survey responses from 30 digitally active tourists primarily aged 18 - 25 the most visually appealing locations such as Jalan Laksamana, Kiehl's Heritage Murals, and Heeren House were identified and featured in the e-poster. The second objective was fulfilled by designing a user-friendly, visually attractive e-poster integrated with QR codes and GPS navigation. The evaluation results showed high satisfaction across all design and functional aspects, with respondents affirming that the e-poster was easy to use, aligned with modern technology, and effective in helping them locate aesthetic spots. In response to the research questions, the study determined that key aesthetic spots are concentrated around heritage and lifestyle areas in Bandar Hilir, and that an interactive e-poster when optimized for mobile use and social sharing is a highly suitable medium for promoting them.

REFERENCES

- Ayeh, J. K. (2020). Authenticity in tourism experience: The role of social media content. *Journal of Travel & Tourism Marketing*, 37(3), 335–349.
- Brito, P. Q., Costa, C., & Leal, C. (2021). Visual storytelling in cultural tourism: Enhancing visitor experiences. *Journal of Destination Marketing & Management*, 19, 100507.
- Castanho, R. A., Santos, C., & Couto, G. (2023). Creative Tourism in Islands and Regional Sustainable Development: What Can We Learn from the Pilot Projects Implemented in the Azores Territory? *Land*, 12(2), 498.
- Creswell, J. W. (2014). *Research design: Qualitative, quantitative, and mixed methods approaches* (4th ed.). Sage Publications.
- Delve, R. (2017). *Design principles for interactive digital media*. Routledge.
- Echtner, C. M., & Ritchie, J. R. B. (2003). The meaning and measurement of destination image. *Journal of Tourism Studies*, 14(1), 37–48.
- Gretzel, U., & Jamal, T. (2022). Digital natives and tourism experiences: Social media, selfies, and visual storytelling. *Journal of Hospitality and Tourism Technology*, 13(3), 563–579.

Gretzel, U., Sigala, M., Xiang, Z., & Koo, C. (2021). *Smart tourism: Foundations and developments*.

Springer.

Hunter, W. C. (2021). Tourists as co-creators: Visual storytelling in the digital age. *Tourism Review International*, 25(2), 101–118.

Ismarizal, B., & Kusumah, A. H. G. (2023). The Instagram Effect on Tourist Destination Choices: Unveiling Key Attraction Elements. *Journal of Consumer Sciences*, 8(2), 124–137.

Jung, T., & tom Dieck, M. C. (2017). Augmented reality and virtual reality in tourism marketing. In D. Buhalis & C. Costa (Eds.), *Tourism management: Digital marketing and smart tourism* (pp. 207–223). Springer.

Koo, C., Yoo, K. H., & Chung, N. (2023). QR code-based smart tourism applications: User acceptance and behavioural intention. *International Journal of Information Management*, 66, 102528.

Li, M., & Lee, S. (2023). Social media and the construction of digital place meaning in tourism. *Journal of Destination Marketing & Management*, 29, 100817.

Lim, S., & Ramli, N. (2023). Promoting heritage tourism in Malaysia through digital storytelling. *Journal of Heritage Tourism*, 18(4), 455–472.

Mariani, M., & Borghi, M. (2021). Online reviews and user-generated content in tourism: Trends and implications. *Current Issues in Tourism*, 24(2), 192–202.

MOTAC (Ministry of Tourism, Arts and Culture Malaysia). (2022). *National tourism policy 2022–2030*. Putrajaya: Ministry of Tourism, Arts and Culture Malaysia.

Sigala, M. (2018). *Social media and customer engagement in the travel industry*. Routledge.

Stylidis, D. (2018). Understanding the role of aesthetic and experiential value in heritage tourism.

Tourism Management, 68, 235–245.

Stylidis, D., Biran, A., Sit, J., & Szivas, E. (2022). Heritage tourism and visual experience: A multi-dimensional approach. *Annals of Tourism Research*, 92, 103341.

Tussyadiah, I., & Wang, D. (2021). Web-based interactive media and visitor engagement. *Information Technology & Tourism*, 23(2), 289–308. Wang, D., Li, X., & Li, Y. (2020).

Tourism experience in the age of social media: Visual storytelling and digital engagement. *Journal of Travel Research*, 59(8), 1391–1405.

- Xiang, Z., & Gretzel, U. (2022). Smart tourism and digital engagement in heritage destinations. *Journal of Destination Marketing & Management*, 23, 100703.
- Yasmin, F., Ahmad, S., & Rahman, M. (2015). Impact of social media on tourist decision-making: A Malaysian perspective. *Procedia – Social and Behavioral Sciences*, 172, 420–427.
- Zhang, H., Zhao, S., & Xu, H. (2015). Micro-trends in social media tourism: Niche locations gaining popularity. *Tourism Management Perspectives*, 16, 312–319.

Upcycling Textile Waste into Functional Outerwear: Technical Development and Evaluation of the Hydrapack Jacket

Noni Lela Hayati Ayob*, Rohayatul Akma Abu Bakar, Siti Nur Shafiqah Alia Sharudin,
Mohamad Aiman Nasrullah Bin Sabarman

Department of Tourism and Hospitality, Politeknik Merlimau,
77300, Merlimau Melaka.

Correspondence e-mail: [*noni@pmm.edu.my](mailto:noni@pmm.edu.my)

Abstract The global rise in textile waste and the environmental burden of fast fashion highlight the need for innovative, sustainable design solutions. This study addresses this challenge by developing and evaluating the HydraPack Jacket, a functional outerwear prototype created through the upcycling of discarded polyester, nylon, and post-consumer fabrics. Guided by principles of sustainable fashion and circular product development, the research aimed to: (1) construct a windbreaker prototype using upcycled materials, (2) evaluate its design, durability, comfort, and sustainability awareness through user-centered assessment, and (3) examine the feasibility of upcycling as a viable strategy for sustainable fashion in Malaysia. An applied research design was employed, involving material preparation, prototype assembly, and a structured user evaluation. Forty-five Diploma students participated using structured questionnaires consisting of four constructs measured on a five-point Likert scale. Reliability analysis indicated strong internal consistency (Cronbach's $\alpha = 0.78\text{--}0.86$). Results revealed consistently high user agreement across all attributes (means = 1.91–2.04), indicating positive perceptions of the prototype's functionality, aesthetic appeal, and environmental value. The findings confirm that upcycled textiles can achieve performance and comfort levels comparable to conventional apparel, challenging assumptions that recycled materials compromise product quality. The HydraPack Jacket also aligns with Sustainable Development Goals, particularly SDG 12 (Responsible Consumption and Production) and SDG 13 (Climate Action), by demonstrating resource-efficient design and encouraging sustainable consumption. Overall, the study provides a replicable model for integrating upcycling into sustainable apparel development and offers valuable insights for advancing circular fashion practices within Malaysia's textile and fashion industries.

Keywords: Upcycling, sustainable fashion, circular economy, eco-innovative apparel, textile waste management

1.0 INTRODUCTION

The global fashion industry remains one of the leading contributors to textile pollution, with Malaysia alone generating more than 200,000 tons of discarded clothing annually (Environmental Innovations, 2020). A large proportion of this waste consists of synthetic materials such as polyester, which require centuries to decompose and release harmful microplastics and chemical pollutants during degradation (Textile Exchange, 2019).

The rapid expansion of fast fashion continues to exacerbate these issues, promoting overconsumption and short product life cycles that result in frequent garment disposal (Bick, Halsey, & Ekenga, 2018). The United Nations Environment Programme (2018) estimates that global textile waste could increase by 60% by 2030 if current consumption patterns persist. Despite these alarming projections, Malaysia still lacks comprehensive textile recycling infrastructure and regulatory frameworks capable of managing post-consumer apparel waste effectively (Solid Waste and Public Cleansing Corporation, 2020). Meanwhile, countries with established circular textile ecosystems have adopted extended producer responsibility (EPR) policies and national take-back schemes (ETC CE, 2023; van Duijn, 2022), whereas equivalent initiatives in Malaysia remain limited. Compounded by low public participation in sustainable fashion practices and inadequate consumer education (Ameera Huda, 2024), the need for systemic reform is urgent. As Nik Suzila (2024) argues, coordinated action between policymakers, industry stakeholders, and consumers is essential to developing a sustainable textile management system in Malaysia.

In response to these challenges, this study introduces an upcycling-based solution through the development of the HydraPack Jacket, a sustainable outerwear prototype constructed from recycled polyester, nylon, and post-consumer fabrics. The jacket incorporates multifunctional design elements—including a detachable hydration system, integrated storage compartments, and lightweight construction—to enhance durability, practicality, and usability while minimizing environmental impact. The project aligns with the United Nations Sustainable Development Goals (SDG), specifically SDG 12 (Responsible Consumption and Production) and SDG 13 (Climate Action), by demonstrating how recycled materials and eco-conscious design strategies can support sustainable consumption patterns. The study aims to (1) develop a functional windbreaker prototype using upcycled textile waste; (2) evaluate the prototype's design, comfort, durability, and sustainability awareness using a user-centered assessment; and (3) examine the potential of upcycling as a viable approach to sustainable fashion and circular product development in Malaysia.

The novelty of this research lies in its integration of sustainability with real-world functionality, illustrating how affordable, practical garments can simultaneously address environmental challenges and meet user needs. By implementing advanced sustainable design strategies, such as zero-waste pattern cutting and modular components, the project demonstrates ways to reduce production waste and carbon footprint. The use of recycled materials further highlights the potential of upcycling to conserve energy, reduce landfill waste, and lower greenhouse gas emissions, reinforcing its relevance within a circular economy framework.

The HydraPack Jacket project offers an innovative and practical response to Malaysia's increasing textile waste problem while contributing to the broader discourse on sustainable apparel design. By merging eco-friendly materials, functional engineering, and user-centered evaluation, the study demonstrates that sustainable fashion can be both environmentally responsible and commercially viable. These insights provide valuable implications for policymakers, designers, and manufacturers as Malaysia advances towards more circular and responsible approaches in the fashion and textile industries.

2. LITERATURE REVIEW

The literature highlights an urgent need—globally and within Malaysia for sustainable design solutions capable of addressing rising textile waste while maintaining consumer expectations for comfort, performance, and aesthetics. The development of the HydraPack Jacket responds directly to this need by applying upcycling strategies to functional outerwear design, contributing to ongoing efforts to advance circular fashion and support national and international sustainability agendas.

The environmental consequences of the fashion industry are well documented, with research emphasizing its substantial contributions to greenhouse gas emissions, resource depletion, and textile waste accumulation. Fletcher (2013) underscores that the industry's reliance on non-renewable inputs and energy-intensive production processes places significant strain on global ecosystems. Consequently, sustainable fashion emerged as a critical paradigm, prioritizing waste reduction, material efficiency, and circular economy principles. Strategies such as recycling and upcycling extend garment life cycles and reduce environmental burdens by keeping materials in circulation for longer periods.

Within this broader context, outerwear particularly windbreakers has undergone significant evolution. Originally inspired by Inuit protective garments, windbreakers have become mainstream apparel items with widespread functional and aesthetic appeal. Leading sportswear brands, including Nike, Adidas, and Patagonia, have increasingly incorporated sustainability principles into their outerwear lines, reflecting a growing shift toward environmentally conscious consumerism. This trend highlights modern consumers' expectations for garments that blend performance, design, and environmental responsibility.

Upcycling has gained prominence as one of the most effective methods for reducing textile waste while maintaining material integrity. Defined as the creative transformation of discarded textiles into new, higher-value products, upcycling avoids the fiber breakdown processes typical of traditional recycling (Lyu, 2020). By preserving fabric quality, upcycling significantly reduces energy use and emissions. This approach supports key global objectives such as SDG 12 (Responsible Consumption and Production) and SDG 13 (Climate Action) by promoting resource efficiency and reducing reliance on virgin materials.

For functional apparel like windbreakers, upcycled garments show promise not only in environmental performance but also in enhancing user experience. Features such as modular components, hydration systems, and optimised storage align with consumer preferences for versatile and practical clothing. These innovations also address common limitations in conventional windbreaker designs, including limited storage or lack of adaptability. Literature increasingly emphasizes that when sustainability is integrated with strong functionality and appealing aesthetics, consumer acceptance of eco-conscious products increases significantly.

In Malaysia, awareness of sustainable fashion is growing, with reports indicating increased interest in garments made from recycled fibers and natural dyes (The Star, 2020). However, barriers such as limited access to sustainable alternatives, higher production costs, and insufficient recycling infrastructure continue to hinder widespread adoption. Educational programs, government support, and growing consumer consciousness are beginning to

strengthen the movement, but innovative, locally relevant solutions remain essential. In this context, prototypes such as the HydraPack Jacket offer practical examples of how sustainable design can be integrated into commercially relevant apparel without compromising performance or style.

3. METHODOLOGY

The methodology implemented in this study provides a structured and comprehensive framework for eco-product development, integrating practical experimentation with empirical assessment. Through this approach, the research demonstrates how sustainable materials and upcycling techniques can be applied within contemporary fashion design. This framework aligns with Malaysia's movement toward circular fashion and contributes meaningful insights to sustainable product innovation.

This study employed an applied research design grounded in sustainable fashion principles, focusing on the systematic development and evaluation of the HydraPack Jacket as an eco-friendly outerwear prototype. The research process encompassed four primary stages: (1) material selection and preparation, (2) prototype assembly, (3) user-centered product evaluation, and (4) cost and feasibility assessment. This structured approach enabled the researcher to assess the technical feasibility of transforming discarded textiles into functional and aesthetically appealing apparel.

The fabrication process began with sourcing recycled textiles—primarily polyester, nylon, and post-consumer fabrics—selected based on availability, durability, and recyclability. These materials were cleaned, cut, and modified before being sewn into the HydraPack Jacket. Key construction procedures, including reinforcement of stress points and integration of multifunctional features such as the detachable hydration system and storage compartments, were meticulously documented to ensure consistency and replicability. Although the methodology initially considered technical performance tests such as tensile strength or water resistance, these assessments were not included in the prototype stage due to equipment limitations; however, they are recommended for future research to complement the user-centered findings.

The evaluation phase adopted a user-centered approach to assess the prototype's comfort, breathability, durability perception, and functional design. A total of 45 Diploma in Tourism Management students participated in the product testing. This sample size was selected based on accessibility, relevance, and the cohort's frequent engagement in outdoor and travel-related activities, making them an appropriate user group for evaluating lightweight outerwear. Participants were recruited using a convenience sampling method.

Data were collected using structured questionnaires comprising four constructs: design, durability, comfort, and sustainability awareness. Each construct consisted of 4–6 Likert-scale items, measured on a five-point scale. Instrument reliability was assessed using Cronbach's alpha, which indicated acceptable internal consistency for all constructs ($\alpha = 0.78\text{--}0.86$). Descriptive statistics and mean score interpretation were applied following Jamaludin and Hassan (2014). In this interpretation framework, lower mean scores (1.00–2.33) indicate a high level of agreement because the Likert scale places “strongly agree” at the lower end. This method provided clarity in evaluating user satisfaction and acceptance of the

prototype. Ethical considerations were addressed throughout the data collection process. Participants were informed of the study's purpose, their involvement was voluntary, and consent was obtained prior to participation. Anonymity and confidentiality were ensured by collecting responses without identifying information. Finally, cost estimation and equipment listing were included to assess the economic feasibility of producing sustainable apparel on a larger scale. These considerations support future scalability and provide practical insights into the viability of upcycled product development. A methodological flow diagram summarizing the research stages is recommended for inclusion to enhance clarity and visualization of the process.

4. MAIN FINDING / RESULTS

The results of this study indicate that the HydraPack Jacket was positively received by users, with consistently strong evaluations across all four measured attributes: design, durability, comfort, and sustainability awareness. Mean scores ranged from 1.91 to 2.04, reflecting high levels of agreement based on the interpretation scale of Jamaludin and Hassan (2014). Reliability analysis further supported the robustness of the instrument, with Cronbach's alpha values between 0.79 and 0.86, confirming acceptable internal consistency across all constructs. Table 1 presents the descriptive statistics and reliability coefficients for each attribute.

Table 1: Descriptive Statistics and Reliability for HydraPack Jacket Evaluation (n = 45)

Attribute	Mean	SD	Interpretation	Reliability (Cronbach's α)
Design	1.91	0.42	High	0.82
Durability	1.96	0.47	High	0.79
Comfort	2.04	0.51	High	0.86
Sustainability Awareness	1.93	0.45	High	0.81

Source: Research Data (2025), interpretation based on Jamaludin & Hassan (2014). Lower mean values indicate stronger agreement.

The design attribute recorded the lowest mean score ($M = 1.91$, $SD = 0.42$), demonstrating strong user agreement regarding the jacket's visual appeal, layout, and integration of functional features. Responses were clustered closely, indicating consistent perceptions across participants. The durability attribute also performed strongly, with a mean of 1.96 ($SD = 0.47$). Participants expressed confidence in the structural reliability of the prototype, citing reinforced stitching and sturdy recycled materials as key factors contributing to its perceived strength. A reliability value of $\alpha = 0.79$ underscores the stability of the durability measurements. The comfort attribute achieved a mean of 2.04 ($SD = 0.51$), reflecting positive evaluations of breathability, weight distribution, and wearability. Although slightly more variation was observed for this construct, overall agreement remained high. The internal consistency for this attribute was strong, supported by a Cronbach's alpha of 0.86.

Finally, the sustainability awareness attribute yielded a mean score of 1.93 (SD = 0.45), indicating that participants strongly appreciated the environmental purpose of the HydraPack Jacket and recognized its contribution to reducing textile waste. With a reliability coefficient of $\alpha = 0.81$, this construct demonstrated dependable internal consistency. The descriptive findings confirm that users evaluated the HydraPack Jacket favorably across design, durability, comfort, and sustainability-related dimensions. The consistently low mean scores, combined with strong reliability values, provide a robust quantitative basis for evaluating the prototype's acceptance and functional performance.

5. DISCUSSION AND CONCLUSION

The findings of this study demonstrate that the HydraPack Jacket successfully achieved its intended objectives of sustainability, functionality, and user comfort. The consistently high mean scores across all evaluated attributes indicate strong user acceptance and affirm the potential of upcycling as a viable approach to apparel development. These results provide empirical support for the application of circular design strategies in the fashion industry, particularly in reducing textile waste and promoting responsible consumption.

The positive reception of the jacket's design reflects the importance of combining aesthetics with functional utility in sustainable fashion. Participants appreciated the modern appearance and integrated features such as the hydration system and concealed storage compartments. This aligns with prior research by Lee, Tanaka, and Wong (2022), who argue that multifunctional apparel enhances user engagement and increases perceived product value. Similarly, Gwilt (2020) emphasizes that successful sustainable fashion must merge environmental responsibility with appealing design elements to gain consumer acceptance. The HydraPack Jacket exemplifies this balance by demonstrating that upcycled garments can attain a commercial level of visual and functional appeal.

Durability also emerged as a key strength of the prototype, as reflected in the high user ratings. This finding is consistent with Fletcher (2013), who underscores durability as a cornerstone of sustainable fashion due to its role in slowing consumption cycles and reducing material demand. The perceived robustness of the jacket supported by reinforced stitching and quality recycled materials suggests that upcycled textiles can perform comparably to virgin fabrics when properly processed. This contributes to broader discussions on the integration of upcycling within circular textile systems, which emphasize extending material lifespans and reducing reliance on resource-intensive production (EMF, 2021).

Comfort, another central attribute of apparel evaluation, was also rated positively. Participants reported that the jacket was lightweight, breathable, and balanced during wear, which aligns with Bye (2010), who argues that comfort is fundamental to user retention and long-term product use. The findings challenge common consumer assumptions that

sustainable or recycled garments compromise comfort or performance, supporting emerging evidence that material recovery does not inherently diminish ergonomic quality.

The high rating for sustainability awareness further illustrates users' recognition of the jacket's environmental value. This resonates with recent studies suggesting that younger consumers, especially university students, demonstrate increasing interest in sustainable fashion and are receptive to products aligned with environmental ethics (Balinas, 2021; Fashion Revolution, 2022). The positive reactions indicate that clear communication of sustainability attributes can strengthen user engagement and support behavioral shifts toward responsible consumption.

These findings collectively support international sustainability objectives, particularly the United Nations Sustainable Development Goals. The prototype directly contributes to SDG 12, which promotes waste reduction and sustainable resource management, and SDG 13, which encourages climate action through environmentally responsible practices. The project also aligns with SDG 9, highlighting the role of innovation in advancing sustainable industrial practices.

Despite these promising outcomes, several limitations must be acknowledged. First, the sample consisted solely of Diploma-level students from a single academic program, which may limit the generalizability of the findings. A broader sample that includes diverse age groups, occupations, and lifestyle backgrounds may offer more representative insights. Second, the evaluation relied on subjective self-reported perceptions rather than objective laboratory performance testing. As such, aspects such as waterproofing, tensile strength, and thermal insulation remain unverified. Third, the prototype was assessed in a controlled context rather than through long-term wear trials, limiting insights into durability over time. Taken together, the findings indicate that all three research objectives of this study were successfully achieved. The prototype was developed using upcycled textile waste, user perceptions across all functional and sustainability attributes were systematically evaluated, and the study demonstrated the broader feasibility of upcycling as a sustainable fashion strategy within Malaysia's circular economy landscape.

The discussion reinforces that the HydraPack Jacket represents a promising example of sustainable product innovation grounded in circular fashion principles. By integrating upcycling strategies with functional and aesthetic considerations, the study contributes meaningfully to ongoing efforts to reduce textile waste and advance eco-conscious apparel design.

5.1 CONCLUSION

This study provides strong evidence that upcycling can serve as an effective and practical strategy for sustainable apparel development, particularly within the Malaysian

fashion context where textile waste continues to rise and recycling systems remain limited. Building on the findings discussed earlier, the study successfully achieved all three of its research objectives.

First, the development of the HydraPack Jacket demonstrated that discarded polyester, nylon, and post-consumer fabrics can be transformed into a functional, durable, and aesthetically appealing outerwear prototype. The systematic construction process and integration of multifunctional features such as the detachable hydration system and modular storage compartments showed that upcycling can produce performance-oriented garments without relying on virgin materials.

Second, the user-centered evaluation confirmed the prototype's acceptability and functionality. Consistently high mean scores across design, durability, comfort, and sustainability awareness indicate that users appreciated both the practical features and the environmental purpose of the jacket. These results, consistent with the Discussion, reaffirm that the prototype aligns with consumer expectations and challenge persistent assumptions that recycled materials compromise product quality or performance. The strong internal consistency of the questionnaire further supports the reliability of the evaluation process.

Third, the study demonstrated the broader feasibility of upcycling as a viable strategy within Malaysia's emerging circular economy framework. As emphasized in the Discussion, the HydraPack Jacket aligns with global sustainability agendas by advancing SDG 12 (Responsible Consumption and Production) through waste reduction and efficient material use, and SDG 13 (Climate Action) through reduced environmental impacts associated with virgin textile production. The project also reflects SDG 9 (Industry, Innovation, and Infrastructure) by showcasing how design innovation can address pressing sustainability challenges in the fashion sector. While the prototype and evaluation yielded promising outcomes, several limitations emerged. The study relied on a homogenous sample of Diploma students, and the assessment focused on perception-based evaluation rather than technical laboratory testing. Addressing these limitations will be important for future research. Recommended directions include long-term wear trials, comparative studies involving different types of recycled materials, and life cycle assessments (LCA) to quantify the environmental advantages of upcycled apparel. Broadening participant demographics will also provide more comprehensive insights into market acceptance and commercial feasibility.

The HydraPack Jacket project contributes meaningful insights to the fields of sustainable fashion, circular product design, and upcycling innovation. By demonstrating that sustainable apparel can deliver high levels of performance, comfort, and user satisfaction, the study reinforces the potential of eco-innovative design to drive responsible consumption practices. As Malaysia progresses toward more circular and environmentally conscious fashion systems, the findings of this study highlight the importance of integrating upcycling

into local manufacturing, educational, and policy initiatives to support long-term sustainability goals.

REFERENCES

- Ameera Huda. (2024, July 21). Make fabric recycling more accessible to public, govt told. Free MalaysiaToday.<https://www.freemalaysiatoday.com/category/nation/2024/07/21/make-fabric-recycling-more-accessible-to-public-govt-told/>
- Balinas, M. (2021). The sustainable fashion consumer: Preferences, habits, and design perception. *Journal of Fashion Innovation*, 8(2), 34–49.
https://www.academia.edu/50745006/Product_Development_for_Recycled_Multifunctional_Excursionist_Winter_Jacket
- Bick, R., Halsey, E., & Ekenga, C. (2018). The global impact of textile and apparel production. The Garment Industry. <https://doi.org/10.1016/j.resconrec.2018.05.017>
- Bye, E. (2010). A direction for clothing and textiles: Human needs and sustainable design. *Clothing and Textiles Research Journal*, 28(3), 177–180.
<https://doi.org/10.1177/0887302X10371341>
- Cerin, L. (2022). How durable are sustainable clothes? Eco Apparel Insights.
<https://ecoapparelinsights.org>
- Chen, H.-L., & Burns, L. D. (2006). Environmental analysis of textile products. *Clothing and Textiles Research Journal*, 24(3), 248–261.
<https://doi.org/10.1177/0887302X06293065>
- Cheong, B. (2020, November 25). Even in Malaysia, fashion goes “green”: Why is sustainability so trendy now? The Star. <https://www.thestar.com.my/>
- Culthred. (2022). Materials and functionality of our sustainable jackets.
<https://www.culthred.com/blogs/news/materials-and-functionality-of-our-sustainable-jackets>
- Dataintelo, Patel, D., & Dataintelo. (2025, January 7). Windbreaker market research report 2032. Dataintelo. <https://dataintelo.com/report/windbreaker-market>
- Ellen MacArthur Foundation. (2021). A new textiles economy: Redesigning fashion’s future. Ellen MacArthur Foundation. <https://ellenmacarthurfoundation.org/>
- Environmental Innovations. (2020). Malaysia’s annual textile waste report 2020. Environmental Innovations Press.
- European Topic Centre on Circular Economy and Resource Use. (2023). EU exports of used textiles in Europe’s circular economy (ETC/CE Report 2023/4). Eionet Portal.
<https://www.eionet.europa.eu/etcs/etc-ce/products/etc-ce-report-2023-4-eu->

- Fashion Revolution. (2022). Consumer behavior and sustainability in fashion. <https://www.fashionrevolution.org/>
- Fletcher, K. (2013). Sustainable fashion and textiles. Routledge. <https://doi.org/10.4324/9781315857930>
- Fletcher, K., & Tham, M. (2019). Earth logic: Fashion action research plan. The J.J. Charitable Trust. <https://earthlogic.info/>
- Fong, F. (2024, March 29). Eco-chic revolution: How Malaysia's fashion scene is turning Swedish green. TRP. <https://www.therakyatpost.com/living/2024/03/01/eco-chic-revolution-how-malaysias-fashion-scene-is-turning-swedish-green/>
- Gwilt, A. (2020). A practical guide to sustainable fashion. Bloomsbury Publishing. <https://doi.org/10.5040/9781350067059>
- Jamaludin, Z., & Hassan, S. H. (2014). Interpretation of mean scores in educational research. US-China Education Review B, 4(11), 693–697.
- Lee, M., Tanaka, K., & Wong, L. (2022). Consumer preferences for functional and stylish apparel: The demand for multi-use clothing. International Journal of Clothing Studies, 15(4), 102–117.
- Lyu, S. (2020, December 28). Reinventing the windbreaker: Windbreaker Hanbok—Pivoting for the pandemic. Iowa State University Digital Repository. <https://doi.org/10.31274/itaa.11866>
- Ministry of Energy, Science, Technology, Environment and Climate Change. (2019). Malaysia environmental performance index report 2019.
- Nik Suzila, N. (2024). Strengthening Malaysia's textile waste management: Policies, challenges, and stakeholder collaboration. Malaysian Journal of Sustainable Development, 6(1), 45–58.
- Norman, D. (2013). The design of everyday things (Revised and expanded ed.). Basic Books.
- Rathinamoorthy, R., & Raja Balasaraswathi, S. (2021). Sustainable fashion consumption among youth: Awareness, attitudes, and behaviour. Journal of Global Fashion Marketing, 12(3), 267–283. <https://doi.org/10.1080/20932685.2021.1877065>
- Solid Waste and Public Cleansing Corporation. (2020). Annual report on solid waste management in Malaysia 2020. SWCorp Malaysia. <https://www.swcorp.gov.my/>
- Textile Exchange. (2019). Preferred fiber and materials market report 2019. Textile Exchange. <https://textileexchange.org/>

United Nations Environment Programme. (2018). Putting the brakes on fast fashion: Environmental impact of the textile industry. UNEP. <https://www.unep.org/>

van Duijn, M. (2022). Textile take-back schemes and extended producer responsibility in Europe. European Circular Textiles Platform.

**TRACK 4:
ELECTRICAL ENGINEERING**

Design and Development Process of the Solar-Powered Automatic Exhaust Fan System

Iskandar bin Jeffri, Hasmaini binti Hashim*

Politeknik Merlimau Melaka, KM 2.4, Jalan Merlimau–Jasin,
78300 Merlimau Melaka

[*hasmaini@pmm.edu.my](mailto:hasmaini@pmm.edu.my)

Abstract In response to the challenges of climate change and the global demand for sustainable energy, this project focuses on developing an automatic solar-powered exhaust fan system to enhance indoor air quality and energy efficiency. The project was motivated by the increasing need for renewable energy integration in daily applications, particularly in educational environments where thermal comfort and ventilation are essential. A review of past studies revealed that poor air ventilation and high CO₂ levels in classrooms can reduce students' focus and productivity. Previous research also highlighted the effectiveness of smart sensor systems and IoT-based ventilation in improving air quality and reducing energy consumption. These findings supported the development of a system that utilizes solar energy combined with automatic temperature-based control. The methodology involved designing a system powered by a solar panel, regulated by an MPPT charge controller, and stored in a 12V rechargeable battery. A DHT22 temperature sensor detects temperature changes, while a PIC18F4520 or Arduino Uno microcontroller controls a 12V DC exhaust fan. Software tools such as MPLAB X IDE and Proteus Design Suite were used for programming, simulation, and testing. Testing results demonstrated that the system responded accurately to temperature variations, activating the fan automatically above 29°C and maintaining energy efficiency through optimal solar utilization. The application of this project extends to classrooms, offices, and enclosed areas, providing a sustainable, low-cost, and energy-efficient ventilation solution. It promotes green technology adoption and serves as a practical model for smart and eco-friendly building systems.

Keywords: Solar energy; automatic ventilation; temperature control; MPPT charge controller; sustainable system; green technology; energy efficiency.

1.0 INTRODUCTION

The study focuses on developing a solar-powered automatic exhaust fan system to enhance indoor air quality and energy efficiency in educational environments, particularly at Politeknik Merlimau, Melaka. With the growing concern over global warming and environmental pollution caused by overreliance on non-renewable energy, the project promotes the use of renewable solar energy as a sustainable alternative. This initiative aligns with Malaysia's efforts to support green technology and environmental conservation through practical, low-cost innovations.

The main issues and challenges identified include poor air circulation and high indoor temperatures in classrooms and laboratories, which reduce comfort and concentration among students. Existing ventilation systems rely heavily on conventional electricity and

require manual operation, often leading to inefficient energy use and higher operational costs. Additionally, there is a lack of intelligent control systems that can automatically regulate airflow based on real-time temperature conditions. Several factors influence these issues, including Malaysia's tropical climate, which contributes to heat buildup in enclosed spaces, and the institution's dependence on electricity-powered fans and air conditioners. The absence of automation and renewable integration further aggravates energy wastage and increases the institution's carbon footprint.

To address these concerns, the proposed system integrates solar energy, a temperature sensor, an MPPT charge controller, and an Arduino Uno microcontroller to automatically activate the fan when the temperature exceeds a set threshold. The project not only provides a practical and sustainable ventilation solution but also serves as an educational model for promoting renewable energy and environmental awareness among students and staff.

2. LITERATURE REVIEW

This chapter presents a review of relevant literature that supports the design and development of the solar-powered automatic exhaust fan system. It covers theories, technologies, and research related to solar energy, automation systems, and smart environmental control. The discussion is organized into three main subtopics: Solar Energy and Photovoltaic Systems, Automation and Microcontroller Technology, and Environmental Monitoring Using Temperature Sensors.

2.1 Solar Energy and Photovoltaic Systems

Solar energy is one of the most promising renewable energy sources for sustainable development. It involves converting sunlight into electrical energy using photovoltaic (PV) cells or through concentrated solar power (CSP) systems (Kannan & Vakeesan, 2016). The photovoltaic effect enables the conversion of sunlight into direct current (DC) electricity, which can then be stored in batteries or converted into alternating current (AC) using an inverter.

Modern PV systems commonly integrate an MPPT (Maximum Power Point Tracking) charge controller, which optimizes energy harvesting efficiency and prevents overcharging of batteries (Kumar & Sudhakar, 2015). These advancements have reduced the cost of solar installations, making them more viable for small-scale applications such as household automation and classroom ventilation systems. According to the International Energy Agency (2021), solar power is projected to become the world's largest source of electricity by 2050, emphasizing its relevance in addressing environmental and energy challenges.

2.2 Automation and Microcontroller Technology

Automation plays a key role in reducing energy wastage and improving operational efficiency. In small-scale renewable systems, microcontrollers serve as the "brain" of automation, processing input signals from sensors and activating devices such as fans or lights accordingly. The Arduino Uno, based on the ATmega328P microcontroller, is widely used due to its open-source nature, simplicity, and

compatibility with various sensors (Banzi & Shiloh, 2014).

In ventilation systems, microcontrollers enable real-time monitoring and control, which improves energy management compared to manual systems (Al-Fuqaha et al., 2015). For instance, Arduino can process temperature data from sensors like the DHT22 and automatically activate a fan when a certain threshold is exceeded. Such systems demonstrate how automation contributes to smart energy solutions, aligning with the goals of sustainability and green technology adoption in educational institutions.

2.3 Environmental Monitoring Using Temperature Sensors

Environmental monitoring is essential for maintaining comfort and air quality in enclosed spaces such as classrooms and laboratories. Temperature and humidity sensors, such as the DHT22, are commonly used in automated systems due to their high accuracy and low power consumption (Wang et al., 2018). These sensors detect real-time environmental conditions and transmit digital signals to a microcontroller for processing.

Studies have shown that maintaining optimal indoor air conditions significantly enhances concentration and productivity among students (Kumar et al., 2020). High indoor temperatures and poor ventilation can cause discomfort and reduced cognitive performance. Integrating sensors into automated systems allows for precise control of airflow, ensuring that fans operate only when necessary — thereby saving energy while improving air quality.

In this project, the DHT22 sensor serves as the primary input device, while the Arduino Uno interprets the data and triggers the fan to maintain thermal comfort. This combination demonstrates the importance of integrating sensor technology with renewable energy systems for sustainable indoor environments.

This chapter reviewed previous studies and technological concepts related to solar energy, automation, and environmental monitoring. The literature establishes that solar technology provides a clean and cost-effective energy source, microcontrollers enable smart automation, and sensors enhance system responsiveness and efficiency. Together, these components form the foundation for the proposed solar-powered automatic exhaust fan system, promoting sustainability and green innovation within educational institutions.

3. METHODOLOGY

This section describes the methodology used in the design and development of a solar-powered automatic exhaust fan system. The project was implemented in several structured phases, beginning with component selection and design planning, followed by circuit simulation, prototype assembly, programming, and performance testing. Key hardware components, including the Arduino Uno, DHT22 temperature sensor, DC exhaust fan, solar panel, rechargeable battery, and MPPT charge controller, were chosen for their efficiency and reliability. The Arduino was programmed using the XC8 compiler to enable automatic fan activation when the temperature exceeds a predefined threshold, while real-time readings are displayed on an LCD. This methodology ensures that the final

product is technically sound, energy-efficient, and practical for improving classroom ventilation and sustainability at Politeknik Merlimau Melaka.

3.1 System Design Overview

This section outlines the overall design of the system through graphic sketches, block diagrams, and flowcharts to illustrate the functional relationships between hardware and software components.

3.1.1 Graphic and Block Diagram

As illustrated in Figure 1, the solar-powered exhaust fan system functions as a closed-loop automation design, with Arduino Uno serving as the central controller. The solar panel collects energy, which is stored in a rechargeable battery through the MPPT charge controller. The microcontroller receives input from the DHT22 temperature sensor and activates the fan through a MOSFET driver when the temperature exceeds the threshold value. The block diagram in Figure 2 shows the power flow and interconnection between components such as the solar source, charge controller, battery, Arduino, temperature sensor, and exhaust fan.




Figure 1: Graphic Design




Figure 2: Block Diagram

3.1.2 Flowchart of the Project

The flowchart in Figure 3 describes the decision-making process of the system. The program continuously monitors temperature input. When a high temperature is detected, the microcontroller triggers the fan; it automatically stops when the temperature returns to a safe level. This ensures energy conservation and autonomous operation.




Figure 3: Flowchart

3.3 Prototype Testing and Validation

The prototype was tested under controlled conditions to evaluate responsiveness and reliability. The system was simulated in Proteus, followed by physical prototype assembly. Testing confirmed that the fan activated at approximately 29°C and deactivated automatically when the temperature dropped below the threshold. Power stability tests verified that the solar and battery system maintained sufficient voltage even in low sunlight conditions. Adjustments to the code and connections were made to improve response accuracy and efficiency. Overall, the testing phase validated the project's functionality, proving it to be an energy-efficient, sustainable, and reliable ventilation solution suitable for classroom use. Figure 4 show the hardware prototype for this project.

This section explained the overall methodology for designing, developing, and testing the Solar-Powered Exhaust Fan System with Temperature Sensor. The integration of solar technology with automatic temperature control has successfully demonstrated an environmentally friendly and cost-effective ventilation system that supports sustainable energy practices in educational institutions.




Figure 4: Project prototype

4. RESULT AND ANALYSIS

This chapter presents the results obtained from the testing and evaluation of the Solar-Powered Automatic Exhaust Fan System. The discussion focuses on the system's performance in responding to temperature changes, power efficiency, and overall functionality under real operating conditions. Tests were conducted to verify whether the exhaust fan operated automatically when the ambient temperature exceeded a set threshold, and to analyze the stability of the solar-powered system in maintaining

sufficient energy supply. The results are compared with the expected outcomes, and the findings are discussed to evaluate the effectiveness, limitations, and possible improvements of the system.

4.1 System Functionality Test

The system was tested in a controlled environment to determine the responsiveness of the fan to temperature variations detected by the DHT22 sensor. Table 2 shows the recorded temperature readings and the corresponding fan operation status. At ambient temperatures below 29°C, the fan remained off, conserving power. When the temperature rose above 29°C, the fan was automatically activated by the microcontroller, and the LCD displayed real-time temperature updates.

The results confirm that the system operates as intended. The fan activation occurred consistently at temperatures exceeding 29°C, indicating accurate sensor calibration and stable control logic. This validates the system's ability to maintain automatic ventilation without human intervention, reducing the risk of overheating and improving indoor air circulation efficiency.

Table 2: Temperature Reading vs. Fan Operation

Temperature (°C)	LCD Display	Fan Status
26.5	26°C	OFF
28.7	29°C	OFF
30.1	30°C	ON
32.4	32°C	ON
27.0	27°C	OFF

4.2 Power Performance and Solar Efficiency

To assess energy performance, the solar panel output voltage and current were measured under varying sunlight intensities. The system maintained sufficient energy to power the fan and controller during daytime operation, while the 12V rechargeable battery provided backup power during low-light periods. The MPPT charge controller maintained efficient charging with a consistent output, achieving an estimated charging efficiency of 85–90%, similar to findings by Rahman et al. (2023), which reported that small-scale solar systems can sustain low-power devices effectively under typical daylight conditions. The power system thus demonstrated adequate reliability for classroom applications, supporting sustainable energy use.

Table 3: Solar Panel Performance at Different Sunlight Conditions

Time	Solar (V)	Voltage Current (A)	Battery Voltage (V)
9:00 AM	11.8	0.42	11.9
12:00 PM	13.6	0.75	12.4
3:00 PM	12.9	0.60	12.2
6:00 PM	10.7	0.28	11.8

4.3 System Stability and Reliability

Long-duration testing over 8 hours was conducted to evaluate the system's stability and endurance. The results showed that the system functioned continuously without interruption, and the fan cycled on and off based on real-time temperature changes. The LCD display provided accurate readings throughout, with minimal fluctuation in sensor values ($\pm 0.2^{\circ}\text{C}$ deviation). This indicates that the Arduino-based control system and MOSFET switching mechanism operate reliably, ensuring consistent output even when the solar input varies. The design's low power demand further enhances stability, as reported in similar microcontroller-based automation systems (Ali & Kumar, 2022).

Overall, the Solar-Powered Automatic Exhaust Fan System successfully meets its objectives by operating automatically based on temperature changes, efficiently utilizing solar energy, supporting green energy initiatives, and maintaining reliable performance under classroom conditions. The findings validate the practicality of using a solar-powered ventilation system for indoor air control. Some limitations include dependency on sunlight for maximum efficiency and minor voltage drops during cloudy conditions. Future improvements may include integrating CO₂ monitoring, Wi-Fi connectivity, or battery level display to enhance usability and monitoring. The data confirmed that the system successfully achieved its functional, energy, and automation goals. The system's reliable response to temperature variation, efficient use of solar power, and stable operation make it a practical solution for energy-saving classroom ventilation. These findings indicate that the project not only meets its technical objectives but also holds strong potential for future enhancement and commercialization as part of green innovation initiatives.

5. CONCLUSION

In conclusion, the Solar-Powered Automatic Exhaust Fan System successfully achieved its objective of providing an energy-efficient, automatic ventilation solution powered by solar energy. The system effectively responded to temperature changes, automatically activating the exhaust fan when the ambient temperature exceeded the threshold level. Through testing, it proved to be reliable, stable, and capable of operating sustainably using renewable energy. This project demonstrates the potential of integrating microcontroller-based automation with solar technology to enhance indoor air quality while reducing electricity consumption. Overall, it serves as a practical and eco-friendly innovation suitable for classrooms and other indoor environments, aligning

with current green technology initiatives and future smart building applications.

ACKNOWLEDGEMENT

The authors would like to extend their sincere gratitude to Politeknik Merlimau Melaka that have made significant contributions to various parts of this research.

REFERENCES

- Al-Fuqaha, A., Guizani, M., Mohammadi, M., Aledhari, M., & Ayyash, M. (2015). Internet of things: A survey on enabling technologies, protocols, and applications. *IEEE Communications Surveys & Tutorials*, 17(4), 2347–2376. <https://doi.org/10.1109/COMST.2015.2444095>
- Banzi, M., & Shiloh, M. (2014). *Getting started with Arduino* (3rd ed.). Maker Media.
- International Energy Agency. (2021). *World energy outlook 2021*. OECD/IEA. <https://www.iea.org/reports/world-energy-outlook-2021>
- Kannan, N., & Vakeesan, D. (2016). Solar energy for future world: A review. *Renewable and Sustainable Energy Reviews*, 62, 1092–1105. <https://doi.org/10.1016/j.rser.2016.05.022>
- Kumar, N. M., & Sudhakar, K. (2015). Performance analysis of solar PV systems in India. *Energy Procedia*, 75, 467–472. <https://doi.org/10.1016/j.egypro.2015.07.436>
- Kumar, A., Rahman, S., & Singh, R. (2020). Smart classroom air quality monitoring using IoT-based sensors. *Journal of Sustainable Education Technology*, 8(2), 45–53.
- Wang, J., Lee, C., & Tan, M. (2018). Temperature and humidity monitoring using DHT sensors in smart automation systems. *International Journal of Smart Engineering Systems*, 10(3), 115–122.

Kajian Transformasi Amalan Penaburan Benih Melalui Integrasi Mesin Separa Automatik Dalam Pertanian Skala Kecil

Nor Zuliana Abdul Latif*, Mohd Fauzi Hassan, Mohamad Shahril Ibrahim

Politeknik Kuching Sarawak

norzuliana@poliku.edu.my*, mfauzi@poliku.edu.my, hb150009@gmail.com

Abstrak Transformasi amalan kerja dalam sektor pertanian kecil semakin diberi tumpuan bagi meningkatkan kecekapan operasi, hasil tanaman, dan kelestarian tenaga kerja. Kajian ini menilai keberkesanan penggunaan mesin penabur benih separa automatik sebagai intervensi teknologi berskala kecil untuk mempertingkatkan produktiviti dan mengurangkan kebergantungan kepada tenaga manual. Penyelidikan ini menggunakan dua pendekatan utama: ujian prestasi mesin melalui analisis kuantitatif sebelum dan selepas penggunaan, serta soal selidik terhadap petani sebagai pengguna langsung bagi menilai persepsi dan penerimaan teknologi. Dapatan ujian operasi menunjukkan bahawa mesin ini meningkatkan jarak operasi daripada 40 meter kepada 100 meter dengan ketepatan taburan benih yang lebih seragam dan kestabilan tinggi. Kecekapan masa kerja meningkat dengan ketara, manakala keperluan tenaga fizikal menurun hampir separuh berbanding kaedah manual. Berdasarkan soal selidik, lebih 90% responden menyatakan bahawa mesin ini mudah digunakan, menjimatkan masa, dan mengurangkan keletihan semasa aktiviti penanaman. Kajian ini turut menunjukkan perubahan positif terhadap sikap dan penerimaan petani kecil terhadap teknologi baharu. Petani yang sebelum ini bergantung sepenuhnya pada kaedah manual menunjukkan minat tinggi untuk beralih kepada penggunaan mesin separa automatik dengan syarat adanya latihan dan sokongan teknikal berterusan. Kesimpulannya, penggunaan teknologi separa automatik yang ringkas, mampu milik, dan sesuai dengan konteks tempatan mampu menjadi pemangkin utama kepada transformasi amalan kerja pertanian kecil ke arah sistem yang lebih cekap dan mampan.

Kata kunci: Automasi pertanian, penaburan benih, petani kecil, perubahan amalan kerja, teknologi separa automatik

1.0 PENGENALAN

Sektor pertanian kekal sebagai salah satu tonggak penting dalam pembangunan ekonomi dan keselamatan makanan negara. Walau bagaimanapun, industri ini semakin berdepan cabaran kritikal seperti pengurangan tenaga kerja, kenaikan kos operasi, serta pergantungan berterusan terhadap kaedah manual. Kajian oleh Food and Agriculture Organization (FAO, 2021) menunjukkan bahawa negara membangun, termasuk Malaysia, mengalami penyusutan tenaga kerja pertanian secara konsisten akibat urbanisasi dan penuaan populasi petani. Data Jabatan Pertanian Malaysia (2022) turut melaporkan bahawa lebih 70% petani kecil masih bergantung kepada kaedah tradisional dalam pelbagai aktiviti penanaman, termasuk penaburan benih secara manual. Kaedah manual ini dibuktikan dalam beberapa kajian sebagai proses yang memakan masa, meningkatkan

keletihan fizikal, dan menghasilkan ketidakseragaman taburan benih yang memberi kesan langsung kepada kadar percambahan serta hasil tanaman (Rahman et al., 2020; Singh & Kumar, 2021).

Keperluan kepada mekanisasi berskala kecil semakin mendesak dalam era pasca-pandemik, khususnya bagi petani kecil yang perlu meningkatkan produktiviti tanpa penambahan tenaga kerja. Dalam konteks ini, mesin penabur benih separa automatik muncul sebagai penyelesaian praktikal yang selaras dengan kemampuan dan skala operasi petani kecil. Tidak seperti sistem automatik sepenuhnya yang mahal, kompleks dan memerlukan penyelenggaraan tinggi, sistem separa automatik direka untuk lebih ringkas, mudah dikendalikan, dan mampu beroperasi dalam persekitaran ladang kecil (Azmi et al., 2019). Kajian terdahulu telah membuktikan bahawa penggunaan mekanisme kawalan aliran benih seperti *gravity-feed*, *roller metering*, dan *seed plate-type systems* dapat meningkatkan ketepatan taburan benih serta mengekalkan konsistensi jarak tabur bagi pelbagai jenis tanaman (Kumar et al., 2018; Liao et al., 2020; Baloch et al., 2022). Walau bagaimanapun, jurang kajian masih wujud kerana banyak analisis tertumpu kepada sistem automatik skala besar, manakala prestasi mesin separa automatik berskala kecil kurang diteliti secara empirik.

Sehubungan itu, kajian ini memberi tumpuan kepada transformasi amalan kerja penanaman melalui penggunaan mesin penabur benih separa automatik dengan menilai keberkesanan operasinya dalam konteks ladang kecil. Fokus analisis bukan hanya terhadap aspek teknikal mesin, tetapi turut meneliti impaknya terhadap masa kerja, tahap keletihan petani, dan kecekapan operasi harian. Dengan menggabungkan dapatan empirikal dan teori mekanisasi pertanian, kajian ini dijangka menyumbang kepada perbincangan akademik yang lebih kukuh mengenai kebolehlaksanaan teknologi separa automatik dalam menyokong transformasi sektor pertanian ke arah sistem yang lebih moden, efisien dan mampan. Walaupun sektor pertanian kekal sebagai tulang belakang kepada keselamatan makanan dan ekonomi luar bandar, amalan penanaman dalam kalangan petani kecil di Malaysia masih terikat dengan kaedah tradisional yang memerlukan tenaga kerja fizikal secara intensif. Aktiviti asas seperti penaburan benih sering dilakukan secara manual membongkok, menyemai secara tidak seragam, dan tanpa kawalan terhadap jarak serta kedalaman benih. Keadaan ini bukan sahaja menyumbang kepada keletihan yang berlebihan dan risiko kecederaan kerja, malah menyebabkan pembaziran benih, pertumbuhan tanaman yang tidak seimbang, dan penurunan hasil.

Dalam masa yang sama, cabaran kekurangan tenaga kerja dalam sektor pertanian menjadi semakin ketara, terutamanya dalam kalangan generasi muda yang kurang berminat untuk bekerja dalam bidang ini. Di samping itu, mesin pertanian automatik sedia ada di pasaran kebanyakannya berskala besar, mahal, dan sukar diakses oleh pengusaha kecil yang memiliki ladang berskala terhad dan sumber kewangan yang terbatas. Meskipun pelbagai inovasi pertanian telah diperkenalkan, masih kurang penyelidikan yang menilai secara empirik bagaimana teknologi mudah seperti mesin penabur separa automatik dapat mengubah amalan kerja petani dari sudut operasi harian, kecekapan tenaga, dan penerimaan terhadap teknologi. Jurang ini menyebabkan banyak teknologi tidak digunakan secara meluas kerana tidak disesuaikan dengan keperluan sebenar pengguna di lapangan.

Oleh itu, satu kajian menyeluruh perlu dijalankan bagi menilai sejauh mana mesin separa

automatik mampu menjadi pemangkin kepada transformasi amalan kerja, bukan sahaja meningkatkan produktiviti, tetapi juga membentuk semula pendekatan petani terhadap penggunaan teknologi yang praktikal dan mampu milik.

Kajian ini dijalankan bagi menilai perubahan prestasi dan amalan kerja yang berlaku hasil penggunaan mesin penabur benih separa automatik dalam persekitaran pertanian kecil. Penilaian dilakukan berdasarkan ujian pra dan pasca penggunaan, serta maklum balas pengguna selepas sesi penggunaan. Berdasarkan data sedia ada, objektif khusus kajian ini adalah seperti berikut:

- i. Menilai peningkatan keupayaan operasi mesin dari segi jarak penaburan, kestabilan pergerakan, dan ketepatan taburan antara fasa pra dan pasca ujian.
- ii. Mengenal pasti pengurangan masa operasi dalam penaburan benih bagi jarak tetap sebelum dan selepas penggunaan mesin yang ditambah baik.

Skop kajian ini memberi tumpuan kepada penilaian prestasi penggunaan mesin penabur benih separa automatik serta impaknya terhadap amalan kerja petani kecil, tanpa menilai atau menguji reka bentuk mesin dari sudut kejuruteraan. Kajian ini tidak merangkumi analisis teknikal mendalam seperti simulasi mekanikal, rekabentuk komponen, pengiraan kejuruteraan atau penilaian struktur dalaman mesin. Sebaliknya, kajian hanya menilai aspek penggunaan mesin dalam situasi sebenar seperti berikut:

- i. Prestasi operasi mesin melalui perbandingan ujian pra dan pasca penggunaan pada jarak operasi yang ditetapkan (40 meter dan 100 meter), termasuk perubahan kecekapan masa dan kelancaran fungsi semasa digunakan.
- ii. Pemerhatian terhadap operasi fizikal mesin, seperti kestabilan pergerakan, ketepatan taburan benih, konsistensi taburan sepanjang laluan, serta kesesuaian mesin untuk digunakan di ladang kecil.
- iii. Analisis pengalaman pengguna, merangkumi tahap keletihan, kemudahan penggunaan, keselesaan kawalan, dan kesediaan pengguna untuk meneruskan penggunaan mesin dalam kerja harian.
- iv. Kajian dijalankan dalam persekitaran ladang kecil dengan keadaan tanah yang relatif rata dan menggunakan satu jenis benih, bagi memastikan penilaian fokus kepada prestasi penggunaan mesin dan bukan variasi agro-teknikal lain.

2.0 KAJIAN LITERATUR

Penggunaan teknologi dalam sektor pertanian bukan lagi satu pilihan, sebaliknya menjadi keperluan mendesak bagi menjamin produktiviti dan daya saing pengusaha kecil dalam landskap pertanian moden. Banyak kajian telah dijalankan untuk menilai impak automasi terhadap keberkesanan kerja di ladang, termasuk dalam aktiviti penaburan benih. Menurut Liu et al. (2020), automasi dalam penaburan memberi kelebihan dari segi konsistensi jarak, kedalaman dan taburan benih, yang secara langsung mempengaruhi kadar percambahan dan hasil tuaian. Tambahan pula, dalam kajian oleh Uddin et al. (2022), penggunaan mesin separa automatik dalam kalangan petani padi di Bangladesh menunjukkan penurunan masa kerja lebih 50% dan pengurangan penggunaan buruh manual.

Mesin penabur benih separa automatik secara umumnya terdiri daripada beberapa komponen utama iaitu hopper benih, mekanisme pengagihan (*seed metering*

mechanism), roda penggerak, dan rangka pemegang. *Hopper* berfungsi menyimpan benih, manakala mekanisme pengagihan lazimnya menggunakan sistem *gravity-feed, roller metering*, atau *seed-plate system* mengawal jumlah benih yang dilepaskan bagi setiap unit jarak. Pergerakan mesin digerakkan oleh roda yang memutar mekanisme metering melalui sistem gear, membolehkan benih ditabur secara berterusan pada kadar yang lebih seragam berbanding kaedah manual. Prinsip operasi ini menjadikan mesin separa automatik lebih stabil, konsisten dan cepat, sambil mengekalkan keperluan interaksi manusia untuk penolakan dan kawalan arah. Kefahaman asas tentang komponen dan mekanisme ini penting kerana prestasi akhir mesin banyak bergantung kepada keserasian reka bentuk dan kestabilan sistem pengagihan benih.

Dalam konteks penerimaan teknologi, Tambo & Mockshell (2018) menekankan bahawa kejayaan integrasi teknologi dalam sektor pertanian kecil sangat bergantung kepada kesesuaian teknologi tersebut dengan keupayaan pengguna dari aspek kos, kemudahan kendalian dan sokongan teknikal. Hal ini disokong oleh Sims & Kienzle (2017) yang mencadangkan supaya inovasi pertanian difokuskan kepada teknologi berskala kecil yang "cukup canggih untuk memberi impak, tetapi cukup ringkas untuk diguna oleh petani".

Kajian oleh Kumari et al. (2023) pula mendapati bahawa persepsi terhadap keletihan kerja memainkan peranan besar dalam kesediaan petani untuk menukar daripada kaedah manual kepada sistem mekanikal. Di sinilah mesin separa automatik menunjukkan nilai praktikal – ia tidak menggantikan sepenuhnya tenaga kerja manusia, tetapi cukup membantu untuk mengurangkan beban kerja fizikal dan menjimatkan masa. Namun, terdapat kekurangan dalam kajian tempatan yang menilai kesan amalan teknologi ini terhadap rutin kerja harian petani kecil, terutama dari perspektif perubahan tingkah laku dan penyesuaian operasi. Maka, kajian ini bertujuan mengisi jurang tersebut dengan menganalisis secara langsung kesan penggunaan mesin penabur separa automatik terhadap perubahan amalan kerja dalam kalangan petani kecil.

3.0 METODOLOGI

Metodologi kajian ini memberi tumpuan kepada penilaian keberkesanan penggunaan mesin penabur benih separa automatik melalui ujian pra-pasca, tanpa melibatkan analisis teknikal mendalam terhadap komponen atau reka bentuk mesin. Walaupun komponen utama dan prinsip operasi dihuraikan bagi memberi gambaran jelas kepada pembaca, kajian tidak menilai mesin dari sudut kejuruteraan, sebaliknya menilai prestasinya ketika digunakan dalam situasi sebenar dan impaknya terhadap amalan kerja petani kecil. Pendekatan ini dipilih bagi memastikan penilaian selari dengan objektif transformasi amalan kerja.

3.1 Reka Bentuk & Penambahbaikan Mesin

Mesin penabur benih separa automatik yang digunakan dalam kajian ini terdiri daripada empat komponen utama:

- a) Hopper Benih (Seed Hopper)
 - i. Kapasiti 1.2–1.5 kg.
 - ii. Direka semula dengan sudut cerun 45° bagi mengelakkan benih tersangkut (*seed bridging*).

- b) Mekanisme Pengagihan Benih (*Seed Metering Mechanism*)
- Menggunakan sistem roller metering yang digerakkan secara mekanikal oleh putaran roda.
 - Diameter roller: 32 mm; bilangan slot: 12 slot untuk benih kecil (padi/halia).
 - Penambahbaikan dilakukan dengan menukar material roller daripada plastik ABS kepada nylon tahan geseran bagi mengurangkan ketakseragaman taburan.
- c) Roda Penggerak (*Ground Wheel Drive System*)
- Diameter 250 mm dengan tapak getah bagi meningkatkan traksi pada tanah lembut.
 - Nisbah gear 1:4 dari roda ke roller memastikan kadar aliran benih konsisten.
 - Rangka & Pemegang (*Frame and Handle Assembly*)
 - Rangka keluli ringan dengan pemegang ergonomik pada ketinggian 95–105 cm.
 - Penambahbaikan dilakukan dengan menambah palang penyokong (*bracing bar*) bagi mengurangkan getaran lateral.
- d) Prinsip Operasi Mesin
- Apabila roda bergerak ke hadapan, putaran roda menghantar daya kepada roller melalui sistem gear. Setiap putaran roller melepaskan benih melalui slot pada kadar tetap. Prinsip ini bergantung kepada:
 - kadar putaran roda
 - bilangan slot pada roller
 - keupayaan hopper memastikan aliran benih berterusan.

3.2 Parameter Kejuruteraan dan Prestasi yang Dinilai

Kajian memberi tumpuan kepada parameter kuantitatif seperti Jadual 1 berikut:

Jadual 1 : Parameter yang digunakan berdasarkan penilaian kuantitatif

Parameter	Unit / Kaedah	Tujuan Penilaian
Kadar Aliran Benih (<i>Seed Flow Rate</i>)	g/min	Menilai konsistensi pengagihan benih.
Ketepatan Jarak Tabur	mm / visual grid	Menilai keseragaman taburan sepanjang laluan.
Jarak Operasi Maksimum	meter	Menentukan keberkesanan mekanikal & rintangan.
Kelajuan Operasi	m/s	Menilai kecekapan masa.
Kestabilan Pergerakan	Skala 1–5	Menilai kebolehkawalan mesin semasa operasi.

Tambahan kepada data kuantitatif, gabungan maklum balas kualitatif pengguna

digunakan untuk menilai transformasi amalan kerja melalui perubahan tahap keletihan, kemudahan penggunaan dan persepsi keberkesanan.

3.3 Reka Bentuk Ujian Pra-Pasca

Kajian dilaksanakan dalam dua fasa:

- i. Fasa 1: Ujian Pra-Penambahbaikan
 - Mesin diuji dalam bentuk asal tanpa modifikasi.
 - Ujian dijalankan pada laluan linear 10 meter di ladang sebenar.
 - Data yang diambil: kelajuan operasi, jarak operasi maksimum, taburan benih, dan kestabilan mesin.
- ii. Fasa 2: Ujian Pasca-Penambahbaikan
 - Mesin diuji selepas penambahbaikan komponen (*roller, hopper angle, frame bracing*).
 - Parameter ujian diseragamkan sama seperti pra-ujian untuk perbandingan yang sah.
 - Pemerhatian maklum balas petani turut direkodkan.
 - Ujian dilakukan sebanyak tiga ulangan ($n=3$) untuk setiap fasa bagi meningkatkan kebolehpercayaan data.

3.4 Prosedur Ujian Lapangan

- i. Laluan ditanda sepanjang 10meter menggunakan tali ukur.
- ii. Mesin diisi dengan 500 g benih setiap sesi ujian.
- iii. Pengguna menolak mesin pada kelajuan normal (tanpa paksaan tambahan).
- iv. Masa dicatat menggunakan jam randik.
- v. Taburan benih di tanah dianalisis menggunakan grid line marking.
- vi. Jarak operasi maksimum dicatat sehingga mesin tidak lagi menabur secara konsisten.
- vii. Kestabilan pergerakan direkod melalui pemerhatian *lateral sway* dan kawalan arah.
- viii. Maklum balas pengguna direkodkan selepas setiap sesi ujian.

3.5 Kaedah Analisis Data

3.5.1 Analisis Kuantitatif

- i. Data pra dan pasca dibandingkan menggunakan analisis deskriptif (peratus perubahan, min, sisihan piawai).
- ii. Ketepatan taburan dinilai melalui coefficient of variation (CV) bagi jarak tabur.
- iii. Peningkatan prestasi dikira berdasarkan perubahan konsistensi dan kelajuan operasi.

3.5.2 Analisis Kualitatif

- i. Maklum balas pengguna dikategorikan kepada tiga tema:

- ii. Tahap keletihan,
- iii. Kemudahan penggunaan,
- iv. Keberkesanan penaburan.
- v. Analisis tema digunakan untuk memadankan perubahan tingkah laku kerja dan persepsi pengguna.

3.5.3 Triangulasi Data

Gabungan data kuantitatif dan kualitatif digunakan untuk menilai sama ada peningkatan prestasi berpunca daripada:

- i. reka bentuk yang ditambah baik,
- ii. mekanisme operasi yang lebih stabil,
- iii. atau perubahan cara penggunaan mesin.

4.0 DAPATAN DAN PERBINCANGAN

Bahagian ini membentangkan dapatan kajian yang diperoleh daripada ujian prestasi mesin dan maklum balas pengguna semasa fasa pra dan pasca penggunaan mesin penabur benih separa automatik. Perbincangan tertumpu kepada tiga aspek utama: kecekapan operasi, perubahan dalam pengalaman kerja pengguna, dan potensi transformasi amalan kerja di ladang berskala kecil.

4.1 Peningkatan Prestasi Operasi

Dapatan dalam Jadual 2 menunjukkan peningkatan ketara dari segi prestasi mesin selepas penambahbaikan dilakukan. Dalam fasa pra-ujian, jarak maksimum yang dicapai oleh mesin adalah sekitar 40 meter, dengan prestasi pergerakan yang tidak stabil dan taburan benih yang tidak seragam. Selepas proses penambahbaikan, jarak operasi meningkat kepada 100 meter dengan prestasi pergerakan yang lebih stabil dan kawalan arah yang lebih konsisten.

Jadual 2: Data ujikaji yang telah diambil

Parameter	Pra-Ujian	Pasca-Ujian
Jarak Operasi Maksimum (m)	40	100
Masa Penaburan untuk 10m (min)	5.2	2.6
Kestabilan Pergerakan	Kurang stabil	Stabil dan konsisten
Ketepatan Taburan	Tidak seragam	Lebih seragam
Keperluan Tenaga Kerja	Tinggi	Rendah
Komen Pengguna	Perlu banyak kawalan manual	Mudah dikendalikan, kurang keletihan

Ketepatan taburan juga menunjukkan peningkatan apabila benih jatuh secara lebih sekata di sepanjang laluan penaburan. Pemerhatian mendapati bahawa penggunaan motor yang dikawal lebih baik serta reka bentuk saluran benih yang ditambah baik menyumbang kepada peningkatan ini. Selain itu, masa yang diambil untuk menabur setiap 10meter berkurang hampir separuh, daripada 5.2 minit kepada 2.6 minit menandakan penjimatan masa yang signifikan.

4.2 Perubahan Pengalaman Kerja

Maklum balas pengguna semasa ujian menunjukkan perubahan positif terhadap pengalaman kerja. Sebelum penggunaan mesin, kerja penaburan dilakukan secara manual memerlukan pembongkaran berulang, menyebabkan keletihan terutamanya pada bahagian belakang dan lutut. Selepas penggunaan mesin, majoriti pengguna menyatakan bahawa mereka dapat menyempurnakan kerja dengan lebih cepat dan selesa. Komen pengguna menyatakan bahawa mesin mudah dikendalikan, tidak memerlukan kemahiran teknikal tinggi, dan tidak menyebabkan ketegangan fizikal yang biasa dialami dalam kerja penaburan manual. Ini menunjukkan bahawa penggunaan mesin ini bukan sekadar meningkatkan prestasi kerja, tetapi juga menyumbang kepada pengurangan beban fizikal petani.

4.3 Transformasi Amalan Kerja

Secara keseluruhan, data menunjukkan bahawa penggunaan mesin penabur benih separa automatik telah membawa perubahan kepada cara kerja petani. Daripada kaedah manual yang memerlukan tenaga fizikal tinggi dan masa yang panjang, mesin ini membolehkan petani menabur benih dengan lebih sistematik dan cekap. Transformasi ini dilihat bukan hanya pada tahap teknologi, tetapi juga pada perubahan sikap terhadap penggunaan alat bantu. Pengguna menyatakan kesediaan untuk terus menggunakan mesin ini dalam amalan harian, menunjukkan potensi mesin ini sebagai alat transformasi amalan kerja di peringkat ladang kecil.

5.0 KESIMPULAN

Hasil kajian ini menunjukkan bahawa penggunaan mesin penabur benih separa automatik telah membawa impak yang positif terhadap amalan kerja petani kecil, khususnya dalam aspek kecekapan masa, pengurangan keletihan fizikal, dan peningkatan ketepatan penaburan. Mesin yang pada awalnya diuji dengan jarak operasi terhad dan ketidaktentuan pergerakan telah melalui proses penambahbaikan yang berjaya meningkatkan prestasi operasi secara signifikan. Jarak operasi meningkat daripada 40meter kepada 100meter, masa penaburan untuk 10meter dikurangkan hampir separuh, dan taburan benih menjadi lebih sekata serta konsisten.

Lebih penting, transformasi ini bukan hanya bersifat teknikal tetapi juga bersifat tingkah laku. Maklum balas pengguna menunjukkan perubahan positif terhadap pengalaman kerja dan persepsi terhadap teknologi. Penggunaan mesin ini dilihat sebagai satu penyelesaian praktikal yang bersesuaian dengan kapasiti, kemahiran, dan keperluan petani skala kecil sekaligus menjawab jurang yang selama ini dihadapi antara teknologi moden dan realiti ladang kecil. Sehubungan itu, kajian ini menyarankan beberapa cadangan utama:

- i. Pelaksanaan program intervensi teknologi berskala kecil melalui latihan, bengkel, dan pendedahan kendalian mesin kepada pengusaha tani luar bandar.
- ii. Pembangunan mesin yang boleh disesuaikan (modular) mengikut jenis benih, saiz ladang dan profil pengguna, agar teknologi ini lebih mudah diterima di pelbagai lokasi.
- iii. Sokongan pembiayaan mikro atau subsidi daripada agensi pertanian kerajaan bagi membolehkan petani memiliki dan menggunakan mesin ini secara meluas.

- iv. Penyelidikan susulan berskala lebih besar, termasuk kajian terhadap impak mesin ini ke atas hasil tanaman, kos per hektar, dan jangka hayat penggunaan dalam keadaan sebenar ladang.

Secara kesimpulannya, kajian ini mengesahkan bahawa mesin penabur benih separa automatik bukan sahaja mampu meningkatkan produktiviti, malah berpotensi menjadi pemangkin kepada transformasi amalan kerja pertanian kecil yang lebih cekap, ergonomik dan mampan.

RUJUKAN

- Liu, X., Zhang, Z., Wang, Y., & Li, D. (2020). Design and development of a precision seed planter with uniform seed spacing. *Computers and Electronics in Agriculture*, 174, 105481.
- Uddin, M. M., Hossain, M. A., & Kabir, M. H. (2022). Evaluation of a low-cost semi-automatic rice transplanter for smallholders. *Agricultural Engineering International: CIGR Journal*, 24(1), 45–54.
- Tambo, J. A., & Mockshell, J. (2018). Differentiated roles of rural institutions in adopting agricultural innovations: Evidence from Nigeria. *Food Policy*, 74, 54–65.
- Sims, B. G., & Kienzle, J. (2017). Making mechanization accessible to smallholder farmers in sub-Saharan Africa. *Environments*, 4(3), 58.
- Kumari, A., Meena, M. L., & Singh, N. (2023). Adoption of labor-saving technologies and perceived drudgery among smallholder women farmers. *Journal of Rural Studies*, 98, 112–121.
- Food and Agriculture Organization (FAO). (2021). *The State of Food and Agriculture 2021: Making agrifood systems more resilient to shocks and stresses*. FAO.
- Jabatan Pertanian Malaysia. (2022). *Laporan Statistik Tanaman Makanan 2022*. Putrajaya: Kementerian Pertanian dan Industri Makanan (MAFI).
- Rahman, M. M., Hossain, M. I., & Hossen, M. A. (2020). Performance comparison of manual and mechanical seed sowing methods for small-scale farmers. *Journal of Agricultural Engineering and Technology*, 11(2), 45–54.
- Singh, R., & Kumar, P. (2021). Impact of manual seeding on farmer fatigue and sowing uniformity in smallholder agriculture. *International Journal of Agricultural Sciences*, 13(1), 77–85.
- Azmi, Y., Man, H. C., & Ahmad, D. (2019). Development trends of small-scale agricultural mechanization in Southeast Asia. *Applied Engineering in Agriculture*, 35(3), 321–330.
- Kumar, S., Singh, B., & Hooda, R. (2018). Design and development of a low-cost seed metering mechanism for small-scale planters. *Agricultural Mechanization in Asia, Africa and Latin America (AMA)*, 49(4), 67–74.

- Liao, Y., Chen, X., & Zhao, Z. (2020). Optimization of seed plate metering mechanism for precision placement in smallholder farming. *Biosystems Engineering*, 192, 180–194.
- Baloch, M. S., Solangi, A. W., & Oad, S. K. (2022). Evaluation of seed drill metering mechanisms for improving sowing uniformity. *Agricultural Engineering International: CIGR Journal*, 24(1), 58–66.

Kajian Awal Perbandingan Teknologi Tenaga Suria dan Aplikasi Optimumnya di Malaysia

Ainul Azniza*, Muhammad Nabil bin Norazman,
Mohamad Ammir Ibtisham Bin Jumat

*Politeknik Merlimau Melaka,

*ainul@pmm.edu.my

Abstrak. Permintaan terhadap tenaga boleh diperbaharui semakin meningkat selari dengan usaha global untuk mengurangkan kebergantungan terhadap bahan api fosil dan menangani isu perubahan iklim. Tenaga suria dikenalpasti sebagai antara sumber paling berpotensi, namun kepelbagaian teknologi yang tersedia seperti sistem fotovoltai (PV), kuasa suria tertumpu (CSP), panel bifacial, sistem suria terma dan panel nipis (thin film) menimbulkan cabaran dalam menentukan teknologi yang paling sesuai bagi aplikasi tertentu, terutamanya dalam konteks iklim tropika dan keperluan tenaga di Malaysia. Kajian ini bertujuan untuk menjalankan penilaian awal terhadap lima teknologi tenaga suria utama melalui pendekatan analisis literatur dan perbandingan kualitatif. Penilaian dibuat berdasarkan faktor seperti kecekapan tenaga, kos pemasangan dan penyelenggaraan, keperluan ruang, serta kesesuaian aplikasi di persekitaran tempatan. Dapatan kajian menunjukkan bahawa tiada satu teknologi yang paling unggul secara mutlak, sebaliknya setiap teknologi mempunyai kekuatan tersendiri mengikut konteks penggunaan. Sebagai contoh, teknologi PV sesuai untuk kediaman dan kawasan luar bandar, manakala CSP dan panel bifacial lebih efisien untuk ladang solar berskala besar. Kajian ini menyimpulkan bahawa pemilihan teknologi tenaga suria yang berpanduan kepada padanan aplikasi dapat meningkatkan kecekapan sistem, mengoptimumkan pelaburan dan menyokong peralihan negara ke arah masa depan tenaga yang lebih lestari.

Kata kunci: tenaga suria, teknologi fotovoltai, kuasa suria tertumpu, aplikasi optimum, Malaysia

1. PENGENALAN

Tenaga suria merupakan salah satu sumber tenaga boleh diperbaharui yang semakin mendapat perhatian global kerana keupayaannya mengurangkan pelepasan karbon, mengurangkan kebergantungan terhadap bahan api fosil dan menyokong agenda kelestarian alam sekitar. Sumber ini diperolehi daripada cahaya matahari yang ditukarkan kepada tenaga elektrik atau haba melalui pelbagai teknologi seperti sistem fotovoltai (PV), kuasa suria tertumpu (CSP), sistem suria terma dan panel nipis (thin film) (Sarker et al., 2023). Malaysia, yang terletak berhampiran garisan Khatulistiwa, menerima purata pancaran suria antara 4 hingga 6 kWh/m² sehari sepanjang tahun, menjadikannya sangat sesuai untuk pembangunan teknologi tenaga suria (Safari et al., 2020). Usaha kerajaan Malaysia dalam memperkukuh sektor ini dapat dilihat melalui inisiatif seperti *Malaysia Renewable Energy Roadmap (MyRER)* dan program insentif

seperti Feed-in Tariff (FiT) serta Net Energy Metering (NEM), yang telah mendorong pertumbuhan pesat dalam pemasangan sistem tenaga suria, terutamanya di sektor kediaman dan komersial (SEDA, 2023). Walau bagaimanapun, walaupun berlaku peningkatan dalam kadar penggunaan, pemilihan teknologi yang bersesuaian masih menjadi cabaran utama kerana terdapat pelbagai sistem dengan prestasi, kos dan keperluan infrastruktur yang berbeza-beza. Kekeliruan ini boleh mengakibatkan pelaburan yang tidak optimum serta prestasi sistem yang kurang efisien, justeru satu kajian komparatif diperlukan untuk memahami padanan teknologi yang paling sesuai dengan konteks dan keperluan tempatan (Zhao et al., 2018; Yeoh, 2021).

2. SOROTAN KAJIAN

Tenaga suria telah menjadi antara bidang penyelidikan utama dalam usaha global untuk mempercepatkan peralihan kepada sumber tenaga boleh diperbaharui. Pelbagai kajian telah dilakukan untuk menilai prestasi, kos, dan kesesuaian pelaksanaan teknologi ini dalam konteks berbeza. Oleh itu, bahagian ini menghimpunkan dapatan-dapatan penting daripada kajian lepas yang berkaitan dengan prestasi teknologi, isu pemilihan aplikasi, serta faktor-faktor kritikal yang mempengaruhi keberkesanan pelaksanaan sistem tenaga suria di peringkat nasional dan tempatan.

2.1 Kajian Prestasi dan Kecekapan Teknologi

Kajian oleh Zhao et al. (2018) meneliti kos pemasangan dan penyelenggaraan sistem PV serta mendapati bahawa lokasi, jenis panel dan kos infrastruktur memberi kesan langsung terhadap pelaburan dan prestasi keseluruhan sistem. Penemuan ini disokong oleh Sarker et al. (2023) yang membuat semakan menyeluruh terhadap prestasi sistem PV di Malaysia dan menekankan bahawa kecekapan sistem amat bergantung kepada konfigurasi teknikal dan kesesuaian reka bentuk dengan keadaan persekitaran. Sementara itu, Yeoh (2021) menunjukkan bahawa walaupun pengumpul tenaga suria plat rata mempunyai kecekapan tinggi dalam persekitaran terkawal, keupayaan penyesuaian kepada variasi suhu dan teduhan adalah cabaran utama yang menjejaskan prestasi sebenar.

2.2 Isu Pemilihan Teknologi Berdasarkan Aplikasi

Safari et al. (2020) menjalankan kajian kes di Mersing dan mendapati bahawa tahap penerimaan masyarakat luar bandar terhadap teknologi suria adalah tinggi apabila kos jangka panjang dan kestabilan bekalan menjadi faktor utama. Namun begitu, pemilihan teknologi yang tidak disesuaikan dengan konteks sosio-ekonomi setempat boleh menyebabkan ketidakefisienan pelaburan. Mohamed et al. (2022) turut mencadangkan bahawa penggunaan teknologi bifacial perlu disokong dengan reka bentuk pemasangan yang mengambil kira pantulan permukaan dan arah panel untuk memastikan kelebihan teknologi tersebut dapat dimanfaatkan secara maksimum.

2.3 Faktor Kesesuaian Teknologi sebagai Elemen Kritikal

Faktor-faktor seperti kos awal pelaburan, kesedaran pengguna, dan kecekapan sistem dalam pelbagai keadaan cuaca menjadi aspek utama dalam pemilihan teknologi tenaga suria (Zhao et al., 2018; Safari et al., 2020). Islam et al. (2019) menegaskan bahawa dalam konteks Malaysia, pemilihan teknologi seperti CSP harus berdasarkan kepada tahap Direct Normal Irradiance (DNI) dan keperluan penyimpanan tenaga haba, memandangkan teknologi ini hanya sesuai untuk aplikasi berskala besar dan kawasan terbuka yang menerima cahaya matahari langsung tanpa halangan.

2.4 Jurang Kajian dan Penyataan Masalah

Walaupun terdapat banyak kajian yang memfokuskan kepada satu-satu jenis teknologi, kajian perbandingan menyeluruh terhadap beberapa teknologi utama seperti PV, CSP, thermal, bifacial dan thin-film dalam konteks aplikasi tempatan masih terhad. Kebanyakan kajian terdahulu hanya memberi tumpuan kepada prestasi teknikal atau aspek pemasangan tanpa mempertimbangkan padanan optimum antara teknologi dan keperluan pengguna sebenar di Malaysia seperti kediaman, perindustrian, luar bandar, dan aplikasi mudah alih (Sulaiman et al., 2013; Rosnani, 2013). Oleh itu, wujud keperluan mendesak bagi satu kajian awal yang dapat menyusun dan membandingkan teknologi berdasarkan parameter praktikal untuk menyokong pemilihan teknologi yang lebih strategik.

3. METODOLOGI KAJIAN [Cambria Heading, 12 font size , bold, left alignment]

3.1 Reka Bentuk Kajian

Kajian ini menggunakan pendekatan kualitatif deskriptif melalui analisis literatur dan perbandingan teknologi bagi menilai prestasi, kelebihan, kekangan serta kesesuaian aplikasi lima jenis teknologi tenaga suria utama. Pendekatan ini bersifat penerokaan (exploratory) yang sesuai digunakan untuk mengenal pasti pola, trend dan jurang pengetahuan yang wujud berdasarkan data sekunder (Sarker et al., 2023; Sulaiman et al., 2013).

3.2 Kaedah Pengumpulan Data

Data bagi kajian ini diperoleh melalui dua sumber utama:

3.2.1 Kajian Literatur

Merangkumi artikel jurnal berwasit, laporan teknikal, dasar kerajaan seperti *Malaysia Renewable Energy Roadmap (MyRER)* serta dokumen dari agensi berkaitan

seperti Suruhanjaya Tenaga, SEDA Malaysia dan IRENA. Dua artikel utama yang dijadikan rujukan utama ialah:

- a. Safari et al. (2020), yang membincangkan penerimaan masyarakat luar bandar terhadap teknologi solar dan faktor sosial yang menyumbang kepada pelaksanaan berjaya.
- b. Zhao et al. (2018), yang menganalisis kos pemasangan dan penyelenggaraan sistem PV serta impaknya terhadap keberkesanan pelaburan.

3.2.2 Sumber Sekunder Tambahan

Kajian juga merujuk Sulaiman et al. (2013), yang menjalankan kaji selidik terhadap sikap rakyat Malaysia terhadap tenaga boleh diperbaharui, dan Yeoh (2021) yang menganalisis prestasi sistem pengumpul tenaga suria melalui pendekatan berangka. Pendekatan ini membolehkan triangulasi maklumat daripada pelbagai sumber.

4. KEPUTUSAN KAJIAN DAN ANALISIS

Kajian ini memfokuskan kepada penilaian komparatif lima teknologi tenaga suria utama yang sedang digunakan atau berpotensi untuk digunakan dalam konteks Malaysia. Penilaian dilakukan bagi mengenal pasti kekuatan, kelemahan dan kesesuaian setiap teknologi berdasarkan pelbagai kriteria teknikal dan praktikal yang relevan dengan keadaan persekitaran tempatan. Lima teknologi yang dianalisis dalam kajian ini ialah:

- Photovoltaic (PV) Solar Systems
- Concentrated Solar Power (CSP)
- Solar Thermal Systems
- Bifacial Solar Panels
- Thin-Film Solar Panels

Setiap teknologi ini dianalisis berdasarkan indikator berikut:

- Kecekapan tenaga dan prestasi
- Kos pemasangan dan penyelenggaraan
- Keperluan infrastruktur dan ruang
- Kesesuaian dengan iklim dan geografi Malaysia
- Kesesuaian dengan aplikasi seperti kediaman, industri, luar bandar dan sistem

mudah alih

Melalui pendekatan ini, kajian bertujuan untuk mengenal pasti padanan teknologi-aplikasi yang paling optimum bagi menyokong pelaksanaan tenaga suria yang efisien dan lestari di Malaysia.

4.1 Analisis Perbandingan Teknologi

Analisis dilakukan secara perbandingan berdasarkan kriteria utama dan dibentangkan dalam bentuk jadual (Rujuk Jadual 1), seperti yang digunakan dalam pendekatan oleh Sarker et al. (2023). Anggaran kecekapan boleh berubah bergantung kepada model, jenama dan keadaan pemasangan sebenar.

Jadual 1: Kadar Pertumbuhan Ekonomi

Teknologi	Kecekapan (anggaran)	Kos Pemasangan	Kelebihan	Kekangan	Aplikasi Paling Sesuai
Photovoltaic (PV)	15–22%	Sederhana	Kos semakin menurun, mudah dipasang, sesuai untuk pelbagai skala	Prestasi menurun pada suhu tinggi, bergantung kepada cahaya terus	Kediaman, komersial, luar bandar
Concentrated Solar Power (CSP)	25–35%	Tinggi	Kecekapan tinggi, boleh simpan haba untuk penggunaan malam	Perlukan kawasan besar dan cahaya matahari langsung, kos tinggi	Loji kuasa berskala besar
Solar Thermal Systems	30–70% (pemanasan)	Rendah ke Sederhana	Sesuai untuk pemanasan air dan proses industri, sistem mudah	Tidak sesuai untuk penjanaan elektrik berskala besar	Pemanasan air domestik, proses industri
Bifacial Solar Panels	+10–20% berbanding PV	Tinggi	Serap cahaya dari dua arah, lebih efisien di permukaan reflektif	Kos tinggi, perlukan orientasi dan permukaan khas	Ladang solar, kawasan bandar permukaan reflektif

Thin-Film Solar Panels	10-12%	Rendah	Fleksibel, ringan, sesuai untuk permukaan tidak rata	Kecekapan rendah, jangka hayat pendek	Peranti mudah alih, bumbung struktur ringan

Sumber: Disusun berdasarkan Zhao et al. (2018) dan Safari et al. (2020) serta perbandingan teknikal umum dalam pasaran semasa.

4.2 Pemetaan Kesesuaian Aplikasi (Application-Technology Fit Mapping)

Kaedah ini digunakan untuk memadankan setiap teknologi dengan aplikasi paling sesuai, berdasarkan faktor tempatan seperti pencahayaan, bentuk muka bumi, dan tahap ekonomi pengguna (Yeoh, 2021; Sulaiman et al., 2013).

Jadual 2: Kadar Pertumbuhan Ekonomi

Konteks Aplikasi	PV Solar	CSP	Solar Thermal	Bifacial Panel	Thin-Film Panel
Kediaman (Individu / Lot Teres)	☑ Sesuai	✗ Tidak Sesuai	☑ Sesuai	✗ Perlukan permukaan reflektif	☑ Sesuai
Komersial (pejabat / kedai)	☑ Sesuai	✗ Tidak Sesuai	☑ Sesuai	☑ Jika ada permukaan reflektif	✗ Kurang Sesuai
Perindustrian / Kilang	☑ Sesuai	☑ Sesuai	☑ Sesuai	☑ Sesuai	✗ Kurang Sesuai
Ladang Solar Berskala Besar	☑ Sesuai	☑ Sangat Sesuai	✗ Tidak Sesuai	☑ Sesuai	✗ Tidak Sesuai
Kawasan Luar Bandar / Terpencil	☑ Sangat Sesuai	✗ Tidak Praktikal	☑ Sesuai	✗ Kos Tinggi	☑ Sesuai
Sistem Mudah Alih / Portable	✗ Tidak Praktikal	✗ Tidak Sesuai	✗ Tidak Sesuai	✗ Berat dan Mahal	☑ Sangat Sesuai

Penjelasan Simbol:

☑ Sesuai: Teknologi selaras dengan keperluan aplikasi dan persekitaran.

✗ Tidak Sesuai: Tidak praktikal dari aspek kos, keperluan ruang atau prestasi.

5. KESIMPULAN

Kajian ini telah menjalankan penilaian awal terhadap lima teknologi tenaga suria utama iaitu sistem fotovoltai (PV), kuasa suria tertumpu (CSP), sistem suria terma, panel bifacial dan panel nipis (thin film). Melalui pendekatan kualitatif deskriptif dan kajian

literatur, perbandingan dilakukan berdasarkan prestasi, kos, keperluan pemasangan dan kesesuaian konteks aplikasi di Malaysia.

Hasil perbandingan menunjukkan bahawa tiada satu teknologi yang paling unggul untuk semua situasi. Sebaliknya, setiap teknologi mempunyai kekuatan tersendiri bergantung kepada keperluan penggunaan dan keadaan persekitaran. Sebagai contoh, teknologi PV adalah paling fleksibel dan sesuai untuk pelbagai skala, manakala CSP lebih berkesan untuk loji berskala besar yang mempunyai pencahayaan langsung tinggi dan kawasan tanah luas. Panel bifacial pula menawarkan kecekapan tambahan di kawasan dengan permukaan reflektif, manakala panel nipis lebih sesuai untuk struktur ringan atau sistem mudah alih.

Bagi memperkukuh dapatan kajian ini, kajian lanjutan disarankan untuk dijalankan secara empirikal di tapak sebenar bagi menilai prestasi teknologi tenaga suria dalam keadaan sebenar iklim, orientasi pemasangan dan beban penggunaan. Selain itu, simulasi menggunakan perisian seperti PVsyst atau SAM juga dicadangkan untuk menganalisis output tenaga, keberkesanan dan pulangan pelaburan secara kuantitatif berdasarkan data iradiasi tempatan. Penilaian lanjut terhadap faktor sosioekonomi pengguna dan kesan dasar semasa seperti Feed-in Tariff (FiT) dan Net Energy Metering (NEM) perlu dilakukan bagi memahami tahap penerimaan serta halangan pelaksanaan sistem suria di pelbagai peringkat komuniti. Seterusnya, pembangunan satu garis panduan atau matriks pemilihan teknologi tenaga suria yang praktikal bagi kategori pengguna yang berbeza boleh membantu pemilik bangunan dan perancang tenaga membuat keputusan yang lebih strategik. Akhir sekali, kajian masa hadapan juga boleh meneliti potensi integrasi teknologi suria dengan sistem penyimpanan tenaga dan grid pintar bagi meningkatkan kecekapan sistem secara menyeluruh.

Secara keseluruhannya, pemilihan teknologi yang tepat mestilah dibuat berdasarkan padanan antara teknologi dan aplikasi sebenar. Ini bertepatan dengan dapatan dari Yeoh (2021) dan Sulaiman et al. (2013) yang menekankan bahawa keberkesanan sistem tenaga suria sangat bergantung kepada konteks pemasangan dan faktor persekitaran tempatan. Selain itu, Safari et al. (2020) juga menunjukkan bahawa faktor sosial seperti penerimaan komuniti turut memainkan peranan penting dalam kejayaan pelaksanaan sistem solar di Malaysia.

PENGHARGAAN

Setinggi-tinggi penghargaan ditujukan kepada POLITEKNIK MERLIMAU, MELAKA atas sokongan berterusan, kemudahan yang disediakan serta peluang yang diberikan sepanjang pelaksanaan kajian ini. Sokongan daripada pihak institusi amat penting dalam memastikan kelancaran penyelidikan ini dan kejayaan pembangunan projek yang dijalankan.

RUJUKAN

Ha, S., Zhou, Z., Im, E.-S., & Lee, Y.-M. (2023). Comparative assessment of future solar power potential based on CMIP5 and CMIP6 multi-model ensembles. *Renewable Energy*, 206, 324–335.

- Islam, M., Huda, N., & Saidur, R. (2019). Current energy mix and techno-economic analysis of concentrating solar power (CSP) technologies in Malaysia. *Renewable Energy*, 140, 107–121.
- Mohamed, N. S. S., Sulaiman, S. I., & Abdul Rahim, S. R. (2022). Energy yield prediction of a bifacial PV system with a miniaturized test array. *ResearchGate*.
- Rosnani, A. (2013). A review of concentrating solar power (CSP) in Malaysian environment. *International Journal of Engineering and Advanced Technology (IJEAT)*, 3(2), 378–382.
- Safari, M. A. M., Masseran, N., Jedi, A., Mat, S., Sopian, K., Bin Abdul Rahim, A., & Zaharim, A. (2020). Rural public acceptance of wind and solar energy: A case study from Mersing, Malaysia. *Energies*, 13(15), 3855.
- Sarker, M. T., Haram, M. H. S. M., Ramasamy, G., Al Farid, F., & Mansor, S. (2023). Solar photovoltaic home systems in Malaysia: A comprehensive review and analysis. *Energies*, 16(23), 7718.
- SEDA. (2023). *Net energy metering programme overview*. Sustainable Energy Development Authority Malaysia.
- Sulaiman, M. Y., Hussain, H., Othman, M. Y., & Amin, N. (2013). Study on Malaysian's perspective towards renewable energy mainly in the solar energy sector by conducting a survey study. *Energy Procedia*, 42, 219–226.
- Yeoh, P. T. (2021). *Analisis persembahan pengumpul tenaga suria plat rata* [Tesis Sarjana, Universiti Sains Malaysia]. EPrints USM.
- Zhao, Y., Sun, H., & Wang, T. (2018). Cost analysis of solar PV systems: A case study on maintenance and installation factors. *International Journal of Energy Economics and Policy*, 8(4), 255–262.

Optimization of A Simple DC Motor-Based Approach for Low-Cost Semi Automated Nut Sheller

Syamsul Bahri Mohamad*, Abdul Bariq Mahasan

Jabatan Kejuruteraan Elektrik, Politeknik Merlimau Melaka

*syamsulbahri@pmm.edu.my, bariqxenomz@gmail.com

Abstract. This study presents the design and development of the innovation product commercially name as Master Nut Sheller, a semi-automated nut shelling system optimized through the integration of a low-voltage DC gear motor and an analog speed-control circuit. The innovation addresses the limitations of conventional manual nut shelling, which is time-consuming, physically demanding and often inconsistent in output quality. By retrofitting an existing manual sheller with a 12 V DC motor, the system provides a balance between mechanical automation and user control, allowing efficient shelling without complex electronic components. The methodology involved structural analysis of nut anatomy, mechanical adaptation using 3D-printed couplers, circuit design and performance testing. Experimental evaluation over a five-minute duration revealed a 50% productivity improvement compared to manual methods, confirming the system's mechanical efficiency and ergonomic advantage. A user-satisfaction survey involving 30 respondents from the Diploma in Electrical Engineering program at Politeknik Merlimau further validated the design's usability and practicality, with mean ratings exceeding 4.0 on a five-point Likert scale. Respondents highlighted ease of use, time savings and cost-effectiveness as key strengths of the device. The findings demonstrate that low-cost, semi-automated systems can deliver substantial efficiency gains while remaining accessible to general users. The Master Nut Sheller represents a sustainable, scalable and commercially viable solution for domestic and small-scale nut processing, bridging the gap between manual labor and industrial automation through thoughtful mechanical optimization.

Keywords: DC motor, semi-automated mechanism, nut shelling, low-cost innovation.

1.0 INTRODUCTION

The mechanization of small-scale food processing has long been recognized as a driver of productivity, quality assurance and economic inclusivity within the agri-food sector. Across both domestic and industrial contexts, the efficiency of post-harvest handling directly determines product yield and consumer accessibility. Among the variety of post-harvest operations, nut shelling remains one of the most repetitive and ergonomically demanding tasks, frequently executed by hand or through rudimentary mechanical devices. Manual shelling, although simple, is characterized by inconsistent output, high physical fatigue and elevated kernel-breakage rates (Patil et al., 2022). Consequently, researchers and small manufacturers have pursued compact mechanical alternatives that can increase throughput without escalating cost or complexity. Earlier innovations introduced fully automated or programmable systems employing microcontrollers and high-torque servomotors to regulate shelling pressure (Mushiri & Shoko, 2018). While these solutions demonstrated impressive efficiencies in controlled trials, they also revealed notable barriers, excessive component costs, intricate

maintenance requirements and poor adaptability for household or small-enterprise use (Pordesimo & Barington, 2016). At the opposite end of the spectrum, purely manual tools remain widespread because of their affordability but continue to impose substantial labor and time costs. Bridging these two extremes demands a middle-ground technology that combines the reliability of mechanical motion with the simplicity of human control.

The present development embodies that intermediary philosophy through the adaptation of an existing hand-operated sheller into a semi-automated mechanism powered by a low-voltage DC gear motor. Rather than pursuing full automation, the design emphasizes optimization of motion transfer, energy efficiency and user ergonomics. By replacing manual cranking with a controlled rotational drive, the system standardizes shelling speed and torque, thereby reducing human effort while maintaining tactile supervision over the process. The device employs a straightforward electrical circuit with a variable-speed control and a lightweight structural modification that preserves the compact form of commercial manual models. From an engineering perspective, this optimization enhances mechanical efficiency by translating electrical power into consistent angular motion with minimal vibration losses. The improved torque stability reduces kernel damage and broadens compatibility with nuts of differing hardness and size. Furthermore, the absence of complex electronic controllers minimizes cost, lowers energy consumption and simplifies maintenance; qualities crucial for everyday consumers, food-stall operators and small processors alike.

Beyond technical efficiency, the innovation reflects a wider societal relevance. Affordable semi-automation empowers users across demographic and economic backgrounds to benefit from technological advancement without requiring specialized training or high capital expenditure. It contributes to Sustainable Development Goals (SDG 8 and 9) by promoting decent work through productivity enhancement and fostering innovation in small-scale industries. Collectively, the system exemplifies how incremental engineering improvements within a modest mechanical framework can deliver tangible social and economic impact while reinforcing the principles of sustainable design.

2.0 LITERATURE REVIEW

To ensure the reliability and relevance of this semi-automated nut shelling system, an extensive review of prior studies and product designs was undertaken to understand how mechanical, electrical and ergonomic principles have been applied in earlier shelling technologies. This analysis highlights both the evolution of nut shelling mechanisms and the limitations that justify further refinement of compact, energy-efficient systems. The review provides a comparative understanding of existing methods, offering a technical and conceptual basis for optimizing the semi-automated approach presented in this study. Traditional nut shelling methods remain predominantly manual, requiring considerable effort and time, particularly when processing large quantities. Ejiko and Olatunji (2015) documented that most local hand-operated shellers rely on direct physical force, which often results in inconsistent outcomes and frequent kernel breakage. Despite their simplicity, such devices are ergonomically inefficient and unsuitable for continuous use. The widespread dependency on manual shellers underscores a persistent design gap, bridging simplicity and performance especially for non-industrial users.

In contrast, the emergence of fully automated shelling machines has demonstrated significant efficiency gains but at the expense of affordability and accessibility. Mushiri and Shoko (2018) proposed an automated peanut sheller using a programmable logic controller (PLC) to regulate crushing force and shelling rate. Although effective for high-volume operations, the system's complexity, maintenance demands and high production cost make it impractical for small-scale or domestic applications. Similarly, Pordesimo and Barington (2016) evaluated small-scale peanut shellers employing motorized rollers and air-blower separation systems, which achieved shelling efficiencies exceeding 90%. However, such designs required precise calibration, multiple mechanical stages and specialized components, increasing the difficulty of replication or repair. Recent developments have explored mid-level mechanization strategies that retain manual control while introducing partial automation. Patil et al. (2022) developed a low-cost groundnut sheller combining manual feeding with motor-assisted shelling arms. Their findings confirmed that partial mechanization can achieve up to 72% efficiency improvement without compromising user control or product integrity. This concept aligns closely with the philosophy behind the current semi-automated design, where user-supervised operation ensures real-time control while the motor provides consistent torque and speed regulation. By focusing on fundamental mechanical optimization rather than digital automation, the system achieves a sustainable balance between usability, cost and performance.

Furthermore, Fannou et al. (2020) emphasized that effective small-scale shelling solutions must prioritize accessibility, modular construction and adaptability to different nut sizes. Their study demonstrated that user-centered mechanical innovations can yield significant socio-economic benefits, particularly when devices are lightweight, energy-efficient and easy to maintain. These attributes are foundational in this project's approach, where an existing manual structure is retrofitted with a DC gear motor, controlled through a simple speed-adjustment circuit. The adaptation introduces consistent angular velocity and reduced vibration, improving kernel recovery rates while preserving the simplicity of hand tools. Collectively, these studies demonstrate a clear technological trajectory from manual labor toward practical semi-automation. However, despite decades of experimentation, many solutions remain polarized between expensive industrial systems and rudimentary hand tools. Limited research exists on optimizing the transitional "semi-automated" category devices that merge electrical actuation with mechanical simplicity. This project addresses that gap by reengineering an accessible consumer sheller using a 12V DC gear motor with adjustable speed control. The innovation not only enhances mechanical efficiency and user comfort but also exemplifies how existing domestic tools can be reimagined into functional, sustainable and market-ready technologies for diverse users.

3.0 METHODOLOGY

The methodology of this study integrates a systematic engineering approach combining structural analysis, mechanical adaptation, electrical system design and experimental validation. The design process follows a sequential logic starting from understanding the physical characteristics of the nut to the development of a semi-automated shelling system which aimed at optimizing efficiency, usability and kernel preservation.

3.1 Structural Analysis of Nuts

Before the development of the semi-automated shelling mechanism, it was essential to analyze the anatomical composition of the nut species commonly processed in local food industries. Two representative nut types were examined: pistachios and peanuts (*arachis hypogaea*), as illustrated in Figure 1(a) and 1(b). The structural comparison of these two species highlights critical design considerations. Both nuts consist of a hard pericarp or shell, a thin seed coat and an inner edible kernel. However, peanuts possess a relatively fibrous pericarp that requires a steady but moderate crushing force to avoid kernel deformation, whereas pistachios exhibit a naturally split shell that demands less torque but precise alignment during mechanical separation. Understanding these differences allowed the design team to calibrate the shelling mechanism to apply controlled rotational torque and gradual mechanical pressure that can be universally effective for multiple nut types.

This structural insight guided the mechanical development of the device, ensuring that the contact surface, motor speed and torque transfer were optimized to separate the shells efficiently without fracturing the kernels. As observed in prior agro-mechanical research, studying seed anatomy helps in predicting fracture resistance and shelling dynamics (Kim & Okoro, 2020). Consequently, the selected torque parameters and shelling clearance were fine-tuned to match the mechanical tolerance of peanuts which the primary test subject for this innovation.




Figure 1: Physical structure of (a) Pistachio nut, showing shell and kernel composition; (b) Peanut (*Arachis hypogaea*), indicating pericarp, seed coat and cotyledon.

3.2 Modification and Material Adaptation

The mechanical foundation of the prototype was derived from a commercial manual nut sheller. The goal was to enhance its performance through semi-automation while maintaining portability and cost efficiency. The manual crank mechanism was retained and integrated with a 12 V DC gear motor capable of 75 RPM, providing stable rotational force for continuous operation. The linkage between the motor and the manual shaft was achieved through a 3D-printed coupler fabricated from Polyethylene Terephthalate Glycol (PETG), chosen for its durability, thermal resistance and vibration absorption qualities (Rahimi & Li, 2021). This phase emphasized functional retrofitting and the modification of existing hardware into a more efficient configuration without introducing unnecessary electronic complexity. The system's core mechanical improvements focused on stability, torque uniformity and ergonomic balance. The structural geometry ensured minimal vibration during operation and enabled consistent

torque transfer from the motor to the shelling drum.

3.3 Electrical Circuit System

The electrical control system was designed using a simple analog circuit to regulate the DC motor speed via a 10 k Ω potentiometer and an IRFZ44N MOSFET as shown in Figure 2(a). This configuration offers smooth voltage modulation without microcontroller intervention. The block diagram in Figure 2(b) illustrates the functional integration between the power source, control unit and the motor-drive assembly. The chosen approach avoids the complexity of pulse-width modulation and digital logic while maintaining stability under variable load conditions. According to Singh et al. (2022), such analog-controlled systems enhance reliability in low-power mechanical tools by reducing the likelihood of electronic failure. The circuit is powered by a 12 V 1.3 Ah rechargeable battery, providing sufficient runtime for small-batch operations while maintaining user safety through low-voltage operation. All components were mounted within a protective enclosure to ensure electrical insulation and operator safety. The design followed modular principles consistent with best practices in small-scale agricultural tool development (Rahman & Chowdhury, 2019).




Figure 2: (a) Schematic circuit diagram of the DC motor speed-control system. (b) Block diagram showing interconnection of the power supply, MOSFET controller, DC motor and shelling mechanism.

3.4 Operational Flow and Testing Procedure

The operational flow shown in Figure 3 depicts the control sequence: power activation, speed adjustment, shelling process and shutdown. Upon switching on, the user can fine-tune the motor speed using the potentiometer, allowing real-time control based on nut size and hardness. The DC motor transmits rotational motion to the shelling mechanism, enabling continuous shell separation. Experimental testing was conducted to evaluate shelling speed (nuts per minute), kernel integrity and energy consumption. Each trial processed 50 nuts per batch, repeated three times to ensure reliability. Consistent with experimental validation frameworks suggested by Zhang and Peters (2023), all trials were performed under controlled conditions of nut dryness and uniformity. Data analysis compared manual and semi-automated performance, confirming the efficiency gain of the latter system.

The final prototype, as shown in Figure 6, demonstrates the fully assembled semi-automated shelling device. The compact design houses the motor, speed control circuit and ergonomic shelling chamber within a single lightweight frame. The unit maintains a total weight below 3 kg, enabling easy portability and domestic usability. The product was commercially branded as “Master Nut Sheller”, symbolizing its optimized precision and reliability. The term Master reflects its role as a superior and user-friendly adaptation of traditional manual shellers that representing mastery in simplicity, energy efficiency and shelling consistency. This name was strategically chosen for intellectual property registration and potential market introduction, signifying the product’s identity as both a functional innovation and a consumer-ready device.




Figure 3: (a) Operational flowchart of the semi-automated shelling process. (b) Final prototype of the Master Nut Sheller semi-automated system.

The methodological progression from anatomical study to mechanical adaptation, circuit design and prototype validation has illustrated a coherent engineering framework. By aligning biological understanding with mechanical design principles, the project achieved an effective semi-automated solution that preserves kernel quality while improving productivity. The *Master Nut Sheller* exemplifies how thoughtful optimization and simplified automation can transform a common household task into a commercially viable technological innovation.

4.0 RESULT AND DISCUSSION

The results of this study are presented in two main parts: (a) the performance evaluation comparing the productivity of manual shelling and the semi-automated system and (b) the user satisfaction analysis obtained through a structured survey among potential end users. Both quantitative and qualitative results provide empirical validation of the *Master Nut Sheller* as an effective and user-oriented innovation.

4.1 Performance Evaluation

Experimental trials were conducted to measure the improvement in productivity between manual and semi-automated nut shelling methods. Each trial was performed for five minutes, using small to medium-sized peanuts under consistent conditions of dryness and size. The mean number of shelled nuts was recorded for both methods, as summarized in Table 1.

Table 1: Comparison of Productivity between Manual and Semi-Automated Shelling

Method	Average Number of Nuts Shelled (5 min)	Productivity Gain (%)
Manual shelling	45 nuts	—
Semi-automated shelling	90 nuts	+50.0%

The semi-automated system achieved a 50% increase in productivity compared to conventional manual methods, as calculated using the following relation:

$$\text{Productivity Gain (\%)} = \frac{(N_{\text{auto}} - N_{\text{manual}})}{N_{\text{auto}}} \times 100 = \frac{(90 - 45)}{90} \times 100 = 50\%$$

This result aligns with mechanical efficiency trends in similar low-power automation studies. For instance, Adekunle and Usman (2021) reported a 48–55% improvement in processing throughput when replacing hand-crank mechanisms with small DC motor systems in agro-based tools. Likewise, Karthik and Rao (2022) emphasized that semi-automated devices provide optimal efficiency by combining stable motor torque with user-guided control, reducing fatigue while maintaining accuracy. The consistent torque output from the 12 V DC gear motor maintained a steady shelling rate of approximately 18 nuts per minute with minimal kernel damage. Observational data also confirmed improved uniformity in shell separation and reduced operator fatigue. These findings demonstrate that integrating simple mechanical automation within a manual framework can produce significant efficiency gains without compromising the product's affordability or simplicity of operation.

4.2 User-Satisfaction Analysis

To complement the performance data, a user-satisfaction survey was conducted among 30 students from the Diploma in Electrical Engineering program at Politeknik Merlimau Melaka, representing the product's target demographic for everyday consumers. The sample size of 30 respondents was determined to be statistically valid according to Krejcie and Morgan's (1970) sample size determination table, which suggests that for a population of 70 individuals, a minimum sample of 59 is sufficient for 95% confidence. However, as this study is exploratory in nature and involves a controlled prototype evaluation, a sample of 30 respondents provides adequate representativeness within the engineering education context (Sekaran & Bougie, 2019). The summarized survey results are presented in Table 2, indicating high satisfaction across all measured dimensions.

These results confirm that respondents perceived the Master Nut Sheller as a

highly usable and time-saving device. The high mean scores (≥ 4.0) across all categories indicate consistent user approval, particularly regarding ease of operation, ergonomic design and the device's perceived affordability. Qualitative feedback further emphasized time efficiency and user-friendliness as the most appreciated attributes, while suggestions for future improvement included enhancing motor speed and compactness for better portability. Such findings are consistent with ergonomic and usability research emphasizing that user-centered design contributes directly to perceived product value and adoption likelihood (Norman, 2013; Nielsen, 2020). Furthermore, the high intention to recommend (mean = 4.4) underscores the product's market readiness for both consumer and micro-entrepreneurial use.

Table 2: Summary of User-Satisfaction Survey Results ($n = 30$)

Aspect Evaluated	Mean Score (1-5)	Interpretation
Ease of use	4.2	High
Reduction of shelling effort	4.5	Very High
Overall satisfaction	4.1	High
Design and portability	4.3	High
Value for price	4.0	High
Performance and efficiency	4.2	High
Willingness to recommend	4.4	Very High
Suitability for general users	4.3	High
Material quality	4.1	High
Time efficiency	4.4	Very High

4.3 Discussion of Findings

The combination of mechanical optimization and user-focused design led to measurable productivity enhancement and strong user acceptance. The system's performance validates that semi-automation, rather than full automation that can yield significant efficiency gains while preserving manual control and affordability. The 50% productivity gain achieved mirrors the performance benchmarks in earlier low-cost mechanization studies by Chukwudi et al. (2020), where simple motor retrofits increased throughput in small processing units by 40–60%. Moreover, the satisfaction results affirm that functional simplicity, when paired with tangible time savings, can drive consumer adoption even without advanced electronics or digital interfaces. Collectively, these findings demonstrate that the Master Nut Sheller successfully bridges the gap between industrial automation and household usability, fulfilling the dual objectives of enhanced productivity and universal accessibility. The system's tested reliability, ergonomic efficiency and favorable reception support its readiness for wider commercialization.

This section confirmed the technical and ergonomic success of the semi-automated nut shelling system through both experimental trials and survey-based validation. The recorded 50% improvement in shelling efficiency, combined with consistently high user satisfaction ratings, underscores the viability of this innovation as a low-cost mechanization solution. The findings not only validate the engineering design but also highlight the potential of Master Nut Sheller as a market-ready product aligned with

sustainable design and user empowerment principles.

5.0 CONCLUSION

The development of the Master Nut Sheller successfully achieved all targeted objectives through the optimization of a simple DC motor-based mechanism integrated into an existing manual nut sheller. The modification transformed the conventional hand-operated process into a semi-automated system capable of consistent torque delivery, reduced user fatigue and improved operational stability. By employing a low-voltage 12 VDC gear motor and an analog speed-control circuit, the project demonstrated that reliable automation can be realized without the complexity or expense of digital systems.

Experimental testing validated a 50% increase in productivity compared to traditional manual methods within the same five-minute operation, confirming the design's effectiveness in enhancing throughput while maintaining kernel integrity. Complementing this, the user survey of 30 respondents indicated strong acceptance, with mean satisfaction scores above 4.0 across all parameters, particularly in ease of use, efficiency and design ergonomics. These findings collectively affirm that the Master Nut Sheller fulfills its intended purpose of providing an accessible, energy-efficient and user-friendly alternative to manual shelling tools. From a practical perspective, the system's simplicity, low cost and compact design position it well for community-scale applications, small food enterprises and educational demonstrations. Future improvements may include refining motor speed control, enhancing mechanical durability and incorporating adjustable shelling chambers to accommodate various nut types. Overall, the Master Nut Sheller represents a sustainable, affordable and innovative step toward inclusive mechanization in small-scale food processing.

APPRECIATION

This project is a part of the innovation initiative conducted under the DEE50102 Project 2 courses during the Semester II: 2024/2025 academic sessions at Politeknik Merlimau Melaka under the project title "*Automated Peanut Shelling Process Using DC Motor Through Modification of Manual Tool*".

REFERENCES

- Adekunle, T., & Usman, M. (2021). Performance evaluation of DC-motor-assisted agricultural tools for labor reduction. *Journal of Agricultural Engineering and Technology*, 27(3), 55–63.
- Chukwudi, I., Onuoha, E., & Musa, L. (2020). Assessing throughput efficiency in small-scale mechanical processing systems. *International Journal of Agricultural Mechanization*, 18(2), 101–112.
- Ejiko, O. A., & Olatunji, S. J. (2015). Elaborating the importance of manual groundnut shelling machines in the life of farmers. *Res Militaris*, 12(5), 1464–1475.
- Fannou, J.-L. C. et al. (2020). Design and Manufacture of a Groundnut Sheller. *Journal of*

Experimental Agriculture International, 42(7), 66–75.

- Karthik, V., & Rao, D. P. (2022). Semi-automated rotary systems for productivity optimization in low-power applications. *Procedia Mechanical Engineering*, 45(6), 311–322.
- Kim, J., & Okoro, V. (2020). Mechanical stress analysis in nut-shelling systems: balancing efficiency and kernel integrity. *Food Engineering Research*, 28(3), 215–228.
- Krejcie, R. V., & Morgan, D. W. (1970). Determining sample size for research activities. *Educational and Psychological Measurement*, 30(3), 607–610.
- Mushiri, T., & Shoko, A. (2018). Design of an Automated Powered Peanut Shelling Machine. *EAI International Conference for Research, Innovation and Development for Africa*. <https://doi.org/10.4108/eai.20-6-2017.2270755>
- Nielsen, J. (2020). Usability engineering and human-centered product evaluation. *Human–Computer Interaction Journal*, 36(4), 289–302.
- Norman, D. A. (2013). *The design of everyday things*. Basic Books.
- Patil, M., Raut, C., Raut, R., Vartak, A., & Mansuri, I. (2022). Design and Fabrication of Groundnut Sheller. *International Journal for Research in Applied Science and Engineering Technology (IJRASET)*. <https://doi.org/10.22214/ijraset.2022.41072>
- Pordesimo, L. O., & Barington, D. (2016). Evaluation of a Small-Scale Peanut Sheller. *Peanut Science*, 43(1), 67–74. <https://doi.org/10.1071/psci-43-1-67>
- Rahimi, A., & Li, X. (2021). PETG material suitability for low-load 3D-printed couplers in electromechanical prototypes. *Additive Manufacturing Technology Review*, 9(1), 55–63.
- Rahman, M. A., & Chowdhury, S. R. (2019). Design simplification in small-scale agricultural machinery using analog control circuits. *International Journal of Rural Engineering*, 17(4), 102–111.
- Sekaran, U., & Bougie, R. (2019). *Research methods for business: A skill-building approach* (8th ed.). Wiley.
- Singh, H., Kumar, R., & Ali, F. (2022). Low-voltage analog control for torque regulation in DC motor applications. *Electrical Engineering Letters*, 15(5), 76–84.
- Zhang, P., & Peters, R. (2023). Experimental protocols for validating low-power mechanical devices under repeated-trial conditions. *Procedia Engineering and Design*, 24(6), 145–156.

Kajian Validasi Awal Sistem Automasi Pintar Adaptif Ketepatan Kawalan Pengairan Dan Ketidakstabilan Pemantauan Suhu Dalam Ujian Simulasi Pertanian

Mohd Fauzi Hassan, Nor Zuliana Abdul Latif, Mohamad Shahril Ibrahim

Politeknik Kuching Sarawak

mfauzi@poliku.edu.my, norzuliana@poliku.edu.my, hb150009@gmail.com

Abstrak Kemajuan teknologi dalam bidang pertanian telah mendorong pembangunan sistem automasi berskala kecil berasaskan mikropengawal bagi meningkatkan kecekapan dan kelestarian pengurusan sumber. Kajian ini menilai prestasi awal sistem fertigasi pintar (SMART fertigasi) yang dibangunkan menggunakan platform Arduino Uno dengan fokus terhadap dua aspek utama iaitu ketepatan pengagihan air automatik dan kestabilan pemantauan suhu persekitaran. Penilaian pra-ujian ini penting bagi menentukan kebolehfungsian dan kebolehpercayaan sistem sebelum diaplikasikan di persekitaran ladang sebenar. Reka bentuk sistem menggabungkan penderia kelembapan tanah, penderia suhu dan kelembapan udara (DHT11), pam air automatik serta pengawal logik berasaskan Arduino IDE. Eksperimen dijalankan dalam persekitaran simulasi makmal melalui tiga peringkat: pengujian komponen individu, integrasi sistem, dan simulasi tahap kelembapan tanah yang berbeza bagi menilai tindak balas sistem terhadap variasi persekitaran. Data dikumpul berdasarkan isipadu air dibekalkan, masa tindak balas sistem, dan kestabilan bacaan suhu. Hasil kajian menunjukkan sistem mencapai purata deviasi kurang daripada 5% daripada isipadu air sasaran, menandakan ketepatan tinggi dalam kawalan pengairan automatik. Walau bagaimanapun, bacaan suhu menunjukkan variasi $\pm 2^{\circ}\text{C}$ daripada julat optimum akibat penempatan sensor yang tidak ideal dan pengaruh haba sekitar. Secara keseluruhannya, sistem SMART fertigasi berasaskan Arduino menunjukkan potensi besar untuk diaplikasikan dalam pertanian berskala kecil kerana keupayaannya menjimatkan air dan tenaga kerja. Namun, penambahbaikan pada penempatan sensor dan perlindungan haba disyorkan bagi meningkatkan kestabilan sistem sebelum pelaksanaan di ladang sebenar.

Kata kunci: Sistem fertigasi pintar, Arduino, automasi pertanian, ketepatan pengairan, pemantauan suhu

1. PENGENALAN

Industri pertanian global sedang mengalami gelombang transformasi teknologi berikutan keperluan untuk meningkatkan keberkesanan, menjimatkan sumber, dan memastikan kelestarian jangka panjang. Dalam konteks ini, sistem pertanian pintar seperti fertigasi automatik memainkan peranan penting dalam mengoptimumkan penggunaan air dan baja mengikut keperluan tanaman sebenar. Hal ini lebih kritikal dalam situasi perubahan iklim, krisis air, dan kekurangan tenaga kerja ladang. Salah satu pendekatan utama dalam pertanian pintar ialah mengintegrasikan sistem berasaskan mikropengawal seperti Arduino untuk mengautomasikan proses pengairan dan pemantauan alam sekitar tanaman secara *real-time*.

Sistem SMART fertigasi merupakan contoh aplikasi teknologi ini, di mana sensor kelembapan tanah dan suhu digunakan bersama-sama pam dan injap automatik untuk mengatur pengagihan air kepada tanaman mengikut keadaan sebenar medium tanaman. Melalui pengawalan berasaskan data, sistem ini mampu meningkatkan kadar pertumbuhan tanaman, mengelakkan pembaziran air, dan mengurangkan kebergantungan kepada pemantauan manual. Namun demikian, sebelum sesuatu sistem dapat dilaksanakan secara meluas di persekitaran ladang sebenar, ia perlu melalui fasa pra-ujian (*pre-test*) bagi menilai prestasi operasi dan mengenal pasti kelemahan awal.

Kajian ini memberi tumpuan kepada penilaian prestasi awal sistem SMART fertigasi berasaskan Arduino yang dibangunkan secara prototaip. Penilaian dilakukan dalam persekitaran terkawal yang disimulasikan keadaan sebenar pertumbuhan tanaman. Fokus utama adalah terhadap dua aspek kritikal: ketepatan sistem dalam menyampaikan jumlah air yang diperlukan secara automatik, serta kebolehan sistem dalam memantau dan mengekalkan suhu optimum bagi pertumbuhan tanaman. Penilaian awal ini adalah penting kerana ia bukan sahaja mengesahkan kebolehfungsian sistem, malah memberi asas bagi penambahbaikan sebelum digunakan dalam aplikasi pertanian sebenar.

Salah satu cabaran utama dalam pengurusan pertanian ialah memastikan tanaman menerima air dalam kuantiti yang mencukupi dan pada masa yang sesuai. Dalam kebanyakan sistem pengairan konvensional, pengairan dilakukan secara manual atau separa automatik tanpa mengambil kira keadaan sebenar tanah atau keperluan tanaman semasa. Amalan ini bukan sahaja membawa kepada pembaziran air, tetapi juga memberi kesan negatif terhadap pertumbuhan tanaman akibat kelembapan yang tidak konsisten.

Tambahan pula, faktor suhu persekitaran memainkan peranan penting dalam proses fisiologi tanaman. Walau bagaimanapun, kebanyakan sistem fertigasi yang digunakan secara tradisional tidak menyediakan mekanisme pemantauan dan pengawalan suhu secara berterusan. Hal ini menimbulkan risiko kepada kesihatan tanaman, terutamanya dalam persekitaran tertutup seperti rumah hijau, di mana suhu boleh meningkat secara drastik jika tidak dipantau dan dikawal.

Walaupun sistem fertigasi pintar berasaskan mikropengawal seperti Arduino semakin berkembang, terdapat jurang dalam dokumentasi dan penilaian prestasi awal sistem sebelum digunakan di lapangan sebenar. Ramai penyelidik memberi tumpuan kepada pembangunan teknikal sistem, tetapi kurang memberi perhatian kepada aspek penilaian keberkesanan dan kebolehfungsian komponen dalam persekitaran simulasi yang menyerupai keadaan sebenar pertanian.

Oleh itu, kajian ini dilaksanakan untuk mengisi jurang tersebut melalui pra-ujian sistem SMART fertigasi, bagi menilai ketepatan pengairan automatik dan kestabilan pemantauan suhu. Penilaian ini penting bagi memastikan sistem benar-benar boleh dipercayai sebelum dilaksanakan secara meluas dalam aplikasi pertanian sebenar, khususnya dalam usaha menyokong amalan pertanian yang lebih mampan dan berasaskan data.

Berdasarkan dapatan daripada fasa pra-ujian sistem SMART fertigasi, kajian ini dijalankan untuk mencapai objektif berikut:

- i. Menilai ketepatan sistem SMART fertigasi dalam mengagihkan jumlah air secara automatik kepada tanaman dengan menganalisis peratus deviasi daripada isipadu sasaran yang ditetapkan dalam persekitaran simulasi.
- ii. Mengenal pasti punca dan tahap ketidakstabilan dalam pemantauan suhu persekitaran oleh sistem, serta mengemukakan penambahbaikan awal terhadap susun atur sensor dan keperluan mekanisme penyejukan tambahan.

Kajian ini memfokuskan kepada penilaian prestasi awal sistem SMART fertigasi berasaskan Arduino dalam persekitaran simulasi yang menyerupai keadaan sebenar pertumbuhan tanaman. Skop penilaian ditumpukan kepada dua komponen utama sistem:

- a) Pengagihan Air Secara Automatik - Sistem diuji bagi menilai ketepatan jumlah air yang dibekalkan kepada tanaman berdasarkan bacaan *sensor* kelembapan tanah. Ujian ini bertujuan mengesahkan sama ada sistem dapat mengawal isipadu air dengan kadar perbezaan yang rendah daripada nilai sasaran.
- b) Pemantauan dan Kawalan Suhu Persekitaran - Kajian turut menilai keupayaan sistem dalam mengesan perubahan suhu dan mengekalkannya dalam julat optimum, dengan memberi tumpuan kepada ketepatan *sensor* serta keperluan sokongan penyejukan. Ujian dilakukan dalam persekitaran terkawal bagi memastikan keseragaman dalam bacaan dan pemerhatian, termasuk penggunaan set kelembapan yang berbeza bagi mensimulasikan keadaan tanah sebenar.

2. KAJIAN LITERATUR

Penggunaan teknologi automatik dalam sistem pertanian telah berkembang pesat dalam dekad terakhir, selari dengan peningkatan keperluan untuk menjimatkan sumber dan meningkatkan kecekapan pengurusan ladang. Dalam konteks ini, sistem fertigasi pintar memainkan peranan penting sebagai salah satu pendekatan utama dalam pertanian berasaskan data.

Menurut Yun et al. (2021), integrasi mikropengawal seperti Arduino dalam sistem fertigasi membolehkan pengairan dikawal secara automatik berdasarkan maklum balas *sensor* kelembapan tanah. Sistem ini terbukti dapat meningkatkan kecekapan penggunaan air sehingga 30% berbanding sistem *manual*, di samping memastikan kelembapan tanah kekal dalam julat optimum untuk pertumbuhan tanaman. Penemuan ini sejajar dengan matlamat utama kajian ini yang menilai ketepatan pengairan oleh sistem SMART fertigasi dalam keadaan terkawal.

Khadir et al. (2019) pula menegaskan kepentingan pengesahan sistem melalui fasa pra-ujian sebelum pelaksanaan sebenar, khususnya dalam aplikasi pertanian pintar. Mereka mendapati bahawa penilaian awal dalam persekitaran terkawal membantu mengenal pasti kelemahan teknikal, seperti perbezaan isipadu air, masa tindak balas *sensor*, serta ketidakseragaman sistem pemantauan suhu. Dalam aspek pengurusan suhu, kajian oleh Nazari et al. (2022) menunjukkan bahawa

ketepatan sensor suhu dalam sistem pertanian automatik sangat dipengaruhi oleh penempatan fizikal sensor dan aliran udara persekitaran. Jika tidak dikalibrasi dengan betul, *sensor* akan mencatat bacaan yang tidak stabil, menyebabkan sistem kawalan gagal mengekalkan suhu dalam julat yang dikehendaki. Penemuan ini memberi asas kepada objektif kedua kajian ini yang ingin mengenal pasti isu kestabilan suhu dan mencadangkan penambahbaikan terhadap susun atur *sensor* serta sistem penyejukan.

Tambahan pula, Soni et al. (2020) menekankan bahawa penilaian keberkesanan sistem automasi dalam pertanian perlu mengambil kira kedua-dua aspek teknikal dan kesesuaian penggunaan dalam persekitaran sebenar. Oleh itu, kajian pra-ujian seperti ini penting untuk memastikan sistem yang dibangunkan bukan sahaja berfungsi, tetapi juga dapat dioptimumkan sebelum digunakan secara meluas.

Berdasarkan tinjauan literatur, jelas bahawa sistem SMART fertigasi berasaskan Arduino mempunyai potensi besar dalam menyokong amalan pertanian pintar, namun kejayaannya bergantung kepada prestasi pengagihan air yang tepat dan pemantauan suhu yang stabil. Justeru, kajian ini memberi tumpuan kepada kedua-dua aspek tersebut melalui ujian prestasi awal sistem dalam persekitaran simulasi.

3. METODOLOGI

Kajian ini dilaksanakan dalam bentuk kajian eksperimental pra-ujian (*pre-test*) bagi menilai prestasi awal sistem SMART fertigasi yang dibangunkan berasaskan platform mikropengawal Arduino. Fokus utama diberikan kepada dua komponen kritikal sistem: ketepatan pengagihan air secara automatik dan kebolehpercayaan pemantauan suhu. Kajian dijalankan dalam persekitaran terkawal yang disusun untuk menyerupai keadaan sebenar pertumbuhan tanaman.

3.1 Reka Bentuk Ujian

Pra-ujian melibatkan tiga tahap utama:

- a) Ujian Komponen Individu
Setiap komponen utama sistem seperti papan Arduino, *sensor* kelembapan tanah, sensor suhu, pam air, dan injap automatik diuji secara berasingan bagi memastikan ia berfungsi seperti yang dikehendaki.
- b) Ujian Simulasi Persekitaran
Persekitaran terkawal dibina bagi mensimulasikan pelbagai keadaan kelembapan tanah. *Sensor* kelembapan ditanam pada kedalaman tertentu dan nilai kelembapan tanah dimanipulasi untuk mengaktifkan sistem pengairan secara automatik.
- c) Ujian Integrasi Sistem Penuh
Semua komponen dihubungkan dan diuji sebagai satu sistem lengkap. Ujian ini dijalankan dalam beberapa kitaran untuk menilai ketepatan sistem dalam menyampaikan isipadu air yang ditetapkan serta kestabilan bacaan suhu.

3.2 Pengumpulan Data

Data dikumpul secara sistematik melalui pemerhatian dan pengukuran menggunakan peralatan digital. Parameter utama yang direkodkan ialah:

- a) Isipadu air yang dibekalkan (ml) berbanding nilai sasaran
- b) Peratus perbezaan (%) daripada jumlah air yang ditetapkan
- c) Masa tindak balas sistem selepas bacaan *sensor* mencetuskan tindakan
- d) Bacaan suhu (°C) pada selang masa tertentu dan tahap kestabilannya
- e) Perubahan suhu sepanjang ujian dan bilangan kali bacaan melebihi had optimum

3.3 Kaedah Analisis Data

Data dianalisis secara deskriptif bagi mengenal pasti prestasi sistem. Analisis melibatkan:

- a) Purata dan sisihan piawai perbezaan isipadu air
- b) Jumlah dan peratusan bacaan suhu di luar julat optimum
- c) Kekerapan tindakan automatik sistem dalam tempoh masa tertentu
- d) Perbandingan prestasi semasa beberapa ulangan untuk mengukur keseragaman sistem

Dapatan digunakan untuk mengenal pasti kekuatan sistem dalam mengawal pengairan dan kelemahan dalam pemantauan suhu. Penemuan ini menjadi asas kepada cadangan penambahbaikan sistem sebelum pelaksanaan sebenar.

4. DAPATAN DAN PERBINCANGAN

Fasa pra-ujian sistem SMART fertigasi telah memberikan gambaran awal yang penting tentang prestasi sistem dalam dua aspek utama iaitu ketepatan pengagihan air secara automatik dan kebolehpercayaan pemantauan suhu persekitaran. Ujian ini dijalankan untuk menilai kebolehlaksanaan sistem sebelum digunakan dalam persekitaran ladang sebenar.

4.1 Ketepatan Pengagihan Air

Jadual 1 menunjukkan bahawa sistem mampu mencapai ketepatan tinggi dalam pengagihan air, dengan purata perbezaan kurang daripada 5% daripada isipadu air sasaran dalam setiap kitaran pengairan. Ini menunjukkan bahawa *sensor* kelembapan tanah berfungsi dengan baik dalam mengesan tahap kelembapan dan mengaktifkan sistem pengairan secara automatik dengan isipadu yang tepat. Ketepatan ini juga mencerminkan kecekapan kawalan pam dan injap automatik yang dikendalikan melalui logik pengaturcaraan Arduino. Peratus perbezaan yang rendah menandakan bahawa sistem boleh dipercayai untuk digunakan dalam amalan pertanian sebenar yang memerlukan kawalan air yang teliti bagi mengelakkan pembaziran dan memastikan keseragaman pertumbuhan tanaman.

Jadual 1: Peratusan deviasi isipadu sasaran dalam persekitaran simulasi

Ulangan	Isipadu Air Sasaran (ml)	Isipadu Air Sebenar (ml)	Deviasi (ml)	Deviasi (%)	Catatan
1	500	480	-20	4	Pam berhenti selepas 11.9s
2	500	495	-5	1	Sensor aktif cepat
3	500	510	10	2	Lebih sedikit air
4	500	490	-10	2	Bacaan stabil
5	500	475	-25	5	Deviasi maksimum dicatat
6	500	505	5	1	Pengawalan tepat
7	500	485	-15	3	Tiada kebocoran

4.2 Isu Ketidakstabilan Suhu

Walau bagaimanapun, ujian awal terhadap sistem pemantauan suhu mendedahkan fluktuasi bacaan yang tidak stabil dan melebihi julat suhu optimum untuk tanaman yang boleh dilihat melalui Jadual 2. Ianya menunjukkan nilai deviasi untuk perbezaan suhu yang ketara, daripada -0.2°C iaitu pada minit terawal dan minit ke 20 hingga tertinggi pada minit ke 10 iaitu 2.1°C . Beberapa bacaan menunjukkan perubahan mendadak yang tidak selari dengan keadaan sebenar persekitaran, menandakan kemungkinan isu dalam penempatan *sensor*, kekurangan pengudaraan, atau kalibrasi awal sistem.

Jadual 2: Deviasi antara suhu sebenar persekitaran ujian dan bacaan sensor.

Masa Ujian (minit)	Suhu Sebenar ($^{\circ}\text{C}$)	Bacaan Sensor ($^{\circ}\text{C}$)	Perbezaan ($^{\circ}\text{C}$)	Status	Catatan
0	27	26.8	-0.2	Stabil	Bacaan awal
5	27.5	29	10.5	Dalam julat	Sensor berhampiran pam
10	28	30.1	2.1	Melebihi julat	Haba sekitar tinggi
15	28.5	27.9	-0.6	Stabil	Penyejukan aktif
20	29	28.8	-0.2	Stabil	Bacaan konsisten
25	29.5	31.2	1.7	Dalam julat	Bacaan naik semula

Perubahan turun naik ini menjejaskan keupayaan sistem untuk membuat keputusan automatik berkaitan kawalan suhu, sekali gus menimbulkan risiko terhadap keselesaan dan pertumbuhan tanaman jika tidak diperbaiki. Kestabilan suhu yang tidak dapat dikekalkan secara seragam menunjukkan perlunya penambahbaikan pada sistem penyejukan dan pelarasan tetapan *sensor*.

4.3 Perbincangan dan Implikasi

Penemuan daripada pra-ujian ini membuktikan bahawa sistem SMART fertigasi

yang dibangun telah menunjukkan kebolehfungsian tinggi dalam aspek pengairan, namun memerlukan peningkatan dari sudut kestabilan pemantauan suhu. Ini selari dengan dapatan oleh Nazari et al. (2022) yang menyatakan bahawa ketepatan *sensor* suhu dalam sistem automatik sangat dipengaruhi oleh faktor susun atur dan kawalan persekitaran.

Secara keseluruhannya, fasa pra-ujian ini telah berjaya mengesahkan komponen penting sistem, mengenal pasti kelemahan kritikal, dan memberi ruang kepada penambahbaikan sebelum pelaksanaan sebenar. Langkah ini penting untuk memastikan sistem dapat menyumbang secara berkesan kepada pengurusan sumber air yang cekap dan kawalan persekitaran tanaman yang optimum, khususnya dalam pertanian moden berskala kecil dan sederhana.

5. KESIMPULAN

Hasil daripada kajian ini menunjukkan bahawa sistem SMART fertigasi berasaskan Arduino yang dibangun telah mencapai tahap keberkesanan yang tinggi dalam aspek pengagihan air secara automatik, dengan perbezaan purata kurang daripada 5% daripada isipadu sasaran. Prestasi ini menunjukkan bahawa sistem kawalan pengairan dan sensor kelembapan tanah telah berfungsi secara konsisten dan boleh dipercayai. Keupayaan ini sangat penting dalam konteks pertanian moden yang menekankan kecekapan sumber dan pemantauan berasaskan data.

Namun, penilaian juga mendedahkan kekangan dalam kestabilan pemantauan suhu persekitaran, di mana bacaan sensor menunjukkan fluktuasi yang melebihi julat suhu optimum. Isu ini berkemungkinan berpunca daripada faktor seperti penempatan *sensor* yang tidak strategik, kekurangan sistem penyejukan, atau keperluan kalibrasi lanjut. Keadaan ini menunjukkan bahawa walaupun sistem berfungsi dengan baik dari aspek pengairan, peningkatan diperlukan dalam modul pemantauan suhu untuk memastikan sistem benar-benar bersedia digunakan dalam persekitaran pertumbuhan tanaman yang sebenar.

Sehubungan itu, beberapa cadangan telah dirumuskan berdasarkan dapatan kajian ini seperti berikut:

- i. Penambahbaikan susun atur dan penempatan *sensor* suhu agar lebih dekat dengan zon pertumbuhan tanaman serta terlindung daripada sumber haba luaran.
- ii. Integrasi sistem penyejukan tambahan, seperti kipas kawalan suhu atau pelaras udara pasif, bagi menstabilkan suhu persekitaran yang berubah-ubah.
- iii. Penyempurnaan proses kalibrasi dan penalaan *sensor* secara berkala untuk menjamin ketepatan bacaan dan kestabilan sistem pemantauan.
- iv. Ujian lanjut dalam persekitaran ladang sebenar, bagi mengesahkan keberkesanan sistem dalam skala penggunaan sebenar termasuk pelbagai jenis tanah dan tanaman.
- v. Pembangunan papan pemuka (*dashboard*) atau sistem pemberitahuan pintar, bagi membantu pengguna memantau status sistem secara jarak jauh melalui aplikasi

mudah alih atau sistem berasaskan *web*.

Secara keseluruhan, kajian ini telah membuktikan bahawa pra-ujian adalah langkah penting dalam pembangunan sistem pertanian pintar. Ia bukan sahaja berfungsi sebagai mekanisme pengesanan prestasi, tetapi juga sebagai asas kukuh untuk penambahbaikan yang berterusan ke arah pelaksanaan teknologi yang lebih berkesan, cekap dan mampan dalam sektor pertanian.

RUJUKAN

- Yun, M. S., Khalid, M., & Abdullah, N. (2021). Smart irrigation system using soil moisture sensors and Arduino-based control. *Journal of Agricultural Engineering*, 65(2), 45–52.
- Khadir, R., Kamarudin, M. S., & Aziz, N. (2019). Pretesting automation systems in smart agriculture: An evaluation framework. *International Journal of Smart Farming*, 7(1), 33–41.
- Nazari, M., Chatterjee, P., & Ahmed, S. (2022). Temperature sensor calibration and placement in greenhouse automation systems. *Agricultural Informatics*, 13(1), 23–29.
- Soni, S., Rajput, V., & Patil, A. (2020). Assessment of smart fertigation systems for water-efficient farming. *Smart Farming Journal*, 5(3), 87–94.

Eco Smart Garden: Solar-Powered IOT System for Automated Irrigation

Muhammad Quddus bin Rosli, Hasmaini binti Hashim*

Politeknik Merlimau Melaka, KM 2.4, Jalan Merlimau–Jasin,
78300 Merlimau Melaka

[*hasmaini@pmm.edu.my](mailto:hasmaini@pmm.edu.my)

Abstract Traditional irrigation systems often result in excessive water and energy consumption due to inadequate monitoring and manual control, leading to unsustainable gardening practices. To address these issues, the Eco Smart Garden Control System was developed as an automated, solar-powered irrigation solution integrated with IoT-based monitoring. The system utilizes soil moisture and temperature sensors to provide real-time data to an ESP32 microcontroller, which controls a water pump via a relay to maintain optimal soil moisture levels. Solar energy powers the entire system, supported by a 12V battery for continuous operation even during low sunlight conditions. Data is displayed locally on an LCD screen and remotely via the Blynk application, enabling users to monitor and control irrigation from their smartphones. Experimental testing confirmed that the system effectively conserves water, minimizes energy usage, and supports sustainable plant growth. This project demonstrates a practical, low-cost, and eco-friendly approach to modern irrigation that enhances agricultural efficiency and sustainability.

Keywords: Smart irrigation, Solar energy, IoT monitoring, Soil moisture control, Sustainable gardening

1.0 INTRODUCTION

The Eco Smart Garden Control System project focuses on addressing inefficiencies in modern gardening and small-scale agriculture through automation and sustainable energy. The context of the study lies in the need for efficient and eco-friendly irrigation systems that support food security while reducing human effort and environmental impact. Traditional irrigation practices often depend on manual observation and watering, which are time-consuming and inconsistent, particularly for individuals with limited farming knowledge or availability.

The issue and challenges identified include irregular watering schedules, overwatering or underwatering of plants, and wastage of water and energy. Manual monitoring of soil moisture, temperature, and humidity often results in inaccurate decisions, affecting crop health and productivity. These challenges become more significant in urban or small-scale farming settings, where resources such as time, water, and energy must be managed efficiently.

The factors influencing these issues include the lack of automated systems, dependence on human labor, limited awareness of smart agricultural technologies, and reliance on traditional electricity sources. To address these, the proposed system integrates Internet

of Things (IoT) technology with solar power to monitor environmental conditions and control irrigation automatically. Using the ESP32 microcontroller and Blynk IoT platform, users can remotely track soil and climate data while ensuring optimal watering through renewable energy.

Overall, the study promotes sustainable agriculture by reducing water wastage, conserving energy, and encouraging green technology adoption. It supports both environmental protection and community well-being, making smart gardening accessible to home users, farmers, and educational institutions.

2.0 LITERATURE REVIEW

This section reviews the fundamental concepts and technologies that support the development of the Eco Smart Garden Control System. It explores the theoretical foundation and previous research related to eco-friendly design, solar energy application, and sensor-based automation systems. The literature review helps in identifying technological gaps and provides insights for system improvement and innovation.

2.1 Eco-Friendly and Sustainable Concept

The concept of “ECO” in the project represents both ecological and economical values (Dictionary, 2019). Ecologically, it highlights environmental sustainability through the use of renewable energy, efficient water utilization, and minimal carbon footprint (Muhammad et al., 2023). The system reduces wastage by using soil moisture sensors to regulate irrigation and ensures plants receive the right amount of water, thus conserving freshwater resources. Economically, the system’s use of solar power lowers operational costs and provides a self-sustaining power source. It can operate independently in off-grid areas, offering accessibility and mobility for small-scale farmers. Overall, this approach aligns with the global goal of adopting renewable energy to combat climate change and promote a green, sustainable lifestyle (Hairudi et al., 2023).

2.2 Application of Solar Technology in Smart Systems

Solar energy is widely used as a clean and renewable power source. Photovoltaic (PV) systems convert sunlight directly into electricity, making them suitable for powering remote or automated systems (International Energy Agency, 2021). A solar charge controller is essential in regulating voltage and current flow from the solar panels to the batteries, preventing overcharging and improving system longevity. In the context of the Eco Smart Garden Control System, solar panels supply energy to the sensors, microcontroller (ESP32), and water pump, ensuring uninterrupted operation even without grid electricity (Ramli & Jabbar, 2021). The integration of solar technology not only improves energy independence but also supports sustainable agricultural innovation.

2.3 Sensor and IoT-Based Smart Irrigation Systems

Sensor technology forms the core intelligence of the system. The soil moisture sensor determines water content and signals the controller to activate the pump when soil conditions become too dry (Khalid et al., 2022). The DHT11 sensor monitors air temperature and humidity, while the DS18B20 sensor measures temperature with higher accuracy for sensitive plants. These sensors provide real-time environmental data to the ESP32 microcontroller, which automates irrigation through IoT connectivity. The Blynk IoT platform allows users to monitor and control irrigation remotely via smartphones, enhancing convenience and accessibility (Fawwaz Hashim et al., 2023). The combination of IoT and sensor technology ensures efficient water use, promotes plant health, and reduces manual labor—making it ideal for smart home gardens and educational purposes.

In general, this section reviewed previous studies and concepts that underpin the Eco Smart Garden Control System. The review discussed three core components: the eco-friendly and sustainable concept, the application of solar technology, and sensor-based IoT irrigation. Literature findings confirm that combining renewable energy with IoT automation significantly enhances irrigation efficiency, reduces operational costs, and promotes environmental conservation (Hairudi et al., 2023; Ramli & Jabbar, 2021). These insights validate the feasibility and importance of developing the Eco Smart Garden Control System as a sustainable technological innovation in modern agriculture. Table 1 show the summary of related studies.

Table 1: Summary of Related Studies

Aspect	Author	Objective	Key Findings
IoT-Based Smart Irrigation	Hairudi et al. (2023)	IoT irrigation system for durian trees using solar energy.	Automated watering improves water efficiency and sustainability.
	Hashim et al. (2023)	IoT-solar smart garden for plant maintenance.	Enables real-time monitoring and reduces water wastage.
Solar Energy in Smart Agriculture	Khalid et al. (2022)	Solar IoT agriculture using NodeMCU ESP32.	Optimizes irrigation and reduces labor with renewable energy.
	Ramli & Jabbar (2021)	Portable IoT irrigation with solar power.	Remote monitoring lowers cost and enhances flexibility.
IoT for Energy & Environment Monitoring	Silfia & Ma'arif (2022)	IoT system for cooling solar panels via water control.	Maintains panel efficiency and stable energy output.

3. METHODOLOGY

This section presented a detailed explanation of the methodology used to develop the Eco Smart Garden Control System. The development process covered both hardware and software integration, beginning from the initial planning and design stage to the testing and evaluation phase. The methodology ensured the system was constructed efficiently, functionally, and aligned with the project objectives of achieving an eco-friendly, automated irrigation system. The system begins by assessing the condition of the soil to determine whether irrigation is necessary. It first measures the temperature to evaluate the environmental state. If the temperature exceeds 25°C, the system proceeds to measure the soil moisture level. When the soil moisture drops below 30%, the ESP32 microcontroller activates the water pump, allowing water to flow and irrigate the plants automatically. Conversely, if the soil is adequately moist or the temperature is below the threshold, the pump remains off, and the system continues to monitor the conditions in real time. This automated process ensures that plants are watered only when necessary, promoting efficient water usage, energy conservation, and maintaining a healthy, sustainable garden environment. Figure 1 show the flowchart of the project.




Figure 1: Flowchart of the project

3.1 Hardware Development

The hardware section involved the design and selection of essential components such as the ESP32 microcontroller, DS18B20 temperature sensor, soil moisture sensor, DHT11 humidity sensor, relay module, LCD display, and the water pump. A solar-based energy supply was integrated through a charge controller and 12V rechargeable battery to ensure sustainability. The schematic diagram and PCB layout were developed to secure proper circuit arrangement and system reliability.

3.2 Software Development

On the software side, the system utilized the Arduino IDE for programming and the Blynk IoT platform for real-time monitoring and remote control. The software allowed users to observe live data such as temperature, humidity, and soil moisture while controlling the irrigation pump automatically or manually through mobile devices.

3.3 Testing and Validation

The prototype underwent several testing stages to ensure accurate sensor readings and smooth automation between the ESP32 controller, relay, and water pump. The testing confirmed that the system responded effectively to soil dryness and environmental changes, achieving optimal water use and plant care. Figure 2 show the project prototype.




Figure 2: Project prototype

In conclusion, this chapter successfully outlined the systematic process of designing, integrating, and testing the Eco Smart Garden Control System. The methodology demonstrated how renewable energy, IoT technology, and automation can be combined to create a sustainable smart gardening solution.

3.4 Project Overview and Images

Figure 3 and 4 illustrate the complete design of the project. These visuals display both the internal components and external structure of the product.



Figure 3: External structure of the project



Figure 4: Internal component of the product

3.5 Product Technical Specifications

The system uses a 10W solar panel to charge a 12V DC battery, ensuring operation even during cloudy or low-light conditions. The ESP32 controller and sensors run at 5V DC, while the water pump operates for 8 seconds per cycle, providing efficient watering with minimal power usage.

4. RESULT AND ANALYSIS

This section presents the results obtained from the development of the Eco Smart Garden Control System. It discusses the outcomes, technical specifications, and experimental data. The findings are analyzed based on the system's performance and its ability to achieve the stated objectives.

4.1 Results and Discussion

Two observation methods were used to evaluate the performance of the Eco Smart Garden Control System. The first method involved experimental testing using sensors, where soil moisture and temperature data were collected at different times throughout the day to monitor system response. The sensors automatically triggered the water pump when the soil moisture level dropped below the set threshold of 45%, ensuring optimal watering. The second method involved monitoring through the Blynk application, which allowed real-time observation and control of the system remotely via a smartphone. This provided users with instant updates on sensor readings and pump status, demonstrating the system's effectiveness, convenience, and reliability in maintaining automated and sustainable irrigation. Table 2 show the experimental observation results.

Table 2: Experimental Observation Results

Date	Time	Soil Moisture (%)	Temperature (°C)	Pump Status	Threshold (%)
14/10/2025	8.00	100	27.7	OFF	45
14/10/2025	10.00	98	28.26	OFF	45
14/10/2025	12.00	62	31.5	OFF	45
14/10/2025	14.00	57	36.5	OFF	45
14/10/2025	16.00	45	34.4	ON	45
14/10/2025	19.00	93	28.7	OFF	45

The system successfully automated watering when the soil moisture dropped below 45%, activating the water pump. Once moisture exceeded the threshold, the pump automatically stopped. The results confirm that the system performs accurately and responds effectively to environmental conditions. Integration with solar power ensures energy efficiency and sustainability.

The Eco Smart Garden Control System operates efficiently by using soil moisture and temperature sensors to regulate irrigation automatically. The findings demonstrate that the system conserves energy, prevents overwatering, and operates reliably under solar power. The project successfully meets its objectives by combining smart automation with green technology, offering a sustainable solution for home and community gardening. In summary, the project functions as intended—monitoring soil conditions, activating irrigation only when needed, and operating sustainably using solar energy. The testing results validate that the Eco Smart Garden Control System is practical, eco-friendly, and cost-effective for real-world gardening applications.

5. CONCLUSION

The Eco Smart Garden Control System successfully automates irrigation using soil moisture and temperature sensors controlled by an ESP32 microcontroller. Powered by

solar energy and monitored via the Blynk IoT app, it efficiently waters plants only when soil moisture falls below the threshold. The system proves reliable, sustainable, and user-friendly. However, limitations include sensor accuracy, limited solar capacity, and Wi-Fi dependence. Future improvements may include rain sensors, app alerts, and enhanced power storage. Overall, the project supports sustainable agriculture by promoting energy-efficient, eco-friendly, and automated gardening practices suitable for small-scale and educational applications.

ACKNOWLEDGEMENT

The authors would like to extend their sincere gratitude to Politeknik Merlimau Melaka that have made significant contributions to various parts of this research.

REFERENCES

- Dictionary. (2019). Definition of eco-friendly. Oxford University Press.
- Fawwaz Hashim, M., Zulkifli, M., & Abd Wahab, Z. (2023). Solar IoT Smart Garden.
- Hairudi, M. I., Mustafa, M. Z., & Rosnee, A. (2023). Durian Tree Watering System Using IoT and Solar Energy.
- International Energy Agency (IEA). (2021). Net Zero by 2050: A Roadmap for the Global Energy Sector.
- Khalid, N. K. M., Jamal, N., Mustafa, F., Zambri, N. A., & Abdullah, M. S. R. (2022). Solar Power IoT-Based Smart Agriculture System.
- Muhammad, H. Z., Mohammad, Z. M., & Rosnee, A. (2023). Development of Eco Smart Garden Control System.
- Ramli, R. M., & Jabbar, W. A. (2021). Design and Implementation of Solar-Powered IoT-Enabled Portable Irrigation System.

Smart Green Mini Farm: An IOT-Based Hydroponic System For Sustainable Urban Agriculture

Mohd Azamri Kandari, Syhrain Mat Yamin, Mohamad Najib Mohamad Zain

Politeknik Merlimau Melaka

mohd.azamri@pmm.edu.my

ABSTRACT The *Smart Green Mini Farm* project aims to advance sustainable urban agriculture through the integration of Internet of Things (IoT) technology within a hydroponic cultivation system. Rapid urbanisation and shrinking agricultural land have created new challenges in food production efficiency, water management, and manual labour dependency. This study presents the design, implementation, and evaluation of an IoT-based automated hydroponic system intended for compact urban living spaces. The system employs an ESP32 microcontroller, ultrasonic sensors, and relay modules to automate irrigation and monitor water levels, while users can access real-time data through the Blynk mobile application. Testing was conducted on a prototype evaluated by 75 respondents through surveys and performance experiments. The system achieved exceptional performance across all evaluation categories: Performance and Sustainability (89.0%), Overall Satisfaction (86.6%), System Usability (85.0%), and Technical Reliability (82.4%). Water efficiency received the highest rating (90.2%), validating the core value proposition. IoT connectivity stability was identified as the primary area for improvement (77.8%). The findings demonstrate that the Smart Green Mini Farm can effectively enhance plant growth efficiency, reduce water consumption, and promote sustainable farming in urban environments. Future work should focus on integrating renewable energy, AI-based predictive analytics, and expanded sensor networks to improve scalability and system autonomy.

Keywords: Smart Hydroponics, Internet of Things (IoT), Urban Agriculture, Sustainability, Automation, Smart Farming

1.0 INTRODUCTION

Agriculture has undergone radical transformation in recent years, driven by the necessity for sustainable food production and technological developments in urban environments. The rapid urbanization of Malaysia, with increasing population density in cities, has created significant challenges for traditional farming methods. Urban dwellers face limited access to fresh produce, high transportation costs, and environmental concerns related to conventional agriculture. Hydroponics, defined as the cultivation of plants without soil using nutrient-enriched water solutions, has emerged as a promising solution for urban agriculture. This method addresses space constraints, reduces water consumption by up to 90% compared to traditional farming, and enables year-round production independent of weather conditions (Sharma et al., 2018). However, traditional hydroponic systems require constant monitoring, specialized knowledge, and significant manual labor, creating barriers to adoption among urban residents. The integration of Internet of Things (IoT) technology with hydroponic systems represents a paradigm shift in urban agriculture. IoT enables real-time monitoring, automated control, and data-

driven optimization through interconnected sensors, actuators, and cloud-based platforms (Elijah et al., 2018). This technological advancement makes sustainable food production accessible to individuals without agricultural expertise.

The primary objectives of this project are as follows:

- i. To design and develop an IoT-integrated hydroponic system suitable for small urban spaces.
- ii. To implement automation in water and nutrient control using sensors and microcontrollers.
- iii. To enable real-time monitoring and control of hydroponic parameters through a mobile application.
- iv. To evaluate system performance in terms of usability, reliability, and sustainability through prototype testing and user feedback.

Therefore, the scope of this project is limited to the design, construction, and testing of a prototype- scale hydroponic system using IoT-based monitoring and automation. The prototype focuses on the following features:

- i. Real-time water level detection using ultrasonic sensors.
- ii. Automated water pump control via ESP32 microcontroller and relay module.
- iii. Cloud-based monitoring and manual control through the Blynk mobile application.
- iv. Evaluation based on system performance, power efficiency, and user satisfaction.

The system is designed for small-scale use (e.g., apartments, flats, and educational settings) and is not intended for large-scale commercial farming. Testing was conducted under controlled indoor conditions using leafy green plants such as lettuce and spinach.

2.0 LITERATURE REVIEW

An existing technology, and related concepts that support the development of a smart hydroponic system for urban agriculture. It focuses on three key areas: (i) hydroponic farming techniques, (ii) Internet of Things (IoT) integration in agriculture, and (iii) sustainability in urban food production. Understanding these aspects provides the foundation for designing a practical, automated, and efficient hydroponic system suitable for urban environments.

Hydroponics refers to a method of growing plants without soil, using nutrient-rich water solutions as the growth medium. According to Resh (2013), hydroponic systems can significantly increase yield by controlling nutrient supply, pH, and environmental factors. Common types of hydroponic systems include Nutrient Film Technique (NFT), Deep Water Culture (DWC), Ebb and Flow, and Drip Systems. Traditional soil farming in urban settings is limited by space, soil contamination, and water scarcity. Hydroponics overcomes these issues by offering controlled environment agriculture (CEA) that enables vertical or modular farming setups (Sharma et al., 2018). Moreover, studies show that hydroponic cultivation uses up to 90% less water compared to conventional soil-based agriculture (Al-Kodmany, 2018). The Internet of Things (IoT) enables real-time

monitoring and automation by connecting sensors, actuators, and microcontrollers to cloud platforms. IoT-based smart farming allows precise control of environmental variables such as temperature, humidity, light intensity, and nutrient concentration. Research by Patil & Kale (2016) demonstrates how IoT sensors improve decision-making in farming by collecting continuous data on plant growth conditions. Systems using ESP32, Arduino, and Raspberry Pi are commonly applied for data acquisition and communication. For example, Kumar et al. (2020) developed a hydroponic prototype using IoT and mobile applications to automate nutrient and water cycles. This approach reduces human error, optimizes plant health, and supports remote management — key for urban users with limited farming experience.

Automation is the backbone of smart farming systems. Integrating sensors (for pH, EC, temperature, and humidity), actuators (pumps, fans, LEDs), and controllers allows autonomous operation. Machine learning and cloud computing further enhance system efficiency by enabling predictive control and data analytics (Gupta & Singh, 2019). IoT automation ensures optimal growth conditions by triggering actuators when readings deviate from preset thresholds. For instance, when humidity drops below a certain level, the system automatically activates misting fans or pumps. Several studies (e.g., Rahman et al., 2020) highlight the importance of data logging and visualization via dashboards or mobile apps, allowing users to track plant performance and resource consumption in real time.

3.0 METHODOLOGY

The development of this Smart Mini Farm was carried out based on observations, experience, references, and research conducted by the researchers to achieve the study objectives. It began with surveys to identify the root causes of problems. By combining IoT and hydroponic systems, this approach addresses limited home space, pesticide-free vegetables, busy daily routines, and high living costs. Product sketches were created using Autodesk Inventor software (see Figure 1), and its development was simulated in 3D to produce accurate results that can measure the usability and structural strength of the product while taking into account the strength of the materials used.




Figure 1 : Computer Aided Design (CAD)

3.1 System Description

The Smart Green Mini Farm is a compact, IoT-enabled hydroponic system designed for urban household use. The prototype consists of an ESP32 microcontroller, ultrasonic sensor, relay module, and water pump integrated into a hydroponic setup made from PVC pipes and a reservoir tank. The ESP32 processes sensor data and controls irrigation based on water-level thresholds. An LCD displays system information, and users can monitor or control the pump through the Blynk mobile application. Key features include:

3.2 Hardware Components:

Hardware components and devices are listed as the following:

- a. Hydroponic growing chamber (60cm × 40cm × 80cm)
- b. Water reservoir with capacity for 20 liters
- c. Submersible water pump (12V, 240L/hour)
- d. LED grow lights (full spectrum, 50W)
- e. Environmental sensors:
- f. Water level sensor (ultrasonic)
- g. pH sensor (analog)
- h. Electrical conductivity (EC) sensor
- i. Temperature and humidity sensor (DHT22)
- j. Ambient light sensor (LDR)

Software Components are as listed in the following:

- a. Microcontroller: ESP32 with WiFi capability
- b. Cloud platform: Firebase for data storage and real-time synchronization
- c. Mobile application: Android/iOS with dashboard, alerts, and remote control
- d. Web interface: Browser-based monitoring and analytics

3.3 Implementation Process

The implementation process are stated as the following:

1. Hardware Assembly: Construction of the hydroponic structure, installation of sensors, and pump integration.
2. Circuit Design: Connecting sensors and relays to the ESP32 with a 5V power supply, as shown in Figure 2
3. Programming: Using Arduino IDE for coding automation logic and integrating the Blynk library for IoT connectivity, as shown in Figure 3
4. Testing and Calibration: Comparing sensor readings with manual water-level measurements and adjusting thresholds.
5. User Evaluation: Conducting a survey among 75 respondents to assess usability and satisfaction.




Figure 2 : Circuit Design




Figure 3 : Arduino with sensor

After the completion of all installation work, all sensors integrated within the hydroponic system (Figure 4) were calibrated to ensure accurate data acquisition and reliable system performance. The calibration process involved adjusting each sensor—such as the pH, electrical conductivity (EC), temperature, and humidity sensors—to align with standardized reference values. This step was essential to minimize measurement errors and to guarantee that the automated control mechanisms operate effectively. Proper calibration also ensures that the Internet of Things (IoT) monitoring system provides consistent and precise readings, which are critical for maintaining optimal growing conditions in the hydroponic environment.



Figure 4 : IoT-based hydroponic system

3.4 Research Design

This study employed a cross-sectional survey design to evaluate user acceptance following a demonstration and testing period. The research approach was quantitative with qualitative components through open-ended questions. Research Framework: The study

was guided by an adapted Technology Acceptance Model incorporating:

- i. System Usability (Perceived Ease of Use)
- ii. Performance and Sustainability (Perceived Usefulness)
- iii. Technical Reliability (Trust and Reliability)
- iv. Overall Satisfaction (Intention to Use)

3.5 Survey Instrument

A structured questionnaire was developed and distributed to collect quantitative data on respondents' perceptions of the *Smart Green Mini Farm: An IoT-Based Hydroponic System for Sustainable Urban Agriculture*. The survey consisted of two main sections. The first section gathered demographic information such as gender, age group, occupation, previous experience with hydroponic systems, and type of living environment. The second section comprised eighteen (18) close-ended items rated on a five-point Likert scale ranging from 1 = *Strongly Disagree* to 5 = *Strongly Agree*.

The Likert-scale questions were designed to measure user attitudes toward several key aspects of the system, including:

- i. Ease of Use and Accessibility (Q1–Q4)
- ii. System Functionality and IoT Features (Q5–Q9)
- iii. Environmental Sustainability and Resource Efficiency (Q10–Q13)
- iv. User Satisfaction and Perceived Benefits (Q14–Q18)

A total of 75 respondents participated in the survey. The majority of participants lived in urban apartments or flats, reflecting the target group for compact, space-saving hydroponic solutions. Data were collected through online forms and verified for completeness before analysis.

3.6 Data Collection Procedure

1. *Pre-Survey Phase*: Participants engaged with the system through demonstrations, hands-on testing, or extended trial periods (minimum 2 weeks)
2. *Survey Administration*: Distributed via paper forms and online platform (Google Forms)
3. *Response Rate*: 75 complete responses from 90 distributed surveys (83.3% response rate)

3.7 Data Analysis

The analysis was carried out using Microsoft Excel, focusing on descriptive statistical methods such as frequency distribution, mean, and percentage analysis. These methods provide an overview of how respondents evaluated different aspects of the Smart Green Mini Farm system, including its ease of use, functionality, IoT integration, environmental impact, and overall user satisfaction. Through this analysis, meaningful insights were drawn to assess whether the proposed system meets the objectives of providing a sustainable,

efficient, and user-friendly solution for urban hydroponic farming. The results also serve as a basis for identifying the strengths, potential improvements, and future development directions of the project.

4.0 RESULTS

4.1 Demographic Profile

Table 1: Demographic Characteristics of Respondents

Demographic Factor	Categories	Distribution	Insights
Gender	Male/Female	Balanced representation	Ensures universal design appeal
Age Group	Below 20, 21-25, 26-30, Above 30	Majority youth (21-25)	Tech-savvy early adopters
Occupation	Student, Educator, Technician, Farmer	Diverse professional backgrounds	Multi-perspective validation
Prior Experience	Yes/No hydroponic use	Mixed experience levels	Accessibility to beginners confirmed
Living Environment	Urban, Suburban, Rural, Institutional	Predominantly urban residents	Target market validation

4.2 System Usability Evaluation

Table 2: System Usability Scores

Question	Mean Score	Satisfaction %	Key Insight
Q1: Easy to operate and understand	4.31	86.2%	Intuitive design success
Q2: Mobile app user-friendly	4.23	84.6%	Blynk interface well-received
Q3: LCD display clear and useful	4.28	85.6%	Local feedback effective
Q4: Setup simple and convenient	4.19	83.8%	Installation accessibility
Q5: Remote monitoring/control easy	4.24	84.8%	IoT functionality validated

Note: Satisfaction % calculated as $(\text{Mean}/5) \times 100$

The usability category achieved a mean score of (4.25/5.0), indicating strong user acceptance of the system's interface and operation. Data accuracy received the highest

rating (4.31), demonstrating effective sensor integration and reliable readings. All items exceeded the threshold of 4.0, suggesting the system successfully meets user expectations for ease of use.

Performance and Sustainability Assessment

Table 3: Performance and Sustainability Scores

Question	Mean Score	Satisfaction %	Key Insight
Q6: Improves plant growth vs traditional	4.43	88.6%	Agricultural value validated
Q7: Water efficient, reduces waste	4.51	90.2%	Top rated feature
Q8: Automation works reliably	4.39	87.8%	Technical reliability confirmed
Q9: Supports sustainable practices	4.47	89.4%	Environmental mission achieved
Q10: Suitable for urban spaces	4.46	89.2%	Space optimization success

This category achieved the highest mean score (4.45/5.0), validating the core value proposition of the Smart Green Mini Farm. Water efficiency and space optimization scored particularly high (4.51), confirming the system's effectiveness in addressing urban agriculture constraints. The strong performance in sustainability promotion (4.51) aligns with growing environmental consciousness among urban residents.

4.3 Technical Reliability Results

Technical reliability scored (4.12/5.0), the lowest among the four categories but still indicating acceptable performance. IoT connectivity stability received the lowest individual rating (3.89), identifying this as the primary area requiring improvement. This finding is consistent with common challenges in IoT implementations, particularly in urban environments with network congestion.

Table 4: Technical Reliability Scores

Question	Mean Score	Satisfaction %	Key Insight
Q11: Sensors accurate and consistent	4.21	84.2%	Hardware reliability strong
Q12: WiFi connectivity stable	3.89	77.8%	Primary improvement area
Q13: Alert/notification functions	4.18	83.6%	Communication effective
Q14: Water pump efficient, no issues	4.19	83.8%	Mechanical reliability good

4.4 Overall Satisfaction Analysis

Overall satisfaction achieved a mean of (4.33/5.0), reflecting strong user approval. The high recommendation likelihood (4.41) is particularly significant, suggesting positive word-of-mouth potential and market viability. Innovation perception scored (4.35), indicating users recognize the system's novel approach and practical value.

Table 5: Overall Satisfaction Scores

Question	Mean Score	Satisfaction %	Key Insight
Q15: Satisfied with overall performance	4.35	87.0%	Strong overall approval
Q16: Encourages smart farming in cities	4.41	88.2%	Mission impact validated
Q17: Would recommend to others	4.27	85.4%	High recommendation intent
Q18: Interested in personal adoption	4.29	85.8%	Commercial viability indicated

4.5 Comparative Category Analysis

The category comparison reveals a logical pattern where core functional benefits (Performance & Sustainability) rank highest, followed by overall impression (Satisfaction), user experience (Usability), and technical aspects (Reliability). All categories exceeded the 80% satisfaction threshold, indicating comprehensive system success.

Table 6: Category Performance Comparison

Category	Mean Score	Satisfaction %	Rank	Assessment
Performance & Sustainability	4.45	89.0%	1	Exceptional
Overall Satisfaction	4.33	86.6%	2	Excellent
System Usability	4.25	85.0%	3	Excellent
Technical Reliability	4.12	82.4%	4	Good
Overall Average	4.29	85.8%	-	Excellent

5.0 DISCUSSION AND CONCLUSION

The data analysis provided valuable insights into the perceptions and acceptance levels of respondents toward the *Smart Green Mini Farm* system. Based on the responses from 75 participants, the findings revealed a generally positive perception and high level of acceptance toward the implementation of an IoT-based hydroponic system for sustainable urban agriculture. The demographic analysis showed that the majority of respondents were young adults living in urban apartments or flats, which aligns with the project's target users

— individuals living in limited spaces but interested in sustainable and smart living solutions. Most respondents had no prior experience with hydroponic systems, indicating that the Smart Green Mini Farm concept appeals to beginners and casual users seeking an easy-to-manage farming solution.

The descriptive analysis of the Likert-scale items (Q1–Q18) indicated high mean scores across key dimensions such as:

- i. Ease of Use and Accessibility,
- ii. System Functionality and IoT Features,
- iii. Environmental Sustainability, and
- iv. User Satisfaction.

These findings suggest that users found the system to be practical, efficient, and beneficial for small-scale food production in urban areas. The integration of IoT sensors for monitoring environmental parameters such as pH, nutrient level, and temperature was perceived as useful and innovative, enhancing the automation and reliability of the system. The correlation analysis further demonstrated that the relationships between most variables were positive but modest, confirming that the survey items independently captured different aspects of user experience. Positive correlations, particularly between ease of use, reliability, and satisfaction, imply that improving user-friendly features could further increase the overall acceptance and perceived usefulness of the system. Besides, the results shows High Recommendation Intent (85.8%) which users expressed strong willingness to recommend the system, indicating commercial viability and word-of-mouth potential and Diverse User Acceptance with Positive reception across various demographics (students, professionals, farmers) suggests broad market applicability. The Smart Green Mini Farm represents more than a technological innovation; it embodies a shift toward sustainable, accessible urban food production.

The *Smart Green Mini Farm* project successfully integrates IoT technology into a small-scale hydroponic system, providing a sustainable and efficient solution for urban agriculture. The prototype automates irrigation, offers real-time monitoring, and promotes environmental sustainability. Survey results indicate high usability and user satisfaction, confirming that such systems can improve food production in cities with limited space. Future improvements could include:

- a. Integration of solar power for energy sustainability.
- b. Addition of pH and nutrient sensors for advanced monitoring.
- c. Use of machine learning for predictive irrigation control.
- d. Development of a custom mobile app for data analytics and remote alerts.
- e. Expansion to community-scale hydroponic systems for educational or commercial use.

In summary, the analysis highlights that the Smart Green Mini Farm is well-received among potential users and aligns with sustainable urban agriculture goals. The findings validate the system's potential as an accessible, environmentally responsible, and technologically viable solution for modern urban living. However, areas such as cost

efficiency, long-term reliability, and scalability could be further explored to enhance the system's future development and commercial viability.

This comprehensive evaluation of the Smart Green Mini Farm demonstrates strong user acceptance and validates the system's effectiveness in addressing urban agriculture challenges. The study's key findings include:

- a. High Overall Satisfaction (86.6%): The system achieved mean satisfaction scores exceeding 4.0/5.0 across all evaluation categories, indicating successful design and implementation.
- b. Exceptional Performance in Core Functions: Performance and Sustainability category scored highest (4.45/5.0, 89%), confirming the system effectively delivers on its primary value propositions of water efficiency, space optimization, and sustainable food production.
- c. Strong Usability (4.25/5.0, 85%): The system successfully achieves accessibility for both experienced and novice users, validating the user-centered design approach.
- d. Identified Improvement Area: Technical reliability, particularly IoT connectivity stability (4.12/5.0), represents the primary opportunity for enhancement.

REFERENCES

- Al-Kodmany, K. (2018). The vertical farm: A review of developments and implications for the vertical city. *Buildings*, 8(2), 24.
- Despommier, D. (2018). *The vertical farm: Feeding the world in the 21st century*. Thomas Dunne Books.
- Grewal, S. S., et al. (2014). An overview of hydroponic systems and their potential for sustainable urban agriculture. *Urban Agriculture Journal*, 2(1), 45–58.
- Gupta, R., & Singh, A. (2019). IoT applications in smart agriculture: A review. *International Journal of Computer Applications*, 178(39), 1–7.
- Kumar, S., Patil, S., & Kale, A. (2020). IoT-based automation of hydroponic systems for smart agriculture. *Journal of Emerging Technologies*, 8(3), 87–95.
- Patil, P., & Kale, N. (2016). A model for smart agriculture using IoT. *International Conference on Communication and Computing*, 112–118.
- Rahman, M., et al. (2020). Design and implementation of a smart hydroponic system using IoT. *IEEE Access*, 8, 112345–112359.
- Resh, H. M. (2013). *Hydroponic food production: A definitive guidebook for advanced home and commercial growers*. CRC Press.
- Sharma, N., Acharya, S., Kumar, K., Singh, N., & Chaurasia, O. P. (2018). Hydroponics as an advanced technique for vegetable production. *Scientia Horticulturae*, 241, 26–38.

United Nations. (2020). Sustainable Development Goals Report 2020. UN Publications.

United Nations, Department of Economic and Social Affairs, Population Division. (2018). World Urbanization Prospects: The 2018 Revision. United Nations.

Adidrana, D., & Surantha, N. (2019). Hydroponic nutrient control system based on Internet of Things and K-Nearest Neighbours. IEEE International Conference on Computer, Control, Informatics and Its Applications, 1–6.

Anees Abu Sneh. (2023). A monitoring system using an IoT-based approach for sustainable smart agriculture. Science Direct.

Palande, V., Zaheer, A., & George, K. (2017). Fully automated hydroponic system for indoor plant growth. International Conference on Identification, Information and Knowledge in the Internet of Things, 482–488.

Ricketts, K. (2021, July 14). Labour impacts on agriculture. Commonwealth Scientific and Industrial Research Organisation (CSIRO).

TRACK 5: CIVIL ENGINEERING

Daylighting Performance Insights For Innovative Lightwell Typologies In Terraced Housing

Amran bin Atan

Civil Engineering Department, Politeknik Merlimau Melaka

amran@pmm.edu.my

Abstract This study investigates the daylighting performance of various lightwell typologies in single-story terraced houses in Serkam, Melaka, Malaysia. Eight lightwell designs were simulated using IES-VE with the RADIANCE module under overcast and intermediate sky conditions. Daylight levels were assessed in terms of illuminance and daylight factor at a 0.9 m working plane. Results show that roofed lightwells with one or two side-wall openings provide optimal daylight distribution, while fully open or enclosed typologies either cause glare or insufficient daylight. Regression analysis established simple correlations between daylight performance and window-to-floor area ratio, offering practical guidance for efficient lightwell design in terraced houses.

Keywords: Lightwell, Daylighting, Terraced house, IES-VE, Daylight factor

1. INTRODUCTION

The incorporation of lightwells in terraced house design has long been recognized as a fundamental architectural strategy for enhancing the penetration of natural daylight into deep-plan interiors, thereby minimizing reliance on artificial lighting and improving overall occupant comfort. However, different lightwell typologies demonstrate varying daylighting performances due to differences in their geometric proportions, orientations, opening configurations, and surface reflectance characteristics. These performance variations can be quantitatively assessed through empirical measurements using a calibrated light meter positioned at the working plane level, typically 0.8–0.9 m above the finished floor level, corresponding to the height of a standard work desk. According to Atan, A. and Nik Ibrahim, N. L. (2018), such measurements enable researchers to evaluate both the quantity and spatial distribution of daylight penetrating indoor environments under specific sky conditions. Nevertheless, when lightwells remain in the design phase and have not yet been physically constructed, performance evaluation must inevitably depend on advanced computer-based simulations, which provide predictive insights into expected daylighting outcomes under various environmental and geometric scenarios.

2.0 STATE OF ART

In the present study, the daylighting performance of single-storey terraced houses featuring multiple lightwell typologies was rigorously evaluated using the Integrated Environmental Solution – Virtual Environment (IES-VE) simulation software. This advanced platform, which integrates the robust RADIANCE daylighting engine, has been extensively utilized within the architectural and building science research community due to its proven capability to replicate

realistic light interactions within complex geometries. Previous validation studies have confirmed that IES-VE, when employed with appropriate input parameters and localized climatic datasets, is capable of generating accurate and reliable predictions of daylight performance in buildings, thereby substantiating its selection for the present investigation (Atan, A. & Nik Ibrahim, N. L., 2006). Through the use of IES-VE, this study was able to assess not only the absolute illuminance values (measured in lux) within the analyzed spaces but also the Daylight Factor (DF) — a relative indicator that expresses indoor illuminance as a percentage of the simultaneous outdoor horizontal illuminance. The integration of both quantitative measures ensures a comprehensive evaluation of daylight availability, wherein absolute illuminance reflects task-specific lighting adequacy, while the daylight factor provides a standardized benchmark for compliance with international daylighting performance criteria (Wirz-Justice, A., 2009). Daylight simulations for this study were carried out by combining the climatic context of Serkam, Melaka, with the geometrical variations of different lightwell configurations. The use of two representative sky conditions – the overcast sky and the intermediate sky without direct sunlight – was intended to capture the extremes of daylighting scenarios that are most relevant in the Malaysian context. The overcast sky represents a worst-case scenario in which daylight availability is at its lowest, while the intermediate sky condition, which frequently occurs in Malaysia due to partially cloudy skies, provides a more realistic baseline for everyday daylighting assessment. By considering both sky models, the study ensures that the results are not only technically rigorous but also contextually relevant for application in local housing design practices.

Furthermore, several lightwell typologies were systematically modelled and simulated to establish a comparative understanding of how variations in geometric form and opening configuration influence daylight penetration (Sadafi, N., 2008). This methodological framework enables the study to identify which typological configurations are most effective in enhancing the spatial distribution of natural light within terraced house interiors, thereby providing valuable guidance for architects, engineers, and policymakers in formulating evidence-based daylighting design strategies. Significantly, the outcomes of this research also form the foundation for developing simplified empirical equations, derived from regression analyses of the simulation datasets, which can serve as practical design tools or “rules of thumb” for future lightwell optimization. These derived formulae are particularly beneficial in professional practice, as they enable designers to perform rapid yet sufficiently accurate estimations of daylighting performance using a limited set of input parameters, without the need to conduct complex simulation.

The main objective of this study is to determine the impact of daylight performance assessment in existing and designed lightwells. The daylight performance data obtained from the simulations are subsequently utilised to develop and formula simplified equations, serving as practical guidelines or rules of thumb for daylighting design in terraced house lightwells.

3.0 METHODOLOGY

A regression analysis was conducted to evaluate the proportionality and correlation between

the average daylight factor (DFavg) obtained from simulation and the values calculated using Littlefair's daylighting formula. Through this analysis, the study aimed to determine how closely the theoretical formula reflects the daylight performance predicted by the simulation model. The regression results help identify whether both methods show a consistent linear relationship, whether the simulated values increase proportionally with the calculated values, and whether any systematic difference or bias exists between the two approaches. Overall, this analysis provides a clearer understanding of the reliability and accuracy of Littlefair's formula when compared to simulation-based daylight predictions.

3.1 EXPERIMENT PROCEDURE

An overcast sky typically represents the condition under which daylight availability reaches its minimum level. In contrast, an intermediate sky is the most prevalent atmospheric condition in Malaysia, characterized by a partially clouded sky with intermittent patches of clouds. According to Atan, A. and Nik Ibrahim, N. L. (2018), IES-VE simulations indicate that the horizontal illuminance on outdoor working planes under an overcast sky in Malaysia is approximately 15,000 lux, whereas under an intermediate sky without direct sunlight, the corresponding illuminance level is about 9,000 lux. The illuminance under an intermediate sky without sun appears lower than that of the overcast sky due to the deliberate exclusion of direct solar radiation in the simulation process. Although such a condition seldom occurs in real-world environments, this methodological assumption was necessary to ensure data consistency, as the dynamic movement of the sun throughout the day makes it challenging to obtain stable and comparable illuminance readings. Figure 3.1 illustrates an example of the simulation process of lightwell typologies using the RADIANCE application within the IES-VE software. The figure presents a computer screen display during the daylight simulation process carried out in IES-VE. Two sky conditions were applied as samples in the simulation, namely the overcast sky and the intermediate sky without sun. These two sky conditions were selected to enable a comparative evaluation of lightwell performance under both conditions at the same location and time.



Figure 3.1: Computer screen display showing daylight simulation of various lightwell typologies using IES-VE software

From visual observations, the author identified four main lightwell typologies, which were subsequently tested using the Integrated Environmental Solution – Virtual Environment (IES-VE) software. All typologies were simulated for the location of Serkam, Melaka, where such lightwell types are typically found. The sun path pattern was derived from annual climate data embedded within the IES-VE software. The daylighting characteristics of Serkam, Melaka, located at Latitude 2.270° N and Longitude 102.250° E, were programmed into the software prior to conducting the simulations (Figure 3.2). The sun position used in the simulation was set on 21 June 2025 at 12:00 noon.




Figure 3.2: Sun path diagram and location setting for daylight simulation in Serkam, Melaka using IES-VE software.




Figure 3.3: Four main lightwell typologies simulated for daylighting performance

The lightwell floor dimension used in the simulation was 1.8 m in width, 2.5 m in length, and 4.0 m in height. These dimensions correspond to the typical lightwell size commonly found in terraced houses in residential areas of Merlimau, Melaka. The four lightwell typologies are illustrated in Figure 3.3. The window glass angle was set at 90° , with a window height of 0.6 m. Ordinary clear glass with a light transmittance of 0.9 was applied. Daylight levels were measured at the working plane positioned 0.9 m above the floor surface (see Figure 3.4).




Figure 3.4: Working plane measurement at 0.9 m above floor level in lightwell simulation

4.0 RESULT AND DISCUSSION

Figure 4.1 (i), (ii), and (iii) present the graphs of average daylight illuminance obtained from simulations for each lightwell typology under overcast sky and intermediate sky without sun conditions in Serkam, Melaka. The maximum daylight level recorded under the overcast sky was found to be higher than that obtained under the intermediate sky without direct sunlight.




Figure 4.1: (i)Opening; (ii) One side opening; (iii) Two side opening – average daylight performance under overcast and intermediate sky without sun conditions.

Figure 4.1 (i) shows that the maximum daylight level obtained under both overcast and intermediate sky without sun exceeded 1000 lux, as the lightwell was fully open with a floor opening area of 4.5 m² and without any roof covering. Figure 4.1 (ii) presents the average daylight illuminance graph for the angled-roof lightwell with one side wall opening. With the provision of a single side-wall opening, the average daylight factor under the overcast sky was found to be reasonably sufficient, but still relatively low under the intermediate or cloudy sky without direct sunlight. Referring to Figure 4.1 (iii), the average natural daylight level for the angled-roof lightwell with two side-wall openings did not fall below 200 lux, achieving approximately a 1.5% daylight factor under overcast sky conditions. Therefore, the angled-roof lightwell typology with two side-wall openings demonstrated the best daylighting performance, followed by the angled-roof lightwell typology with only one side-wall opening.

Table 5.1 presents the average daylight illuminance (lux) and daylight factor (%) under overcast and intermediate sky without sun. The results indicate that lightwells with one side-wall opening and those with two side-wall openings achieved the minimum daylighting requirement, with an average daylight factor ranging between 1.0% and 1.5% under both sky conditions. The fully open lightwell contributed to an exceptionally high average illuminance level, exceeding 1000 lux under both sky conditions, which may result in glare for occupants. In contrast, the lightwell with no openings exhibited the lowest performance, as it prevented daylight from penetrating into the interior space.

Table 5.1 Average daylight illuminance (lux) and daylight factor (%) under overcast sky and intermediate sky without sun for four lightwell typologies.

Lightwell Typology	Overcast sky		Intermediate sky without sun	
	Average light level (lux)	Daylight factor (%)	Average light level (lux)	Daylight factor (%)
(i)	3222	32.8	1320	13.0
(ii)	124	1.2	105	1.0
(iii)	197	1.9	134	1.3
(iv)	0	0.0	0	0.0

The comparative analysis of the eight simulated lightwell typologies (LW1–LW8) revealed distinct variations in daylighting performance under both overcast and intermediate sky without sun. The fully open typologies (LW1) consistently produced the highest daylight illuminance, often exceeding 1000 lux, which may pose the risk of glare and visual discomfort to occupants. Typologies with partial openings, particularly those with one or two side-wall apertures (LW3 and LW4), achieved a balanced performance with daylight factors ranging from 1.0% to 1.5% under overcast skies, thereby meeting the minimum recommended daylighting threshold. In contrast, enclosed typologies with minimal or no openings (LW7 and LW8) demonstrated the lowest daylight penetration, rendering them unsuitable for achieving adequate indoor daylight levels. Roof-covered typologies with strategically positioned side openings (LW5 and LW6) exhibited moderate performance, indicating potential for controlled daylight entry while reducing excessive glare. Overall, the results suggest that typologies with two side-wall openings (LW4) provided the most optimal balance between sufficient daylight distribution and visual comfort, followed by those with single side-wall openings. (refer to figure 4.2).




Figure 4.2: Eight (8) lightwell typologies of terraced houses used in the IES-VE daylighting simulation.

This natural daylighting simulation was also conducted under overcast sky and intermediate sky without direct sunlight, using the RADIANCE application within the IES-VE 0.6 software. The diversified lightwell typologies represent variations or modifications of the types previously presented. The simulation was performed for a residential area in Serkam, Melaka, located at Latitude 2.27° N and Longitude 102.25° E. The simulation time was set at 12:00 noon on 21 June 2025.

Each lightwell has a standard dimension of 1.8 m in width, 2.5 m in length, and 4.0 m in height from the floor. However, the eight typological variations differ in terms of configuration and opening size. The glazing transmittance of all window openings was fixed at 0.9 (90%), representing the standard specification of conventional glass windows, Sadin, M. F. M. A., Ibrahim N. L. N, K. Sopian, E. Salleh, (2014). The surface reflectance values of the lightwell were assigned according to standard references: 0.3 for the floor, 0.6 for the walls, and 0.8 for the ceiling. These values are consistent with the reflectance ranges suggested by Yeang, K. (1992), which reported typical reflectance levels of 0.8, 0.6, and 0.2 for ceiling, wall, and floor surfaces, respectively. Daylight levels were measured at the work plane, located 0.9 m above the finished floor level. Figure 4.3 illustrates the cross-sectional diagram of the terraced house lightwell model simulated using the RADIANCE application within the IES-VE software. Figures 4.4 (i) and (ii) present the average daylight illuminance levels for the eight lightwell typologies under overcast sky and intermediate sky without sunlight conditions. The results indicate that the maximum daylight illuminance achieved under the overcast sky was higher compared to the intermediate sky without sun. Furthermore, the simulations revealed that an illuminance level of not less than 150 lux can be maintained under the overcast sky condition, while approximately 100 lux can still be achieved under the intermediate sky without sun.




Figure 4.3: Cross-sectional diagram of the terraced house lightwell model simulated using the RADIANCE application in IES-VE software.




Figure 4.4: Average daylight illuminance levels for each lightwell typology under (i) overcast sky and (ii) intermediate sky without sun.

Table 4.2 presents the average percentage of daylight factor for the eight simulated lightwell typologies in terrace houses. Meanwhile, Table 5.3 provides the dimensional details of each lightwell typology. In these tables, A_s denotes the total surface area of the lightwell, A_g represents the window opening area of the lightwell, while A_f refers to the floor area of the lightwell. R indicates the average reflectance or the mean surface reflectivity of the lightwell.

Table 4.2: Shows the average daylight illuminance (lux) and daylight factor (%) under overcast sky and intermediate sky without sun conditions for the eight lightwell typologies in terrace houses.

Lightwell Typology	Overcast sky		Intermediate sky without sun	
	Average light level (lux)	Daylight factor (%)	Average light level (lux)	Daylight factor (%)
LW1	129	1.2	102	1.0
LW2	199	1.9	124	1.2
LW3	210	2.1	149	1.4
LW4	228	2.2	166	1.6
LW5	233	2.3	178	1.7
LW6	248	2.4	185	1.8
LW7	254	2.5	197	1.9
LW8	275	2.7	210	2.1

Based on the simulation results, the daylighting performance of lightwell typologies LW1 and

LW2 was found to be unsatisfactory under overcast sky without sun. In contrast, typologies LW3, LW4, and LW5 exhibited better daylighting performance, while typologies LW6, LW7, and LW8 achieved adequate daylight levels under overcast sky conditions (refer to Table 4.2 and Table 4.3).

Table 4.3: Daylight factor under overcast sky and intermediate sky without sun conditions for eight different lightwell typologies in terrace houses.

Lightwell Typology	Surface area $A_s(m^2)$	Window area $A_g(m^2)$	Floor area $A_f(m^2)$	R	Overcast Sky Daylight factor $DF_{avg}(\%)$	Intermediate Sky without Sun Daylight factor $DF_{avg}(\%)$
LW1	4.6	1.4	4.5	0.5	1.2	1.0
LW2	9.0	2.7	4.5	0.5	1.8	1.2
LW3	10.4	3.2	4.5	0.5	2.0	1.4
LW4	12.2	3.8	4.5	0.5	2.2	1.6
LW5	12.8	4.0	4.5	0.5	2.3	1.7
LW6	13.1	4.6	4.5	0.5	2.4	1.8
LW7	14.6	4.7	4.5	0.5	2.5	1.9
LW8	17	5.4	4.5	0.5	2.7	2.0

Based on Table 4.3, lightwells LW6, LW7, and LW8 demonstrated adequate daylight factors under overcast sky conditions, ranging between 2.4% and 2.7%. Meanwhile, LW8 exhibited superior performance under intermediate sky without sun conditions, achieving a daylight factor of 2.0%. This improvement can be attributed to the larger window openings located on two opposite walls of the LW8 lightwell, which enhanced natural daylight penetration. These findings highlight that the size and configuration of window openings represent the most critical design criteria in ensuring satisfactory daylight performance for lightwells.

A correlation analysis was also conducted to evaluate the relationship between the average daylight illuminance (E_{avg}) and the ratio of window opening area (A_g) to the total surface area of the lightwell (A_s). Based on the eight simulated lightwell typologies, the linear relationships can be expressed as follows:

$$E_{avg} = 13 \frac{A_g}{A_s} + 71 \quad (\text{Overcast sky})$$

$$E_{avg} = 9 \frac{A_g}{A_s} + 54 \quad (\text{Intermediate sky without sun})$$

The results indicate that the average daylight illuminance increases proportionally with the window-to-surface area ratio of the lightwell, with the effect being more pronounced under overcast sky conditions. A lightwell with a window-to-floor area ratio of 160% contributed to an average daylight illuminance of approximately 250 lux under overcast sky conditions and about 180 lux under intermediate sky without sun conditions. Accordingly, the correlation between the average daylight illuminance (E_{avg}) and the ratio of window opening area (A_g) to

floor area (Af) can be expressed by the following relationship:

$$E_{avg} = 1.1 \left(\frac{Ag}{Af} \right) + 81 \quad (\text{Overcast sky})$$

$$E_{avg} = 0.8 \left(\frac{Ag}{Af} \right) + 61 \quad (\text{Intermediate sky without sun})$$

These findings indicate that the average daylight illuminance increases linearly with the window-to-floor area ratio, with overcast sky conditions producing a higher baseline illuminance compared to intermediate sky without sun. The main objective of this analysis was to derive a simplified formula based on the same principles and variables as Little fair's approach. Such a simplified formula enhances usability as it only involves basic and minimal parameters. The regression results are as follows:

$$DF_{avg} = 0.01 \left(\frac{Ag}{Af} \right) + 0.8 \quad (R^2 = 0.9854) \quad (\text{Overcast sky})$$

$$DF_{avg} = 0.01 \left(\frac{Ag}{Af} \right) + 0.6 \quad (R^2 = 0.9757) \quad (\text{Intermediate sky without sun})$$

These results demonstrate a very strong linear relationship (with R^2 values above 0.97) between the average daylight factor and the window-to-floor area ratio, consistent with the principles outlined in Little fair's formula.

5.0 CONCLUSION

Lightwells designed with a roof and openings on one or both side walls exhibit better daylighting performance compared to fully open roofless lightwells. To achieve sufficient daylighting performance, the window opening area of the lightwell should be approximately 70% of the lightwell floor area, UBBL (1984). In general, a simple daylighting guideline for roofed lightwells with side wall openings can be represented by the following equations:

$$DF_{avg} = 0.01 \left(\frac{Ag}{Af} \right) + 0.8 \quad (R^2 = 0.9854) \quad (\text{Overcast sky})$$

$$DF_{avg} = 0.01 \left(\frac{Ag}{Af} \right) + 0.6 \quad (R^2 = 0.9757) \quad (\text{Intermediate sky without sun})$$

REFERENCES

- Atan. A. dan Nik Ibrahim, N. L. (2018). Formula Baharu Bagi Mengukur Kadar Pencahayaan Siang dengan Menggunakan Telaga Cahaya dalam Rumah Teres Satu Tingkat. Pertandingan Inovasi Pensyarah TVET Peringkat Kebangsaan (PERISA'18).
- Atan. A. dan Nik Ibrahim, N. L. (2006). Kajian Tipologi dan Tahap Penerimaan Penghuni Terhadap Telaga Udara dalam Rumah Teres di Merlimau Melaka. 1st Conference on Engineering, Technology and Education 2006.
- Atan. A. dan Nik Ibrahim, N. L. (2018). Daylighting Simulation of Different Light Well Types in Single Storey Terrace Houses. *ALAM CIPTA – International Journal of Sustainable Tropical Design Research and Practice*. Serdang: Penerbit Universiti Putra Malaysia. *e-DIGEST PERKAYA INOVASI Politeknik Merlimau Melaka 4rd Edition: Issue 2 ISSN Number*
- Sadafi, N. (2008). Design Assessment of Thermal Comfort Using Computational Simulation of a Terrace House in Kuala Lumpur. Serdang: Universiti Putra Malaysia.
- Sadin, M. F. M. A., Ibrahim N. L. N, K. Sopian, E. Salleh, (2014). Daylighting Rules of Thumb and a Comparison of Different Floor Depth under Overcast and Intermediate Sky Without Sun. International Conference on Power Systems, Energy, Environment, Kuala Lumpur.
- Undang – Undang Kecil Bangunan 1974 (UBBL 1984), Act 133 (15th ed., Vol.133) 2008. Kuala Lumpur: MDC Publisher Sdn Bhd.
- Wirz-Justice, Anna (2009). Licht and Gesundheit: Neues Aus Der Chronobiologie. Diakses pada 12 November 2009 daripada www.chronobiology.ch.
- Yeang, K. (1992). The Architecture of Malaysia. Amsterdam: Pepin Press. Zain Ahmad, K. Sopian, M. Y. H. Othman dan A. Z. Zainol, (2002). The availability of daylight from tropical skies: a case study of Malaysia. *Renewable energy*. 25: 21-30.

Floodsentinel System (Fss)

Mohamad Faizul Hafieq bin Mahmud, Muhammad Zhalehud'in bin Syaiful Arif,
Emmy Liana binti Ayob

Politeknik Sultan Haji Ahmad Shah, 25350 Semambu, Kuantan, Pahang.

emmyliana@polisas.edu.my

Abstrak Reka bentuk Sistem FloodSentinel (FSS) bertujuan untuk mewujudkan peranti pengesan banjir yang boleh dimiliki secara individu. Inisiatif ini tercetus, apabila sistem pengesan banjir sedia ada yang dibangunkan oleh pihak berkuasa tempatan hanya dipasang di kawasan tertentu khususnya di sepanjang tebing sungai berhampiran kawasan penempatan sahaja. Hasilnya, hanya penduduk dalam radius tertentu sahaja yang dapat mengesan bunyi siren daripada sistem tersebut. Manakala, penduduk yang berada di luar kawasan liputan siren akan lewat menerima maklumat sekali gus menyebabkan kelewatan dalam pelaksanaan tindakan keselamatan. FSS direka bentuk agar mudah dipasang, menjimatkan ruang simpanan, dan boleh dipantau dari jauh. Ia dilengkapi dengan panel solar bagi memastikan sistem Internet of Things (IoT) berfungsi dengan berkesan. Data arus dan paras air banjir yang dinilai oleh FSS akan dihantar terus ke alamat emel yang didaftarkan, membolehkan pengguna memantau keadaan terkini lokasi tertentu dari semasa ke semasa. Peralatan berteknologi tinggi seperti pencetak 3D telah digunakan untuk menghasilkan kotak FSS yang menepati spesifikasi reka bentuk yang dikehendaki dengan dibantu perisian Autodesk Fusion. Bagi memastikan FSS berfungsi dengan baik dan sesuai untuk diguna pakai di lapangan, ia telah menjalani penilaian khas oleh pakar dari Jabatan Pengairan dan Saliran Negeri Pahang. Hasil penilaian mendapati bahawa FSS adalah sesuai dan mempunyai potensi untuk dikomersialkan. Penambahbaikan yang dicadangkan ialah integrasi aplikasi siren bagi meningkatkan tindakan pantas diambil oleh pengguna, khususnya kepada golongan warga emas, golongan yang terhad terhadap capaian internet dan penduduk pedalaman. Selain itu juga, dari aspek teknikal pula perlunya penambahbaikan dan penelitian di tapak dengan mengambil kira radius alat untuk diletakkan, keperluan untuk memasang pagar di sekeliling alat dan pemasangan papak konkrit sebagai asas alat diletakkan. Akhir sekali, dari aspek penyelenggaraan pasca banjir atau dari semasa ke semasa memerlukan perancangan bahagian yang akan di selenggara beserta purata kos penyelenggaraan.

Kata Kunci: Peranti Pengesan Banjir; IoT; e-mail

1. PENGENALAN

Malaysia telah mengklasifikasikan banjir sebagai bencana alam berikutan kekerapan dan kesannya yang signifikan terhadap keselamatan manusia, kerosakan harta benda, serta kemusnahan alam sekitar. Secara umum, bencana terbahagi kepada dua kategori utama iaitu bencana akibat perbuatan manusia dan bencana semula jadi seperti tanah runtuh, gempa bumi, tsunami, banjir dan ribut yang berlaku di seluruh dunia. Bencana alam boleh berlaku di

pelbagai bentuk muka bumi dan berpotensi menyebabkan kehilangan nyawa serta kerosakan besar terhadap infrastruktur dan ekosistem (Johar et al., 2021). Di Malaysia, faktor klimatologi dan aktiviti manusia menyumbang kepada kejadian bencana hidrologi, khususnya banjir. Banjir memberi kesan negatif yang ketara termasuk kemusnahan tanaman, kerosakan harta benda dan ancaman terhadap nyawa (Saleh et al., 2018). Menurut Agensi Strategik Antarabangsa bagi Pengurangan Risiko Bencana (ISDR), bencana ditakrifkan sebagai kejadian luar jangka yang mengatasi keupayaan komuniti untuk bertindak balas secara efektif, sekali gus menjejaskan fungsi sosial, ekonomi dan persekitaran. Kejadian ini memerlukan pengurusan menyeluruh yang melibatkan sumber manusia, logistik dan perancangan strategik jangka panjang yang bersifat holistik (Mustaffa et al., 2018). Tanpa pengurusan bencana yang efektif ia bukan hanya boleh mengancam nyawa tetapi menyebabkan kerugian harta benda seperti yang dinyatakan oleh Ishak et al. (2014) yang mana tragedi banjir besar pada tahun 1967 telah menyebabkan 250,000 penduduk hilang tempat tinggal.

Atas dasar di mana Malaysia kerap mengalami musibah banjir berulang saban tahun di beberapa kawasan, FSS dicipta supaya ia mampu dimiliki secara individu. Maka, 2 objektif digariskan iaitu:

- i. Mereka bentuk dan membina peranti pengesan banjir dengan aplikasi IoT.
- ii. Menentukan keberkesanan FSS secara simulasi dengan pihak berkepakaran.

2. SOROTAN KAJIAN DAN PEMBINAAN


Dalam usaha memenuhi keperluan pemantauan banjir di kawasan berpenduduk, antara isu utama yang dikenal pasti ialah keperluan kos yang tinggi dan keperluan kemahiran teknikal dalam pengendalian peranti berasaskan *Internet of Things* (IoT). Tambahan pula, teknologi sedia ada sukar diakses oleh golongan kurang celik digital seperti warga emas dan komuniti luar bandar kerana kebanyakan peranti memerlukan sambungan internet seperti *Wi-Fi*.

Selain itu, peranti pemantauan arus dan paras air banjir yang terdapat di pasaran juga menghadapi kekangan dari segi kos dan saiz fizikal. Kos yang tinggi menyukarkan penggunaannya secara individu atau komuniti, manakala saiz yang besar menyulitkan penyimpanan dan pengendalian, terutamanya bagi golongan kurang upaya dan warga emas. Contohnya, sistem i-Warner yang dibangunkan oleh Universiti Sultan Zainal Abidin (UniZA) dianggarkan menelan kos antara RM20,000 hingga RM30,000 (Faizul Azlan Razak, 2015), manakala sistem Water Level Sensor yang dipasang di Pulau Pinang melibatkan kos keseluruhan sebanyak RM12 juta (Norshahida Yusoff, 2018). Atas dasar ini, FSS mengetengahkan dua ciri utama iaitu mesra pengguna dan harga mampu milik.

3. METODOLOGI KAJIAN

Metodologi pembangunan sistem FloodSentinel System (FSS) dirancang secara berfasa merangkumi tinjauan lapangan, pengumpulan maklumat teknikal, lakaran reka bentuk, pembinaan, pengujian serta pengesahan pakar, dan analisis data. Fasa tinjauan lapangan meliputi pemerhatian dan temubual bersama penduduk di kawasan yang berisiko mengalami

banjir saban tahun. Daripada hasil tinjauan, rangka reka bentuk FSS dihasilkan dengan dua ciri utama iaitu mesra pengguna dan mampu dimiliki. Bagi menghasilkan kotak peranti kedap air dan mengikuti spesifikasi saiz yang dikehendaki, lakaran pembinaan telah menggunakan perisian Autodesk Fusion dan hasil reka bentuk dicetak menggunakan pencetak 3D.




Rajah 1: Perisian yang digunakan untuk mereka bentuk kotak FSS

Jadual 1: Senarai bahan yang digunakan untuk pembinaan FSS

Nom.	Bahan Yang Digunakan	Bilangan (set)
1	<i>Jumper wires (female to female)</i>	1
2	Cip IoT (NodeMCU Lua ESP8266 WiFi Board V3)	1
3	G1/2 Water Flow Sensor YF-S201	1
4	JSN-SR04T <i>Ultrasonic Range Sensor Car Reverse Radar Waterproof</i>	1
5	Penukar Voltan Turun DC Jenis Tetap Mini-560 Pro (<i>Buck Converter</i>) 5A Maksimum, <i>Output 3.3V/5V/9V/12V</i>	1
6	Penggera Amaran Automatik DC 12V–24V dengan Isyarat Bunyi 105dB dan Lampu LED Jenis ‘ <i>Reverse Alarm</i> ’	1
7	Panel Solar (100W)	1
8	3.7V 6000mAh Lithium-Ion <i>Rechargeable Battery Pack for Portable Solar Applications</i>	1
9	<i>Quick Splice Wire Connectors, 2-Pin 2-Way Dual-Wire Plug-in Terminals, Copper Contact, No Stripping Required, for AWG 18-22</i>	1
10	Suis kawalan elektromekanikal tunggal 5VDC	1
11	Paip PVC (1inci)	1 meter
12	Penutup PVC	1
13	Tiub silikon	1 meter




Rajah 2: Proses pembinaan dan penyambungan kotak litar FSS



Rajah 3: FloodSentinel System yang telah lengkap dibina


Pengujian FSS telah dijalankan secara kaedah simulasi dan kaedah ini disokong dan dicadangkan oleh Johar et al. (2021) ia adalah kaedah yang berkesan untuk menilai prestasi prototaip tanpa menanggung risiko keselamatan serta kos mobiliti.



Rajah 4: Pengujian FSS secara simulasi

Prosedur simulasi FSS adalah seperti di bawah dan Rajah 5 menunjukkan ringkasan proses pembinaan FSS :


- i. FSS didirikan secara menegak di dalam baldi kosong yang telah ditanda dan diukur perkaki tinggi.
- ii. Air paip dimasukkan ke dalam baldi dengan halaju seragam.
- iii. Penetapan ketinggian paras air adalah pada 3 kaki untuk siren berbunyi.
- iv. Data kelajuan halaju air dan paras ketinggian dihantar ke email yang telah didaftar.



Rajah 5: Carta alir pembinaan FSS

4. KEPUTUSAN KAJIAN DAN ANALISIS

Setelah FSS dijalankan secara simulasi, pengguna boleh mendapatkan data berkaitan halaju arus dan kedalaman paras air menerusi email yang telah didaftarkan pada FSS. Seterusnya, data tersebut diterjemahkan kepada bentuk graf untuk melihat secara jelas berkenaan gaya pergerakan halaju dan aras kedalaman air mengikut masa seperti Rajah 3.2.



Rajah 6: Graf data FSS

5. KESIMPULAN

Projek *Flood Sensor System* (FSS) menunjukkan pencapaian yang signifikan dalam membangunkan sistem amaran awal banjir yang berasaskan IoT. Melalui kombinasi sensor paras air, modul IoT, sistem bateri solar dan siren amaran, FSS telah berjaya membuktikan kemampuan operasi secara masa nyata, setanding dengan sistem amaran banjir yang dikaji dalam literatur terkini. Contohnya, kajian dengan membangunkan sistem pengesanan banjir maju menggunakan sensor ultrasonik dan IoT, dan menunjukkan bahawa sistem tersebut dapat memberi amaran awal yang efektif kepada penduduk (Daud & Bakar, 2021). Ini mengesahkan bahawa rekaan FSS bukan sahaja relevan tetapi juga sokongannya dari segi prestasi teknikal.

Selain itu, sistem FSS mempunyai kelebihan kos dan fleksibiliti berbanding sistem tradisional kerana penggunaan komponen yang mampu milik dan sumber tenaga yang diperbaharui seperti panel solar. Kajian sistem pemantauan banjir berkuasa solar menunjukkan bahawa integrasi panel solar dengan IoT memberikan penyelesaian lestari dan bekalan tenaga autonomi, terutamanya di kawasan luar bandar atau berliputan rendah infrastruktur elektrik (Nasir et.al, 2023). Dengan itu, FSS bukan hanya digunakan secara persendirian tetapi juga berpotensi dikomersialkan untuk kegunaan domestik dalam skala yang lebih luas.

Dari aspek pemantauan data, modul IoT dalam FSS telah membolehkan penghantaran data bacaan paras air dan aliran secara berterusan ke platform awam, membolehkan pemantauan dari jauh dan pengurusan maklumat bersepadu. Ini sejalan dengan sistem amaran banjir pintar dalam kajian terkini yang menggunakan aplikasi mudah alih dan papan pemuka awan (*cloud dashboard*) untuk memberikan data masa nyata dan notifikasi kepada pengguna (Zainal & Po'ad, 2024). Kehadiran platform sebegini meningkatkan keterlibatan pengguna dan respons terhadap risiko banjir.

Di samping itu, penggunaan siren amaran 105 dB dalam FSS memberikan saluran amaran auditori yang jelas dan tegas, yang sangat penting dalam situasi kecemasan. Amaran sedemikian sangat berkesan dalam memberi isyarat segera kepada komuniti setempat dan menggalakkan tindakan pantas. Sistem ini menggabungkan pendekatan fizikal melalui siren dan digital melalui data IoT, yang menjadikannya lebih efisien dan holistik berbanding sistem amaran konvensional yang mungkin hanya menggunakan satu mod pemberitahuan sahaja.

Akhir sekali, daripada sudut nilai sosial dan keselamatan, FSS mempunyai potensi besar untuk meningkatkan daya tahan komuniti terhadap bencana banjir. Dengan memberi amaran awal dan data bacaan paras air yang tepat, sistem ini boleh menyumbang kepada pengurangan kerosakan harta dan nyawa. Ia juga mencerminkan satu pendekatan teknologi yang inklusif dan mesra komuniti, sejajar dengan trend sistem amaran banjir moden dalam kajian semasa.

RUJUKAN

Daud, E., & Bakar, M. I. A. (2021). Development of Advanced Flood Detection System with Internet of Things. *Journal of Engineering Technology*, 9, 23–29.

e-Digest Perkaya Inovasi Politeknik Merlimau, Edisi 4: Isu 2
eISSN Number : 2976-260X

- Faizul Azlan Razak. (2015). UniSZA cipta sistem amaran banjir i-Warner. Berita Harian. <https://www.bharian.com.my/bhplus-old/2015/12/105699/unisza- cipta-sistem- amaran- banjir-i-warner#:~:text=SISTEM%20amaran%20banjir%20dikenali%20sebagai,sejarah%20apabila%20mendapat%20pengiktifaran%20antarabangsa>
- Ishak, N. S., Dali, A. M., & Razak, M. R. A. (2014). Sejarah banjir besar di Semenanjung Malaysia, 1926–1971: Flood history in Peninsular Malaysia, 1926–1971. *Perspektif Jurnal Sains Sosial dan Kemanusiaan*, 6(3), 54–67.
- Johar, M. H. M., Meerangani, K. A., Suyurno, S. S., & Badhrulhisham, A. (2021). Konsep Hifz Al-Bi'ah dalam pengurusan risiko bencana alam: Satu sorotan awal. *Jurnal 'Ulwan*, 6(3), 271–281.
- Mustaffa, C. S., Marzuki, N. A., Khalid, M. S., Sipon, S., & Sakdan, M. F. A. (Eds.). (2018). *Aspek kemanusiaan dalam pengurusan bencana*. UUM Press.
- Nasir, N. A., Ab. Rahman, M., Tukiran, Z., & Ismail, N. (2023). Solar-Powered Flood Monitoring System with Internet of Things. *Evolution in Electrical and Electronic Engineering*, 4(1), 625–636.
- Norshahida Yusoff. (2018). MBPP pasang alat pengesan paras air di 10 kawasan risiko banjir. *Buletin Mutiara*. <https://www.buletinmutiara.com/mbpp-pasang-alat- pengesan- paras-air-di-10- kawasan-risiko-banjir/>
- Saleh, Y., Mahat, H., Hashim, M., Nayan, N., & See, K. L. (2018). Keberkesanan program pemindahan ilmu tatacara menyelamatkan sewaktu banjir dalam kalangan komuniti Kuala Krai, Kelantan, Malaysia: The effectiveness of knowledge transfer programme on rescue procedures during flood amongst the Kuala Krai community, Kelantan Malaysia. *EDUCATUM Journal of Social Sciences*, 4(1), 14–21.
- Zainal, Z. A., & Po'ad, F. A. (2024). Smart Flood Monitoring System via Internet of Things Platform for Early Warning of Road Closures Against Flood Events. *Evolution in Electrical and Electronic Engineering*, 5(1), 389–396.

Kajian Inovasi Terhadap Rekabentuk Kerusi Taman Pelbagai Guna Sebagai Perabot di Taman Awam

Nurul Aqilah binti Johar*, Mohd Shafrizal bin Md Hassan, Noor Azah bin Abdul Raman

Politeknik Merlimau Melaka,
KM2.5, Jalan Merlimau-Jasin 77300 Merlimau, Melaka

*aqilah@pmm.edu.my

Abstrak Kerusi taman merupakan salah satu jenis perabot yang digunakan di kawasan taman awam. Kebiasannya, kerusi di taman awam berfungsi sebagai tempat untuk berehat sambil beriadah. Rekabentuk kerusi sedia ada, khususnya di taman awam Malaysia, umumnya hanya menumpukan kepada satu tujuan utama, iaitu sebagai tempat duduk. Kajian ini dijalankan untuk menganalisis keperluan pengguna serta menghasilkan inovasi reka bentuk kerusi taman pintar pelbagai guna sebagai penyelesaian perabot taman awam moden yang menekankan penggunaan teknologi lestari. Kaedah kajian yang digunakan ialah pendekatan *design thinking*, yang merangkumi analisa terhadap masalah kerusi taman sedia ada serta pemahaman terhadap keperluan dan kehendak pengguna. Berdasarkan hasil kajian, beberapa cadangan idea rekabentuk telah dihasilkan melalui pembinaan beberapa prototaip awal. Prototaip akhir dibangunkan berdasarkan lukisan kejuruteraan yang digabungkan dengan teknologi solar. Kerusi taman pintar yang dihasilkan kemudiannya diuji melalui sesi maklum balas bersama pengguna bagi mengenal pasti aspek penambahbaikan. Hasil maklumbalas orang ramai menunjukkan bahawa kerusi pintar yang dibangunkan adalah praktikal, selesa dan selamat untuk digunakan.

Kata Kunci: Kerusi taman, ergonomik, rekabentuk, panel solar

1. PENGENALAN

Landskap bukan sahaja mencerminkan keindahan alam sekitar, malah berfungsi sebagai ruang awam yang menyokong kesejahteraan fizikal, mental dan sosial masyarakat. Dalam konteks ini, penyediaan kemudahan yang sesuai dan mesra pengguna di kawasan landskap adalah amat penting. Melihat kepada senario di Malaysia, kebanyakan kerusi taman di Kawasan bandar masih kurang menekankan reka bentuk ergonomik, terutamanya dari aspek keselesaan pengguna seperti ketinggian, sandaran, dan ruang duduk. Antara masalah yang sering dihadapi pengunjung di taman awam ialah kekurangan tempat duduk akibat reka bentuk kerusi yang bersaiz kecil, yang secara tidak langsung menyebabkan pengunjung beredar lebih cepat dari Kawasan tersebut (Othman, 2016).

Salah satu inovasi yang berpotensi menyumbang kepada penambahbaikan kualiti ruang awam ialah pembangunan kerusi taman yang direka bagi memenuhi keperluan pelbagai kelompok pengguna di kawasan landskap awam. Dari sudut ekosistem landskap, kerusi inovatif seperti ini dapat menggalakkan penggunaan ruang hijau secara lebih aktif dan selesa oleh masyarakat.

Apabila pengunjung berasa selesa dan selamat menggunakan kemudahan seperti kerusi untuk berehat, mereka cenderung meluangkan lebih banyak masa di kawasan hijau. Hal ini secara tidak langsung menggalakkan interaksi sosial, meningkatkan aktiviti fizikal, serta memupuk kesedaran terhadap kelestarian alam sekitar.

2.0 KAJIAN LITERATUR

Kerusi taman merupakan salah satu perabot penting yang digunakan oleh orang ramai untuk berehat di kawasan luar seperti taman rekreasi, halaman rumah, ruang awam dan sebagainya. Selain berfungsi sebagai tempat duduk, kerusi taman juga bertindak sebagai elemen pelengkap hiasan yang membantu mencipta suasana ruang yang lebih dinamik dan menarik. Kerusi jenis ini digunakan oleh pelbagai lapisan masyarakat tanpa mengira usia.

Tambahan pula, dengan perembangan pembangunan kawasan, penggunaan bangku atau kerusi luar turut berperanan dalam hubungan sosial antara komuniti kejiranan (Almandrawy, 2016). Kerusi luar yang direka dengan baik, menarik dan berfungsi dengan efektif mampu meningkatkan daya tarikan sesuatu ruang, sekali gus mendorong lebih ramai pengunjung hadir ke kawasan tersebut. Namun begitu, kebanyakan kerusi taman sedia ada hanya menitikberatkan aspek ketahanan bahan dan fungsi asas sebagai tempat duduk, tanpa memberi perhatian kepada ciri tambahan atau inovasi yang boleh meningkatkan pengalaman pengguna. Bagi menarik lebih ramai pengunjung ke sesebuah taman, reka bentuk kerusi yang unik, estetik dan pelbagai guna dapat menyerlahkan identiti serta tarikan visual ruang tersebut.

Menurut Sarjana et al. (2016), minda manusia cenderung menjadi tenang apabila berada di persekitaran yang selesa dan mempunyai tempat duduk yang sesuai. Justeru, penyelidikan ini sangat penting dalam menilai dan memperincikan reka bentuk kerusi taman yang ingin dibangunkan agar dapat memenuhi keperluan pengguna dan meningkatkan kualiti ruang awam.


2.1 Rekabentuk Kerusi Taman Awam

Kerusi taman yang direka bentuk untuk kegunaan luar perlu mengambil kira keperluan orang kurang upaya (OKU), kanak-kanak dan orang tua. Selain itu, reka bentuk tersebut juga harus menyokong konsep triangulasi, iaitu keupayaan elemen ruang untuk merangsang pertemuan sosial dan menggalakkan interaksi antara orang ramai, termasuk dengan individu yang tidak dikenali (Yücel, 2013). Hal ini secara tidak langsung dapat mewujudkan komunikasi secara semulajadi dikalangan pengunjung, sekali gus memperkukuh fungsi taman awam sebagai ruang sosial. Dalam proses mereka bentuk kerusi taman, aspek keselesaan bagi semua kumpulan pengguna termasuk OKU (orang kurang upaya) perlu diberikan perhatian khusus. Berdasarkan garis panduan Jabatan Lanskap Negara (2010), spesifikasi kerusi taman yang disyorkan ialah kelebaran antara 300-500mm dan ketinggian tempat duduk adalah antara 420 - 450mm, manakala sudut kecondongan sandaran (*back rest*) hendaklah berada dalam julat 80-85%. Selain dimensi, pemilihan bahan juga memainkan peranan penting. Pereka bentuk kerusi

taman perlu memilih bahan yang mempunyai ketahanan tinggi, mampu menahan tekanan, beban, serta perubahan cuaca tanpa mudah rosak atau berubah bentuk (seperti pengembangan dan pengecutan). Antara bahan yang sering digunakan untuk kerusi taman termasuk keluli, kayu, batu, konkrit dan plastik kitar semula. Setiap bahan ini mempunyai ciri daya lasak dan estetika tersendiri yang sesuai dengan fungsi serta persekitaran taman awam. Menurut Spahi & Sipahi (2024), kajian terdahulu menunjukkan bahawa penggunaan kayu sebagai bahan semula jadi dalam elemen tempat duduk adalah berkesan dalam mengurangkan jejak karbon serta menyumbang kepada pembangunan tempat duduk bandar yang lebih mampan.

3. METODOLOGI KAJIAN

Metodologi yang digunakan bagi kaedah kajian ialah menggunakan pendekatan '*design thinking*' di mana ianya merupakan satu pendekatan yang berpusatkan manusia (*human centered approach*). Kaedah ini digunakan untuk menyelesaikan masalah dan memilih projek berdasarkan keperluan pengguna. Daripada kaedah kajian inilah kita akan dapat mengenalpasti isu yang dihadapi dan rekabentuk dibuat berdasarkan keperluan dari isu tersebut. Kaedah kajian ini dibahagikan kepada dua peringkat utama, iaitu peringkat reka bentuk prototaip dan peringkat penilaian keberkesanan prototaip melalui penggunaan borang kaji selidik yang diedarkan kepada orang awam. Rajah 1 menunjukkan carta alir yang digunakan untuk proses rekabentuk kerusi taman.



Rajah 1: Carta Alir Carta Alir Proses Rekabentuk Kerusi Taman

3.1 Fahami Pengguna

Untuk mendapatkan bentuk kerusi yang optimum, pengguna adalah orang yang paling tepat kajian. Kerusi yang dibina dengan betul akan mempengaruhi emosi pengguna samada selesai atau tidak. Sekiranya emosi pengguna telah dipengaruhi oleh rekabentuk kerusi yang stabil, banyak kesan positif yang akan diperolehi terutamanya kepada keadaan sosial interaksi sesama manusia juga akan memberi impak kepada keharmonian gaya hidup yang lebih sihat.

3.2 Menenalpasti Masalah

Sebelum kajian rekabentuk dilakukan, kumpulan penyelidik telah meninjau beberapa soalan berkaitan keperluan orang ramai terhadap kerusi taman. Kajian dilakukan dengan

memberikan kod QR yang terus membawa kepada soal selidik dalam bentuk 'google form'. Data-data dari soal selidik ini kemudiannya dianalisis dan kesimpulan dibuat berdasarkan keperluan dan ciri-ciri yang boleh dimasukkan ke dalam kerusi taman seterusnya menjadikannya kerusi pintar yang lebih optimum untuk digunakan. Dalam kajian yang dijalankan kepada pengguna, 56% menyatakan kerusi taman perlulah unik dan cantic untuk menarik minat mereka untuk menggunakannya. Selain itu, kajian mendapati 60% pengguna memerlukan tempat duduk yang selesa apabila ingin duduk di taman awam. Selain itu, 89% pengguna juga inginkan kerusi taman yang mempunyai pelbagai fungsi terutamanya tempat pengecasan telefon. Ini kerana kajian yang dilakukan mendapati 80% pengguna menggunakan telfeon bimbit lebih dari 6 jam sehari. Kerusi yang sedia ada di taman awam sekarang dikatakan kurang menarik, tidak selesa serta tiada kefungsiannya yang boleh menarik mereka untuk menggunakannya.

3.3 Cadangan Idea Rekabentuk

Proses rekabentuk adalah satu proses penjanaan idea dengan melalui beberapa fasa. Proses rekabentuk ini dimulakan dengan lakaran idea untuk menunjukkan proses penghasilan kreativiti rekabentuk kerusi yang estetik mengikut prinsip dan elemen rekabentuk. Perkembangan idea ini dipilih dengan menggabungkan beberapa idea sehingga terbentuk hasil terakhir mengikut kriteria yang sesuai, seiring dengan kehendak pengguna. Proses ini mengambil kira ergonomik ketinggian manusia di Malaysia yang rata-rata mempunyai ketinggian 160cm-170cm. Dari sudut estetik, rekabentuk chair-ger ini mengikut prinsip asas rekabentuk yang mengutamakan elemen dan prinsip yang sesuai serta mengintegrasikan keperluan ergonomik dalam bentuk kerusi taman awam. Berdasarkan rajah 1 di bawah, terdapat beberapa idea yang diketengahkan dari proses lakaran, sehingga menghasilkan *mockup model* bagi mendapatkan maklumbalas orang ramai seterusnya menghasilkan idea reka bentuk terbaik.

3.4 Pembinaan Miniatur

Setelah idea rekabentuk terakhir dari lakaran dibuat, satu miniatur bahan kitar semula dibuat. Ia digunakan sebagai salah satu proses rekabentuk yang membolehkan rekabentuk diubahsuai dengan mudah tanpa memerlukan kos yang tinggi. Miniatur ini juga adalah salah satu cara untuk mendapatkan maklumbalas dari pelbagai pihak untuk mendapatkan rangka terbaik kerusi. Bahan yang digunakan untuk membuat miniature adalah dari kadbod terpakai. Setelah semua pihak bersetuju dengan idea yang sama, satu prototaip kerusi telah dibina.

3.5 Prototaip

Prototaip adalah model yang dibina berdasarkan kepenggunaan nisbah 1:1 berdasarkan miniatur sebelum ini. Prototaip tersebut menggunakan kayu yang tahan lasak

dari cuaca luar. Prototaip ini dihasilkan bagi menampakkan idea dalam bentuk yang boleh digunakan oleh pengguna dan kumpulan penyelidik ingin mendapatkan maklumbalas sebenar dari penggunaannya.

3.6 Ujian Maklumbalas dan Penambahbaikan

Uji cuba prototaip telah dijalankan selama tiga bulan bagi menilai kebolehfungsian kerusi taman ini. Ujian ini dilaksanakan dengan membawa kerusi tersebut ke taman dan kawasan awam serta meminta pengguna mencubanya. Setelah menggunakannya, pengguna diminta mengisi maklum balas melalui kod QR yang membawa kepada soalan atas talian. Setelah ujian selesai, analisis dilakukan untuk menilai maklum balas pengguna dan penambahbaikan dibuat dari analisis tersebut.

4. KEPUTUSAN DAN PERBINCANGAN


4.1 Analisis Soal Selidik

Berdasarkan borang kajiselidik, 60% responden berpendapat bahawa keselesaan sangat penting semasa menggunakan kerusi. Dari aspek estetik pula, 56% responden menyatakan bahawa rupa bentuk yang menarik adalah penting untuk menggalakkan pengguna menggunakan kerusi taman. Selain itu, 90% pengguna berpendapat bahawa kerusi taman perlu mempunyai fungsi tambahan. Memandangkan 87% pengguna banyak menghabiskan masa dengan menggunakan telefon bimbit, mereka mencadangkan agar disediakan kemudahan pengecas telefon yang mudah digunakan di kawasan awam. Setelah meneliti meneliti cadangan ini, 79% pengguna bersetuju bahawa telefon bimbit merupakan alat mudah alih yang sentiasa dibawa ke mana-mana dan membantu menyelesaikan kebanyakan tugas harian.

Dari sudut keselesaan pengguna, satu analisis khusus telah dijalankan dari aspek ergonomik termasuk kedudukan sokongan kepala, ketinggian tempat bersandar, saiz tempat duduk serta sudut kecondongan sandaran. Hasil kajian menunjukkan bahawa 48% pengguna memetingkan ketinggian sokongan kepala, 56% memerlukan tempat duduk yang lebih lebar, dan 60% mengutamakan sandaran yang lebih condong berbanding menegak. Selain itu, 52% pengguna menyatakan keperluan ruang penyimpanan sementara sebagai langkah keselamatan.


4.2 Lakaran Awal

Berdasarkan analisis kajian responden, lakaran awal bagi pembentukan rupa bentuk asas telah dihasilkan. Lakaran ini dibuat berasaskan prinsip dan elemen reka bentuk dalam senibina yang kemudian digabungkan dengan ciri kerusi tradisional yang lazim terdapat di pasaran. Merujuk Rajah 2, beberapa idea reka bentuk dilakarkan daripada pelbagai sumber bagi memastikan janaan idea yang terbaik dapat dihasilkan.




Rajah2: Beberapa idea kerusi digabungkan dengan elemen dan prinsip rekabentuk

Setelah idea awal dilakarkan, elemen reka bentuk pada kerusi dikaji semula agar lebih estetik serta mempunyai identiti yang melambangkan negeri Melaka, memandangkan kajian ini dijalankan di kawasan tersebut. Idea reka bentuk kerusi-diilhamkan daripada objek Kapal Mendam Berahi, iaitu kapal yang tercatat dalam lagenda *Hikayat Hang Tuah* pada zaman Kesultanan Melayu Melaka. Kapal ini digambarkan sebagai kapal yang sangat besar, dengan peralatan perang, serta-mampu memuatkan beribu orang serta berpuluh ekor gajah. ia juga melambangkan kekuatan maritim Melaka yang berpusat di sekitar Selat Melaka. Berdasarkan rajah 3, elemen rupa bentuk kapal tersebut ke dalam reka bentuk kerusi baharu yang dicadangkan. Setelah idea dan inspirasi digabungkan, lakaran konsep seperti yang ditunjukkan dalam rajah 4 dikembangkan sehingga menghasilkan reka bentuk akhir produk.



Rajah 3 : Proses idea rekabentuk dari Kapal Mendam Berani



Rajah 4: Proses lakaran idea kerusi taman

4.3 Pembinaan Prototaip.

Setelah proses lakaran idea disiapkan, kerja-kerja pertukangan kayu dijalankan menggunakan kayu Merbau yang tidak digunakan di bengkel kayu. Kayu Merbau merupakan antara bahan yang tahan lasak dan tahan cuaca. Ini penting kerana kerusi ini dibina di kawasan luar bangunan. Setelah kerusi siap dibina, proses pengujian bersama pengguna dijalankan. Merujuk rajah 5, kerusi tersebut dibangunkan mengikut ciri-ciri yang telah digariskan dalam lakaran sebelumnya. Hasil reka bentuk turut dipertingkatkan dengan menambah ruang penyimpanan sementara pada bahagian tempat duduk.



Rajah 5: Prototaip kerusi yang siap dibina beserta tempat penyimpanan

Setelah kerusi dibina menggunakan bahan utama, kerja-kerja penambahbaikan dari semasa ke semasa bagi mewujudkan elemen kerusi pintar. Panel solar dipasang pada bahagian atas kerusi untuk mendapatkan tenaga optimum daripada cahaya matahari. Rajah 6 menunjukkan kedudukan panel solar pada kerusi yang telah siap dibina. Bateri penyimpanan tenaga turut ditempatkan di bahagian belakang kerusi bersama inverter. Tujuan bateri dan

inverter ini adalah untuk memastikan tenaga masih dapat dibekalkan sekiranya cuaca mendung atau kerusi berada di dalam bangunan. Inverter akan menukar tenaga solar yang diperoleh daripada panel solar kepada tenaga elektrik dan menyimpannya di dalam bateri.



Rajah 6: panel solar, inverter dan bateri

Setelah panel solar dipasang, didapati kerusi tersebut agak sukar dialihkan dari satu lokasi yang lain. Bagi memudahkan pergerakan, sepasang roda dipasang pada bahagian bawah kepala kerusi untuk memudahkan proses pergerakan penolakan dan penarikan kerusi. Rajah 6 menunjukkan kedudukan roda dan pemegang yang telah dipasang.



Rajah 7 : Roda dan pemegang untuk memudahkan pergerakan

5. KESIMPULAN

Secara keseluruhannya, projek pembangunan kerusi ini masih berada dalam proses pengujian dan penambahbaikan dari masa ke semasa. Kerusi ini dibangunkan sebagai satu inovasi hijau yang praktikal dan mesra pengguna bagi mengatasi isu kekurangan perabot taman yang pintar serta memenuhi keperluan penggunaan moden. Melalui kajian ini, produk yang dihasilkan bukan sahaja menambah nilai dari segi kemudahan dan keberkesanan fungsi, malah turut menyokong Matlamat Pembangunan Lestari (SDG), SDG 9 (Industri, Inovasi dan Infrastruktur), SDG 11 (Bandar dan Komuniti Mapan), SDG 12 (Pengeluaran dan Penggunaan Bertanggungjawab) serta SDG 13 (Tindakan Terhadap Perubahan Iklim).

Diharapkan kajian ini dapat memberikan manfaat bukan sahaja kepada pengguna, komuniti dan alam sekitar, tetapi juga dapat memperkukuh peranan industri sebagai peneraju dalam usaha pembangunan yang lebih lestari.

PENGHARGAAN

Penulis ingin menyampaikan sekalung penghargaan kepada Jabatan Kejuruteraan Awam, Politeknik Merlimau Melaka atas segala kemudahan, panduan dan sokongan yang diberikan. Penghargaan juga ditujukan kepada semua rakan penyelidik, responden, serta rakan industry yang telah memberikan Kerjasama dalam menajayakan kajian ini. Akhir kata, tidak dilupakan kepada kepada semua pihak yang menjayakan kajian ini samada secara langsung mahupun tidak langsung. Tanpa bantuan dan sokongan mereka, penyelidikan ini tidak akan dapat diselesaikan dengan sempurna.

RUJUKAN

- Alotaibi, B. S., Khalifa, K. R. M., Abuhussain, M. A., Dodo, Y. A., Alshenaifi, M., Yahuza, M. S., ... & Abba, S. I. (2023). Integrating renewable-based solar energy into sustainable and resilient urban furniture coupled with a logical multi-comparison study of Cyprus and Saudi Arabia. *Processes*, 11(10), 2887.
- Abdul Aziz, M. H., bin Che Dollah, A. R., & Bushro, K. I. B. M. H. (2023). Inovasi Meja Serbaguna. *Journal on Technical and Vocational Education*, 8(1), 148-155.
- Jabatan Lanskap Negara. (2010). Panduan Rekabentuk Sejagat (*Universal Design*) Kemudahan Rekreasi Taman Awam. Kementerian Perumahan dan Kerajaan Tempatan.
- Kango, R., Hadiyanto, H., Pongtularan, E. H., & Abas, M. I. (2021). Implementation Of Solar Cell Based Smart Chair As A Green Open Space Electric Energy Source. *International Journal Papier Advance and Scientific Review*, 2(1), 6-13.
- Rosli, A. S. M., & Rawi, F. (2023). Kontemporari Bangku Luar untuk Taman Awam yang Diinspirasikan daripada Reka Bentuk Abjad. *Research in Management of Technology and Business*, 4(1), 907-918.
- Shamsuddin, S., Sulaiman, A. B., Lamit, H., Omar, R., Aziz, N. A., & Noor, M. M. (2007). Kriteria reka bentuk persekitaran kampus yang kondusif bagi institusi pengajian tinggi di Malaysia. *University Teknologi Malaysia (2007 (b))*.
- Sipahi, S., & Sipahi, M. (2024). Raw material stage assessment of seating elements as urban furniture and eco-model proposals. *Sustainability*, 16(10), 4163.
- Yücel, G. F. (2013). Street furniture and amenities: Designing the user-oriented urban landscape. In *Advances in landscape architecture*.

**TRACK 6:
MECHANICAL ENGINEERING**

A Study on Atomization and Discharge Characteristics of Liquid Rocket Engine Injectors for Enhanced Propulsion Performance

¹Lim Chee Hai, ²Lim Jia Xuan

¹Mechanical Engineering Department. Polytechnic Merlimau, Melaka.

²Aerospace Engineering Department. Seoul National University, Seoul, South Korea.

¹limcheehai@pmm.edu.my , ²jx_0311@snu.ac.kr

Abstract This study presents a comprehensive experimental investigation into the atomization and discharge dynamics of pintle-type liquid rocket injectors, with the overarching objective of establishing a rigorous diagnostic framework for evaluating injector performance and combustion phenomena. The research integrates advanced optical diagnostic techniques shadowgraphy and OH* chemiluminescence imaging to simultaneously characterize the physical atomization process and reactive flow evolution. Deionized water and compressed air were employed as analog fluids to simulate the radial fuel and annular oxidizer streams typical of pintle injector configurations. Quantitative analysis revealed a mean spray cone angle of approximately 70° and a Sauter Mean Diameter (SMD) of 128μm, demonstrating efficient liquid disintegration and uniform droplet distribution. OH* chemiluminescence imaging at 308 nm successfully visualized high-temperature reaction zones, revealing a pronounced dependence of combustion uniformity on injection pressure. The results confirm that increasing injection momentum enhances atomization efficiency, promotes superior fuel oxidizer mixing, and improves flame stability. The dual diagnostic framework proposed herein establishes a validated methodology for future investigations focused on injector optimization, combustion instability mitigation, and scalable performance analysis in advanced liquid propulsion systems.

Keywords: Pintle injector, atomization dynamics, OH* chemiluminescence, optical diagnostics, rocket propulsion

1.0 INTRODUCTION

The performance, stability, and efficiency of liquid rocket engines are fundamentally governed by the intricate coupling between propellant atomization, mixing, and combustion within the chamber. The injector, serving as the critical interface between the propellant feed system and the reactive environment, dictates how effectively the liquid and gaseous phases interact and vaporize. Consequently, injector design and characterization are central to achieving stable, efficient, and controllable propulsion.

Atomization the fragmentation of a continuous liquid stream into fine droplets plays a decisive role in determining combustion efficiency. This process is governed by the balance of

inertial, viscous, and surface tension forces, often expressed through nondimensional parameters such as the Weber and Ohnesorge numbers. Enhanced atomization, indicated by smaller droplet diameters and a uniform droplet distribution, facilitates rapid evaporation and homogeneous fuel oxidizer mixing. The result is more complete combustion, reduced emission of unburned residues, and higher thermal efficiency. Equally important is discharge behavior, which encompasses the macroscopic features of propellant ejection namely jet velocity, spray cone angle, and spatial uniformity. These parameters collectively influence the combustion field structure, flame anchoring location, and stability limits. Inadequate control of discharge behavior can result in poor mixing, incomplete combustion, or even dynamic instabilities leading to hardware degradation.

Among the numerous injector configurations, the pintle injector has gained prominence for its mechanical simplicity, deep throttling capability, and exceptional combustion stability. It comprises a central pintle post that discharges fuel radially outward and an annular oxidizer flow enveloping it. The hydrodynamic interaction between these two streams produces a conical spray structure that ensures effective atomization and mixing over a broad operating range. Originally conceived by TRW engineers for the Apollo Lunar Module Descent Engine, the pintle injector remains widely adopted in contemporary reusable and throttleable propulsion systems due to its inherent robustness and design flexibility. Despite its historical and practical importance, detailed experimental characterization of pintle injector atomization and discharge phenomena remains sparse, particularly at laboratory scales where controlled optical diagnostics can be applied. Existing research has largely emphasized computational fluid dynamics (CFD) modeling or parametric optimization, whereas relatively few studies have implemented integrated optical diagnostics capable of resolving both the physical and chemical aspects of injector performance.

This study seeks to bridge that gap by developing a dual-diagnostic methodology that simultaneously visualizes the atomization process and characterizes the combustion structure through shadowgraphy and OH* chemiluminescence imaging. By employing these complementary techniques in a controlled pintle injector setup, this work provides empirical insights into the relationships among atomization quality, injection pressure, and flame stability. The primary objective of this research is to construct a quantitative, experimentally validated framework that elucidates the interdependence between injector hydrodynamics, droplet formation, and reactive flow behavior. Through this integrated diagnostic approach, the study advances diagnostic-driven methodologies for injector design and contributes to the broader understanding of multiphase and reactive flow processes in liquid rocket propulsion.

2.0 LITERATURE REVIEW

2.1 Fundamentals of Liquid Atomization in Rocket Injectors

Atomization within liquid rocket injectors is a complex multiphase phenomenon governed by the interplay of inertial, viscous, and surface tension forces acting on a high-velocity liquid jet. The transition from a continuous liquid stream to ligaments and subsequently fine droplets is determined by nondimensional parameters such as the Weber number (We) and the

Ohnesorge number (Oh). The Weber number expresses the ratio of inertial to surface tension forces, while the Ohnesorge number quantifies the influence of viscous damping. As elucidated by Lefebvre and McDonell (2017), higher Weber numbers promote ligament formation and secondary droplet fragmentation, whereas lower Ohnesorge numbers signify minimal viscous resistance, enabling fully developed atomization.

The efficiency of atomization is commonly expressed through the Sauter Mean Diameter (SMD), which correlates the droplet surface area to its volume. Smaller SMD values correspond to finer atomization and enhanced interfacial area, leading to faster evaporation and more homogeneous fuel–oxidizer mixing. This process facilitates near-stoichiometric combustion, higher thermal efficiency, and improved flame stability. Conversely, insufficient atomization results in larger droplets, incomplete vaporization, and spatially uneven fuel distribution, potentially inducing combustion instabilities. Thus, optimizing atomization is central to achieving high combustion performance and operational reliability in rocket propulsion systems.

2.2 Pintle Injector Architecture and Mixing Mechanisms

The pintle injector, originally designed by TRW in the 1960s for the Apollo Lunar Module Descent Engine, remains a cornerstone of throttleable rocket propulsion due to its geometric simplicity, combustion stability, and adaptability (Sutton, G.P., & Biblarz, O. 2016). Its architecture consists of a central pintle post that delivers fuel radially outward, surrounded by an annular oxidizer flow. The interaction between these two streams produces a conical sheet that disintegrates through shear instabilities, generating a fine, evenly distributed spray.

This injector configuration offers several intrinsic advantages: (1) a broad throttling range, (2) improved propellant mixing efficiency, and (3) strong resistance to combustion-driven oscillations. Experimental studies, such as those by Chen, Li, and Cheng, (2019) have demonstrated that the momentum-flux ratio between the radial fuel jet and the annular oxidizer flow critically influences spray morphology. Variations in pintle tip geometry, annular spacing, and injection pressure alter droplet size, spray cone angle, and near-field flow structure, thereby affecting downstream combustion characteristics. These hydrodynamic parameters govern the spatial distribution of equivalence ratio and flame anchoring, linking mechanical design directly to combustion behavior. The pintle's simplicity and dynamic control capability ensure its continued relevance in modern reusable and deep-throttling propulsion systems.

2.3 Optical Diagnostics for Spray–Flame Characterization

Recent advancements in optical diagnostics have transformed the study of multiphase and reactive flow phenomena, providing non-intrusive, high-fidelity insights into atomization and combustion dynamics. Among the most widely adopted methods, shadowgraphy and OH^* chemiluminescence imaging stand out for their ability to reveal the coupled physical and chemical behavior of sprays. Shadowgraphy captures refractive index gradients produced by density variations within the spray field, offering direct visualization of primary and secondary breakup processes. As demonstrated by Nassir et al. [2020], pulsed illumination and high-speed

imaging allow accurate measurement of spray boundaries, breakup length, and cone angle evolution. The technique's capacity to resolve transient flow structures without disturbing the system makes it invaluable for injector characterization. OH* chemiluminescence imaging provides complementary information by mapping reactive flow behavior through spontaneous emission from excited hydroxyl radicals near 308 nm. This emission delineates high-temperature reaction zones, offering a reliable indicator of local heat release and flame intensity (Turns, S.R. 2013). Kim and Park [2021] employed OH* imaging to analyze flame stabilization mechanisms in high-pressure combustors, while Hao et al. [2023] established correlations between OH* intensity and fuel-air mixing uniformity in dual-swirl configurations. When combined, shadowgraphy and chemiluminescence imaging enable concurrent assessment of atomization efficiency and combustion structure, yielding a unified understanding of injector performance.

2.4 Research Gaps

Despite decades of research on pintle injectors, integrated experimental investigations coupling atomization and combustion diagnostics remain limited. The majority of prior studies treat atomization and flame structure as distinct phenomena either through cold-flow visualization or isolated chemiluminescence analysis thereby neglecting their inherent coupling. Furthermore, laboratory-scale experiments often utilize surrogate fluids whose thermophysical properties differ substantially from operational propellants, resulting in discrepancies in nondimensional similarity parameters such as We and Oh. These differences complicate direct scaling to engine-representative conditions.

Bridging this gap requires a comprehensive diagnostic framework capable of simultaneously quantifying spray geometry, droplet size distribution, and flame structure under controlled injection conditions. Such an approach would provide empirical datasets to validate computational models and elucidate the mechanistic relationships between injection parameters, atomization efficiency, and reactive flow dynamics. Establishing this linkage is fundamental for optimizing injector design and improving predictive accuracy in high-fidelity simulations.

2.5 Working Hypotheses

Based on the synthesis of existing literature and theoretical principles, this study advances the following hypotheses:

- i. H1 (Atomization Behavior): Increasing the injection momentum ratio via elevated inlet pressure intensifies aerodynamic shear, thereby reducing the Sauter Mean Diameter and expanding the spray cone angle.
- ii. H2 (Combustion Structure): Conditions characterized by smaller droplet sizes and broader spray angles produce stronger and more spatially uniform OH* chemiluminescence intensity fields, signifying enhanced mixing and combustion homogeneity.

- iii. H3 (Atomization Combustion Coupling): Statistically significant correlations between atomization metrics (SMD, cone angle) and OH* intensity distributions demonstrate a causal linkage between injector hydrodynamics and reactive flame structure.

3.0 METHODOLOGY

3.1 Overview of Experimental Framework

This study establishes a rigorous experimental framework to demonstrate the capability of integrated optical diagnostic techniques, shadowgraphy and OH* chemiluminescence imaging in elucidating the fundamental mechanisms governing atomization and combustion efficiency in liquid-fueled systems. Rather than focusing on injector optimization, the methodology seeks to validate these complementary approaches as precise diagnostic tools for correlating droplet-scale dynamics with macroscopic combustion behavior.

The experimental campaign was divided into two distinct phases:

- i. Cold-flow atomization analysis, aimed at quantifying droplet formation, spray dispersion, and breakup dynamics using deionized water and compressed air as surrogate fluids.
- ii. Reactive combustion analysis, focused on employing OH* chemiluminescence to visualize flame structure, reaction-zone intensity, and overall combustion uniformity across varying injection pressures.

Together, these diagnostic approaches provide a unified basis for understanding how droplet atomization characteristics influence flame stability, heat release, and combustion efficiency.

3.2 Shadowgraphy for Atomization Characterization

3.2.1 Experimental Setup




Figure 1. Shadowgraphy experiment setup.

Shadowgraphy was implemented to capture the evolution of the atomization process and quantify the statistical distribution of droplet sizes in non-reactive conditions. A collimated LED light source and optical lens assembly produced a uniform backlit field, while a Phantom VEO-710 high-speed camera operating at 10,000 frames per second (1024×1024 resolution) recorded instantaneous images of the spray field. The short exposure time ($\leq 5 \mu\text{s}$) minimized motion blur, enabling clear visualization of transient breakup phenomena and droplet trajectories. The experimental alignment was carefully calibrated such that the optical axis intersected the central spray region. This ensured repeatable measurements of the spray angle and the near-field breakup structure, providing the foundation for droplet-scale analysis.

3.2.2 Image Processing and Analysis

The recorded videos were processed entirely in MATLAB. Each high-speed video sequence was first decomposed into individual frames, and the resulting image set was stacked pixel by pixel to generate a time-averaged intensity image. This averaging technique enhanced the clarity of persistent flow features while minimizing random optical noise. The averaged image was then used to extract quantitative spray parameters, including spray angle, breakup length, and Sauter Mean Diameter (SMD). The equation of SMD is shown below:

$$D_{32} = \frac{\sum_{i=1}^N d_i^3}{\sum_{i=1}^N d_i^2}$$

Edge detection was performed using the Sobel operator to define the spray boundaries, and droplet diameters were statistically analyzed based on grayscale intensity variations. The SMD was calculated according to where is the droplet diameter and is the droplet count in each size class. This method provided a quantitative measure of droplet dispersion and atomization behavior, establishing the baseline for comparison with reactive combustion measurements.

3.3 OH* Chemiluminescence for Combustion Visualization

3.3.1 Optical Configuration



Figure 2. OH* Chemiluminescence experiment setup

To investigate flame development and combustion efficiency, OH* chemiluminescence imaging was used to detect emission near 308 nm associated with electronically excited hydroxyl radicals. This emission serves as a reliable indicator of heat release and active reaction zones. A LaVision High-Speed Star 8 CMOS camera equipped with a 105 mm f/2.8 UV lens and a 308 ± 5 nm bandpass filter was utilized to isolate the OH* signal. The imaging axis was oriented perpendicular to the flame, allowing capture of the complete two-dimensional flame geometry. The imaging frequency was maintained at 7 kHz to capture transient flame structures, while experiments were performed under low- and high-pressure conditions to evaluate the correlation between injection momentum, flame intensity, and reaction-zone uniformity.

3.3.2 Data Acquisition and Processing

The recorded OH* chemiluminescence videos were also processed exclusively in MATLAB. Each video was decomposed into sequential frames, and the corresponding pixel matrices were stacked and averaged to obtain a composite mean- intensity image representing the time-averaged flame structure. This method effectively highlighted steady-state flame regions while suppressing short-term fluctuations. From the averaged images, the integrated OH* chemiluminescence intensity, was calculated as where denotes the local pixel intensity across the flame area. The resulting intensity fields provided spatial maps of reaction zones, enabling the evaluation of flame uniformity and relative heat-release strength.

4.0 RESULT AND ANALYSIS

This section presents a detailed interpretation of the findings derived from integrated optical diagnostics, shadowgraphy for atomization analysis and OH* chemiluminescence imaging for combustion characterization. The combined observations elucidate the fundamental coupling between injection pressure, droplet breakup behavior, and combustion efficiency. Each diagnostic method provides a distinct yet complementary perspective, demonstrating that improved atomization quality enhances both the uniformity and intensity of the combustion process.

i. Atomization Characteristics



(a)




Figure 3. (a) Water-air spray averaged image. (b) Sobel operator calculated spray angle.

Figure 3. (a) displays representative shadowgraphy images captured during the atomization tests. The water–air spray was recorded to evaluate the droplet formation process and the overall morphology of the spray cone. The recorded high- speed video was processed in MATLAB, where each frame was decomposed and stacked to generate a time-averaged intensity image. This approach enhanced the visibility of stable flow structures while reducing transient noise and random fluctuations. The averaged image revealed a clear conical spray pattern with well- defined boundaries, allowing accurate quantification of droplet distribution and cone geometry. The spray maintained good axisymmetric across, and its expansion rate increased with injection momentum, suggesting consistent liquid–gas interaction and stable atomization.

The spray cone angle was determined directly from the averaged shadowgraphy image using MATLAB-based edge detection. The spray boundaries were identified using a Sobel operator, and linear regression lines were fitted along the two outer edges as shown in Figure 3. (b). The intersection points at the injector exit defined the vertex of the cone, while the angle between the two fitted lines provided the total spray cone angle. Under the tested conditions, the total spray angle was measured to be approximately 70°, indicating a wide and stable dispersion pattern representative of efficient aerodynamic breakup.




Figure 4. Distribution of droplet diameters.

Individual droplets observed within the near-field spray region were analyzed to estimate droplet diameter. MATLAB image segmentation techniques were applied to isolate droplet regions based on intensity thresholds, and the equivalent diameters were calculated and the results are shown in Figure 4. The statistical mean of these droplet diameters yielded a Sauter Mean Diameter (SMD) of approximately 128 μm . This value characterizes the mean droplet size weighted by surface area and serves as a critical indicator of atomization quality. Smaller SMD values correspond to finer droplets, greater interfacial area, and faster vaporization rates, all of which are beneficial for combustion efficiency. The results confirm that high-speed shadowgraphy, combined with MATLAB- based frame extraction and image averaging, can accurately capture and quantify the essential parameters of spray behavior. The measured spray cone angle and droplet size values demonstrate the reproducibility and precision of the method, validating its suitability for non-intrusive atomization analysis. These outcomes provide a quantitative foundation for linking atomization characteristics to combustion efficiency in subsequent diagnostic studies.

ii. Combustion Behavior (OH* Chemiluminescence Imaging)




Figure 5. OH* filtered flame image of (a) low fuel injection pressure. (b) high fuel injection pressure.

The OH* chemiluminescence diagnostic was employed to visualize active reaction zones and assess flame uniformity. Figure 5. shows the averaged OH* images processed in MATLAB using the same frame extraction and stacking approach. The emission near 308 nm originates from electronically excited hydroxyl radicals, which serve as direct indicators of heat-release regions in hydrocarbon and alcohol-based combustion.

As shown in Figure 6., at lower injection pressures, the flame appeared compact and localized near the injector exit, characterized by relatively low emission intensity. In contrast, at higher injection pressures, the flame exhibited a more extended and uniformly luminous structure with increased intensity throughout the reaction zone. This spatial broadening and enhancement in brightness suggest improved fuel air mixing and more complete combustion under elevated injection momentum. The comparison between low and high-pressure cases reveals that enhanced atomization produces finer droplets, which in turn promote more homogeneous vapor-phase mixing. This improved mixture preparation results in stronger and more evenly distributed OH* emission, reflecting higher reaction rates and better thermal efficiency. The transition from a compact to an elongated flame structure demonstrates the

influence of atomization quality on flame stability and combustion performance.




Figure 6. Comparison of OH* intensity vs. distance.

5.0 CONCLUSION

This study demonstrated the successful application of integrated optical diagnostic techniques shadowgraphy and OH* chemiluminescence imaging for the quantitative characterization of atomization behavior and combustion performance in a liquid-fueled system. The experimental results provide clear evidence that improvements in atomization directly enhance combustion efficiency through increased mixing uniformity and more stable flame structures. From the shadowgraphy analysis, the atomization process was effectively visualized and quantified using high-speed imaging and MATLAB-based processing. The extracted spray angle of approximately 70° and a Sauter Mean Diameter (SMD) of 128 μm indicate efficient aerodynamic breakup and fine droplet formation. These parameters validate the ability of non-intrusive image-based diagnostics to resolve detailed features of liquid breakup and dispersion under dynamic flow conditions. The OH* chemiluminescence imaging further established a strong correlation between atomization quality and combustion behavior. As injection pressure increased, the flame structure transitioned from compact and weakly luminous to more elongated and uniformly bright, signifying enhanced heat release and improved combustion stability. The observed spatial broadening of the reaction zone confirmed that finer droplet atomization leads to more homogeneous vapor-phase mixing and sustained energy release. Collectively, these findings demonstrate that combining droplet-scale and flame-scale optical diagnostics enables a comprehensive assessment of the physical and chemical coupling mechanisms in combustion systems. The use of frame extraction and image stacking in MATLAB proved to be a robust method for enhancing data reliability and visualization quality.

In conclusion, the developed dual-diagnostic framework offers a validated, non-intrusive approach for linking atomization characteristics with combustion efficiency. The methodology not only advances the understanding of spray flame interactions but also establishes a foundation for future optimization of liquid propulsion and energy conversion technologies through integrated optical analysis.

REFERENCES

- Chen, Q., Li, Q., & Cheng, P. (2019). Experimental study on spray characteristics of a pintle injector with different pintle tip geometries. *Experimental Thermal and Fluid Science*, 102, 586-595.
- Glassman, I., Yetter, R.A., & Glumac, N. G. (2014). Combustion (5th ed.). *Academic Press*.
- Hao, W., Zhang, Y., Wang, Y., & Wang, Z. (2023). Correlations of OH* chemiluminescence intensity and uniformity with fuel-air mixing in a dual- swirl combustor. *Aerospace Science and Technology*, 138, 108343.
- Kim, S., & Park, J. (2021). Analysis of flame stabilization characteristics of a non- premixed methane-air flame in a model high-pressure combustor using OH* chemiluminescence imaging. *Journal of Mechanical Science and Technology*, 35(5), 2119-2127.
- Lefebvre, A.H., & McDonell, V.G. (2017). Atomization of Sprays (2nd ed.). *CRC Press*.
- Nassir, A., Almalki, M., An, S., Lee Y., & Lee, S. Y. (2020). Spray breakup and atomization of a pintle injector element using shadowgraphy and digital in- line holography. *Experiments in Fluids*, 61(11), 226.
- Sutton, G.P., & Biblarz, O. (2016). Rocket Propulsion Elements (9th ed.). *John Wiley & Sons*.
- Turns, S.R. (2013). An Introduction to Combustion: Concepts and Applications (SI Edition). *McGraw-Hill*.

The Impact of Electrode Type on Weld Quality in Low-Carbon Steel

Nazaruddin Mohtaram^{1,*}, Muhammad Hazizan Atan², Mohamad Najib Mohamad Zain³

^{1,3}Politeknik Merlimau Melaka

²Politeknik Kuching Sarawak

*Corresponding Author's Email: nazaden1096@gmail.com

Abstract This research examines how various electrode types affect the weld quality of low-carbon steel, a material frequently used in structural and industrial applications due its ductility and ease of welding. The study focuses on three widely used electrodes E6013, E7018, and E7024 and evaluates their performance based on weld bead appearance, penetration depth, mechanical strength and defect occurrence. Controlled experimental welding trials were conducted, followed by visual inspections, tensile strength tests, and macrostructural evaluations. The findings indicate that E7018, a low-hydrogen electrode, produced welds with superior mechanical properties and reduced porosity, making it highly suitable for high-strength applications. E6013 provided smoother arc stability and a better surface finish but demonstrated moderate strength and higher levels of spatter. E7024 showed high deposition rates and productivity but was less effective in vertical and overhead welding positions. Overall, the results highlight the importance of selecting the appropriate electrode based on specific welding requirements, including position, load capacity and surface finish quality. This research offers valuable insights for welders, engineers and manufacturers seeking to optimize welding processes and maintain structural integrity in low carbon steel fabrication.

Keywords: Low carbon steel, electrode type, weld quality, E6013, E7018, E7024, arc stability, mechanical strength, porosity, welding defects

1.0 INTRODUCTION

Welding is a crucial technique in the fabrication and assembly of metallic structures, extensively used across various industries such as construction, automotive, shipbuilding, and manufacturing. Among the different types of steel employed in these sectors, low-carbon steel is a preferred choice due to its excellent weldability, ductility, and cost-effectiveness. Nevertheless, achieving high quality welds on low carbon steel depends on several factors, including welding parameters, technique, and particular, the type of electrode-used. Electrodes serve as a conduit for current to flow to the workpiece, significantly affecting the characteristics of the weld bead, penetration depth, mechanical strength, and defect formation. Electrode performance varies according to factors such as coating composition, arc stability, deposition rate, and hydrogen content, all of which affect the final weld quality. For instance, rutile-coated electrodes like E6013 are known for their smooth arcs characteristics and ease of handling,

while low-hydrogen electrodes such as E7018 offer superior mechanical properties and lower porosity. Despite the common usage of these electrodes, there exists a scarcity of comparative studies that systematically investigate their performance on low carbon steel under controlled conditions. This study aims to address that gap by examining how various electrode types specifically E6013, E7018, and E7024 affect the weld quality of low carbon steel. Through experimental welding trials and comprehensive analysis, this research seeks to provide practical insights for welders, engineers, and manufacturers in selecting the most suitable electrode for specific applications. The findings of this study will contribute to enhanced welding practices, improved structural integrity, and better-informed decision-making in industrial environments where low carbon steel is extensively employed.

2.0 LITERATURE REVIEW

Welding low carbon steel is a common practice in industrial fabrication due to its favorable ductility, affordability, and weldability. However, weld quality is highly dependent on the type of electrode used. This section reviews the existing literature on how the characteristics of electrodes such as coating type, hydrogen content, and deposition rate impact weld performance.

a) Electrode Classification and Coating Types

Electrodes employed in Shielded Metal Arc Welding (SMAW) are categorized based on tensile strength, suitability for different welding positions, and the type of coating used. Rutile-coated electrodes such as E6013 are known for producing a smooth arc and are user-friendly, making them appropriate for general-purpose welding. Conversely, low-hydrogen electrodes like E7018 deliver higher mechanical strength and a lower likelihood of hydrogen-induced cracking, rendering them ideal for structural applications.

b) Mechanical Properties and Weld Integrity

Njoku et al. examined the mechanical and microstructural characteristics of low carbon steel welded with various electrodes. Their research indicated that E7018 resulted in welds with superior tensile strength and finer grain structures compared to E6013, which exhibited increased spatter and surface imperfections. The study highlighted the significance of managing electrode moisture to avert hydrogen embrittlement. Khan et al. supported these findings, confirming that low-hydrogen electrodes offered deeper penetration and stronger welds, while rutile electrodes provided improved surface finishes yet exhibited lower strength.

c) Weld Defects and Operational Efficiency

Singh and Kumar analyzed weld defects resulting from E6013 and E7018 electrodes. They found that welds created with E7018 had fewer defects such as porosity and slag inclusion, attributed to their stable arc and efficient slag removal. E6013, though easier to manage, was more susceptible to surface defects if not applied with the correct technique. Jones noted that

improper electrode selection and handling could lead to arc instability and higher defect rates, especially in critical structural applications.

d) Deposition Rate and Positional Suitability

E7024 electrodes are crafted for high deposition rates and are predominantly utilized in flat and horizontal welding setups. Tanaka and Saito observed that E7024 increased welding speed and productivity; however, it was less effective in vertical and overhead positions due to its fluid slag and limited positional adaptability. Kumar and Sharma conducted microstructural assessments of SMAW welds using a variety of electrodes, concluding that the choice of electrode directly influences grain refinement and hardness distribution throughout the weld zone.

e) Industry Standards and Practical Implications

The American Welding Society (AWS) specifies performance criteria for carbon steel electrodes in its ANSI/AWS A5.1 guidelines. It advocates for low-hydrogen electrodes in applications where high weld integrity and strength are necessary. The AWS Welding Handbook further highlights the role of electrode coating in ensuring arc stability, penetration, and minimizing spatter. El-Sayed and El-Mahallawy compared SMAW, MIG, and OAW methods on low carbon steel, concluding that SMAW when used with the right electrodes can yield welds with competitive mechanical attributes. The choice of electrode within SMAW was identified as a crucial factor impacting weld quality.

3.0 METHODOLOGY

3.2 Materials and Equipment

- a) Base Material: Low carbon steel plates (AISI 1018), dimensions 150 mm × 100 mm × 6 mm.
- b) Electrodes Utilized: E6013 (rutile-coated), E7018 (low-hydrogen), and E7024 (high-deposition).
- c) Welding Technique: Shielded Metal Arc Welding (SMAW).
- d) Welding Equipment: AC/DC inverter-type welder with adjustable current settings.
- e) Testing Instruments: Universal Testing Machine (UTM), metallurgical microscope, and visual inspection tools.

3.2 Welding Process

- a) Plates were cleaned and beveled to ensure consistent joint preparation.
- b) Welding was carried out in a flat position using a single-pass technique.

- c) Current settings were optimized for each electrode type following manufacturer guidelines.
- d) Three samples were welded for each electrode type to ensure consistency in results.

3.3 Evaluation Techniques

- a) Visual Inspection: Evaluated bead appearance, spatter, and surface defects.
- b) Tensile Testing: Assessed ultimate tensile strength (UTS) of each weld.
- c) Macrostructure Analysis: Cross-sections were etched and scrutinized for penetration depth and grain structure.
- d) Defect Identification: Inspected for porosity, slag inclusion, and undercut using visual and microscopic methods.

4.0 RESULTS

This section presents the findings from the experimental welding trials conducted with three electrode types E6013, E7018, and E7024 on low carbon steel plates. The evaluation focused on visual inspection, tensile strength testing, macrostructure analysis, and defect identification.

4.1 Visual Inspection

Each weld was assessed for bead appearance, surface smoothness, spatter, and visible defects:

- a) E6013 (Rutile-coated)
 - Bead appearance: Smooth and uniform
 - Spatter: Moderate, requiring post-cleaning
 - Defects: Occasional undercut and minor porosity
 - Slag removal: Easy and clean
- b) E7018 (Low-hydrogen)
 - Bead appearance: Consistent and well-defined
 - Spatter: Minimal
 - Defects: Very low occurrence of porosity or slag inclusion
 - Slag removal: Smooth and self-lifting
- c) E7024 (High-deposition)
 - Bead appearance: Wide and flat profile
 - Spatter: Low
 - Defects: Some slag inclusion in overlap zones
 - Slag removal: Moderate effort required

4.2 Tensile Strength Testing

Tensile tests were conducted using a Universal Testing Machine (UTM). The average Ultimate Tensile Strength (UTS) for each electrode type is detailed in table 1.

Table 1: The average Ultimate Tensile Strength (UTS) for each electrode type

Electrode Type	Average UTS (MPa)	Fracture Location
E6013	420	Near weld zone
E7018	510	Base metal (indicates strong weld)
E7024	470	Weld zone

E7018 produced the most robust welds, with fractures occurring in the base metal rather than the weld, which indicates excellent fusion and strength.

4.3 Macrostructure Analysis

Cross-sectional samples were etched and evaluated under a metallurgical microscope to investigate penetration depth, grain structure, and fusion quality:

- a) E6013
Penetration: Shallow
Grain structure: Coarse grains present in the heat-affected zone (HAZ)
Fusion: Satisfactory but less uniform
- b) E7018
Penetration: Deep and consistent
Grain structure: Fine grains with minimal distortion in the heat-affected zone
Fusion: Excellent, with a smooth transition between the weld and base metal
- c) E7024
Penetration: Moderate
Grain structure: Mixed grain sizes caused by high deposition rates
Fusion: Good in flat regions, but less consistent in overlap areas

4.4 Weld Defects

Table 2: Defects were detected via visual and microscopic inspections.

Electrode Type	Porosity	Slag Inclusion	Undercut	Spatter Level
E6013	Moderate	Low	Occasional	Moderate
E7018	Low	Very Low	None	Minimal
E7024	Low	Moderate	None	Low

E7018 exhibited the best overall performance in terms of strength, penetration, and defect management. While E6013 was simpler to handle, it produced weaker welds, and E7024 provided high productivity but compromised on positional control and defect rates.

5.0 DISCUSSION AND CONCLUSION

The findings of this study indicate that the type of electrode has a significantly impact on the quality of welds in low carbon steel. Each electrode exhibited distinct characteristics that influenced mechanical performance, defect development, and operational efficiency.

5.1 Mechanical Strength and Fusion Quality

E7018 electrodes resulted in the highest tensile strength (510 MPa), with fractures occurring in the base material instead of the weld area. This reflects excellent fusion and weld integrity, in agreement with research by Njoku et al. (2025) and Khan et al. (2020), who highlighted the superior mechanical properties of low-hydrogen electrodes. The deep penetration and fine grain structure seen in macrostructure analysis further affirm its suitability for structural applications.

Conversely, E6013 electrodes produced lower tensile strength (420 MPa) and exhibited signs of undercut and porosity. Although easier to use and providing smoother arc performance, their rutile coating restricts penetration depth and increases spatter, rendering them less suitable for load-bearing joints. These results correspond with Singh and Kumar's (2022) observations regarding defect occurrence in rutile-coated electrodes. E7024 electrodes showed moderate strength (470 MPa) along with high deposition rates, making them effective for flat-position welding. Nevertheless, slag inclusion and inconsistent fusion in overlap areas suggest limitations in positional versatility, as noted by Tanaka and Saito (2021).

5.2 Weld Defects and Operational Considerations

The research indicated that E7018 had the lowest defect occurrence, with minimal porosity and clean slag removal. This supports AWS recommendations for utilizing low-hydrogen electrodes in critical scenarios. E6013, though user-friendly, demonstrated moderate

spatter and occasional undercut, necessitating post-weld cleaning and inspection. E7024's high productivity was counterbalanced by moderate slag inclusion, emphasizing the importance of careful handling and position control. (ANSI/AWS A5.1, 2020).

5.3 Practical Implications

The outcomes highlight the necessity of choosing electrodes based on specific welding requirements. For applications demanding high strength and structural integrity, E7018 is the preferred option. For general fabrication and user-friendliness, E6013 remains a viable choice. E7024 is most appropriate for high-volume production in flat positions. These insights align with industry standards set by AWS (2018) and are supported by comparative studies like those by El-Sayed and El-Mahallawy (2023).

5.4 Conclusion

This study has demonstrated that the type of electrode used in SMAW has a significantly impacts on the weld quality of low carbon steel. Based on visual inspections, tensile tests, and macrostructural analysis, the following conclusions were drawn:

- i. E7018 provides superior mechanical strength, deep penetration, and minimal defects, making it highly suitable for structural applications.
- ii. E6013 offers ease of use and good surface finish but is limited by lower strength and higher spatter levels.
- iii. E7024 enhances productivity in flat welding but requires careful control to mitigate slag-related defects.

The findings underscore that electrode selection should be guided by the specific application, welding position, and necessary mechanical properties. By aligning electrode choice with operational demands, manufacturers and welders can improve weld performance, reduce defect rates and ensure structural integrity in low carbon steel fabrication.

REFERENCES

- Paktechpoint, "Selection and Use of Electrodes for SMAW of Low Carbon Steel," 2023. [Online]. Available: <https://paktechpoint.com/selection-and-use-of-electrodes-for-smaw-of-low-carbon-steel>
- C. Njoku et al., "Effect of Welding Parameters on Mechanical and Microstructure of Low Carbon Steel," *Journal of Materials and Environmental Science*, vol. 16, no. 4, p. 4045, 2025.
- M. A. Khan et al., "Effect of Electrode Type on Weld Bead Geometry and Mechanical Properties of Mild Steel," *Materials Today: Proceedings*, vol. 28, pp. 1234–1240, 2020.
- R. Singh and A. Kumar, "Comparative Study of Weld Defects Using E6013 and E7018 Electrodes,"

- International Journal of Welding Technology, vol. 10, no. 2, pp. 78–85, 2022.
- D. R. Jones, “Arc Welding Safety and Electrode Selection for Structural Steel,” Journal of Occupational Safety and Engineering, vol. 7, no. 1, pp. 45–52, 2019.
- H. Tanaka and M. Saito, “Performance Evaluation of High Deposition Electrodes in SMAW,” Welding Engineering Review, vol. 18, no. 3, pp. 112–119, 2021.
- V. Kumar and P. Sharma, “Microstructural Analysis of SMAW Welds Using Different Electrodes on Low Carbon Steel,” International Journal of Materials Research, vol. 14, no. 4, pp. 210–218, 2021.
- American Welding Society, Specification for Carbon Steel Electrodes for Shielded Metal Arc Welding (ANSI/AWS A5.1), Miami, FL, 2020.
- AWS Welding Handbook, Volume 2: Welding Processes, American Welding Society, Miami, FL, 2018.
- M. El-Sayed and N. El-Mahallawy, “Investigation of Mechanical Properties of Low Carbon Steel Weldments Using SMAW, MIG, and OAW Techniques,” SVU International Journal of Engineering Sciences, vol. 6, no. 2, pp. 255–270, 2023.

Kajian Prestasi Dan Keluaran Mesin Pengayak Tepung Automatik Terhadap Kualiti Penghasilan Tepung Bagi Pembuatan Kuih Tradisional Putu Bambu Di Industri Kecil Dan Sederhana Di Pontian, Johor

Mohamad Halim Ibrahim¹, Muhammad Zahrin Bin Tokijan², Mohamad Shahril Ibrahim^{3,*}

Politeknik Merlimau Melaka^{1,2}
Politeknik Kuching Sarawak³

*hb150009@gmail.com

Abstrak Proses pengayakan tepung secara manual masih menjadi amalan utama dalam kalangan pengusaha kuih tradisional di Pontian, Johor seperti putu bambu, namun kaedah ini memerlukan masa yang lama, tenaga kerja yang tinggi, serta menghasilkan tepung yang tidak seragam dari segi kehalusan. Masalah ini menjejaskan produktiviti serta konsistensi kualiti produk dalam kalangan pengusaha Industri Kecil dan Sederhana (IKS). Kajian ini dijalankan bagi menilai prestasi dan hasil keluaran mesin pengayak tepung automatik yang dibangunkan untuk meningkatkan kecekapan pengeluaran serta kualiti tepung beras halus. Tiga objektif utama kajian ini ialah menilai prestasi mesin dari aspek masa dan kapasiti pengayakan, menganalisis kehalusan tepung yang dihasilkan, serta menilai kesan penggunaan mesin terhadap produktiviti IKS. Mesin ini direka menggunakan motor elektrik 1 HP dengan jaring keluli tahan karat 20 mesh dan diuji menggunakan 5 kg tepung beras. Keputusan ujian menunjukkan bahawa masa pengayakan berkurang daripada 30 minit kepada 21 minit, mencatatkan peningkatan kecekapan sebanyak 30% berbanding kaedah manual. Selain itu, berat sisa kasar selepas pengayakan berkurang sebanyak 35%, menunjukkan peningkatan kehalusan tepung kepada 97.1%. Dari sudut produktiviti, penggunaan mesin ini meningkatkan kapasiti pengeluaran sebanyak 25–30% sehari serta mengurangkan kebergantungan kepada tenaga manusia. Secara keseluruhannya, kajian ini membuktikan bahawa penggunaan mesin pengayak tepung automatik mampu meningkatkan kecekapan operasi, mengekalkan kualiti tepung halus yang seragam, dan memperkukuh daya saing pengusaha IKS dalam pengeluaran kuih tradisional putu bambu.

Kata kunci: Mesin pengayak tepung automatik, kecekapan operasi, kehalusan tepung, prestasi mesin, produktiviti IKS, putu bambu

1.0 PENGENALAN

Dalam era pembangunan industri makanan tempatan, peningkatan produktiviti dan konsistensi kualiti produk merupakan aspek penting bagi memastikan daya saing pengusaha Industri Kecil dan Sederhana (IKS). Industri makanan tradisional di Malaysia terutama di Pontian, Johor seperti pembuatan kuih putu bambu, putu piring, dan seri muka, masih banyak bergantung kepada proses manual yang memerlukan masa dan tenaga kerja yang tinggi. Salah satu proses kritikal dalam penghasilan kuih tradisional ini ialah proses pengayakan tepung

beras, yang menentukan tekstur, kelembutan, dan kehalusan hasil akhir produk (Rashidi, 2023). Secara tradisional, proses pengayakan dijalankan secara manual menggunakan ayak tangan atau penapis halus. Walaupun kaedah ini mudah dan murah, ia sering kali menghasilkan tepung dengan tahap kehalusan yang tidak seragam, selain mengambil masa yang panjang serta memerlukan pengawasan berterusan (Yokasing, 2024). Masalah ini menyebabkan kadar pengeluaran menjadi terhad dan mutu produk tidak konsisten antara satu batch dengan yang lain. Tambahan pula, pengusaha IKS yang bergantung kepada tenaga manusia menghadapi cabaran dalam menampung permintaan pelanggan yang semakin meningkat serta mengekalkan piawaian kualiti produk.

Perkembangan teknologi mekanikal dan automasi mudah kini membuka peluang kepada pengusaha kecil untuk beralih kepada sistem pengeluaran yang lebih cekap. Pembangunan mesin pengayak tepung automatik merupakan satu inovasi yang dapat membantu meningkatkan kecekapan pengeluaran melalui pengurangan masa operasi dan peningkatan kualiti ayakan tepung (Avrampos, 2024). Mesin ini direka bentuk untuk beroperasi menggunakan motor elektrik dan sistem getaran bagi mempercepatkan proses pengasingan partikel tepung, di samping memastikan hasil ayakan lebih seragam dan halus.

Dalam konteks kajian ini, tumpuan diberikan kepada penilaian prestasi dan hasil keluaran mesin pengayak tepung automatik yang dibangunkan khas untuk pengeluaran tepung beras bagi pembuatan kuih tradisional putu bambu. Kajian ini dijalankan bagi menilai tahap kecekapan mesin dari aspek masa pengayakan, kapasiti muatan, serta kesan terhadap kualiti tepung halus yang terhasil. Dengan pelaksanaan sistem automatik ini, diharapkan pengusaha IKS di Pontian, Johor dapat meningkatkan produktiviti, mengurangkan kebergantungan terhadap tenaga kerja manual, dan mengekalkan kualiti produk tradisional secara konsisten.

Dalam industri pembuatan makanan tradisional, khususnya penghasilan kuih putu bambu, kualiti tepung beras memainkan peranan yang sangat penting dalam menentukan tekstur, rasa dan rupa bentuk produk akhir. Proses pengayakan tepung secara manual masih menjadi amalan utama dalam kalangan pengusaha kecil, kerana ia tidak memerlukan kos modal yang tinggi dan mudah dijalankan. Namun begitu, kaedah ini menimbulkan beberapa isu utama dari sudut prestasi, tenaga kerja dan kawalan kualiti.

Pertama, kaedah manual mengambil masa yang panjang untuk mengayak tepung dalam kuantiti yang besar. Pengusaha perlu menapis tepung secara berulang-ulang bagi memastikan ia benar-benar halus, menyebabkan masa pengeluaran meningkat sehingga menjejaskan kadar produktiviti harian. Kajian terhadap mesin ayakan komersial menyatakan bahawa penggunaan alat mekanikal atau automatik memberi kecekapan jauh lebih tinggi berbanding ayakan manual tradisional. (Madayag et al., 2024). Kedua, tahap kehalusan dan seragamnya tepung yang dihasilkan tidak konsisten kerana ia bergantung sepenuhnya kepada tenaga manusia. Faktor seperti keletihan, teknik ayakan, dan peralatan tradisional yang terhad menjadikan hasil pengayakan sukar mencapai tahap kualiti yang diinginkan secara berterusan (Rashidi et al., 2023).

Selain itu, penggunaan tenaga manusia yang berlebihan dalam proses pengayakan turut meningkatkan kos operasi serta risiko kecederaan akibat aktiviti berulang (repetitive motion).

Dalam konteks pengusaha IKS yang beroperasi pada skala kecil, ketidakefisienan ini menyebabkan mereka sukar menampung permintaan pasaran serta mengekalkan standard kualiti produk tradisional seperti putu bambu secara konsisten.

Oleh itu, wujud keperluan untuk membangunkan dan menilai prestasi sebuah mesin pengayak tepung automatik yang dapat menggantikan proses manual ini. Mesin tersebut diharap mampu mempercepatkan masa pengayakan, menghasilkan tepung yang lebih halus dan seragam, serta meningkatkan kecekapan pengeluaran secara keseluruhan (Madayag et al., 2024; Naveen Kumar et al., 2023). Kajian ini dijalankan bagi menilai sejauh mana penggunaan mesin pengayak tepung automatik dapat memberikan kesan positif terhadap prestasi pengeluaran dan kualiti tepung beras untuk pembuatan kuih putu bambu.

Kajian ini dijalankan bagi menilai prestasi dan output mesin pengayak tepung automatik terhadap kualiti tepung halus yang digunakan dalam pembuatan kuih tradisional putu bambu. Secara khusus, objektif kajian ini adalah untuk:

- i. Menilai prestasi mesin pengayak tepung automatik dari aspek masa pengayakan dan kapasiti operasi berbanding kaedah manual yang biasa digunakan oleh pengusaha kecil.
- ii. Menganalisis kualiti dan kehalusan tepung beras yang dihasilkan oleh mesin pengayak automatik bagi menentukan keseragaman dan kesesuaian untuk pembuatan kuih putu bambu.
- iii. Menilai impak penggunaan mesin automatik terhadap peningkatan kecekapan dan produktiviti pengeluaran dalam kalangan pengusaha Industri Kecil dan Sederhana (IKS).

Berdasarkan pernyataan masalah dan objektif yang telah dirumuskan, beberapa persoalan utama telah dikenalpasti bagi memandu hala tuju penyelidikan ini. Persoalan kajian ini bertujuan untuk mendapatkan jawapan terhadap tahap prestasi dan kualiti hasil pengayakan tepung menggunakan mesin automatik berbanding kaedah manual. Antara persoalan kajian yang dikemukakan ialah:

- i. Sejauh manakah mesin pengayak tepung automatik mampu mengurangkan masa pengayakan dan meningkatkan kapasiti operasi berbanding kaedah manual yang digunakan oleh pengusaha kecil?
- ii. Adakah tepung yang dihasilkan oleh mesin pengayak automatik mempunyai tahap kehalusan dan keseragaman yang lebih baik untuk memenuhi keperluan pembuatan kuih tradisional putu bambu?
- iii. Apakah kesan penggunaan mesin pengayak tepung automatik terhadap tahap kecekapan dan produktiviti pengeluaran dalam kalangan pengusaha Industri Kecil dan Sederhana (IKS)?

Skop kajian ini tertumpu kepada penilaian prestasi dan output mesin pengayak tepung automatik yang dibangunkan khusus untuk kegunaan pengusaha Industri Kecil dan Sederhana (IKS) di Pontian, Johor dalam pemprosesan tepung beras bagi pembuatan kuih tradisional putu bambu. Kajian ini memberi tumpuan kepada aspek berikut:

- i. Jenis bahan yang digunakan adalah tepung beras kering yang biasa digunakan dalam pembuatan kuih putu bambu. Tepung ini diuji untuk menilai tahap kehalusan dan keseragaman hasil selepas proses pengayakan.

- ii. Parameter prestasi mesin yang dikaji meliputi masa pengayakan, kapasiti muatan (5 kg setiap kitaran), serta tahap kecekapan operasi mesin berbanding kaedah pengayakan manual.

Ujian dijalankan dalam skala makmal dan bengkel kejuruteraan bagi menilai keberkesanan fungsi mekanikal, daya tahan struktur, dan konsistensi hasil ayakan yang diperolehi.

Kajian ini tidak melibatkan analisis ekonomi terperinci seperti kos pengeluaran besar-besaran atau analisis tenaga elektrik, namun menekankan aspek teknikal dan prestasi mesin dari segi kecekapan masa dan kualiti tepung yang dihasilkan. Skop ini dirangka bagi memastikan penilaian dapat dijalankan secara fokus terhadap keupayaan mesin pengayak tepung automatik dalam meningkatkan kualiti dan produktiviti pengeluaran tepung beras untuk industri makanan tradisional berskala kecil.

2.0 KAJIAN LITERATUR

Proses pengayakan tepung merupakan langkah penting dalam penghasilan makanan yang melibatkan tepung beras, terutamanya dalam pembuatan kuih tradisional seperti putu bambu, putu piring, dan seri muka. Tujuan utama proses ini adalah untuk memastikan partikel tepung beras menjadi lebih halus, seragam dan bebas daripada ketulan atau bahan asing. Kajian oleh Hassan et al. (2023) menjelaskan bahawa tahap kehalusan dan keseragaman tepung yang digunakan memberi kesan langsung terhadap tekstur dan kualiti makanan yang dihasilkan. Dalam konteks industri kecil, pengayakan manual sering dilakukan menggunakan penapis keluli halus, namun kaedah ini tidak efisien untuk pemprosesan dalam kuantiti besar dan mudah menjejaskan konsistensi hasil.

Bagi mengatasi isu tersebut, pengenalan kepada sistem pengayak automatik berasaskan getaran telah mula diterokai oleh pengeluar kecil dan penyelidik teknikal. Kamarudin et al. (2022) menyatakan bahawa penggunaan motor elektrik dengan mekanisme getaran dapat mempercepatkan proses pengasingan partikel tanpa memerlukan tenaga manusia yang banyak. Sistem automatik ini bukan sahaja mengurangkan masa pengeluaran, malah menghasilkan ayakan tepung yang lebih sekata, meningkatkan produktiviti dan kebersihan dalam proses pemprosesan makanan.

Dalam kajian oleh Jagadeesh et al. (2021), mesin pengayak berasaskan motor aruhan menunjukkan peningkatan kecekapan sebanyak 25–40% berbanding kaedah manual, manakala Rizwan et al. (2024) menegaskan bahawa automasi mudah berskala kecil dapat diaplikasikan secara meluas dalam industri makanan tradisional untuk meningkatkan daya saing pengusaha tempatan. Di Malaysia, pembangunan mesin pengayak tepung automatik berskala IKS masih dalam peringkat awal, namun projek-projek terdahulu menunjukkan potensi tinggi untuk menggantikan proses manual yang memakan masa.

Secara keseluruhannya, literatur menunjukkan bahawa penggunaan mesin pengayak tepung automatik berpotensi besar dalam meningkatkan kecekapan, mengurangkan kos tenaga

kerja, dan menjamin kualiti tepung beras yang halus serta seragam untuk penghasilan kuih tradisional seperti putu bambu. Kajian ini dijalankan bagi mengesahkan keberkesanan inovasi tersebut melalui penilaian prestasi sebenar mesin terhadap masa pengayakan, kapasiti dan kualiti hasil tepung.

3.0 METODOLOGI

Metodologi kajian ini dirancang bagi memastikan penilaian prestasi dan output mesin pengayak tepung automatik dapat dijalankan secara sistematik dan selaras dengan objektif kajian. Tiga objektif utama ialah:

- i. Menilai prestasi mesin dari aspek masa dan kapasiti.
- ii. Menganalisis kualiti dan kehalusan tepung yang dihasilkan.
- iii. Menilai kesan penggunaan mesin terhadap kecekapan dan produktiviti pengeluaran.

Bagi mencapai ketiga-tiga objektif tersebut, kajian ini dilaksanakan melalui empat fasa utama iaitu (i) Reka Bentuk Mesin, (ii) Pemilihan Bahan dan Persediaan Sampel, (iii) Ujian Prestasi, dan (iv) Analisis Data.

3.1 Fasa 1: Reka Bentuk dan Spesifikasi Mesin (Objektif 1 & 3)

Fasa pertama tertumpu kepada pembangunan dan kefungsiian mesin bagi memastikan kecekapan operasi dan kesesuaian untuk aplikasi industri kecil. Mesin pengayak tepung automatik ini direka dengan ciri-ciri utama berikut:

- i. Komponen utama: motor elektrik 1 HP, gear pengurang 1:50, tali sawat penghantar kuasa, dan jaring keluli tahan karat berukuran 20 mesh (lubang/inci).
- ii. Rangka mesin: diperbuat daripada keluli tahan karat jenis 304 untuk ketahanan, kebersihan dan kestabilan struktur. Kapasiti operasi: maksimum 10 kg tepung beras bagi setiap kitaran, namun ujian utama dijalankan pada 5 kg untuk keseragaman analisis.
- iii. Prinsip operasi: pengayakan dilakukan melalui getaran dan putaran berterusan aci utama yang digerakkan oleh motor elektrik dengan kadar putaran antara 1200–1500 rpm.

Reka bentuk ini membolehkan penilaian prestasi sebenar mesin dilakukan dalam keadaan operasi normal yang menyerupai penggunaan sebenar oleh pengusaha IKS.

3.2 Fasa 2: Pemilihan Bahan dan Persediaan Sampel (Objektif 2)

Tepung beras kering yang digunakan dalam kajian ini diperoleh daripada pembekal tempatan dan merupakan bahan asas dalam pembuatan kuih putu bambu. Sebanyak 5 kg tepung beras digunakan bagi setiap sesi pengayakan. Tepung diayak menggunakan dua kaedah berbeza:

- i. Kaedah manual: menggunakan penapis keluli tahan karat halus yang digerakkan tangan.
- ii. Kaedah automatik: menggunakan mesin pengayak yang dibangunkan.
- iii. Persampelan dilakukan dalam persekitaran kering bagi memastikan hasil pengayakan tidak dipengaruhi oleh kelembapan udara. Setiap batch tepung yang telah diayak disimpan dalam bekas kedap udara sebelum dinilai dari segi tekstur dan kehalusan.

3.3 Fasa 3: Ujian Prestasi Mesin (Objektif 1 & 2)

Ujian prestasi dijalankan untuk mengukur kecekapan operasi mesin berdasarkan masa pengayakan, kapasiti pengendalian, dan kualiti tepung halus yang dihasilkan.

a. Ujian Masa Pengayakan

Masa diukur menggunakan jam randik digital bermula dari saat mesin dihidupkan sehingga semua 5 kg tepung selesai diayak. Proses ini diulang sebanyak tiga kali bagi mendapatkan nilai purata. Perbandingan dibuat antara masa pengayakan manual dan automatik untuk menentukan kadar peningkatan kecekapan.

b. Ujian Kapasiti Operasi

Mesin diuji dengan beban 5 kg, 10 kg dan 15 kg untuk menilai keupayaan maksimum tanpa gangguan. Pengukuran dilakukan terhadap masa tambahan yang diperlukan dan kestabilan operasi motor. Hasilnya digunakan untuk menentukan kapasiti optimum operasi (kg/jam).

c. Ujian Kualiti Tepung Halus

Hasil ayakan dinilai dari segi:

Kehalusan partikel: diperiksa menggunakan ayak piawai makmal bersaiz 250 µm dan 500 µm.

Kandungan sisa kasar: diukur berdasarkan berat baki partikel yang tertinggal pada penapis.

d. Pemerhatian visual: tekstur tepung dinilai secara kualitatif untuk melihat keseragaman dan ketulan yang masih wujud.

Kualiti tepung dibandingkan antara dua kaedah (manual dan automatik) bagi menentukan sama ada mesin dapat menghasilkan tepung yang lebih halus dan sesuai untuk produk putu bambu.

3.4 Fasa 4: Analisis Data (Objektif 3)

Data prestasi mesin dianalisis secara deskriptif dan perbandingan bagi menilai keberkesanan mesin terhadap kecekapan dan produktiviti. Analisis melibatkan:

Perbandingan masa pengayakan (minit) antara kaedah manual dan automatik.

Peratus peningkatan kecekapan masa (%), dikira menggunakan formula:

$$\text{Peningkatan Kecekapan (\%)} = \frac{T_{\text{manual}} - T_{\text{automatik}}}{T_{\text{manual}}} \times 100$$

Peratus kehalusan tepung (%), berdasarkan berat sisa kasar selepas pengayakan.

Pemerhatian kualitatif, seperti konsistensi tepung dan tahap kebersihan hasil ayakan.

Hasil analisis ini kemudiannya digunakan untuk menilai sama ada penggunaan mesin automatik benar-benar dapat meningkatkan produktiviti pengusaha IKS dari sudut masa, kualiti dan jumlah output.

Secara keseluruhannya, metodologi ini direka bentuk bagi memastikan setiap objektif kajian dapat diuji secara empirikal. Pendekatan eksperimen sebenar digunakan untuk menilai

prestasi mesin dari segi masa dan kapasiti (Objektif 1), kualiti tepung halus yang dihasilkan (Objektif 2), serta kesan keseluruhan terhadap kecekapan dan produktiviti pengeluaran (Objektif 3). Kaedah ini membolehkan penilaian yang menyeluruh terhadap keberkesanan mesin pengayak tepung automatik dalam konteks aplikasi sebenar industri kecil tempatan.

4.0 DAPATAN DAN PERBINCANGAN

Bahagian ini membentangkan dapatan hasil ujian prestasi yang dijalankan terhadap mesin pengayak tepung automatik. Analisis ini memberi tumpuan kepada tiga aspek utama, iaitu masa dan kecekapan operasi, kualiti tepung halus yang dihasilkan, serta impak mesin terhadap produktiviti dan kebolegunaan dalam konteks industri kecil.

4.1 Dapatan Ujian Masa dan Kapasiti Pengayakan

Berdasarkan ujian yang dijalankan, masa pengayakan bagi 5 kg tepung beras secara manual adalah 30 minit, manakala menggunakan mesin automatik hanya mengambil 21 minit. Ini menunjukkan penjimatan masa sebanyak 30% bagi setiap kitaran pengayakan. Selain itu, mesin ini mampu menampung beban sehingga 10 kg tepung tanpa menjejaskan kestabilan operasi motor, walaupun prestasi mula menurun sedikit apabila kapasiti dinaikkan ke 15 kg akibat tekanan berlebihan pada tali sawat.

Jadual 1: Perbandingan Masa dan Kapasiti Pengayakan

Kaedah Pengayakan	Berat (kg)	Tepung Purata (minit)	Masa Peningkatan (%)	Kecekapan
Manual	5	30	—	
Automatik	5	21	30.0	
Automatik	10	30	0	
Automatik	15	45	-50.0 (penurunan prestasi)	

Dapatan ini menunjukkan bahawa prestasi optimum dicapai pada muatan 5–10 kg, di mana masa pengayakan lebih cepat dan mesin beroperasi dengan lancar tanpa berlaku “slipping” pada tali sawat. Hasil ini membuktikan bahawa mesin ini sesuai digunakan oleh pengusaha IKS yang menghasilkan tepung dalam kuantiti sederhana.

4.2 Kualiti dan Kehalusan Tepung Hasil Ayakan

Analisis terhadap tekstur tepung menunjukkan bahawa hasil pengayakan menggunakan mesin automatik menghasilkan partikel tepung yang lebih halus dan seragam, dengan sisa kasar yang tertinggal di atas penapis berkurang sehingga 35% berbanding kaedah manual. Pemerhatian visual juga mendapati tepung yang dihasilkan mempunyai warna yang lebih sekata dan bebas daripada ketulan. Apabila digunakan dalam proses pembuatan putu bambu, tepung halus ini menghasilkan tekstur kuih yang lebih lembut dan padat, menandakan peningkatan kualiti produk akhir.

Jadual 2: Analisis Perbandingan Kehalusan Tepung

Kaedah Pengayakan	Berat (kg)	Tepung Berat (g)	Sisa Kasar (%)	Peratus Kehalusan Tepung (%)
Manual	5000	225	95.5	
Automatik	5000	145	97.1	

Peratus kehalusan tepung meningkat sebanyak 1.6%, namun perbezaan kecil ini memberi impak besar kepada konsistensi produk apabila dihasilkan dalam jumlah besar. Ia menunjukkan bahawa mesin automatik bukan sahaja menjimatkan masa, tetapi turut membantu mengekalkan piawaian kualiti bahan mentah yang digunakan.

4.3 Impak Terhadap Produktiviti dan Operasi IKS

Dari sudut produktiviti, penggunaan mesin automatik membolehkan pengusaha putu bambu meningkatkan kadar pengeluaran harian tanpa menambah bilangan pekerja. Berdasarkan simulasi pengeluaran, sekiranya satu kitaran pengayakan dijalankan enam kali sehari, penggunaan mesin automatik dapat menjimatkan masa operasi sebanyak 54 minit sehari, bersamaan peningkatan kapasiti pengeluaran 25–30%.

Selain itu, pengurangan kebergantungan kepada tenaga manusia juga menurunkan risiko keletihan serta meningkatkan konsistensi hasil pengeluaran. Walaupun terdapat sedikit isu tali sawat tergelincir apabila kapasiti melebihi 10 kg, masalah ini boleh diatasi melalui penggunaan bahan tali sawat berdaya regangan tinggi dan sistem tegangan laras.

4.4 Perbincangan Keseluruhan

Hasil ujian menunjukkan bahawa mesin pengayak tepung automatik memberikan peningkatan yang ketara dalam tiga aspek utama:

- i. Kecekapan masa operasi meningkat 30%.
- ii. Kualiti dan keseragaman tepung bertambah baik sebanyak 1.6%.
- iii. Produktiviti pengeluaran meningkat sekitar 25–30%.

Peningkatan ini selaras dengan objektif kajian yang menekankan kecekapan dan kualiti hasil pengayakan bagi pembuatan putu bambu. Mesin ini membuktikan potensi besar untuk menggantikan kaedah manual dalam pengeluaran berskala kecil. Walau bagaimanapun, bagi penggunaan jangka panjang, reka bentuk sistem penghantaran kuasa perlu diperbaiki untuk mengekalkan prestasi optimum pada kapasiti yang lebih tinggi. Secara keseluruhan, dapatan kajian ini menunjukkan bahawa automasi mudah seperti mesin pengayak tepung bukan sahaja mampu mempertingkatkan kecekapan dan kualiti pengeluaran, malah dapat menyokong kelestarian industri makanan tradisional dalam era moden.

5.0 KESIMPULAN

Kajian ini telah menilai prestasi dan output mesin pengayak tepung automatik terhadap

kualiti tepung halus bagi pembuatan kuih tradisional putu bambu dalam konteks pengusaha Industri Kecil dan Sederhana (IKS) di Malaysia. Hasil ujian menunjukkan bahawa penggunaan mesin automatik memberikan peningkatan ketara dari segi kecekapan masa, keseragaman hasil ayakan, dan produktiviti pengeluaran berbanding kaedah manual. Secara keseluruhannya, mesin pengayak tepung automatik mampu mengurangkan masa pengayakan sebanyak 30%, di samping menghasilkan tepung dengan tahap kehalusan yang lebih baik dan konsisten. Kualiti tepung yang dihasilkan terbukti sesuai digunakan untuk menghasilkan putu bambu yang lebih lembut dan sekata dari segi tekstur. Dari sudut operasi, pengurangan kebergantungan terhadap tenaga manusia turut meningkatkan kecekapan proses, mengurangkan keletihan pekerja, serta membolehkan pengusaha menampung permintaan pasaran yang lebih tinggi. Hasil kajian ini selaras dengan objektif penyelidikan iaitu menilai prestasi mesin, menganalisis kualiti tepung, dan menilai impaknya terhadap produktiviti IKS. Kajian ini juga membuktikan bahawa penerapan teknologi automasi mudah dalam industri makanan tradisional mampu menyokong usaha pekekalan warisan tempatan melalui peningkatan kecekapan dan konsistensi pengeluaran.

5.1 Cadangan

Berdasarkan dapatan dan analisis yang diperolehi, beberapa cadangan dikemukakan untuk penambahbaikan masa hadapan:

- i. Peningkatan sistem penghantaran kuasa:
 - Menggantikan tali sawat sedia ada dengan jenis timing belt atau rantai berketahanan tinggi untuk mengelakkan masalah tergelincir semasa beban tinggi (lebih 10 kg).
- ii. Reka bentuk hopper anti-lekat:
 - Permukaan dalaman hopper boleh disalut dengan bahan seperti Teflon coating bagi mengelakkan tepung melekat dan mengganggu kelancaran aliran semasa proses pengayakan.
- iii. Integrasi kawalan elektronik:
 - Penambahan sistem kawalan kelajuan motor (Variable Speed Drive) dan timer controller boleh meningkatkan ketepatan operasi serta membolehkan pengguna melaraskan kelajuan mengikut jenis tepung yang digunakan.
- iv. Ujian lapangan sebenar bersama pengusaha IKS:
 - Disarankan agar kajian lanjutan dijalankan terus di premis pengusaha bagi menilai prestasi mesin dalam keadaan kerja sebenar serta kesesuaian terhadap pelbagai jenis tepung tempatan.
- v. Analisis ekonomi dan tenaga:
 - Kajian masa hadapan wajar menilai impak penjimatan kos tenaga kerja dan penggunaan elektrik untuk membuktikan keberkesanan mesin dari aspek ekonomi dan kelestarian tenaga.

RUJUKAN

- Akinnuli, B. O., Abadariki, S. O., & Fasan, J. O. (2023). Design and performance evaluation of a low-cost vibration sifter for small-scale food industries. *Journal of Engineering and Applied Technology*, 17(2), 45–54.
- Babajide, N. A., & Aremu, D. O. (2022). Development of small-scale flour processing machines for micro-enterprises in developing countries. *Applied Mechanics and Materials*, 928, 103–114.
- Hassan, M., Rahman, N., & Saiful, M. (2023). Effect of flour particle uniformity on the texture and quality of traditional rice-based products. *International Journal of Food Engineering and Innovation*, 18(3), 211–225.
- Jagadeesh, P., Kumar, R., & Suresh, V. (2021). Performance analysis of vibratory sieving mechanism for fine flour separation. *Asian Journal of Mechanical Engineering*, 15(1), 64–73.
- Kamarudin, S., & Ahmad, M. N. (2022). Implementation of low-cost motorized flour sifter for improving productivity among SMEs in Malaysia. *ASEAN Journal of Engineering and Technology*, 14(1), 45–56.
- Mohamad Haikal Aiman (Mohamad Rashidi) — Automatic flour sieving machine (UiTM e-print, 2023)
- Madayag, B. J. A., Alcaraz, J. M., Agpaoa, R. I., Rodriguez, E. T., & Nerona, N. A. (2024). *Development of a multi-grade flour sieving machine: Its performance and financial feasibility*. IOER International Multidisciplinary Research Journal. <https://doi.org/10.54476/ioer-imrj/246694>
- Rizwan, M., Latif, A., & Wahid, H. (2024). Adoption of simple automation for traditional food industries: Enhancing quality and efficiency. *Journal of Sustainable Manufacturing Systems*, 12(2), 87–98.
- Yusoff, N., & Abdullah, F. (2021). Automation in traditional food production: A review on design and performance of small-scale machines. *Journal of Food Process Engineering*, 44(5), e13789.
- Murtidjo, B. A. (2021). Modernization of traditional food processing through small-scale mechanical innovation. *Asian Journal of Agricultural Technology*, 9(2), 33–47.
- Alarifi, I. M., & Almutairi, A. (2024). Productivity optimization in small-scale mechanical systems using applied automation principles. *International Journal of Advanced Manufacturing Systems*, 22(1), 55–66.

Singh, P., & Rajendran, V. (2020). Impact of particle size distribution on flour-based food texture and process consistency. *Journal of Food Quality Engineering*, 13(4), 255–268.

Inovasi Pengawal Keselamatan Mesin Penggerudi: Kos-Efektif Dan Berfungsi

Noor Azlan bin Ngasman¹, Emmanuel Daniel², Zaini Bin Ashaari³

^{1,2} Jabatan Kejuruteraan Mekanikal, Politeknik Merlimau Melaka

³Jabatan Kejuruteraan Petrokimia, Politeknik Tun Syed Nasir

Abstrak Projek bertajuk "Inovasi Pengawal Keselamatan Mesin Penggerudi untuk Menjadi Kos-Efektif dan Berfungsi" menangani kebimbangan keselamatan kritikal yang berkaitan dengan mesin penggerudi Scantool Type 16 AEF yang digunakan di Politeknik Melaka Merlimau (PMM). Pada masa ini, mesin penggerudi ini beroperasi tanpa pengawal keselamatan, yang menyebabkan risiko signifikan seperti kecederaan akibat sentuhan dengan mata penggerudi yang berputar dan pendedahan kepada daya putaran. Situasi ini menyebabkan ketidakpatuhan terhadap Piawaian OSHA 29 CFR 1910.212(a)(1), yang mewajibkan mesin dilengkapi dengan pengawal keselamatan yang sesuai untuk melindungi pengendali. Objektif utama projek ini adalah untuk mereka dan membangunkan pengawal keselamatan yang tidak hanya meningkatkan perlindungan pengguna tetapi juga tetap kos-efektif untuk institusi pendidikan. Projek ini melibatkan penciptaan prototaip yang boleh dipasang secara sementara pada mesin penggerudi untuk mengelakkan pengubahsuaian kekal. Pengawal ini akan memberi tumpuan khusus kepada penutupan kawasan mata penggerudi sambil memastikan bahawa pengawal tidak mengganggu fungsi operasi mesin. Selain itu, pengawal keselamatan akan direka untuk menampung mata penggerudi shank lurus keluli berkelajuan tinggi (HSS) dengan diameter dari 0.5 mm hingga 13 mm. Dengan menangani kedua-dua kebimbangan keselamatan dan kos, projek ini bertujuan untuk menyediakan penyelesaian praktikal yang mematuhi piawaian keselamatan dan meningkatkan keselamatan keseluruhan di bengkel. Pendekatan inovatif ini diharapkan dapat memberikan pengawal keselamatan yang kos-efektif dan berfungsi, memenuhi piawaian industri, dan memberikan manfaat yang ketara dari segi keselamatan dan produktiviti.

Kata Kunci: pengawal keselamatan, mesin gerudi, prototaip

1.0 PENGENALAN

Keselamatan merupakan aspek penting dalam bidang kejuruteraan mekanikal, terutamanya di bengkel yang menggunakan mesin seperti mesin penggerudi. Mesin penggerudi Scantool Type 16 AEF yang digunakan secara meluas di institusi pendidikan seperti Jabatan Kejuruteraan Mekanikal (JKM) Politeknik Merlimau Melaka direka untuk kerja penggerudian yang tepat tetapi mempunyai risiko keselamatan yang tinggi. Risiko ini termasuk kecederaan akibat mata penggerudi yang berputar laju dan serpihan yang terpelanting, yang boleh menyebabkan kemalangan serius jika tidak dikawal dengan baik. Bahaya ini menunjukkan keperluan langkah keselamatan yang berkesan untuk melindungi pengendali tanpa menjejaskan fungsi mesin.

Di bengkel JKM, pengawal keselamatan sedia ada untuk mesin penggerudi sering menunjukkan kelemahan yang ketara. Banyak pengawal ini rosak pada bahagian pemasangan atau mempunyai komponen polikarbonat yang kabur atau retak akibat penggunaan berpanjangan. Kerosakan ini bukan sahaja mengurangkan tahap penglihatan tetapi juga menyukarkan pengendali untuk memantau kerja mereka dengan berkesan. Ketidakmampuan untuk melihat dengan jelas boleh menyebabkan kesilapan penjajaran dan meningkatkan risiko kecederaan. Oleh itu, projek ini bertujuan untuk mencipta reka bentuk pengawal keselamatan yang inovatif khusus untuk mesin penggerudi Scantool Type 16 AEF, dengan menambah baik perlindungan, menjadikannya kos-efektif, serta mudah dipasang dan ditanggalkan.

Mesin penggerudi Scantool Type 16 AEF digunakan secara meluas dalam persekitaran pendidikan dan industri untuk tugas penggerudian yang tepat. Namun, penggunaannya membawa risiko keselamatan yang ketara, termasuk kecederaan akibat mata penggerudi berputar laju dan serpihan yang terpelanting. Banyak pengawal keselamatan sedia ada gagal memberikan perlindungan yang mencukupi, sering menghalang penglihatan dan memerlukan pengubahsuaian kekal pada mesin penggerudi, yang tidak praktikal dalam persekitaran bengkel yang dinamik. Cabaran utama adalah mencari penyelesaian yang meningkatkan keselamatan pengguna tanpa menjejaskan fungsi mesin. Produk sedia ada tidak membolehkan pengendali memantau kerja mereka dengan berkesan, sekali gus menimbulkan risiko keselamatan. Projek ini bertujuan untuk mereka bentuk pengawal keselamatan yang inovatif, meningkatkan penglihatan dan membolehkan pemasangan sementara, agar mesin penggerudi boleh digunakan dengan selamat dan cekap tanpa pengubahsuaian kekal.

Mesin penggerudi digunakan secara meluas di bengkel Politeknik Merlimau Melaka untuk tugas penggerudian yang tepat, dan merupakan alat penting dalam kurikulum pendidikan pelajar kejuruteraan mekanikal. Namun, risiko operasi yang dikaitkan dengan mesin ini tidak boleh diabaikan. Banyak pengawal keselamatan sedia ada gagal memberikan perlindungan yang mencukupi, sering menghalang penglihatan dan memerlukan pengubahsuaian kekal yang tidak sesuai dalam persekitaran pembelajaran. Tambahan pula, pengawal yang biasa digunakan di bengkel sering rosak, menimbulkan kebimbangan keselamatan yang perlu ditangani segera. Pengendali sering terdedah kepada mata penggerudi berkelajuan tinggi, yang boleh menyebabkan kecederaan jika langkah keselamatan tidak mencukupi. Selain itu, kemungkinan serpihan terpelanting semasa operasi memerlukan peralatan perlindungan yang kukuh untuk melindungi pengguna. Malangnya, banyak pengawal keselamatan semasa tidak menangani cabaran ini dengan berkesan. Pengguna sering melaporkan penglihatan yang terhalang akibat komponen yang rosak, yang menyukarkan penjajaran bahan kerja dan akhirnya menjejaskan keselamatan. Oleh itu, terdapat keperluan mendesak untuk pengawal keselamatan yang meningkatkan perlindungan pengguna sambil mengekalkan fleksibiliti dan kemudahan penggunaan. Cabaran utama dengan pengawal keselamatan sedia ada bagi mesin penggerudi Scantool Type 16 AEF di bengkel JKM ialah ketidakmampuannya untuk memberikan perlindungan yang mencukupi sambil memastikan penglihatan yang jelas dan akses mudah ke kawasan kerja. Pengendali sering mengalami kesukaran untuk memantau kerja mereka disebabkan oleh pandangan yang terhalang, yang boleh membawa kepada risiko keselamatan semasa operasi. Banyak pengawal keselamatan rosak pada bahagian pemasangan atau mempunyai komponen polikarbonat yang kabur dan retak, menjadikannya tidak berfungsi

dengan baik. Projek ini bertujuan untuk mereka bentuk pengawal keselamatan yang inovatif, yang dapat meningkatkan tahap penglihatan dan membolehkan pemasangan sementara, sekali gus mengelakkan sebarang pengubahsuaian kekal pada mesin. Matlamat utama adalah untuk menghasilkan penyelesaian yang mengutamakan keselamatan sambil meningkatkan kecekapan operasi, memastikan mesin penggerudi dapat digunakan secara berkesan dalam pelbagai konteks pendidikan. Justuru, objektif projek ini adalah untuk mereka bentuk prototaip pengawal keselamatan yang disesuaikan untuk mesin penggerudi Scantool Type 16 AEF yang membolehkan pemasangan sementara tanpa pengubahsuaian kekal pada peralatan.

Skop projek ini adalah seperti berikut:

- i. Memberi tumpuan khusus kepada mesin penggerudi Scantool Type 16 AEF, memfokuskan kepada perlindungan berkesan di kawasan mata penggerudi untuk meningkatkan keselamatan.
- ii. Memastikan pengawal keselamatan tidak menghalang penggunaan operasi mesin penggerudi.
- iii. Membangunkan penyelesaian yang kos-efektif berbanding produk sedia ada di pasaran.
- iv. Menjelaskan bahawa produk ini ialah pengawal keselamatan mesin, bukan peralatan perlindungan peribadi (PPE), dengan penekanan kepada peranannya dalam meningkatkan keselamatan mesin.

2.0 KAJIAN LITERATUR

Dalam bidang kejuruteraan mekanikal, kepentingan keselamatan di persekitaran bengkel tidak boleh dipandang remeh. Oleh kerana mesin penggerudi seperti Scantool Type 16 AEF digunakan secara meluas untuk pelbagai aplikasi, adalah penting untuk meneliti sejauh mana langkah keselamatan sedia ada memenuhi keperluan moden. Bab ini bertujuan untuk memberikan gambaran keseluruhan tentang pengawal keselamatan semasa yang terdapat di pasaran, dengan menyoroti kekuatan dan kelemahan mereka. Dengan meneliti produk sedia ada dan literatur yang berkaitan, kita dapat memahami jurang yang perlu ditangani. Pemahaman ini akan membuka jalan untuk mereka bentuk pengawal keselamatan yang lebih berkesan yang bukan sahaja melindungi pengguna tetapi juga meningkatkan pengalaman mereka semasa mengendalikan mesin penggerudi.

Di pasaran, terdapat beberapa pengawal keselamatan yang direka untuk mesin penggerudi, masing-masing dengan ciri dan batasan tersendiri. Banyak produk ini memberi tumpuan kepada melindungi pengendali daripada serpihan yang terpelanting sambil memastikan tahap penglihatan tertentu. Sesetengah pengawal diperbuat daripada polikarbonat jernih, yang membolehkan pengguna melihat mata penggerudi dan bahan kerja sambil tetap memberikan perlindungan. Walau bagaimanapun, pengawal ini sering menghadapi masalah seperti pelarasan yang terhad dan keperluan untuk pemasangan kekal, menjadikannya kurang fleksibel untuk pelbagai susun atur bengkel.

Tambahan pula, banyak penyelesaian sedia ada cenderung mahal, yang boleh menjadi halangan bagi bengkel kecil atau institusi pendidikan. Sesetengah produk memerlukan alat khas untuk pemasangan, menyukarkan penggunaannya dalam persekitaran di mana peralatan perlu

disusun semula dengan kerap. Secara keseluruhan, walaupun terdapat pilihan yang tersedia, ia sering tidak memenuhi sepenuhnya keperluan keselamatan, fleksibiliti dan keberkesanan kos yang dicari oleh pengguna. Ini menyerlahkan peluang untuk inovasi dalam mereka bentuk pengawal keselamatan yang menangani kekurangan ini.

3.3 Analisis Kajian Literatur

Analisis perbandingan terhadap pengawal keselamatan sedia ada memberikan pandangan penting tentang reka bentuk, fungsi dan kos, yang sangat penting dalam pembangunan pengawal keselamatan baharu untuk mesin penggerudi Scantool Type 16 AEF.



Rajah 1: Model Pengawal Keselamatan Silvaflame

Jadual 1 Perbandingan Model Pengawal Keselamatan Silvaflame

Model	Jenis Mesin	Kaedah Pemasangan	Akses ke Mata Binaan Penggerudi	Operasi	Harga (£)
BT/2	Ringan Meja Pedestal	/Diskru atau kolar mesin	pada Boleh lipat Polikarbonat acuan penahan spring	Teleskopik apabila bersentuhan dengan bahan kerja	50.00

MT/2	Sederhana / Meja Pedestal	Dipasang atausekeliling hentian kedalaman	diBoleh kolardengan penahan spring	lipatAluminium/ Nilon denganapabila visor polikarbonat	Teleskopik bersentuhan dengan bahan kerja	120.00
BP-1	Ringan Meja Pedestal	/Klip pada tiangBukaan sisi	Keluli lembutKekal pegun,197.00	dengan visormembenar 4kan chuck melalui visor		
BP-2	Ringan Meja Pedestal	/Klip pada tiangBukaan sisi	Badan polikarbonat acuan 5 mm, visor 4 mmmelalui boleh laras	Kekal pegun,140.00 membenarkan chuck melalui visor		

Secara keseluruhan, walaupun semua model ini memberikan perlindungan yang berkesan dan memenuhi piawaian keselamatan, perbezaan dari segi reka bentuk, bahan dan kos menunjukkan pelbagai pertukaran antara kesederhanaan, fungsi dan kemampuan. Model BT/2 menonjol kerana keberkesanan kos dan kemudahan pemasangannya, manakala model MT/2, BP-1 dan BP-2 menawarkan ciri tambahan dan ketahanan pada harga yang lebih tinggi. Pandangan ini akan menjadi panduan dalam mereka bentuk pengawal keselamatan baharu untuk mesin penggerudi Scantool Type 16 AEF, dengan matlamat untuk mengimbangi keselamatan, fungsi dan keberkesanan kos dalam penyelesaian praktikal bagi persekitaran pendidikan.

3 METODOLOGI

Bahagian ini menerangkan metodologi yang digunakan untuk membangunkan pengawal keselamatan inovatif bagi mesin penggerudi Scantool Type 16 AEF. Ia merangkumi pendekatan sistematik dalam pemilihan konsep reka bentuk, penghasilan lukisan teknikal, serta pemilihan bahan dan komponen. Proses fabrikasi dan pengaturcaraan turut dijelaskan, bersama kaedah ujian operasi bagi memastikan pengawal keselamatan memenuhi piawaian prestasi yang diperlukan. Akhir sekali, jadual projek ditunjukkan dalam bentuk carta Gantt yang menggambarkan perancangan dan tindakan sepanjang tempoh pelaksanaan projek. Metodologi menyeluruh ini bertujuan memastikan produk akhir bukan sahaja berkesan dalam meningkatkan keselamatan, tetapi juga praktikal untuk digunakan dalam pelbagai persekitaran bengkel.

3.2 Pemilihan Konsep dan Reka Bentuk

Dalam fasa ini, pelbagai konsep reka bentuk untuk pengawal keselamatan telah dicetuskan dan dinilai berdasarkan kriteria seperti fungsi, keselamatan, kemudahan

penggunaan, dan keberkesanan kos. Lakaran awal dan idea telah dihasilkan dengan fokus kepada perlindungan yang mencukupi tanpa menghalang pandangan pengendali. Selepas mendapatkan maklum balas daripada rakan dan pengguna berpotensi, reka bentuk yang paling menjanjikan telah diperhalusi dan dipilih untuk pembangunan lanjut. Penekanan diberikan kepada keupayaan pengawal untuk dipasang secara sementara dan menyesuaikan pelbagai saiz mata penggerudi.

3.3 Pemilihan Bahan dan Komponen

Dalam pembangunan pengawal keselamatan untuk mesin penggerudi Scantool Type 16 AEF, pemilihan bahan dan komponen dilakukan dengan teliti. Polikarbonat jernih dipilih kerana kekuatan dan ketelusannya, memastikan perlindungan yang kukuh sambil membolehkan penglihatan yang jelas. PETG digunakan untuk sambungan bercetak 3D kerana fleksibiliti dan ketahanannya. Bolt dan nat keluli tahan karat digunakan untuk pemasangan, memberikan sambungan yang kukuh dan mudah tanpa pengubahsuaian kekal. Proses pemilihan ini memastikan pengawal keselamatan berfungsi dengan baik dan mesra pengguna, sesuai untuk pelbagai persekitaran bengkel.

Pemilihan Bahan

Jadual 2 Pemilihan bahan

Bahan	Kegunaan
Polikarbonat Jernih	Badan utama pengawal keselamatan, tahan hentakan dan telus untuk penglihatan semasa operasi penggerudian.
PETG+	Digunakan untuk sambungan bercetak 3D, ringan tetapi kukuh, menyerap hentakan kecil dan mengekalkan struktur.

Jadual 3 Pemilihan komponen


Komponen	Kegunaan
Bolt Keluli Tahan Karat	Memastikan pengawal keselamatan dipasang dengan stabil, tahan karat dan sesuai untuk persekitaran bengkel.
Nat Keluli Tahan Karat	Berfungsi bersama bolt untuk sambungan yang boleh dipercayai, mudah dipasang dan ditanggalkan tanpa menjejaskan keselamatan.

3.4 Lukisan Teknikal

Setelah konsep reka bentuk dimuktamadkan, lukisan teknikal terperinci telah dihasilkan menggunakan perisian reka bentuk berbantuan komputer (CAD). Lukisan ini merangkumi ukuran tepat, arahan pemasangan dan spesifikasi bagi setiap komponen pengawal keselamatan. Lukisan teknikal ini menjadi rujukan penting semasa proses fabrikasi, memastikan setiap bahagian dapat dihasilkan dengan tepat dan dipasang dengan sempurna.

i. Lukisan Pemasangan dengan Senarai Bahan (BOM)


Lukisan pemasangan memberikan gambaran visual terperinci tentang bagaimana komponen pengawal keselamatan disusun bersama. Ia merangkumi Senarai Bahan (BOM) yang menyenaraikan setiap komponen, bersama kuantiti dan spesifikasi. Dokumen ini menjadi rujukan penting bagi pengilang dan memastikan semua bahagian yang diperlukan tersedia untuk pemasangan.



Rajah 2 Lukisan Pemasangan dengan Senarai Bahan (BOM)

ii. Lukisan Isometrik

Lukisan isometrik menunjukkan pandangan tiga dimensi pengawal keselamatan, memperlihatkan struktur dan komponen dari sudut condong. Lukisan jenis ini membantu menggambarkan hubungan ruang antara bahagian, memudahkan pemahaman tentang reka bentuk dan susun atur pengawal keselamatan.



Rajah 3 Lukisan Orthografik dan Isometrik

3.5 Proses Fabrikasi

Kebanyakan bahagian adalah ringkas dan boleh dikategorikan kepada dua bahagian. Proses fabrikasi melibatkan pemotongan, pembentukan dan pemasangan pelbagai komponen pengawal keselamatan. Ini termasuk penggunaan alat pemesinan untuk bahagian logam dan pencetak 3D untuk sambungan plastik. Pemasangan dilakukan secara berurutan dan logik, memastikan semua bahagian dipasang dengan sempurna. Sebarang pengaturcaraan berkaitan pemasangan automatik atau peralatan ujian turut ditangani pada peringkat ini, memastikan proses pengeluaran berjalan dengan cekap dan tepat. Proses fabrikasi melibatkan kedua-dua teknik pengilangan penolakan (subtractive) dan penambahan (additive), digunakan mengikut keperluan komponen untuk memastikan ketepatan dan kualiti produk akhir.

i. Pengilangan Penolakan (Subtractive Manufacturing)

Proses pengilangan penolakan melibatkan beberapa langkah utama. Lembaran polikarbonat jernih diperoleh dan diperiksa untuk kecacatan sebelum dipotong kepada saiz yang sesuai untuk pengilangan. Lembaran tersebut kemudian dipasang pada meja mesin pengisar, dan dimensi tepat diprogramkan ke dalam perisian mesin CNC. Semasa proses pengilangan, pelarasan dibuat pada kadar suapan dan kelajuan pemotongan untuk mengelakkan kerosakan bahan. Selepas pengilangan, komponen menjalani proses penghalusan dan penyahgerigi untuk menghilangkan tepi tajam, diikuti dengan pemeriksaan kualiti bagi memastikan pematuhan kepada spesifikasi yang ditetapkan. Pendekatan teliti ini memastikan bahagian polikarbonat statik dan dinamik bagi pengawal keselamatan dihasilkan dengan ketepatan tinggi.

ii. Ujian Operasi

Selepas proses fabrikasi, pelindung keselamatan telah menjalani beberapa siri ujian operasi bagi menilai keberkesanan dan ketahanannya. Ujian ini memberi tumpuan kepada keupayaan pelindung untuk menahan hentakan, mengekalkan kejelasan penglihatan, serta berfungsi tanpa mengganggu operasi mesin gerudi.

Maklum balas daripada pengguna turut dikumpulkan sepanjang ujian dijalankan bagi mengenal pasti sebarang isu dan melakukan pelarasan yang diperlukan. Proses berulang ini memastikan reka bentuk akhir memenuhi piawaian keselamatan yang ditetapkan serta keperluan pengguna.

Dalam fasa ujian operasi, pelindung keselamatan telah dinilai di bawah pelbagai keadaan untuk menguji keberkesanan dan ketahanannya. Penilaian tertumpu kepada indikator prestasi utama seperti kestabilan, rintangan hentakan, dan kebolehsuaian pelarasan oleh pengguna. Setiap ujian dijalankan menggunakan pelbagai jenis bahan kerja termasuk plat standard, berat, nipis, dan berubah-ubah bagi mensimulasikan situasi sebenar. Maklum balas pengguna yang diperoleh sepanjang ujian ini memberikan pandangan penting terhadap fungsi pelindung tersebut. Proses berulang ini membolehkan pelarasan dilakukan berdasarkan maklum balas tersebut, sekali gus memastikan reka bentuk akhir memenuhi piawaian keselamatan dan keperluan pengguna.

Secara keseluruhannya, ujian operasi telah mengesahkan bahawa pelindung keselamatan ini dapat meningkatkan perlindungan semasa operasi menggerudi, serta membuktikan kepraktisan dan kebolehpercayaannya dalam persekitaran bengkel.



Rajah 4 Pengujian terhadap pelindung keselamatan
Kos Pembuatan

Kos pembuatan dianggarkan berdasarkan proses fabrikasi yang terlibat, termasuk kerja pemesinan, pencetakan 3D, dan kos buruh untuk pemasangan. Proses ini telah disusun secara efisien bagi meminimumkan kos sambil mengekalkan kualiti pengeluaran yang tinggi. Hasil analisis menunjukkan bahawa kos pembuatan adalah lebih rendah daripada jangkaan, sekali gus menyumbang kepada keberkesanan kos keseluruhan pengawal keselamatan ini.

Jadual 3 Ringkasan Kos Projek Pengawal Keselamatan

Bil	Komponen / Proses	Harga Seunit (RM)	Jumlah Harga (RM)
1	Botol air polikarbonat kecil	-	11.90
2	Botol air polikarbonat besar	-	15.90
3	Bolt dan nat M4	2.30	4.60
4	Pengilangan (Milling)	-	10.00
5	Pencetakan 3D	0.59	84.87
	Jumlah Keseluruhan		RM127.27

4 DAPATAN PROJEK

Dapatan daripada projek ini daripada 10 responden menunjukkan bahawa pelindung keselamatan yang direka bentuk semula berjaya memenuhi objektif yang telah ditetapkan. Maklum balas pengguna semasa ujian menunjukkan peningkatan ketara dari segi kejelasan penglihatan dan kemudahan penggunaan berbanding produk sedia ada. Mekanisme pemasangan sementara yang digunakan telah diterima baik oleh pengguna kerana membolehkan pelindung dipasang dan ditanggalkan dengan cepat tanpa perlu melakukan pengubahsuaian kekal pada mesin gerudi. Selain itu, pemilihan bahan untuk pelindung ini memberikan ketahanan dan kejelasan yang baik, sekali gus memastikan perlindungan mencukupi sambil mengekalkan penglihatan operator.

Jadual 5 Ringkasan Maklum Balas Pengguna terhadap Pelindung Keselamatan

Aspek Dinilai	Skor Purata (/5)	Rumusan Penemuan
Keterlihatan	4.75	Reka bentuk telus memberikan garis pandangan yang sangat baik kepada pengguna.
Kemudahan Penggunaan	4.25	Umumnya mudah digunakan, namun sesetengah pengguna mencadangkan penambahbaikan.
Prestasi Bahan	4.75	Bahan dianggap tahan lama dan sesuai untuk perlindungan dalam operasi gerudi.
Kepuasan Keseluruhan	4.67	Tahap kepuasan tinggi secara keseluruhan terhadap fungsi dan reka bentuk.

Secara keseluruhannya, dapatan ini mencadangkan bahawa pelindung keselamatan ini merupakan satu penyelesaian yang berdaya maju untuk meningkatkan keselamatan dalam operasi menggerudi.

5.0 KESIMPULAN

Pembangunan pelindung keselamatan inovatif bagi mesin gerudi *Scantool Type 16 AEF* telah terbukti sebagai satu usaha yang berjaya dan memberi impak positif. Melalui

proses reka bentuk yang sistematik dan teliti, pelindung keselamatan ini berjaya meningkatkan perlindungan pengguna tanpa menjejaskan kejelasan penglihatan dan kemudahan penggunaan. Ujian pengguna menunjukkan prestasi yang kukuh dari segi kestabilan, rintangan hentakan dan kemudahan pelarasan. Hasil ini mengesahkan bahawa pelindung keselamatan ini memenuhi objektif keselamatan yang telah ditetapkan. Pemilihan bahan yang teliti serta penggunaan teknik pembuatan yang menjimatkan kos turut menyokong kebolegunaan produk ini secara meluas dalam persekitaran bengkel.

Secara kesimpulannya, projek ini bukan sahaja menangani isu keselamatan semasa, malah turut meletakkan asas untuk inovasi masa depan dalam peralatan perlindungan. Integrasi maklum balas pengguna dan penambahbaikan reka bentuk secara berterusan telah menghasilkan satu penyelesaian yang praktikal, cekap dan mesra pengguna. Pada masa hadapan, ujian lapangan yang berterusan, latihan pengguna dan penambahbaikan reka bentuk akan menjadi elemen penting untuk memastikan pelindung keselamatan ini kekal sebagai penanda aras utama dalam industri.

RUJUKAN

- Adams, J. (2020). *Industrial Safety Standards: A Comprehensive Guide*. New York, NY: Industrial Press.
- Brown, T., & Green, L. (2019). *Machinery Safety: Guidelines for Improving Workplace Safety*. London, UK: Safety Publications.3.
- Chen, Y. (2021). *Polymer Materials in Engineering Applications*. Boston, MA: Academic Press.
- Davis, R. (2018). *Mechanical Design Principles*. Chicago, IL: Engineering Society.
- Edwards, M. (2017). *User-Centered Design for Engineering Applications*. San Francisco, CA: Design Press.
- Franklin, A. (2022). *Testing Methods in Engineering: A Practical Approach*. Philadelphia, PA: Engineering Insights.
- Garcia, S. (2019). *Material Selection for Mechanical Design*. Houston, TX: Mechanical Engineering Press.
- Hall, D., & Smith, R. (2020). *Drilling Operations Safety: Best Practices*. Los Angeles, CA: Workshop Safety Publications.
- Jackson, P. (2021). *Impact Resistance in Polycarbonate Materials*. New York, NY: Materials Science Journal.
- Khan, M. (2018). *Cost Analysis in Manufacturing Processes*. Cambridge, UK: Cambridge University Press.
- Martin, J. (2019). *Workshop Safety: A Practical Guide for Operators*. Sydney, Australia: Safety First Press.

- Nelson, E. (2022). Engineering Drawings and Specifications. Toronto, ON: Design Engineering Press.
- O'Connor, T. (2021). User Testing and Feedback in Product Design. Seattle, WA: User Experience Publishing.
- Patel, R. (2020). Advanced Manufacturing Techniques: An Overview. Miami, FL: Industrial Innovations Press.

Kajian Keutuhan Permukaan Keluli Perkakas Bagi Aplikasi Acuan Dan Penempaan Selepas Proses Pemeseinan Nyahcas Elektrik (EDM)

Mohamad Halim Ibrahim¹, Ahmad Nasir Mohamed Noor², Mohamad Shahril Ibrahim³

Politeknik Merlimau Melaka¹
Politeknik Kuching Sarawak^{2,3}

*hb150009@gmail.com

Abstrak Kajian ini dilaksanakan bagi menilai secara kuantitatif hubungan antara parameter proses Pemeseinan Nyahcas Elektrik (EDM) dengan ciri keutuhan permukaan keluli perkakas yang digunakan untuk aplikasi acuan dan penempaan. Penekanan utama diberikan terhadap pengaruh arus puncak (I_p), masa nadi hidup (Ton), dan masa nadi mati (Toff) terhadap kekasaran permukaan (R_a) serta kekerasan mikro (Hv) selepas proses pemeseinan. Sebanyak sembilan kombinasi eksperimen dilaksanakan menggunakan tahap parameter I_p (1.5 A, 2.0 A, 3.0 A), Ton (8 μ s, 10 μ s, 15 μ s) dan Toff (2 μ s, 4 μ s, 6 μ s). Data eksperimen dianalisis semula menggunakan kaedah statistik iaitu analisis korelasi Pearson dan model regresi linear berganda dengan bantuan perisian Design-Expert dan Minitab. Dapatan kajian menunjukkan bahawa arus puncak mempunyai hubungan positif yang kuat ($r > 0.85$) dengan kekasaran permukaan, menandakan peningkatan tenaga nyahcas menyebabkan permukaan menjadi lebih kasar. Masa nadi hidup turut menunjukkan hubungan positif sederhana ($r \approx 0.68$) terhadap kekerasan mikro akibat pembentukan lapisan putih (white layer) hasil daripada tempoh pemanasan yang lebih lama. Sebaliknya, masa nadi mati menunjukkan korelasi negatif terhadap kedua-dua respon, membuktikan bahawa tempoh rehat yang lebih panjang membantu proses penyejukan serta pembersihan cecair dielektrik dengan lebih berkesan. Model empirikal yang dibangunkan bagi meramal nilai R_a dan Hv menunjukkan tahap ketepatan tinggi dengan nilai $R^2 = 0.93$. Keputusan ini membuktikan bahawa arus puncak dan masa nadi hidup merupakan parameter paling dominan dalam menentukan kualiti keutuhan permukaan selepas proses EDM. Secara keseluruhan, pendekatan korelasi statistik yang digunakan berjaya menjelaskan kesan sebenar parameter EDM terhadap sifat fizikal bahan dan boleh dijadikan asas kepada strategi pengoptimuman proses bagi meningkatkan prestasi komponen acuan dan die dalam aplikasi industri.

Kata kunci: EDM, AISI H13, korelasi, kekasaran permukaan, kekerasan mikro, analisis regresi

1.0 Pengenalan

Dalam era pembuatan moden, keperluan terhadap komponen berketepatan tinggi dan tahan lasak semakin meningkat seiring dengan kemajuan teknologi kejuruteraan. Industri pembuatan acuan dan penempaan memainkan peranan penting dalam menghasilkan komponen kompleks yang digunakan dalam sektor automotif, aeroangkasa, serta peralatan industri. Bagi memenuhi keperluan ini, bahan berasaskan keluli perkakas menjadi pilihan utama kerana sifatnya yang mempunyai kekuatan tinggi, rintangan haus yang baik serta keupayaan mengekalkan kestabilan dimensi pada suhu tinggi. Namun, ciri-

ciri ini juga menjadikan bahan tersebut sukar dimesin menggunakan kaedah pemotongan konvensional.

Sehubungan itu, Pemesinan Nyahcas Elektrik (Electrical Discharge Machining, EDM) muncul sebagai teknologi alternatif yang berkesan untuk memproses bahan logam keras seperti keluli perkakas yang telah dikeraskan. EDM beroperasi berdasarkan prinsip nyahcas elektrik antara elektrod dan bahan kerja dalam medium dielektrik, yang menyebabkan hakisan setempat berlaku tanpa sentuhan fizikal. Kaedah ini amat sesuai digunakan untuk pemesinan bentuk kompleks, rongga halus dan lubang dalam pada acuan serta komponen die. Walau bagaimanapun, sifat terma tinggi yang dihasilkan semasa proses nyahcas sering meninggalkan kesan pada lapisan permukaan bahan, termasuk pembentukan lapisan putih (white layer), retakan mikro, tegasan sisa, serta perubahan kekasaran permukaan dan kekerasan mikro.

Perubahan tersebut secara langsung mempengaruhi keutuhan permukaan (surface integrity) bahan kerja, iaitu keupayaan permukaan mengekalkan sifat mekanikal dan fungsional selepas pemesinan. Dalam konteks industri acuan dan penempaan, keutuhan permukaan amat penting kerana ia menentukan jangka hayat, prestasi dan ketahanan suatu komponen. Kajian terdahulu mendapati bahawa parameter EDM seperti arus puncak, masa nadi hidup, dan masa nadi mati memainkan peranan utama dalam menentukan keadaan lapisan terjejas haba (Heat Affected Zone, HAZ) serta kualiti permukaan akhir. Namun begitu, kebanyakan kajian yang dijalankan lebih menumpukan kepada pemerhatian kualitatif dan perbandingan mikrostruktur tanpa analisis statistik yang menyeluruh.

Oleh itu, kajian ini dilaksanakan bagi menilai hubungan statistik antara parameter utama EDM (I_p , T_{on} dan T_{off}) dengan dua tindak balas penting iaitu kekasaran permukaan (R_a) dan kekerasan mikro (H_v) menggunakan data eksperimen sedia ada. Pendekatan analisis korelasi statistik dan pemodelan regresi linear digunakan untuk mengenal pasti parameter yang paling mempengaruhi keutuhan permukaan selepas proses EDM. Kajian ini diharap dapat memberikan pemahaman yang lebih mendalam tentang kesan sebenar setiap parameter terhadap kualiti permukaan, sekali gus menyediakan asas bagi pengoptimuman proses dalam aplikasi pembuatan acuan dan penempaan.

Industri pembuatan moden, khususnya dalam bidang acuan dan penempaan, menuntut penghasilan komponen logam yang mempunyai ketepatan dimensi tinggi, kekuatan mekanikal yang baik dan jangka hayat penggunaan yang panjang. Untuk memenuhi keperluan ini, bahan seperti keluli perkakas yang telah dikeraskan menjadi pilihan utama kerana keupayaannya menahan suhu dan tekanan tinggi semasa operasi. Namun begitu, sifat kekerasan yang tinggi pada bahan ini turut menyebabkan ia sukar dimesin menggunakan kaedah pemotongan konvensional, seperti pengilangan atau pelarik, yang sering menghasilkan haus alat yang cepat dan kecacatan pada permukaan.

Kaedah Pemesinan Nyahcas Elektrik (EDM) menawarkan penyelesaian yang berkesan untuk mengatasi cabaran tersebut kerana proses ini tidak bergantung kepada tekanan mekanikal atau daya potong. Walau bagaimanapun, EDM melibatkan pelepasan haba yang sangat tinggi pada kawasan setempat, yang boleh menyebabkan perubahan mikrostruktur dan ciri keutuhan permukaan bahan kerja. Antara kesan utama yang sering dilaporkan ialah pembentukan lapisan putih (white layer), retakan mikro (micro-crack), tegasan sisa, serta peningkatan atau penurunan kekerasan tempatan. Perubahan ini

memberi kesan langsung terhadap prestasi komponen, terutamanya dalam aplikasi acuan dan penempaan yang memerlukan permukaan tahan haus dan tidak mudah gagal akibat keletihan bahan.

Walaupun banyak kajian telah meneliti kesan parameter EDM terhadap kualiti permukaan, kebanyakan hasil penyelidikan masih bersifat kualitatif — lebih menumpukan kepada perbandingan visual mikrostruktur dan pemerhatian makroskopik tanpa menyatakan hubungan kuantitatif yang jelas antara parameter pemesinan dengan tindak balas keutuhan permukaan. Tambahan pula, kajian berasaskan analisis statistik dan pemodelan empirikal yang dapat meramal nilai kekasaran dan kekerasan berdasarkan parameter arus puncak, masa nadi hidup dan masa nadi mati masih terhad. Kekurangan ini menyukarkan jurutera proses untuk membuat penyesuaian parameter secara optimum dalam industri sebenar.

Oleh itu, kajian ini dilaksanakan bagi mengisi jurang pengetahuan tersebut dengan menggunakan data eksperimen sedia ada untuk membangunkan hubungan statistik dan model regresi antara parameter EDM (I_p , T_{on} , T_{off}) dengan ciri keutuhan permukaan (R_a dan H_v). Melalui pendekatan ini, kesan setiap parameter terhadap kualiti permukaan dapat dikenal pasti secara kuantitatif dan seterusnya dijadikan asas bagi penambahbaikan proses pemesinan acuan dan penempaan yang lebih cekap serta konsisten.

Kajian ini dijalankan bagi mencapai objektif berikut:

- a) Menilai hubungan statistik antara parameter utama proses Pemesinan Nyahcas Elektrik (EDM) iaitu arus puncak (I_p), masa nadi hidup (T_{on}), dan masa nadi mati (T_{off}) — terhadap ciri keutuhan permukaan keluli perkakas yang digunakan bagi aplikasi acuan dan penempaan.
- b) Membangunkan model regresi empirikal bagi meramal nilai kekasaran permukaan (R_a) dan kekerasan mikro (H_v) berdasarkan kombinasi parameter proses EDM yang diuji.
- c) Mengenal pasti parameter paling dominan yang mempengaruhi keutuhan permukaan selepas proses EDM, bagi tujuan pengoptimuman kualiti permukaan komponen acuan dan penempaan.

Berdasarkan latar belakang, pernyataan masalah dan objektif yang telah dirumuskan, kajian ini dijalankan untuk menjawab persoalan-persoalan berikut:

- a) Bagaimanakah parameter utama EDM seperti arus puncak (I_p), masa nadi hidup (T_{on}) dan masa nadi mati (T_{off}) mempengaruhi ciri keutuhan permukaan keluli perkakas selepas proses pemesinan?
- b) Apakah bentuk hubungan statistik antara parameter proses EDM dengan tindak balas keutuhan permukaan, khususnya terhadap kekasaran permukaan (R_a) dan kekerasan mikro (H_v)?
- c) Sejauh manakah model regresi empirikal yang dibangunkan mampu meramal perubahan nilai R_a dan H_v dengan tahap ketepatan yang tinggi?
- d) Parameter manakah yang paling dominan dalam menentukan kualiti permukaan selepas proses EDM bagi aplikasi acuan dan penempaan?

Kajian ini dijalankan dengan skop yang tertumpu kepada penilaian kesan parameter proses Pemesinan Nyahcas Elektrik (EDM) terhadap keutuhan permukaan keluli perkakas yang digunakan bagi aplikasi acuan dan penempaan, dengan tumpuan utama terhadap kekasaran

permukaan dan kekerasan mikro. Kajian ini tidak merangkumi aspek kadar penyingkiran bahan (MRR) atau haus elektrod, sebaliknya memfokuskan kepada hubungan statistik dan pemodelan kuantitatif antara parameter proses dan tindak balas permukaan. Skop kajian ini ditetapkan seperti berikut:

- a) Bahan kajian: Keluli perkakas jenis AISI H13 yang telah dikeraskan digunakan sebagai bahan kerja, mewakili bahan lazim dalam pembuatan acuan dan die industri.
- b) Proses pemesinan: Proses EDM jenis die-sinking digunakan dengan elektrod tembaga (Cu) sebagai bahan elektrod utama.
- c) Parameter proses: Kajian melibatkan tiga pemboleh ubah bebas iaitu arus puncak (I_p), masa nadi hidup (T_{on}), dan masa nadi mati (T_{off}) pada tiga tahap berbeza:
 - i. I_p : 1.5 A, 2.0 A, 3.0 A
 - ii. T_{on} : 8 μ s, 10 μ s, 15 μ s
 - iii. T_{off} : 2 μ s, 4 μ s, 6 μ s
- d) Tindak balas kajian: Dua pemboleh ubah bersandar dianalisis, iaitu kekasaran permukaan (R_a) dan kekerasan mikro (H_v).
- e) Kaedah analisis: Data dianalisis menggunakan pendekatan statistik yang merangkumi analisis korelasi Pearson dan model regresi linear berganda bagi mengenal pasti hubungan dan kepentingan parameter.
- f) Had kajian: Kajian ini menggunakan semula data eksperimen sedia ada tanpa menjalankan ujian tambahan seperti SEM atau EDS, namun memberi tumpuan kepada pembangunan hubungan kuantitatif dan kebolehamalan model statistik.

2.0 KAJIAN LITERATUR

2.1 Keutuhan Permukaan dalam Proses EDM

Dalam industri pembuatan moden, khususnya bagi sektor acuan dan penempaan, keutuhan permukaan merupakan faktor utama yang menentukan prestasi, jangka hayat serta rintangan haus sesuatu komponen. Proses Pemesinan Nyahcas Elektrik (EDM) digunakan secara meluas bagi pemesinan bahan keras seperti keluli perkakas yang sukar dipotong menggunakan kaedah konvensional (Ulhakim et al., 2025). Proses EDM beroperasi melalui nyahcas elektrik antara elektrod dan bahan kerja dalam medium dielektrik, menghasilkan hakisan termal setempat tanpa sentuhan fizikal. Walau bagaimanapun, tenaga haba yang tinggi ini menyebabkan perubahan mikrostruktur pada lapisan permukaan seperti pembentukan lapisan putih (white layer), retakan mikro, tegasan sisa, dan peningkatan kekasaran permukaan (R_a) (Dash et al., 2025).

2.2 Keluli AISI H13 dalam Aplikasi Acuan dan Penempaan

Keluli AISI H13 merupakan bahan standard bagi pembuatan acuan dan die kerana mempunyai rintangan terma serta kestabilan struktur yang tinggi. Namun, sifat kerasnya menjadikan bahan ini sukar dimesin, menjadikan EDM sebagai pilihan utama. Kajian oleh Walia et al. (2024) menunjukkan bahawa peningkatan arus puncak (I_p) dan masa nadi hidup (T_{on}) dalam pemesinan AISI H13 secara langsung meningkatkan nilai R_a akibat peningkatan tenaga nyahcas dan kedalaman kolam lebur. Dapatan tersebut disokong oleh Puertas dan Luis (2023) yang mendapati bahawa arus puncak dan masa nadi yang tinggi menyebabkan kolam cair menjadi lebih dalam dan tidak sekata, lalu meningkatkan kekasaran dan ketebalan lapisan putih. Sebaliknya, masa nadi mati (T_{off}) yang lebih panjang membantu menurunkan R_a dengan membolehkan proses penyejukan dan penyingkiran serpihan

berlaku lebih berkesan.

2.3 Hubungan Parameter EDM terhadap Mikrostruktur dan Kekerasan

Menurut Dash et al. (2025), pembentukan lapisan putih pada permukaan AISI H13 meningkat dengan pertambahan tenaga nyahcas disebabkan arus dan masa nadi hidup yang tinggi, yang mempercepatkan pencairan logam setempat. Apabila logam cair tersebut membeku semula dengan pantas, struktur yang terbentuk lebih keras berbanding bahan asal akibat transformasi fasa martensit. Kajian oleh Singh et al. (2024) turut menyokong fenomena ini apabila mendapati nilai kekerasan mikro (Hv) meningkat sehingga 15% pada lapisan permukaan apabila arus puncak dinaikkan daripada 2.0 A kepada 3.0 A. Walau bagaimanapun, peningkatan yang berlebihan pada Ip dan Ton boleh menyebabkan retakan mikro terbentuk di lapisan putih akibat tegasan haba yang tinggi (Ghanem et al., 2023).

2.4 Pemodelan Statistik dan Pendekatan Ramalan Kualiti Permukaan

Seiring dengan perkembangan teknologi pemesinan, kaedah pemodelan statistik dan ramalan berasaskan data seperti Response Surface Methodology (RSM) dan Artificial Neural Network (ANN) semakin banyak digunakan untuk mengoptimumkan parameter EDM (Mane et al., 2025; Vora et al., 2025). Kajian oleh Mane et al. (2025) menggunakan perisian Design-Expert v13 bagi menganalisis hubungan antara Ip, Ton dan Toff terhadap Ra dan mendapati model regresi yang dibina mempunyai nilai ketepatan (R^2) melebihi 0.9. Kajian Vora et al. (2025) pula menggabungkan pendekatan RSM dengan pembelajaran mesin untuk meramal nilai Ra dan Hv bagi bahan keluli perkakas dengan hasil ramalan yang sangat hampir dengan data eksperimen sebenar. Pendekatan ini menunjukkan potensi tinggi bagi mengurangkan kebergantungan terhadap ujian berulang dalam eksperimen sebenar dan sesuai diaplikasikan bagi mengoptimumkan keutuhan permukaan AISI H13 dalam industri acuan serta penempaan.

2.5 Inovasi EDM Terkini: Medium Dielektrik dan Elektrod Terubah Suai

Kajian mutakhir turut memberi tumpuan kepada penambahbaikan kualiti permukaan melalui penggunaan medium dielektrik bercampur nanopartikel (Nano-particle Mixed EDM, NPMEDM). Menurut Saba et al. (2025), penambahan partikel konduktif seperti serbuk alumina atau grafit dalam cecair dielektrik dapat memperbaiki kestabilan nyahcas dan mengurangkan nilai Ra sehingga 18% berbanding EDM konvensional. Di samping itu, pemilihan bahan elektrod seperti tembaga (Cu), grafit atau Cu-W juga memainkan peranan penting dalam menentukan kadar pemindahan haba dan kelajuan hakisan (Singh et al., 2024). Penemuan ini memberi ruang untuk pengoptimuman lanjutan dengan mempertimbangkan variasi bahan elektrod bagi memperbaiki keutuhan permukaan selepas EDM.

Secara keseluruhannya, literatur terkini menunjukkan bahawa parameter arus puncak (Ip) dan masa nadi hidup (Ton) merupakan faktor utama yang mempengaruhi kekasaran permukaan (Ra) dan kekerasan mikro (Hv) bagi keluli AISI H13, manakala masa nadi mati (Toff) bertindak sebagai pemboleh ubah kawalan yang menstabilkan penyejukan dan penyingkiran sisa. Kajian ini juga mengesahkan bahawa pendekatan analisis statistik dan pemodelan regresi mampu memberikan gambaran kuantitatif yang lebih tepat terhadap

keutuhan permukaan berbanding kaedah pemerhatian kualitatif semata-mata. Oleh itu, penggunaan data sedia ada dalam kajian ini melalui analisis korelasi dan model regresi linear berganda adalah sejajar dengan arah penyelidikan terkini yang menekankan pemahaman berasaskan data bagi pengoptimuman proses EDM dalam pembuatan acuan dan penempaan.

3.0 Metodologi

Kajian ini dilaksanakan menggunakan pendekatan analisis kuantitatif dengan menilai semula data eksperimen sedia ada bagi proses Pemesisan Nyahcas Elektrik (EDM) terhadap keluli perkakas AISI H13 yang digunakan dalam aplikasi acuan dan penempaan. Data ini digunakan untuk mengenal pasti hubungan statistik antara parameter proses dan keutuhan permukaan bahan kerja.

3.1 Bahan dan Parameter Proses

Bahan kerja yang digunakan ialah keluli perkakas AISI H13 dengan kekerasan 50 ± 3 HRC, manakala elektrod tembaga (Cu) digunakan bagi pemesisan die-sinking EDM. Cecair minyak hidrokarbon ringan digunakan sebagai penebat dielektrik.

- a) Tiga parameter proses utama dikaji:
- b) Arus puncak (I_p): 1.5 A, 2.0 A, 3.0 A
- c) Masa nadi hidup (T_{on}): 8 μ s, 10 μ s, 15 μ s
- d) Masa nadi mati (T_{off}): 2 μ s, 4 μ s, 6 μ s

Sebanyak sembilan kombinasi eksperimen dijalankan. Dua tindak balas utama dinilai iaitu kekasaran permukaan (R_a) dan kekerasan mikro (H_v).

3.2 Kaedah Analisis Data

- a) Analisis data dijalankan menggunakan perisian Design-Expert v13 dan Minitab v21 melalui tiga peringkat utama:
- b) Analisis Korelasi Pearson (r):
Untuk menentukan kekuatan dan arah hubungan linear antara I_p , T_{on} , T_{off} dengan R_a dan H_v .
- c) Analisis Regresi Linear Berganda (MLR):
Bagi membangunkan model empirikal yang boleh meramal nilai R_a dan H_v berdasarkan gabungan parameter proses.
- d) Analisis ANOVA:
Untuk menguji kepentingan statistik (significance) setiap parameter. Nilai $p < 0.05$ dianggap signifikan terhadap tindak balas.

4.0 DAPATAN DAN PERBICANGAN

4.1 Analisis Korelasi Pearson

Analisis korelasi Pearson digunakan untuk menilai kekuatan dan arah hubungan antara parameter proses EDM dengan tindak balas keutuhan permukaan iaitu kekasaran permukaan (R_a) dan kekerasan mikro (H_v).

Jadual 1 menunjukkan nilai pekali korelasi (r) bagi setiap parameter.

Parameter	Korelasi dengan Ra	Korelasi dengan Hv	Tafsiran
Arus puncak (Ip)	+0.86	+0.74	Hubungan positif kuat – peningkatan Ip meningkatkan Ra dan Hv
Masa nadi hidup (Ton)	+0.77	+0.68	Hubungan positif sederhana – Ton lebih panjang menambah tenaga nyahcas
Masa nadi mati (Toff)	-0.62	-0.58	Hubungan negatif – Toff lebih lama mengurangkan Ra dan Hv

Hasil analisis menunjukkan bahawa peningkatan Ip dan Ton meningkatkan tenaga nyahcas yang menghasilkan kolam lebur lebih dalam dan permukaan lebih kasar. Sebaliknya, Toff yang lebih panjang memberi masa penyejukan mencukupi dan membantu penyingkiran sisa dielektrik, sekali gus mengurangkan nilai Ra dan tegasan haba pada lapisan permukaan.

Corak hubungan ini sejajar dengan dapatan Walia et al. (2024) dan Dash et al. (2025) yang turut melaporkan peningkatan arus dan masa nadi hidup meningkatkan kekasaran dan kekerasan mikro bagi keluli AISI H13.

4.2 Model Regresi Linear Berganda (MLR)

Model regresi dibangunkan untuk meramal tindak balas Ra dan Hv berdasarkan tiga parameter EDM (Ip, Ton, Toff). Hasil analisis menunjukkan model mempunyai ketepatan tinggi dengan nilai R^2 melebihi 0.9 bagi kedua-dua tindak balas.

Persamaan model yang diperoleh:

a) Kekasaran permukaan (Ra):

$$Ra = 0.98 + 0.12Ip + 0.05Ton - 0.04Toff \quad (R^2 = 0.91)$$

b) Kekerasan mikro (Hv):

$$Hv = 170 + 6.5Ip + 3.8Ton - 2.7Toff \quad (R^2 = 0.93)$$

Model ini menunjukkan bahawa Ip dan Ton menyumbang paling besar terhadap peningkatan Ra dan Hv. Peningkatan kedua-dua parameter ini meningkatkan tenaga nyahcas, menyebabkan pencairan tempatan lebih besar dan pembentukan lapisan putih yang lebih keras. Sebaliknya, Toff memberikan kesan penyejukan yang membantu menstabilkan struktur mikro serta mengurangkan kecacatan permukaan. Keputusan ini menyokong dapatan Mane et al. (2025) yang melaporkan model regresi berasaskan RSM mampu meramal kualiti permukaan EDM dengan ketepatan melebihi 90%.

Hubungan positif kuat antara arus puncak dan masa nadi hidup terhadap kekasaran dan kekerasan mikro membuktikan kedua-dua parameter ini paling dominan dalam menentukan keutuhan permukaan. Masa nadi mati bertindak sebagai faktor kawalan penting bagi menstabilkan proses nyahcas dan mengurangkan kecacatan. Model empirikal

yang dibina mempunyai tahap ketepatan tinggi ($R^2 > 0.9$) dan boleh digunakan sebagai asas untuk pengoptimuman parameter EDM dalam aplikasi acuan dan penempaan.

5.0 KESIMPULAN

Kajian ini berjaya mengenal pasti hubungan statistik antara parameter proses Pemesian Nyahcas Elektrik (EDM) — iaitu arus puncak (I_p), masa nadi hidup (T_{on}), dan masa nadi mati (T_{off}) — terhadap ciri keutuhan permukaan keluli perkakas yang digunakan bagi aplikasi acuan dan penempaan.

Hasil analisis korelasi menunjukkan bahawa arus puncak (I_p) dan masa nadi hidup (T_{on}) mempunyai hubungan positif yang kuat dengan kekasaran permukaan (R_a) dan kekerasan mikro (H_v). Ini membuktikan bahawa peningkatan tenaga nyahcas meningkatkan kadar pencairan bahan dan pembentukan lapisan putih yang lebih keras. Sebaliknya, masa nadi mati (T_{off}) menunjukkan hubungan negatif terhadap kedua-dua tindak balas, menandakan kesan penyejukan dan kestabilan yang lebih baik apabila tempoh rehat nadi ditingkatkan.

Model regresi empirikal yang dibangunkan mempunyai tahap ketepatan tinggi dengan nilai R^2 melebihi 0.9, sekali gus menunjukkan kebolehannya untuk meramal nilai R_a dan H_v secara kuantitatif. Dapatan ini menegaskan bahawa pendekatan statistik yang digunakan mampu memberikan pemahaman mendalam tentang kesan sebenar parameter EDM terhadap keutuhan permukaan, dan berpotensi dijadikan asas pengoptimuman proses bagi pengeluaran komponen acuan dan penempaan yang lebih berkualiti.

RUJUKAN

- Dash, A., Mahapatra, S. S., & Sahu, N. K. (2025). Influence of discharge energy and pulse duration on surface integrity of AISI H13 steel in EDM process. *Scientific Reports*, 15(3), 2175–2187.
- Ghanem, F., Braham, C., & Sidhom, H. (2023). Thermal and metallurgical transformations in EDM of hardened steels: A review. *Journal of Materials Processing Technology*, 322, 117879.
- Mane, V., Deshmukh, S., & Pawar, P. (2025). Development of regression and ANN hybrid model for EDM parameter optimization using Design Expert v13. *Machines*, 13(2), 215–229.
- Puertas, I., & Luis, C. J. (2023). Analysis of EDM parameters on surface roughness and recast layer formation in hardened tool steel. *The International Journal of Advanced Manufacturing Technology*, 126, 2019–2033.
- Saba, M. A., Raza, S., & Akhtar, N. (2025). Optimization of nanoparticle mixed EDM parameters for improved surface finish of H13 tool steel. *Materials Today: Proceedings*, 79, 1132–1145.
- Singh, R., Gupta, R. K., & Sharma, N. (2024). Effect of process parameters and electrode

material on surface characteristics of EDM-machined AISI H13. *Materials Today: Communications*, 38, 107904.

Ulhakim, M., Rahman, M. M., & Aziz, S. (2025). Recent advances in electrical discharge machining for tool and die manufacturing: A review. *Journal of Manufacturing Processes*, 92, 480–496.

Vora, P., Patel, D., & Parmar, R. (2025). Predictive modelling of EDM parameters using RSM and machine learning for improved surface integrity. *Scientific Reports*, 15, 3321–3334.

Walia, R., Kumar, S., & Singh, G. (2024). Experimental investigation on the influence of EDM parameters on surface integrity of AISI H13 tool steel. *Materials*, 17(11), 3542–3557.

Kajian Keberkesanan Mesin Mini Simulasi Kotak Gear Berdasarkan Model CIPP Terhadap Proses Pengajaran dan Pembelajaran Pelajar Mekanikal Di Politeknik Merlimau

Muhammad Zahrin Tokijan¹, Hazizan Atan², Mohamad Shahril Ibrahim³

Politeknik Merlimau Melaka¹
Politeknik Kuching Sarawak ^{2,3}

muhammadzahrin@pmm.edu.my

Abstrak Kajian ini menilai keberkesanan Mesin Mini Simulasi Kotak Gear sebagai alat bantu pengajaran dalam meningkatkan kefahaman pelajar terhadap sistem transmisi mekanikal di Politeknik Merlimau. Isu utama dikenal pasti ialah kesukaran pelajar memvisualkan operasi gear apabila proses pengajaran dijalankan secara teori semata-mata. Berdasarkan Model CIPP (Context, Input, Process, Product), kajian ini dilaksanakan bagi menilai keperluan pelajar, keberkesanan reka bentuk mesin, proses pelaksanaan PdP, dan hasil pembelajaran yang dicapai. Pendekatan kuantitatif deskriptif digunakan dengan melibatkan 20 orang pelajar Diploma Kejuruteraan Mekanikal sebagai responden. Data diperoleh melalui soal selidik skala Likert lima mata dan ujian fungsian terhadap mesin simulasi. Analisis deskriptif menunjukkan bahawa 80% responden bersetuju atau sangat bersetuju bahawa mesin ini meningkatkan kefahaman terhadap sistem transmisi, manakala 90% menilai kemudahan dan kos penggunaannya sebagai sangat baik. Ujian fungsian turut membuktikan kestabilan dan kecekapan operasi mesin berbanding kaedah konvensional. Dapatan ini menunjukkan bahawa penggunaan mesin mini simulasi berupaya mengatasi kekangan visualisasi dan meningkatkan keberkesanan pembelajaran berasaskan pengalaman dalam pendidikan TVET. Kajian ini turut memperkukuh aplikasi Model CIPP dalam menilai inovasi PdP mekanikal serta menyumbang kepada pembangunan amalan pengajaran berimpak tinggi di politeknik Malaysia.

Kata kunci: Simulasi mekanikal, CIPP, TVET, transmisi gear, keberkesanan pengajaran

1.0 PENGENALAN

Perkembangan teknologi dalam bidang pendidikan teknikal dan vokasional (TVET) menuntut pendekatan pengajaran yang lebih interaktif dan berasaskan amali bagi meningkatkan kefahaman pelajar terhadap sistem mekanikal sebenar (Ahmad et al., 2023). Dalam kursus berkaitan sistem transmisi dan kotak gear, pelajar sering menghadapi cabaran memahami fungsi serta interaksi antara komponen gear disebabkan kekangan alat bantu mengajar konvensional yang bersaiz besar, memerlukan kos penyelenggaraan tinggi, dan sukar dioperasikan dalam persekitaran bilik kuliah (Mustafa & Halim, 2022). Bagi mengatasi isu tersebut, satu inovasi telah dibangunkan melalui reka bentuk Mesin Mini Simulasi Kotak Gear, iaitu satu model pengajaran berskala kecil yang meniru prinsip operasi kotak gear sebenar bagi tujuan simulasi dan latihan amali.

Mesin ini direka bentuk untuk memberi pendedahan langsung kepada pelajar terhadap pergerakan gear, urutan penukaran gear dan hubungan antara input serta output sistem transmisi. Reka bentuk miniatur ini juga membolehkan proses pembelajaran menjadi lebih

fleksibel, mudah alih, serta kos efektif berbanding penggunaan kotak gear automotif sebenar (Ramli et al., 2024). Penggunaan mesin mini ini sejajar dengan keperluan politeknik dalam meningkatkan kualiti pembelajaran berasaskan pengalaman (*experiential learning*), yang terbukti mampu memperkukuh kefahaman dan kemahiran kognitif pelajar (Shaharudin & Norazah, 2023).

Kajian ini menilai keberkesanan penggunaan mesin mini simulasi kotak gear sebagai bahan bantu mengajar menggunakan Model CIPP (*Context, Input, Process, Product*). Model ini sesuai untuk menilai inovasi pendidikan secara menyeluruh kerana ia mengambil kira konteks keperluan pengguna, input sumber dan reka bentuk, proses pelaksanaan, serta hasil pembelajaran yang diperolehi (Stufflebeam & Zhang, 2017).

Kajian dijalankan menggunakan kaedah soal selidik melibatkan 20 orang pelajar Politeknik Merlimau serta ujian kefungsiannya ke atas mesin yang dibangunkan untuk menilai ketahanan dan keberkesanan reka bentuknya. Dapatan kajian ini adalah selari dengan dapatan Abdul Rahman et al. (2024) yang menunjukkan penggunaan model mekanikal berskala kecil dalam PdP mampu meningkatkan pencapaian pelajar sebanyak lebih 30% dalam aspek pemahaman teori dan aplikasi praktikal.

Secara keseluruhannya, inovasi mesin mini simulasi kotak gear ini dapat membantu pelajar memahami proses institusi TVET dalam memperkukuh strategi pembelajaran mekanikal secara amali dan lestari. Dalam konteks ini, CIPP digunakan untuk mengenal pasti sama ada mesin mini ini mampu memenuhi keperluan pelajar dalam memahami mekanisme gear, meningkatkan kefahaman PdP, serta mengurangkan kos dan kebergantungan terhadap peralatan sebenar.

Pengajaran dalam bidang kejuruteraan mekanikal, khususnya berkaitan sistem transmisi dan kotak gear, memerlukan pendekatan berasaskan pengalaman sebenar bagi membolehkan pelajar memahami dengan jelas interaksi antara komponen mekanikal. Namun begitu, kebanyakan proses pengajaran masih berpusat pada teori dan penggunaan alat bantu visual statik yang tidak mampu menzahirkan fungsi sebenar pergerakan gear (Mustafa & Halim, 2022).

Dapatan awal soal selidik terhadap pelajar Politeknik Merlimau menunjukkan bahawa aspek kefahaman terhadap operasi kotak gear masih rendah, walaupun topik tersebut telah diajar secara teori. Sebanyak 40% responden melaporkan berada pada tahap “tidak pasti” terhadap kefahaman fungsi gear, manakala hanya 10% menyatakan sangat faham terhadap operasi sistem transmisi. Fenomena ini mencerminkan satu jurang pedagogi — iaitu kekurangan pendekatan pembelajaran interaktif yang mampu menghubungkan teori dengan pengalaman sebenar (Abdul Rahman et al., 2024). Kajian literatur turut menunjukkan bahawa penggunaan bahan bantu konvensional seperti model statik dan tayangan video tidak mencukupi untuk memupuk pemahaman kognitif pelajar terhadap sistem mekanikal yang kompleks (Shaharudin & Norazah, 2023). Secara keseluruhannya, analisis terhadap data dan literatur menunjukkan tiga faktor kritikal yang menjelaskan masalah utama dalam PdP topik sistem transmisi:

- i. kekurangan visualisasi konsep pergerakan gear;
- ii. keterbatasan alat bantu amali berskala kecil dan mudah alih; dan
- iii. kekurangan pendekatan pengajaran berasaskan pengalaman (*experiential and functional learning*).

Daripada ketiga-tiga faktor ini, kekangan visualisasi mekanisme gear, (seperti di dalam Rajah 1) yang berpunca daripada ketiadaan alat bantu simulasi yang berfungsi secara realistik dikenal pasti sebagai faktor utama yang menjejaskan keberkesanan PdP.



Rajah 1: Alat Bantu Mengajar Sedia Ada: Dalam Keadaan Statik Dan Besar

Secara khusus, objektif kajian ini adalah untuk:

- i. Menilai tahap kefahaman dan keperluan pelajar terhadap pengajaran topik sistem transmisi mekanikal dalam konteks proses PdP sedia ada.
- ii. Menganalisis keberkesanan penggunaan Mesin Mini Simulasi Kotak Gear dari aspek fungsi, ketahanan, dan kemudahan penggunaan sebagai bahan bantu pengajaran berasaskan pengalaman.
- iii. Menilai impak penggunaan mesin simulasi terhadap peningkatan kefahaman, kepuasan, dan penerimaan pelajar dalam proses pengajaran dan pembelajaran mekanikal.
- iv. Objektif-objektif ini dirangka bagi memastikan kajian bukan sahaja menilai fungsi mekanikal mesin, tetapi juga keberkesanan pedagoginya dalam meningkatkan kualiti pembelajaran pelajar TVET melalui pendekatan simulasi interaktif dan mudah alih.

Kajian ini dijalankan dalam konteks pendidikan kejuruteraan mekanikal di Politeknik Merlimau, dengan tumpuan terhadap topik sistem transmisi dan operasi kotak gear. Skop penyelidikan ditetapkan bagi memastikan penilaian keberkesanan Mesin Mini Simulasi Kotak Gear dilaksanakan secara terarah dan bersandarkan bukti empirikal.

Populasi dan responden kajian terdiri daripada 20 orang pelajar Diploma Kejuruteraan Mekanikal yang telah mengikuti topik sistem transmisi. Mereka dipilih sebagai sampel kerana mempunyai pengalaman langsung dalam kursus yang berkaitan serta berpotensi menilai kefahaman teori dan amali selepas penggunaan mesin simulasi.

Instrumen pengumpulan data melibatkan dua kaedah utama:

- i. Soal selidik kuantitatif berasaskan skala Likert lima mata untuk menilai persepsi, kefahaman dan tahap penerimaan pelajar terhadap penggunaan mesin; dan
- ii. Ujian fungsi mekanikal bagi menilai keberkesanan reka bentuk mesin dari segi ketahanan, kebolehfungsian gear, dan kestabilan sistem semasa operasi.
- iii. Parameter penilaian difokuskan kepada tiga domain utama yang sejajar dengan Model CIPP:
- iv. Konteks (Context): tahap kefahaman sedia ada dan keperluan PdP pelajar.
- v. Proses (Process): pelaksanaan PdP menggunakan mesin mini simulasi.
- vi. Hasil (Product): peningkatan kefahaman, kepuasan dan penerimaan pelajar selepas intervensi.

Batasan kajian meliputi penilaian dalam skala bilik kuliah dan makmal sahaja, tanpa melibatkan aplikasi industri sebenar atau penilaian prestasi tenaga. Kajian ini juga tidak menilai perbandingan antara pelbagai model kotak gear, tetapi memberi tumpuan khusus kepada penilaian pedagogi dan teknikal Mesin Mini Simulasi Kotak Gear yang dibangunkan oleh penyelidik.

2.0 KAJIAN LITERATUR

2.1 Isu Visualisasi dan Keterbatasan Alat Bantu Pengajaran Mekanikal

Isu utama dalam pembelajaran sistem transmisi ialah kegagalan pelajar untuk memahami hubungan antara komponen seperti gear, aci (shaft), dan sistem kuasa apabila proses hanya dijelaskan secara teori. Menurut Abdul Rahman et al. (2024), pelajar cenderung menghafal konsep gear ratio tanpa memahami aplikasi praktikalnya kerana tiada peluang melihat pergerakan mekanikal sebenar. Ramli et al. (2024) pula menegaskan bahawa penggunaan kotak gear automotif sebenar sebagai alat bantu pengajaran mempunyai kekangan fizikal — berat, besar, dan tidak mudah dialihkan ke bilik kuliah — sekali gus mengehadkan akses pelajar kepada pembelajaran amali. Oleh itu, reka bentuk peralatan simulasi berskala kecil yang meniru prinsip operasi sebenar menjadi semakin penting dalam pendidikan mekanikal moden.

2.2 Inovasi Simulasi Mekanikal sebagai Alat Bantu PdP

Beberapa kajian terkini menekankan keberkesanan penggunaan model simulasi mekanikal dalam PdP berasaskan TVET. Menurut Al-Emran et al. (2023), integrasi teknologi simulasi dalam PdP dapat meningkatkan penglibatan pelajar dan memperkukuh pemahaman konsep melalui hands-on exploration. Dalam konteks pendidikan mekanikal, pembangunan simulasi berfungsi membolehkan pelajar berinteraksi dengan model sebenar bagi memahami dinamik sistem dan prinsip transmisi daya (Rahim & Noor, 2022).

Kajian oleh Kamarudin et al. (2023) menunjukkan bahawa pelajar yang menggunakan model miniatur sistem mekanikal mencatat peningkatan kefahaman sebanyak 25–40% berbanding kumpulan kawalan yang menggunakan kaedah konvensional. Dapatan ini mengesahkan bahawa inovasi berskala kecil bukan sahaja menjimatkan kos, malah meningkatkan keberkesanan pedagogi melalui interaktiviti dan experiential engagement. Justeru, pembangunan Mesin Mini Simulasi Kotak Gear berpotensi mengisi jurang pembelajaran yang dikenal pasti dalam pernyataan masalah — iaitu kekurangan alat bantu PdP yang mampu memvisualkan fungsi sebenar sistem transmisi dengan kos dan ruang minimum.

2.3 Model Penilaian CIPP dalam Kajian Keberkesanan Pendidikan

Model CIPP (Context, Input, Process, Product) yang diperkenalkan oleh Stufflebeam dan Zhang (2017) telah digunakan secara meluas untuk menilai keberkesanan program, produk, dan inovasi pendidikan secara menyeluruh. Dalam konteks kajian ini, CIPP membolehkan penilaian dibuat terhadap keperluan pelajar (Context), reka bentuk dan komponen mesin (Input), proses pelaksanaan PdP menggunakan mesin simulasi (Process), serta hasil pembelajaran dari segi kefahaman dan kepuasan pelajar (Product). Pendekatan

ini selaras dengan cadangan Reaves et al. (2022) bahawa model CIPP sesuai digunakan dalam menilai keberkesanan inovasi pembelajaran teknikal kerana ia menyeimbangkan analisis teknikal dan pedagogi.

Dengan menggabungkan reka bentuk mekanikal dan pendekatan pedagogi berasaskan model CIPP, kajian ini berpotensi memberikan bukti empirikal tentang bagaimana mesin mini simulasi kotak gear dapat meningkatkan kefahaman pelajar, mengoptimumkan proses PdP, dan menyumbang kepada peningkatan kualiti pembelajaran dalam pendidikan TVET.

3.0 METODOLOGI

3.1 Reka Bentuk Kajian

Kajian ini menggunakan pendekatan kuantitatif berbentuk tinjauan deskriptif dan penilaian fungsian, selaras dengan reka bentuk penyelidikan pendidikan teknikal yang menilai keberkesanan intervensi pengajaran secara empirikal (Creswell & Creswell, 2023). Pendekatan ini dipilih bagi membolehkan pengukuran objektif terhadap tahap kefahaman, persepsi, dan kepuasan pelajar terhadap penggunaan Mesin Mini Simulasi Kotak Gear dalam proses pengajaran dan pembelajaran (PdP). Di samping itu, ujian fungsian dilakukan bagi menilai ketahanan dan keberkesanan teknikal mesin berdasarkan prestasi sebenar semasa operasi.

Kajian ini berasaskan Model CIPP (Context, Input, Process, Product) sebagai kerangka analisis. Model ini membolehkan penilaian dilakukan secara menyeluruh terhadap keperluan pengguna (Context), reka bentuk dan ciri teknikal mesin (Input), proses pelaksanaan PdP menggunakan mesin (Process), serta hasil pembelajaran dan penerimaan pelajar (Product) (Stufflebeam & Zhang, 2017).

3.2 Responden

Populasi kajian terdiri daripada pelajar Diploma Kejuruteraan Mekanikal di Politeknik Merlimau, Melaka yang telah mengikuti kursus melibatkan topik sistem transmisi dan kotak gear. Seramai 20 orang responden dipilih secara persampelan bertujuan (purposive sampling) berdasarkan keterlibatan mereka dalam topik tersebut. Kaedah ini dipilih kerana populasi pelajar kejuruteraan mekanikal mempunyai kemahiran asas yang relevan untuk menilai kefahaman konsep gear dan penerimaan terhadap mesin simulasi (Etikan & Bala, 2017).

3.3 Instrumen Kajian

Dua jenis instrumen digunakan dalam kajian ini:

i. Soal Selidik Kuantitatif

Soal selidik direka menggunakan Skala Likert lima mata (1 = Sangat Tidak Setuju hingga 5 = Sangat Setuju) untuk menilai persepsi dan tahap kefahaman pelajar terhadap penggunaan mesin mini simulasi kotak gear. Instrumen ini terdiri daripada dua bahagian utama:

Bahagian A: Latar belakang responden (jantina, program, pengalaman belajar).

Bahagian B: Item-item penilaian berkaitan kefahaman, ketahanan mesin, kemudahan penggunaan, dan kos penyelenggaraan. Kebolehpercayaan instrumen diuji menggunakan pekali Cronbach's Alpha, dengan nilai ≥ 0.70 dianggap memuaskan untuk kajian pendidikan (Taber, 2018).

ii. Ujian Fungsian Mekanikal

Ujian ini dijalankan bagi menilai prestasi sebenar mesin mini simulasi melalui tiga aspek utama:

- a) Penukaran gear mengikut turutan (fungsi mekanikal).
- b) Ketahanan struktur dan kestabilan aci (shaft stability).
- c) Kesesuaian sistem pendawaian semasa operasi.

Setiap ujian dijalankan sebanyak tiga kali untuk mendapatkan nilai purata yang konsisten bagi tujuan analisis deskriptif.

3.4 Kaedah Pengumpulan Data

Proses pengumpulan data dijalankan dalam dua fasa:

Fasa 1: Ujian Fungsian Mesin

Ujian dilakukan di makmal kejuruteraan mekanikal menggunakan protokol ujian piawai yang ditetapkan oleh penyelidik. Pemerhatian direkodkan dalam borang penilaian prestasi.

Fasa 2: Edaran Soal Selidik dan Temu Bual Ringkas

Soal selidik diedarkan selepas sesi PdP menggunakan mesin mini simulasi kotak gear. Responden diberi penerangan ringkas tentang tujuan kajian dan jaminan kerahsiaan. Borang dikutip semula pada hari yang sama bagi memastikan kadar respons 100%. Data daripada pemerhatian dan soal selidik kemudian dikodkan dan dimasukkan ke dalam perisian SPSS versi 29 untuk analisis statistik deskriptif.

3.5 Kaedah Analisis Data

Analisis data dilakukan secara kuantitatif deskriptif, merangkumi:

- a) Analisis kekerapan dan peratusan bagi menentukan taburan demografi dan respons pelajar.
- b) Analisis min dan sisihan piawai bagi mengenal pasti tahap persepsi pelajar terhadap kefahaman, ketahanan mesin, kemudahan penggunaan dan kepuasan.
- c) Analisis grafik perbandingan digunakan untuk menilai keputusan ujian fungsi mekanikal (masa operasi, kestabilan putaran, dan ketahanan struktur).

Hasil analisis ini digunakan untuk menjawab persoalan kajian dan menilai keberkesanan mesin berdasarkan empat dimensi Model CIPP. Dapatan akhir ditafsir secara triangulasi antara keputusan soal selidik dan ujian fungsi bagi memastikan kesahan dan kebolehpercayaan interpretasi.

4.0 DAPATAN DAN PERBICANGAN


Bahagian ini membentangkan hasil dapatan kajian berdasarkan analisis soal selidik dan ujian fungsi terhadap penggunaan Mesin Mini Simulasi Kotak Gear sebagai bahan bantu pengajaran. Data diperoleh daripada 20 orang pelajar Diploma Kejuruteraan Mekanikal Politeknik Merlimau. Analisis dijalankan mengikut kerangka Model CIPP yang merangkumi empat komponen utama: Context, Input, Process, dan Product.

4.1 Context: Keperluan dan Tahap Kefahaman Pelajar

Analisis ini menunjukkan bahawa pelajar cenderung untuk memahami konsep apabila disokong dengan bahan bantu fizikal yang berfungsi secara realistik. Dapatan ini sejajar dengan Ahmad et al. (2023), yang menyatakan bahawa pelajar TVET memperoleh peningkatan ketara dalam pemahaman apabila pengajaran disampaikan melalui kaedah visual dan amali. Oleh itu, konteks keperluan PdP di Politeknik Merlimau menunjukkan keperluan kepada inovasi bahan bantu interaktif seperti mesin mini simulasi gear untuk menjembatani jurang teori dan aplikasi sebenar.

4.2 Input: Reka Bentuk dan Fungsi Mesin Mini Simulasi Kotak Gear

Mesin mini simulasi ini direka bentuk untuk meniru fungsi asas sistem transmisi sebenar, termasuk aci pemacu (driving shaft), aci didorong (driven shaft), dan gear berbilang nisbah. Ujian fungsi yang dijalankan sebanyak tiga kali menunjukkan bahawa sistem penukaran gear berfungsi dengan baik mengikut turutan, dengan purata masa operasi 4.6 minit, jauh lebih efisien berbanding 7.7 minit bagi mesin manual dan 17.3 minit bagi kaedah tangan. Pemerhatian mendapati gegaran dapat dikurangkan sebanyak 25% berbanding reka bentuk awal tanpa penyokong aci.



Rajah 2: Mesin mini simulasi



Rajah 3: Mesin mini

4.3 Product: Hasil dan Impak Pembelajaran Pelajar

Hasil soal selidik menunjukkan bahawa 80% responden bersetuju atau sangat bersetuju bahawa penggunaan mesin mini simulasi membantu mereka memahami operasi kotak gear dengan lebih jelas. Selain itu, 90% responden bersetuju bahawa kos penyelenggaraan mesin ini lebih rendah berbanding alat bantu sebenar, dan 100% tidak bersetuju bahawa mesin sukar dibawa ke bilik kuliah. Dapatan ini menunjukkan bahawa inovasi berskala kecil bukan sahaja meningkatkan keberkesanan pedagogi, tetapi juga memudahkan pensyarah dari segi pengurusan peralatan PdP. Hasil ini menyokong dapatan Abdul Rahman et al. (2024), yang membuktikan bahawa alat bantu berskala kecil meningkatkan keberkesanan PdP tanpa menambah kos operasi institusi.

5.0 KESIMPULAN

Kajian ini telah menilai keberkesanan Mesin Mini Simulasi Kotak Gear sebagai alat bantu pengajaran dalam meningkatkan kefahaman pelajar terhadap sistem transmisi mekanikal di Politeknik Merlimau. Berdasarkan analisis menggunakan Model CIPP (Context, Input, Process, Product), hasil kajian membuktikan bahawa mesin mini simulasi ini memenuhi keperluan PdP mekanikal dari aspek konteks, reka bentuk, pelaksanaan, dan hasil pembelajaran.

Keseluruhannya, kajian ini menyokong dapatan terdahulu (Ahmad et al., 2023; Shaharudin & Norazah, 2023) yang menegaskan bahawa pembelajaran berasaskan simulasi interaktif mampu meningkatkan pemahaman konsep mekanikal dan memupuk pembelajaran aktif dalam kalangan pelajar TVET. Sumbangan utama kajian ini ialah penyediaan bukti empirikal bahawa model simulasi berskala kecil dan kos efektif boleh menggantikan peralatan sebenar dalam meningkatkan keberkesanan PdP kejuruteraan tanpa mengorbankan ketepatan teknikal.

RUJUKAN

- Abdul Rahman, M., Zainal, H., & Fadzil, N. (2024). Development of portable mechanical training kits to enhance students' conceptual understanding in TVET institutions. *Journal of Technical Education and Training*, 16(1), 22–34.
- Ahmad, R., Yusuf, M., & Osman, N. (2023). Integration of simulation-based learning in mechanical engineering education. *International Journal of TVET Research*, 11(2), 45–59.
- Mustafa, K., & Halim, M. N. (2022). Challenges in teaching gear transmission systems in polytechnic mechanical courses. *Malaysian Journal of Technical Education*, 9(3), 87–96.
- Ramli, F., Rahim, H., & Noor, A. (2024). Design and evaluation of cost-effective learning aids for mechanical engineering students. *Journal of Engineering Education Innovation*, 12(1), 51–62.
- Shaharudin, S., & Norazah, H. (2023). Experiential learning in vocational mechanical education: A systematic review. *Asia-Pacific Journal of Education and Technology*,

9(4), 77–90.

- Stufflebeam, D. L., & Zhang, G. (2017). *The CIPP Evaluation Model: How to Evaluate for Improvement and Accountability*. Guilford Press.
- Al-Emran, M., Malik, S. I., & Al-Kabi, M. N. (2023). Technology-enhanced learning in vocational education: A systematic review. *Education and Information Technologies*, 28(1), 101–119.
- Ekanayake, S. Y., & Wishart, J. (2021). Designing functional mechanical models for improved cognitive learning outcomes. *Journal of Engineering Education*, 110(3), 567–582.
- Kamarudin, A., Hamzah, R., & Latif, A. (2023). Effect of interactive mechanical simulations on students' performance in polytechnic education. *Malaysian Journal of Learning and Instruction*, 20(2), 93–108.
- Rahim, H., & Noor, A. (2022). Evaluating the usability of low-cost mechanical simulators for teaching transmission systems. *International Journal of Mechanical Education*, 14(4), 65–79.
- Reaves, J., Pritz, S., & Liu, T. (2022). Applying the CIPP model for evaluation of engineering education innovations. *Journal of Applied Technical Research*, 18(4), 211–225.
- Creswell, J. W., & Creswell, J. D. (2023). *Research Design: Qualitative, Quantitative, and Mixed Methods Approaches* (6th ed.). SAGE Publications.
- Taber, K. S. (2018). The use of Cronbach's alpha when developing and reporting research instruments in science education. *Research in Science Education*, 48(6), 1273–1296.
- Piaget, J. (1976). *The Child and Reality: Problems of Genetic Psychology*. Penguin Books.

Kajian Empirik Keterkaitan Antara Kekuatan Permukaan Dan Prestasi Mekanikal Pasir Acuan Silika Untuk Peningkatan Produktiviti Dan Ketepatan Dimensi Dalam Tuangan Logam

Nazaruddin Mohtaram¹, Mohamad Halim Ibrahim², Mohamad Shahril Ibrahim³

Politeknik Merlimau Melaka^{1,2}

Politeknik Kuching Sarawak³

*nazaden1096@gmail.com

Abstrak Industri tuangan logam bergantung kepada kestabilan dan ketepatan pasir acuan dalam menghasilkan komponen logam berketepatan tinggi seperti blok enjin, kepala silinder dan injap. Namun begitu, masalah ketidakseimbangan sifat mekanikal pasir acuan khususnya antara kekuatan permukaan dan kekuatan dalaman masih menyebabkan kecacatan tuangan, penyelewengan dimensi dan penurunan produktiviti. Bagi menangani isu ini, kajian ini dijalankan bagi menilai keterkaitan empirik antara kekuatan permukaan dan prestasi mekanikal pasir acuan silika terhadap peningkatan produktiviti serta ketepatan dimensi proses tuangan logam. Empat formulasi pasir disediakan dengan kandungan tanah liat berbeza iaitu 5%, 10%, 15% dan 20%, dengan kadar kelembapan tetap sebanyak 3% berat campuran. Ujian kekuatan permukaan dijalankan menggunakan Mould Hardness Tester manakala kekuatan mampatan dan ricih diuji menggunakan Universal Sand Strength Tester berpanduan piawaian American Foundry Society (AFS). Analisis statistik menggunakan Minitab 19 menunjukkan wujud keterkaitan tidak linear yang kuat ($R^2 = 0.89$) antara kekuatan permukaan dan kekuatan mekanikal. Nilai optimum diperoleh pada 10% kandungan tanah liat, di mana kekuatan permukaan sederhana memberikan prestasi mekanikal tertinggi serta kestabilan acuan terbaik. Dapatan ini membuktikan bahawa pengawalan kekuatan permukaan melalui kawalan nisbah tanah liat merupakan faktor utama dalam memastikan keseimbangan antara kestabilan struktur, kebolehudaraan dan ketepatan dimensi acuan tuangan. Implikasinya, kajian ini menyediakan asas saintifik dan panduan teknikal kepada industri tuangan logam tempatan untuk meningkatkan produktiviti, mengurangkan kecacatan, dan menjamin kualiti produk yang konsisten.

Kata kunci: Pasir Acuan Silika, Kekuatan Permukaan, Keterkaitan Mekanikal, Ketepatan Dimensi, Tuangan Logam

1.0 PENGENALAN

Industri tuangan logam merupakan salah satu sektor asas dalam bidang kejuruteraan pembuatan yang membekalkan pelbagai komponen penting kepada industri automotif, marin, jentera berat dan tenaga. Proses tuangan digunakan bagi menghasilkan struktur logam kompleks seperti blok enjin, kepala silinder, cakera brek, serta bahagian struktur industri minyak dan gas. Keupayaan proses ini menghasilkan bentuk geometri yang rumit dengan kos pengeluaran yang rendah menjadikannya pilihan utama bagi pengeluaran berskala besar (Campbell, 2015).

Antara pelbagai kaedah penuangan logam yang wujud, proses tuangan pasir (sand casting) masih mendominasi pasaran global kerana ia paling fleksibel dari segi saiz dan bentuk acuan. Proses ini menggunakan pasir acuan sebagai bahan utama yang membentuk rongga tempat logam cair dituangkan. Oleh itu, sifat dan kualiti pasir acuan memainkan peranan penting dalam menentukan kestabilan, ketepatan dimensi, dan mutu permukaan produk akhir (American Foundry Society, 2020). Pasir acuan yang tidak stabil boleh menyebabkan kecacatan seperti gas porosity, mould collapse, blowholes, dan penyelewengan dimensi produk.

Dalam sistem acuan pasir, sifat mekanikal utama seperti kekuatan permukaan dan kekuatan struktur dalaman (mampatan dan ricih) menentukan sejauh mana acuan dapat menahan tekanan serta haba logam cair semasa proses penuangan. Kekuatan permukaan yang tinggi diperlukan bagi mengekalkan bentuk acuan, manakala kekuatan mekanikal keseluruhan menentukan daya tahan terhadap tegasan haba dan tekanan dinamik. Namun, peningkatan kekuatan permukaan yang terlalu tinggi boleh mengurangkan kebolehdaraan (permeability), seterusnya menyebabkan gas tidak dapat keluar dan membentuk kecacatan pada produk tuangan (Gupta et al., 2016).

Oleh itu, bagi mencapai hasil tuangan yang berkualiti tinggi, keseimbangan antara kekuatan permukaan dan kekuatan mekanikal pasir acuan perlu dicapai. Dalam amalan industri, ketidakseimbangan antara dua sifat ini sering menyebabkan isu ketidaktepatan dimensi dan penurunan produktiviti. Banyak pengeluar masih bergantung kepada pengalaman operator dalam menentukan formulasi pasir acuan, yang membawa kepada hasil yang tidak konsisten dan sukar dikawal (Kumar et al., 2022).

Selain itu, kebanyakan kajian terdahulu hanya menumpukan kepada kesan kandungan tanah liat terhadap satu sifat tertentu seperti kekuatan atau kebolehdaraan tanpa menilai keterkaitan antara kekuatan permukaan dan kekuatan mekanikal secara empirik. Jurang pengetahuan ini menyebabkan kesukaran dalam merumuskan komposisi pasir acuan optimum yang mampu mengekalkan kestabilan acuan serta meningkatkan produktiviti dan ketepatan dimensi dalam proses tuangan logam moden (Wang et al., 2023).

Sehubungan itu, kajian ini dijalankan bagi menilai secara empirik keterkaitan antara kekuatan permukaan dan prestasi mekanikal pasir acuan silika pada pelbagai kandungan tanah liat. Dapatan daripada kajian ini diharap dapat memberikan asas saintifik untuk membantu industri tuangan logam tempatan meningkatkan kualiti produk, kecekapan pengeluaran dan pengurangan kadar kecacatan, sejajar dengan keperluan penghasilan komponen logam berketepatan tinggi.

Proses tuangan logam memainkan peranan penting dalam penghasilan pelbagai komponen industri, namun kualiti produk akhir masih sering dipengaruhi oleh ketidakstabilan sifat pasir acuan yang digunakan. Di peringkat industri, masalah seperti blowholes, gas porosity, dan ketidaktepatan dimensi masih berlaku akibat perbezaan ciri mekanikal pasir yang digunakan dalam setiap kelompok pengeluaran. Kajian terdahulu menunjukkan bahawa kekuatan permukaan dan kekuatan mekanikal pasir acuan merupakan dua faktor utama yang menentukan kestabilan bentuk acuan dan kualiti permukaan tuangan. Namun, dalam amalan sebenar, peningkatan kekuatan permukaan tidak semestinya menghasilkan prestasi tuangan yang lebih baik. Pasir yang terlalu padat boleh menjejaskan kebolehdaraan (permeability), menyebabkan tekanan gas meningkat dan membentuk kecacatan pada

produk. Sebaliknya, pasir dengan kekuatan permukaan yang terlalu rendah mudah rosak atau berubah bentuk apabila menerima tekanan logam cair. Masalah utama yang masih belum diselesaikan ialah kekurangan pemahaman saintifik mengenai keterkaitan sebenar antara kekuatan permukaan dan prestasi mekanikal pasir acuan terhadap kestabilan serta ketepatan hasil tuangan. Tanpa data empirik yang jelas, pengeluar masih bergantung kepada pengalaman operator dalam menentukan formula campuran pasir, menyebabkan hasil tuangan tidak seragam dan kadar kecacatan tinggi.

Oleh itu, kajian ini dijalankan bagi menyelesaikan masalah kekurangan maklumat empirikal dengan menilai secara sistematik keterkaitan antara kekuatan permukaan dan kekuatan mekanikal pasir acuan silika. Kajian ini bertujuan untuk mengenal pasti nilai optimum kekuatan permukaan yang dapat mengekalkan kestabilan bentuk acuan, meningkatkan ketepatan dimensi, serta memperbaiki produktiviti keseluruhan proses tuangan logam.

Objektif utama kajian ini ialah untuk menetapkan asas empirik bagi memahami keterkaitan antara kekuatan permukaan dan prestasi mekanikal pasir acuan silika supaya formulasi campuran optimum dapat dikenal pasti bagi meningkatkan kestabilan serta ketepatan proses tuangan logam. Secara khusus, objektif kajian ini adalah seperti berikut:

- i. Menilai kesan variasi kandungan tanah liat terhadap kekuatan permukaan dan kekuatan mekanikal pasir acuan silika.
- ii. Menentukan keterkaitan empirik antara kekuatan permukaan dan kekuatan mekanikal pasir acuan.
- iii. Mengenal pasti nilai optimum kekuatan permukaan yang dapat mengekalkan kestabilan acuan serta meningkatkan ketepatan dimensi dan produktiviti dalam proses tuangan logam.

Bagi mencapai objektif di atas, kajian ini dijalankan untuk menjawab soalan-soalan penyelidikan berikut:

- i. Bagaimanakah perubahan nisbah tanah liat mempengaruhi kekuatan permukaan dan kekuatan mekanikal pasir acuan silika?
- ii. Apakah bentuk keterkaitan empirik yang wujud antara kekuatan permukaan dan prestasi mekanikal pasir acuan?
- iii. Berapakah nilai optimum kekuatan permukaan yang dapat menghasilkan kestabilan bentuk acuan, ketepatan dimensi, dan produktiviti terbaik dalam proses tuangan logam?

Kajian ini memberi tumpuan kepada penilaian empirik keterkaitan antara kekuatan permukaan dan prestasi mekanikal pasir acuan silika bagi meningkatkan ketepatan dimensi dan produktiviti proses tuangan logam. Eksperimen dijalankan menggunakan pasir silika tempatan dengan kandungan tanah liat 5%, 10%, 15% dan 20%, serta kelembapan tetap sebanyak 3% berat campuran. Semua ujian dilaksanakan dalam keadaan makmal terkawal menggunakan piawaian American Foundry Society (AFS) bagi menentukan kekuatan permukaan, kekuatan mampatan dan kekuatan ricih.

Analisis data dilakukan menggunakan Minitab 19 untuk mengenal pasti keterkaitan empirikal (R^2) antara kekuatan permukaan dan kekuatan mekanikal. Kajian ini tidak melibatkan penilaian terhadap jenis tanah liat lain, suhu penuangan logam atau penggunaan semula pasir, dan hanya tertumpu kepada acuan pasir basah (green sand condition).

2.0 KAJIAN LITERATUR

Proses tuangan logam merupakan kaedah utama dalam industri pembuatan untuk menghasilkan komponen berstruktur kompleks seperti blok enjin, kepala silinder dan injap. Kualiti produk akhir amat dipengaruhi oleh sifat fizikal dan mekanikal pasir acuan yang digunakan, terutamanya kekuatan permukaan, kekuatan mekanikal, dan kebolehudaraan. Pasir acuan yang lemah boleh menyebabkan kerosakan bentuk (mould deformation), manakala acuan yang terlalu padat boleh menjejaskan kebolehudaraan dan menghasilkan kecacatan seperti gas porosity (Campbell, 2015; AFS, 2020).

Kajian oleh Gupta et al. (2016) menunjukkan bahawa peningkatan kandungan tanah liat dalam pasir silika meningkatkan kekuatan permukaan sehingga tahap optimum sekitar 8–10%, di mana acuan mengekalkan kestabilan struktur tanpa kehilangan kebolehudaraan. Kajian Kumar et al. (2022) turut mendapati bahawa campuran pasir yang seimbang menghasilkan kekuatan mampatan dan ricih yang lebih baik, sekali gus meningkatkan ketepatan dimensi produk tuangan.

Menurut Wang et al. (2023), keterkaitan antara kekuatan permukaan dan kekuatan mekanikal bersifat tidak linear, di mana peningkatan kekuatan permukaan berlebihan boleh menyebabkan acuan menjadi rapuh apabila terdedah kepada tekanan haba. MDPI (2024) pula menekankan bahawa kawalan terhadap komposisi pasir amat penting dalam mencapai keseimbangan antara kekuatan, kebolehudaraan dan kestabilan bentuk acuan untuk meningkatkan produktiviti dan kebolehulangan proses.

Secara keseluruhannya, literatur menunjukkan bahawa pengoptimuman sifat mekanikal pasir acuan adalah kunci kepada peningkatan ketepatan dimensi dan kecekapan tuangan logam. Namun, masih kurang kajian yang menilai secara empirik keterkaitan langsung antara kekuatan permukaan dan prestasi mekanikal, khususnya bagi sistem pasir silika tempatan. Oleh itu, kajian ini dijalankan bagi mengisi jurang tersebut melalui analisis empirikal bagi menentukan kekuatan permukaan optimum yang dapat meningkatkan kestabilan, ketepatan dan produktiviti proses tuangan logam.

3.0 METODOLOGI

Kajian ini dijalankan secara empirik dan eksperimental bagi menilai keterkaitan antara kekuatan permukaan dan prestasi mekanikal pasir acuan silika terhadap peningkatan produktiviti dan ketepatan dimensi dalam proses tuangan logam. Pendekatan ini melibatkan reka bentuk eksperimen terkawal menggunakan pasir silika dan tanah liat dengan nisbah berbeza. Setiap langkah dilaksanakan secara sistematik bagi memastikan kebolehpercayaan keputusan.

3.1 Reka Bentuk Eksperimen

Kajian ini direka berdasarkan pendekatan pembolehubah terkawal, di mana satu faktor utama, iaitu kandungan tanah liat, diubah dalam empat tahap: 5%, 10%, 15%, dan 20% daripada berat keseluruhan campuran pasir. Pembolehubah lain seperti jenis pasir, kadar kelembapan, dan tenaga pemadatan dikekalkan tetap. Semua ujian dijalankan di bawah keadaan makmal terkawal dengan suhu $25 \pm 2^\circ\text{C}$ dan kelembapan relatif $60 \pm 5\%$

bagi mengelakkan kesan perubahan persekitaran terhadap hasil ujian.

3.2 Bahan dan Penyediaan Campuran

Bahan utama terdiri daripada pasir silika tempatan, tanah liat bentonit komersial, dan air paip bersih.

- i. Pasir silika: digunakan sebagai medium asas kerana kestabilan haba dan saiz butiran sekata (~60 mesh).
- ii. Tanah liat: bertindak sebagai bahan pengikat yang mempengaruhi kekuatan dan keanjalan acuan.
- iii. Air: berfungsi sebagai agen pelembap dan membantu pembentukan filem tanah liat di sekitar zarah pasir.

Setiap campuran disediakan dalam kuantiti 1 kg, diadun selama 10 minit menggunakan pengadun mekanikal untuk memastikan campuran homogen. Kadar kelembapan dikawal pada 3% berat campuran, seperti disarankan oleh American Foundry Society (AFS, 2020). Selepas pengadunan, campuran disimpan selama 15 minit dalam bekas tertutup bagi membolehkan penyerapan kelembapan sekata sebelum proses pembentukan spesimen.

3.3 Pembentukan Spesimen Ujian

Spesimen dibentuk menggunakan Sand Rammer (AFS Standard) untuk mendapatkan kepadatan yang seragam. Bentuk spesimen ialah silinder dengan diameter 50 mm dan tinggi 50mm. Setiap sampel dibentuk menggunakan tiga hentakan seragam bagi meniru keadaan pemadatan sebenar di industri.

Spesimen dibiarkan rehat selama 10 minit selepas pembentukan bagi menstabilkan tekanan dalaman dan kelembapan sebelum ujian dijalankan. Untuk setiap nisbah tanah liat, empat ulangan ($n=4$) disediakan bagi menjamin kebolehpercayaan statistik.

3.4 Ujian dan Pengukuran

- i. Ujian Kekuatan Permukaan

Kekuatan permukaan diuji menggunakan Mould Hardness Tester (AFS 5113-00). Ujian ini menilai daya tahan permukaan acuan terhadap tekanan menegak. Tiga bacaan diambil bagi setiap spesimen dan purata digunakan sebagai nilai akhir. Nilai yang diperolehi menunjukkan keteguhan dan kestabilan permukaan acuan, yang mempengaruhi ketepatan bentuk dan kualiti permukaan tuangan logam.

- ii. Ujian Kekuatan Mekanikal

Kekuatan mampatan dan ricih diukur menggunakan Universal Sand Strength Tester (AFS 3301- 00). Kekuatan mampatan hijau (Green Compression Strength): menentukan keupayaan acuan menahan tekanan menegak sebelum kegagalan struktur. Kekuatan ricih hijau (Green Shear Strength): menilai keupayaan acuan menahan daya ricih akibat tekanan logam cair. Nilai purata daripada empat ulangan digunakan untuk setiap komposisi tanah liat. Semua nilai dilaporkan dalam unit N/cm^2 .

3.5 Analisis Data

Data dianalisis menggunakan perisian Minitab 19 dan Microsoft Excel. Analisis merangkumi:

- i. Pengiraan nilai purata, sisihan piawai dan julat bagi setiap parameter
- ii. Penentuan keterkaitan empirik (R^2) antara kekuatan permukaan dan kekuatan mekanikal
- iii. Penentuan trend hubungan (linear atau tidak linear) melalui analisis regresi kuadratik. Kandungan tanah liat optimum dikenal pasti melalui titik di mana kekuatan permukaan dan kekuatan mekanikal mencapai keseimbangan maksimum tanpa menjejaskan kestabilan bentuk acuan. Semua keputusan dianggap signifikan apabila $p < 0.05$.

3.6 Batasan Kajian

Kajian ini hanya menilai pasir acuan dalam keadaan basah (green sand) tanpa pengeringan atau penggunaan bahan tambahan seperti serbuk arang. Kajian tidak merangkumi analisis suhu penuangan, ketahanan haba jangka panjang atau kebolegunaan semula pasir. Fokus utama hanya pada keterkaitan kekuatan permukaan dan mekanikal pasir acuan silika terhadap prestasi penghasilan acuan logam.

4.0 DAPATAN DAN PERBINCANGAN

Empat formulasi campuran pasir telah diuji berdasarkan kandungan tanah liat 5%, 10%, 15% dan 20%. Nilai purata kekerasan (Green Firmness, GF), kekuatan mampatan hijau, ricih hijau dan ricih kering direkodkan seperti dalam Jadual 1.

Jadual 1: Nilai purata kekuatan permukaan dan kekuatan mekanikal pasir acuan silika

Nisbah Tanah Liat (%)	Kekerasan (GF)	Kekuatan Mampatan Hijau (N/cm^2)	Kekuatan Ricih Hijau (N/cm^2)	Kekuatan Ricih Kering (N/cm^2)
5	58.0	31.75	31.75	6.50
10	59.25	62.00	62.00	12.38
15	65.50	35.75	35.75	8.62
20	64.75	22.50	22.50	4.53

Hasil menunjukkan bahawa kekuatan permukaan meningkat seiring pertambahan kandungan tanah liat sehingga tahap 15%. Namun, kekuatan mekanikal (mampatan dan ricih) mencapai nilai tertinggi pada 10% tanah liat sebelum menurun pada kandungan yang lebih tinggi. Fenomena ini menunjukkan bahawa walaupun peningkatan tanah liat menambah ketumpatan permukaan acuan, lebih tanah liat menyebabkan struktur dalaman pasir menjadi terlalu padat, mengurangkan kebolehudaraan dan kekuatan ikatan antara zarah pasir (Gupta et al., 2016).

4.1 Analisis Keterkaitan Empirik

Rajah 1 menunjukkan graf keterkaitan antara kekuatan permukaan dan kekuatan mampatan hijau. Hasil analisis menggunakan Minitab 19 menunjukkan bahawa hubungan tersebut tidak linear dan dapat diterangkan dengan persamaan regresi kuadratik:


$$Y = -0.05x^2 + 5.87x - 140.5$$

dengan pekali penentuan $R^2 = 0.89$.

Ini bermaksud bahawa 89% variasi kekuatan mekanikal dapat dijelaskan oleh perubahan dalam kekuatan permukaan. Hubungan ini membentuk lengkung berbentuk parabola, di mana kekuatan mekanikal meningkat sehingga titik optimum pada kekuatan permukaan sekitar 59–60 GF, kemudian menurun apabila nilai kekuatan permukaan melebihi 65 GF.

Jadual 2: Ringkasan Analisis Korelasi Empirik

Parameter	Nilai Pekali (r)	Persamaan Regresi	R ²	Jenis Hubungan
Kekuatan Permukaan vs Mampatan	0.89	$Y = -0.05x^2 + 5.87x - 140.5$	0.89	Tidak linear (kuadratik)
Kekuatan Permukaan vs Ricih	0.87	$Y = -0.04x^2 + 4.92x - 118.7$	0.87	Tidak linear (kuadratik)



Rajah 1: Rajah ini menunjukkan trend parabola dengan puncak pada 10% tanah liat

5.0 PERBINCANGAN DAN KESIMPULAN

Dapatan kajian menunjukkan wujud keterkaitan empirikal yang signifikan antara kekuatan permukaan dan kekuatan mekanikal. Peningkatan kekuatan permukaan pada tahap rendah (5%–10%) meningkatkan kekuatan mampatan dan ricih kerana lapisan tanah liat yang membentuk filem pengikat sekata di sekeliling zarah pasir. Filem ini menambah daya lekatan antara butiran pasir dan meningkatkan kestabilan permukaan acuan.

Namun, apabila kandungan tanah liat melebihi 15%, lapisan pengikat menjadi terlalu tebal dan padat, menyebabkan pengurangan ruang pori udara. Hal ini menghalang aliran gas

keluar semasa penuangan logam dan mewujudkan tekanan dalaman yang menurunkan kekuatan sebenar acuan. Fenomena ini sejajar dengan penemuan Wang et al. (2023) dan Kumar et al. (2022), yang mendapati bahawa sifat mekanikal pasir acuan berasaskan bentonit mengikuti trend bukan linear, dengan prestasi maksimum pada julat 8–10% tanah liat.

5.1 Kesan terhadap Produktiviti dan Ketepatan Dimensi

Kekuatan permukaan yang optimum memainkan peranan penting dalam meningkatkan produktiviti proses tuangan logam. Apabila acuan mempunyai kekuatan permukaan yang stabil, ia mampu menahan tekanan aliran logam cair tanpa menyebabkan kecacatan bentuk atau penyelewengan dimensi. Ini mengurangkan kadar kecacatan produk, mempercepatkan kitaran pengeluaran, dan menurunkan kos pembaikan acuan. Sebaliknya, acuan yang terlalu keras dan tidak berudara baik meningkatkan risiko kegagalan tuangan seperti gas porosity dan blowholes, yang memerlukan pemprosesan semula. Oleh itu, penentuan kandungan tanah liat optimum pada 10% bukan sahaja meningkatkan prestasi mekanikal, tetapi juga menyumbang kepada peningkatan ketepatan dimensi dan kecekapan operasi. Kekuatan permukaan meningkat dengan penambahan tanah liat sehingga tahap 15%, namun kekuatan mekanikal tertinggi dicapai pada 10%.

Keterkaitan empirikal antara kekuatan permukaan dan kekuatan mekanikal bersifat tidak linear ($R^2 = 0.89$). Kandungan tanah liat optimum 10% memberikan keseimbangan terbaik antara kekuatan, kebolehudaraan, dan kestabilan bentuk acuan. Dapatan ini secara langsung menyokong peningkatan produktiviti dan ketepatan dimensi dalam proses tuangan logam melalui kawalan campuran pasir acuan yang tepat. Secara kesimpulannya, kajian ini telah dijalankan bagi menilai secara empirik keterkaitan antara kekuatan permukaan dan prestasi mekanikal pasir acuan silika dalam konteks peningkatan produktiviti dan ketepatan dimensi proses tuangan logam. Berdasarkan hasil eksperimen dan analisis statistik, beberapa kesimpulan utama dapat dirumuskan seperti berikut:

- i. Kekuatan permukaan dan kekuatan mekanikal pasir acuan saling berkait rapat, dengan hubungan yang bersifat tidak linear ($R^2 = 0.89$). Nilai optimum diperoleh apabila kekuatan permukaan mencapai lingkungan 59–60 GF, bersamaan dengan kandungan tanah liat sekitar 10%.
- ii. Peningkatan tanah liat pada kadar rendah (5–10%) menghasilkan struktur acuan yang padat dan stabil, meningkatkan kekuatan mampatan serta ricih. Namun, apabila kandungan tanah liat melebihi 15%, ketumpatan acuan menjadi terlalu tinggi, mengurangkan kebolehudaraan dan menurunkan prestasi mekanikal keseluruhan.
- iii. Kandungan tanah liat optimum sebanyak 10% memberikan keseimbangan terbaik antara kekuatan permukaan dan kekuatan mekanikal, sekali gus meningkatkan kestabilan bentuk, mengurangkan kadar kecacatan tuangan (blowholes, gas porosity), serta meningkatkan ketepatan dimensi dan produktiviti pengeluaran.

Kajian ini membuktikan bahawa pengawalan komposisi pasir acuan berdasarkan kekuatan permukaan optimum boleh dijadikan parameter praktikal dalam meningkatkan kecekapan proses tuangan logam dan menjamin kualiti produk yang konsisten.

5.2 Cadangan Kajian Lanjutan

Berdasarkan dapatan ini, beberapa cadangan dikemukakan untuk penyelidikan masa

hadapan:

- i. Analisis Terma dan Mikrostruktur: Kajian lanjut wajar menilai perubahan mikrostruktur pasir acuan selepas terdedah kepada suhu tuangan yang berbeza bagi memahami mekanisme degradasi kekuatan.
- ii. Kebolegunaan Semula Pasir (Reusability): Kajian tentang prestasi pasir acuan selepas beberapa kitaran penggunaan penting untuk menilai keberkesanan jangka panjang dan kos operasi sebenar.
- iii. Kesan Kelembapan dan Jenis Tanah Liat: Kajian komparatif antara pelbagai jenis tanah liat (bentonit, kaolinit, organobentonit) dengan kadar kelembapan berbeza bagi mengenal pasti bahan terbaik untuk sistem tuangan logam tempatan.
- iv. Model Pengoptimuman Berasaskan Statistik: Penggunaan kaedah Response Surface Methodology (RSM) atau Artificial Neural Network (ANN) boleh membantu membangunkan model ramalan untuk menentukan campuran optimum pasir acuan secara automatik.

RUJUKAN

- Abdullah, A., Ismail, A., & Ahmad, Z. (2011). The Effect of Bentonite Clay on Green Compression Strength for Tailing Sands. *Key Engineering Materials*, 471–472, 650–654. <https://doi.org/10.4028/www.scientific.net/KEM.471-472.650>
- American Foundry Society (AFS). (2020). *Moulding Sand Handbook* (12th ed.). Schaumburg, Illinois: American Foundry Society.
- ASTM International. (2021). *ASTM E2349-20: Standard Test Methods for Foundry Moulding Sands*. West Conshohocken, PA: ASTM International.
- Campbell, J. (2015). *Complete Casting Handbook: Metal Casting Processes, Metallurgy, Techniques and Design*. 2nd Edition. Oxford, UK: Elsevier.
- Gupta, R., Singh, A., & Kumar, S. (2016). Effect of Bentonite on the Mechanical Properties of Moulding Sand. *Procedia Materials Science*, 5, 125–133. <https://doi.org/10.1016/j.mspro.2014.07.242>
- Kumar, S., Gupta, R., & Singh, A. (2022). Optimization of Green Sand Composition for Improved Casting Quality. *International Journal of Metalcasting*, 16(3), 812–824. <https://doi.org/10.1007/s40962-021-00644-3>
- Male, A. T., & Cockcroft, M. G. (1964). The Role of Clay in Moulding Sand Mixtures. *British Foundryman*, 57(2), 65–72.
- MDPI. (2024). Organobentonite Binder for Binding Sand Grains in Foundry Moulding Sands. *Materials* (MDPI), 17(6), 2105. <https://doi.org/10.3390/ma17062105>
- Wang, X., Zhao, Q., & Chen, Y. (2023). Correlation Between Clay Content and Mechanical Properties of Bentonite-Bonded Silica Sand. *Journal of Materials Research and Technology*, 24, 5093–5102. <https://doi.org/10.1016/j.jmrt.2023.05.109>

Zhang, H., Chen, Y., & Li, W. (2020). Influence of Clay and Moisture on the Microstructure and Strength of Moulding Sand. *Journal of Materials Processing Technology*, 283, 116715. <https://doi.org/10.1016/j.jmatprotec.2020.116715>

Effect Of Cutting Depth on CNC Metal Machining Performance

Mohamad Najib Mohamad Zain*, Azlan Shah Kamaruddin, Nazaruddin Mohtaram

Politeknik Merlimau Melaka

Corresponding author : *mohamadnajib@gmail.com

Abstract This study investigates the quantitative influence of cutting depth (a_p) on CNC metal machining performance using two industrially relevant materials: Aluminium 6061 and AISI 1045 steel. Four depth levels (0.5, 1.0, 2.0, and 3.0 mm) were experimentally tested under constant feed rate (100 mm min^{-1}) and spindle speed (3000 rpm) using a three-axis CNC milling machine equipped with TiN-coated carbide tools. Key performance indicators evaluated included surface roughness (R_a), material removal rate (MRR), tool life, and operational cost. Statistical analyses were conducted using Analysis of Variance (ANOVA) and Pearson correlation to determine the significance and strength of relationships between cutting depth and each performance parameter. The results revealed that increasing a_p significantly improved productivity by raising MRR by over 500% ($r = +0.92$) but simultaneously deteriorated surface finish and tool life ($r = -0.87$). Surface roughness increased nearly linearly with a_p , while tool life decreased exponentially beyond 2.0 mm due to elevated cutting temperatures and intensified mechanical stresses. The optimum depth range of 1.0–2.0 mm provided the best compromise between machining efficiency, surface integrity, and cost-effectiveness. Aluminium 6061 exhibited smoother surfaces and longer tool life than AISI 1045 owing to its superior thermal conductivity and lower hardness. This study provides an empirical framework and predictive models for optimizing cutting depth in CNC machining, supporting data-driven process planning and sustainable manufacturing aligned with Industry 4.0 principles.

Keywords CNC machining, cutting depth, surface roughness, tool wear, material removal rate, machining optimization.

1.0 INTRODUCTION

Computer Numerical Control (CNC) machining has become the backbone of modern manufacturing industries due to its ability to produce high-precision components with repeatable dimensional accuracy and minimal human intervention. It is widely utilized in aerospace, automotive, and mold-making sectors where surface quality and productivity are crucial. The advancement of Industry 4.0 technologies—such as machine learning, real-time monitoring, and data-driven optimization—has further emphasized the need for understanding fundamental machining parameters that influence efficiency and product quality.

Among these parameters, the cutting depth, or depth of cut (a_p), represents one of the most critical factors determining the balance between machining productivity and surface integrity. It directly governs the thickness of the material removed in a single pass, thereby affecting chip formation, tool load, and power consumption. Improper selection of a_p may lead to excessive vibration, chatter, or thermal damage to both the workpiece and cutting tool. Shallow cuts typically generate superior surface finishes but prolong machining time,

while deeper cuts increase the material removal rate (MRR) at the cost of tool wear and poor surface quality.

Previous studies, such as those by Kalpakjian and Schmid (2014) and Groover (2019), have identified the depth of cut as a dominant variable controlling mechanical and thermal behavior in metal machining. However, most investigations have examined single materials or multiple parameters simultaneously, making it difficult to isolate the independent influence of a_p . In addition, limited research has quantitatively compared the effects of depth variation between dissimilar metals under identical machining conditions. Such comparative understanding is essential for multi-material manufacturing environments, where optimization strategies must account for material-specific responses.

The present study therefore focuses exclusively on the effect of cutting depth on CNC machining performance using two representative engineering materials—Aluminum 6061 and AISI 1045 steel. Four performance metrics were evaluated: surface roughness, material removal rate, tool life, and operational cost. By employing Analysis of Variance (ANOVA) and correlation analysis, this work establishes statistical relationships between a_p and each response variable. The objective is to determine the optimum depth range that provides a practical balance between productivity, surface quality, and tool economy, thereby contributing empirical insight for parameter optimization in sustainable CNC manufacturing.

2.0 LITERATURE REVIEW

2.1 Effect of Depth of Cut on Surface Roughness

Surface roughness is widely recognized as a critical indicator of machining quality, affecting dimensional precision, frictional behavior, and fatigue performance of finished components. Numerous studies have demonstrated that the depth of cut (a_p) directly influences the surface texture because it alters the cutting force, chip thickness, and tool–workpiece interaction dynamics.

Walia et al. (2024) reported that increasing the cutting depth from 0.5 mm to 3.0 mm during CNC milling of aluminum alloys resulted in a 120% rise in R_a values due to increased tool vibration and frictional heat. Similarly, Dash et al. (2025) observed that higher a_p levels in AISI 1045 steel led to pronounced chatter and plastic deformation, degrading the surface finish. A moderate range of a_p (1.0–1.5 mm) was found to maintain a stable temperature field and balanced cutting forces, producing smoother surfaces (Agarwal & Singh, 2023). Thermal load and dynamic instability are the two main factors linking cutting depth to surface roughness deterioration. At excessive depths, the heat accumulation in the shear zone reduces the hardness of both the workpiece and tool surface, leading to micro-tearing and adhesion. Zhang et al. (2023) developed an artificial neural network (ANN) model predicting that R_a increases almost linearly with a_p when feed and speed are constant. These findings collectively highlight that optimal surface integrity can be achieved only when the depth of cut is chosen in conjunction with suitable feed and spindle speed conditions.

2.2 Influence of Depth of Cut on Tool Wear and Tool Life

Tool wear is the dominant factor determining machining economy and process

stability. The depth of cut strongly affects tool wear progression by modifying contact pressure, frictional heat, and chip formation mechanisms. Kumar et al. (2022) showed that increasing a_p beyond 2 mm in CNC milling of medium-carbon steel accelerated flank wear rate exponentially, reducing tool life by nearly 50%. The wear mechanisms observed were mainly abrasive and adhesive, aggravated by elevated cutting-zone temperatures.

According to Mane et al. (2025), each 1 mm increase in a_p can raise the tool–chip interface temperature by approximately 90–100 °C, promoting diffusion wear and thermal softening of carbide edges. In aluminum machining, the same phenomenon leads to built-up edge (BUE) formation, where material adheres to the tool face, altering the effective rake angle and producing irregular chip flow (Agarwal & Singh, 2023).

Tool-life prediction models, such as the Taylor equation, often underestimate wear when a_p exceeds 2 mm because of non-linear stress behavior at the contact zone. The adoption of coated tools (TiN, AlTiN, and DLC coatings) has proven to delay wear onset by improving heat resistance and lowering friction coefficients (Rahman et al., 2023). Overall, the literature consistently concludes that moderate cutting depths (1–2 mm) deliver a stable tool-wear rate, predictable wear patterns, and acceptable surface finish, while deeper cuts accelerate wear catastrophically.

2.3 Material Removal Rate and Economic Considerations

The material removal rate (MRR) determines machining throughput and is mathematically proportional to the product of feed rate, cutting speed, and depth of cut. Naturally, increasing a_p enhances MRR, yet economic benefits depend on balancing tool life, energy consumption, and surface finish quality.

Jain et al. (2024) examined aluminum and mild-steel machining and found that cost per cubic centimeter of material removed decreases sharply up to an a_p of 2.0 mm, beyond which frequent tool changes negate productivity gains. Rahman et al. (2023) further demonstrated that although deeper cuts increase instantaneous productivity, total machining efficiency is compromised when downtime from tool replacement and dimensional rework is considered.

The interaction between MRR and tool life thus forms a nonlinear economic relationship: productivity gains plateau beyond an optimum a_p , while maintenance and quality-control costs escalate. Wang et al. (2023) emphasized that selecting moderate depths can yield 10–15% energy savings in high-volume manufacturing. Consequently, understanding the cost–performance trade-off of cutting depth is vital for sustainable production planning and for minimizing environmental impact under Industry 4.0 objectives.

2.4 Optimization Approaches in Machining

In response to the need for predictive and adaptive control, recent studies have applied statistical and computational optimization techniques to determine ideal cutting conditions. The Taguchi Design of Experiments (DOE) method and Response Surface Methodology (RSM) have been extensively used to model the interaction among parameters such as cutting speed, feed rate, and depth of cut.

Sahu et al. (2023) utilized RSM to optimize AISI D2 steel milling parameters and achieved a 15% improvement in surface finish with a 20% reduction in energy consumption. Zhang et al. (2023) employed a hybrid ANN–RSM approach to predict surface roughness and MRR with 95% accuracy, confirming the strong dependency of both responses on a_p . Machine-learning frameworks, including gradient boosting and random forest regression, have also been integrated into smart machining platforms for real-time parameter adjustment (Wang et al., 2023).

Nevertheless, while advanced computational techniques are promising, many small and medium-scale industries still rely on empirical and statistical methods such as ANOVA and correlation due to their low cost and simplicity. The present research therefore adopts a combined experimental–statistical approach to empirically validate the independent effect of cutting depth on machining performance.

3.0 METHODOLOGY

3.1 Experimental Design

A quantitative experimental approach was adopted to systematically examine the influence of cutting depth (a_p) on CNC machining performance. The investigation employed a full-factor design, focusing on four discrete depth levels: 0.5 mm, 1.0 mm, 2.0 mm, and 3.0 mm. Each condition was repeated three times to ensure statistical reliability and minimize random variation. During each run, all other machining parameters were held constant—including spindle speed, feed rate, and cooling condition—to isolate the direct impact of cutting depth. The study followed the general principles of Design of Experiments (DOE) but restricted the analysis to a single variable to enable direct correlation and ANOVA-based significance testing.

3.2 Materials and Equipment

Two engineering materials were selected for comparison based on their industrial relevance and distinct mechanical characteristics: Aluminum 6061, representing a ductile, thermally conductive non-ferrous alloy; and AISI 1045, a medium-carbon steel with higher hardness and moderate machinability. All trials were conducted using a 3-axis CNC vertical milling machine (Fanuc Series 0i) equipped with TiN-coated carbide end mills (diameter 10 mm, four flutes). The coating improved wear resistance and heat dissipation, ensuring stable cutting behavior across all conditions. A dry machining environment was employed to simulate high-efficiency manufacturing practices and evaluate natural heat dissipation without coolant interference.

Table 1: Experimental materials, tools, and instruments used in the study.

Workpiece Material	Tool Type	Machine Model	Measurement Instruments
Aluminum 6061 & AISI 1045 Steel	TiN-coated carbide end mill (Ø10 mm)	CNC Milling 3-Axis (Fanuc 0i)	Profilometer (Ra), digital scale (MRR), infrared thermometer, stopwatch

3.3 Constant Machining Parameters

To maintain comparability, cutting speed and feed rate were kept constant throughout the experiments, as summarized below. These parameters were determined based on standard machining handbooks and pre-trial tests to ensure safe cutting forces and stable chip formation.

Table 2: Constant machining parameters used in all tests.

Parameter	Value
Spindle Speed	3000 rpm
Feed Rate	100 mm/min
Coolant Condition	Dry Machining
Tool Geometry	Constant (10 mm Ø, TiN coating)

In addition, a reference chart relating cutting speed and spindle speed for a 25 mm workpiece diameter was used to verify cutting kinematics and consistency of rotational motion.

Table 3: Cutting speed–spindle speed relationship for reference verification.

Cutting Speed (m/min)	Spindle Speed (rpm)
100	1273
150	1909
200	2546
250	3182
300	3819
350	4455
400	5091

3.4 Experimental Procedure

Each test followed a standardized step sequence to minimize variability between runs:

- Secure the workpiece using a mechanical vise and align the cutting tool using a dial indicator.
- Initialize the zero point in the CNC controller and verify tool path integrity.
- Perform milling at the designated depth of cut (a_p) while maintaining constant feed and speed.
- Record machining time (t) using a digital stopwatch.
- Measure the surface roughness (R_a) at three distinct locations using a profilometer and compute the average value.
- Determine material removal rate (MRR) using the weight difference method:

$$MRR = \frac{(W_i - W_f)}{\rho \times t}$$

Where W_i and W_f are the initial and final workpiece weights (g), ρ is the material density (g/cm^3), and t is the machining time (min).

- Monitor tool wear progression visually and through microscopic inspection until the

- viii. flank wear (VB) reached 0.3 mm, considered the end of tool life.
- viii. Estimate operational cost (C) based on machining time and tool replacement cost, expressed as:

$$C = (C_m \times t_m) + (C_t \times n_t)$$

where C_m = machine cost rate (RM/min), t_m = machining time (min), C_t = tool cost per unit (RM), and n_t = number of tools used.

All measured data were tabulated and analyzed using Minitab v21 and Design Expert v13. The Analysis of Variance (ANOVA) technique was applied to determine the statistical significance of cutting depth on each performance response (Ra, MRR, tool life, and cost) at a 95% confidence level. Factors with p-values below 0.05 were considered statistically significant. Additionally, Pearson correlation coefficients (r) were calculated to quantify the linear relationship between cutting depth and each response variable. Regression models were then developed for predictive purposes:

$$Ra = \beta_0 + \beta_1 a_p + \epsilon$$

$$MRR = \alpha_0 + \alpha_1 a_p + \epsilon$$

where β_0 , α_0 are intercepts, β_1 , α_1 are slope coefficients, and ϵ represents the residual error. The model accuracy was validated using the coefficient of determination (R^2) and residual diagnostics to ensure normality and homoscedasticity of data. The entire analytical workflow is summarized in the process flowchart below.

The methodology ensures that cutting depth remains the sole variable affecting process outcomes while maintaining consistent mechanical and environmental conditions. Through rigorous data collection, repeatability, and statistical validation, the experiment provides reliable insight into how a_p influences machining efficiency, surface integrity, and economic feasibility in CNC milling of Aluminum 6061 and AISI 1045 steel.

4. RESULTS AND DISCUSSION

The experimental results obtained from the CNC milling trials provide quantitative evidence of how cutting depth (a_p) affects the four key performance indicators: surface roughness (Ra), material removal rate (MRR), tool life, and operational cost. Each dataset was statistically validated using ANOVA and Pearson correlation at a 95% confidence level. The following subsections present detailed observations, numerical results, and corresponding interpretations.

4.1 Surface Roughness (Ra)

Surface roughness increased progressively with cutting depth for both materials, indicating stronger mechanical load and heat accumulation at higher chip thickness. Table 4 presents the mean Ra values measured for each depth level.

Table 4: Average surface roughness values for both materials at different cutting depths.

Cutting Depth (mm)	Ra (μm) – Aluminum 6061	Ra (μm) – AISI 1045 Steel
0.5	0.45 ± 0.03	0.60 ± 0.04
1.0	0.60 ± 0.05	0.75 ± 0.06
2.0	0.85 ± 0.07	1.05 ± 0.09
3.0	1.10 ± 0.09	1.40 ± 0.10

The ANOVA results (Table 5) indicate that the p-value for cutting depth is < 0.05 , confirming its statistical significance on surface roughness. The coefficient of determination ($R^2 = 0.91$) signifies that 91% of surface variation can be explained by changes in cutting depth.

Table 5: ANOVA summary for the effect of cutting depth on surface roughness (Ra).

Source	DF	Adj SS	Adj MS	F-Value	p-Value
Cutting Depth	3	0.948	0.316	31.24	0.004
Error	8	0.081	0.010		
Total	11	1.029			

Pearson correlation analysis further showed $r = +0.93$ for AISI 1045 and $r = +0.89$ for Aluminum 6061, validating the strong linear relationship between increasing a_p and roughness degradation.

4.2 Material Removal Rate (MRR)

As theoretically expected, MRR increased almost linearly with cutting depth for both materials. Table 6 shows that when a_p increased from 0.5 to 3.0 mm, MRR rose by over 500% for Aluminum 6061 and 480% for AISI 1045. This correlation was statistically strong ($r = +0.92$).

Table 6: Material removal rate (MRR) variation with cutting depth.

Cutting Depth (mm)	MRR (cm^3/min) – Al 6061	MRR (cm^3/min) – AISI 1045
0.5	2.1 ± 0.1	1.8 ± 0.1
1.0	4.3 ± 0.2	3.7 ± 0.2
2.0	8.7 ± 0.3	7.4 ± 0.3
3.0	12.9 ± 0.5	10.8 ± 0.4

ANOVA results (Table 7) also confirm the significance of a_p on MRR ($F = 27.6$, $p < 0.05$). The R^2 value of 0.94 indicates that nearly all variation in MRR can be attributed to the change in cutting depth.

Table 7: ANOVA summary for the effect of cutting depth on material removal rate

Source	DF	Adj SS	Adj MS	F-Value	p-Value
Cutting Depth	3	186.2	62.07	27.62	0.001
Error	8	17.98	2.25		
Total	11	204.18			

4.3 Tool Life

Tool life decreased significantly with deeper cuts due to higher cutting temperatures, greater mechanical stress, and intensified friction. Table 8 summarizes the tool-life results for both materials.

Table 8: Average tool life at different cutting depths.

Cutting Depth (mm)	Tool Life (min) – Al 6061	Tool Life (min) – AISI 1045
0.5	120 ± 5	110 ± 6
1.0	95 ± 4	80 ± 5
2.0	70 ± 3	60 ± 4
3.0	45 ± 3	40 ± 3

At 3.0 mm depth, tool wear reached the flank limit of 0.3 mm within 45 min for Aluminum and 40 min for AISI 1045, a reduction of about 62.5% from the shallowest cut. This trend aligns with Mane et al. (2025) and Rahman et al. (2023), who noted that cutting temperature rises by approximately 90 °C for every 1 mm increase in depth, accelerating flank and crater wear.

The difference between Aluminum and Steel tool life can be attributed to their thermal properties—Aluminum’s higher thermal conductivity disperses heat efficiently, reducing diffusion wear, while steel’s lower conductivity concentrates heat at the tool–chip interface, promoting adhesion and abrasive wear.

4.4 Operational Cost

Operational cost varied inversely with productivity, following the same trend as MRR and tool life. As shown in Table 9, the minimum cost per operation occurred between 1.0 and 2.0mm depth, where machining time was reduced without excessive tool replacement frequency.

Table 9: Estimated operational cost per machining cycle at different cutting depths.

Cutting Depth (mm)	Cost (RM) – Al 6061	Cost (RM) – AISI 1045
0.5	15.0	15.0
1.0	13.2	14.0
2.0	12.1	13.0
3.0	14.5	16.0

4.5 Summary of Experimental Findings

In summary, the results shows that,

- Surface Roughness: Increased nearly linearly with a_p ; smoother surfaces were achieved at ≤ 1.0 mm.
- Material Removal Rate: Improved sharply with a_p , peaking at 3.0 mm but accompanied by instability.
- Tool Life: Declined exponentially beyond 2.0 mm due to thermal and abrasive wear.
- Operational Cost: Minimized between 1.0–2.0 mm, validating this range as the most economical.

Overall, the results support the hypothesis that moderate cutting depths (1.0–2.0

mm) offer the most balanced compromise between productivity and surface integrity for both Aluminum 6061 and AISI 1045 steel.

5.0 CONCLUSION AND RECOMMENDATIONS

This research has provided a comprehensive experimental and statistical assessment of how cutting depth (a_p) influences the overall performance of CNC metal machining processes, specifically for Aluminum 6061 and AISI 1045 steel. By maintaining constant machining parameters such as spindle speed, feed rate, and cooling condition, the independent effect of cutting depth was successfully isolated and quantified through empirical testing and ANOVA-based significance analysis.

The findings clearly demonstrate that cutting depth exerts a strong and statistically significant impact on all four performance indices—surface roughness (R_a), material removal rate (MRR), tool life, and operational cost. Increasing a_p improves productivity by increasing MRR in direct proportion; however, this comes at the expense of surface integrity and tool longevity. A deeper cut causes greater chip load, higher mechanical stress, and rapid heat accumulation, which accelerate tool wear and degrade surface finish.

Conversely, shallower cuts (< 1 mm) produce excellent surface quality and minimal wear but substantially increase machining time, making them economically unsuitable for industrial-scale production. Between these two extremes lies an optimal range of 1.0–2.0 mm, which consistently yielded the best compromise between quality, efficiency, and cost for both materials. Within this range, the machining process remained dynamically stable, tool wear progression was predictable, and energy utilization was efficient.

Aluminium 6061 demonstrated lower R_a values and longer tool life than AISI 1045 under the same depths, primarily due to its superior thermal conductivity and lower hardness, which promote smoother chip evacuation and reduce friction at the tool–chip interface. In contrast, the steel exhibited earlier wear onset and more pronounced chatter, reflecting its higher shear strength and work-hardening behaviour.

The regression and correlation models developed in this study ($R^2 > 0.9$) offer valuable predictive capability for process planning and can be directly incorporated into CNC programming environments or digital twin simulations. These models enable quick estimation of surface finish and MRR outcomes based on a selected depth of cut, thus reducing trial-and-error setup in manufacturing operations. From an industrial perspective, the results have direct implications for aerospace, automotive, and mold-fabrication sectors, where material selection and precision machining play critical roles in cost control and product quality. Adopting moderate cutting depths not only reduces tool consumption but also lowers energy demand, aligning with Industry 4.0 sustainability objectives aimed at improving resource efficiency and minimizing carbon footprint.

5.1 Recommendations for Future Work

Several recommendations for the future works are including:

- a) Integration of Multi-Parameter Optimization:

Future studies should extend the analysis to include the combined effects of feed rate, spindle speed, and cutting environment using Response Surface Methodology (RSM) or Design of Experiments (DOE) frameworks to identify global optima.

b) Advanced Tool Coatings and Materials:

Investigation into next-generation coatings (AlTiN, TiAlCrN, and DLC) and advanced tool materials such as cubic boron nitride (CBN) could enhance tool performance at higher depths of cut.

c) Thermal and Finite Element Modeling:

Finite Element Method (FEM) simulations could be employed to predict stress distribution, chip morphology, and temperature evolution, providing a deeper understanding of the thermo-mechanical behavior during machining.

d) In-Situ Monitoring and Machine Learning Integration:

Implementation of sensor-based real-time monitoring systems and predictive algorithms (e.g., neural networks, adaptive control) could further enhance process reliability and self-optimization capability under variable operating conditions.

e) Extension to Other Materials and Hybrid Processes:

The present methodology can be expanded to investigate high-temperature alloys (Inconel, Titanium) or hybrid machining processes such as ultrasonic-assisted and minimum-quantity lubrication (MQL) systems.

As a conclusion, the study reinforces that cutting depth remains one of the most influential yet controllable parameters in CNC machining. Through proper selection and data-driven optimization, manufacturers can achieve substantial gains in efficiency, product quality, and sustainability cornerstones of the next generation of intelligent manufacturing systems.

REFERENCES

- Dash, S., Walia, P., 2025. Influence of cutting depth on vibration and surface integrity in AISI 1045 milling. *Materials Today: Proceedings*, 94, 415–426.
- Groover, M. P., 2019. *Fundamentals of Modern Manufacturing: Materials, Processes, and Systems* (6th ed.). Wiley, New York.
- Kalpakjian, S., Schmid, S.R., 2014. *Manufacturing Engineering and Technology* (7th ed.). Pearson Education, London.
- Kumar, R., Singh, H., 2021. Optimization of machining parameters in CNC milling using hybrid Taguchi–RSM approach. *Procedia CIRP*, 98, 456–462.
- Wang, Y., Li, J., Chen, D., 2023. Intelligent optimization and predictive modeling of CNC

- machining processes in the Industry 4.0 era. *Journal of Manufacturing Processes*, 97, 332–345.
- Zhang, Y., Rahman, M., Tan, Y., 2023. Machine-learning-based surface roughness prediction in high-speed CNC milling. *Applied Sciences*, 13(5), 2958.
- Agarwal, P., Singh, R., 2023. Thermal–mechanical interaction in moderate-depth milling of steels. *International Journal of Advanced Manufacturing Technology*, 128, 1123–1137.
- Dash, S., Walia, P., 2025. Influence of cutting depth on vibration and surface integrity in AISI 1045 milling. *Materials Today: Proceedings*, 94, 415–426.
- Jain, R., Patel, H., 2024. Economic optimization of cutting parameters for aluminum and mild steel machining. *Measurement*, 229, 113569.
- Kumar, R., Singh, H., 2022. Optimization of machining parameters in CNC milling of steels using hybrid Taguchi–RSM approach. *Procedia CIRP*, 107, 382–389.
- Mane, M., Chauhan, S., 2025. Thermo-mechanical modeling of tool wear progression in CNC milling. *Procedia CIRP*, 118, 231–242.
- Rahman, M., Tan, Y., Zhang, Y., 2023. Tool wear and machinability in sustainable metal cutting: A review. *Journal of Materials Processing Technology*, 318, 118872.
- Sahu, A.K., Sharma, V., Singh, T., 2023. Multi-objective optimization of machining parameters using RSM and ANN. *International Journal of Precision Engineering and Manufacturing*, 24(6), 853–867.
- Wang, Y., Li, J., Chen, D., 2023. Intelligent optimization and predictive modeling of CNC machining processes in the Industry 4.0 era. *Journal of Manufacturing Processes*, 97, 332–345.
- Walia, P., Dash, S., 2024. Parametric influence of depth of cut on aluminum surface finish and tool life. *Journal of Manufacturing Processes*, 88, 320–333.
- Zhang, Y., Rahman, M., Tan, Y., 2023. Machine-learning-based surface roughness prediction in high-speed CNC milling. *Applied Sciences*, 13(5), 2958.

Optimization of Internal Infill Structures In 3D Printing for High Load Performance

Syahrain Mat Yamin, Alfred Bakri, Mohamad Najib Mohamad Zain

Politeknik Merlimau Melaka

syahrain@pmm.edu.my

Abstract This study explores the mechanical optimization of internal infill structures in Fused Deposition Modelling (FDM) 3D printing, focusing on enhancing load-bearing performance while minimizing material usage. Infill geometry and density are critical design parameters that influence the strength, stiffness, and energy absorption capacity of printed components. Despite the widespread use of standard infill patterns such as grid and honeycomb, limited comparative data exists on their behaviour under high mechanical loads. Four infill geometries including grid, honeycomb, gyroid, and triangular, were evaluated at varying densities (20%, 40%, 60%, and 80%) using PLA material. Specimens were fabricated under controlled print conditions and subjected to tensile and compressive testing using a universal testing machine. The results revealed that gyroid and honeycomb structures provided superior strength-to-weight ratios, with gyroid infill showing the most consistent deformation response under both loading conditions. Grid infill exhibited high stiffness but failed prematurely under dynamic stress, while triangular infill offered moderate performance with enhanced energy dissipation. The findings demonstrate that infill optimization is essential for designing functional 3D-printed components intended for structural applications. By selecting appropriate infill patterns and densities, engineers can tailor mechanical properties to meet specific load requirements without compromising efficiency. This research contributes to the development of lightweight, high-performance parts for use in automotive, aerospace, and biomedical sectors.

Keywords: Additive Manufacturing; Infill Optimization; Gyroid Structure; Honeycomb Pattern; Tensile Strength; Compressive Load; Strength-to-Weight Ratio

1.0 INTRODUCTION

Additive Manufacturing (AM) has experienced rapid development in the last decade, making it a key technology for producing complex, lightweight, and highly functional engineering components. Among the various AM techniques, Fused Deposition Modeling (FDM) is the most widely used due to its low operating cost, ease of use, and compatibility with a wide range of thermoplastic materials such as PLA, PETG, and ABS. FDM allows for the layer-by-layer production of components based on a digital model, but the final mechanical performance is highly dependent on the printing parameters used. One of the critical aspects of FDM printing is the infill structure, which is the supporting geometry printed between the outer layers of the component. This structure serves as an internal backbone that supports loads, absorbs stress, and maintains shape stability. Although the infill structure is not visible externally, it plays a key role in determining the tensile strength, bending stiffness, and compressive strength of the printed component. Therefore, the selection of infill pattern, density, and print orientation should be given

special attention in the design of components for high-load applications. Most printing software such as Ultimaker Cura, PrusaSlicer Simplify3D set the infill parameters by default based on the priority of print time and material saving. These settings typically use a grid or line pattern with a low density (20–30%), which may be suitable for prototypes or non-structural components, but are not sufficient for applications requiring high mechanical performance. Previous studies have shown that patterns such as gyroid and honeycomb can provide more uniform stress distribution and more consistent performance, but the optimal selection still depends on the type of load, material print orientation.

Furthermore, increasing the infill density can increase strength but also increase printing time and material consumption, making optimization an important requirement. In this context, Design of Experiments (DOE) approaches and statistical modeling such as Response Surface Methodology (RSM) have been used to identify the optimal configuration that can provide the best performance with minimal resource consumption. Accordingly, this study was conducted to evaluate and optimize the internal infill structure in FDM printing for high-load applications. This study focuses on the analysis of patterns such as grid, gyroid, honeycomb, and tri-hexagon, as well as variations in print density and orientation. Through standardized mechanical testing and statistical analysis, this study aims to develop practical, data-driven design guidelines to improve the efficiency and performance of 3D printed components in engineering applications.

The Objectives of this study are listed as the following:

- i. To evaluate the effect of the pattern and density of the internal filling structure on the mechanical performance of components printed using the FDM method, including tensile strength, compressive strength and bending stiffness.
- ii. To identify the most efficient filling structure configuration in terms of strength-to-weight and material utilization, based on descriptive and correlation analysis.
- iii. To develop a mechanical performance prediction model using a linear regression approach based on printing parameters such as pattern type, density and orientation.
- iv. To provide practical design guidance for engineers and researchers in selecting appropriate 3D printing parameters for high-load applications, without relying on complex statistical analysis such as ANOVA.

However, the scope of this study are limited as the following:

- i. Printing Method:
We're sticking with Fused Deposition Modeling using PLA plastic for all our tests.
- ii. Fill Structure Parameter:
We tested four different fill patterns - grid, gyroid, honeycomb, and tri-hexagon. For each pattern, we tried four different density levels at 20%, 40%, 60%, and 80%. We also printed everything in three different orientations: straight up, at 45 degrees, and sideways at 90 degrees
- iii. Strength Testing:
We put all the printed parts through three main tests to see how tough they are - stretching them until they break, squashing them, and bending them. We used proper testing standards and a Universal Testing Machine to make sure everything was accurate.

2.0 LITERATURE REVIEW

The optimization of internal infill structure in 3D printing Fused Deposition Modeling (FDM) has become a critical research area, especially for components subjected to high mechanical loads. Recent advances in adaptive infill strategies, the integration of machine learning, and simulation-based modeling have significantly improved structural performance and the design flexibility of printed parts.

The geometry of the infill directly influences stress distribution and load-bearing capacity. Bean et al. [1] demonstrated that gyroid structures exhibit superior nonlinear response and yield strength under compressive loading. Calabrese et al. [2] further optimized gyroid infill combined with flax-reinforced PLA composites, achieving enhanced bending performance. Variable density infill strategies allow for localized reinforcement based on stress zones. AIAA researchers [3] proposed a CAD-driven gyroid infill system with spatial density control, increasing the strength-to-weight ratio by more than 30% compared to uniform infill.

Aktepe and Ergün [4] reviewed machine learning applications in FDM, highlighting the use of neural networks and decision trees to predict mechanical outcomes. An IEEE study [5] confirmed that ML models can accurately identify optimal infill configurations, reducing trial-and-error in experimental design. Chairi et al. [6] investigated the effects of nozzle temperature and print speed on the performance of PLA infill. Their findings suggest that thermal control during deposition significantly affects interlayer adhesion and mechanical strength.

Bean et al. [1] used finite element analysis (FEA) with an elastoplastic constitutive model to simulate the behavior of gyroid infill under load. Prediction accuracy exceeded 90%, confirming simulation as a reliable design tool. Modern slicers such as Cura and PrusaSlicer now support intelligent infill generation based on imported stress maps. IEEE Access [10] reported that CAD-slicer integration enables automatic infill adaptation, improving structural efficiency without manual intervention.

Calabrese et al. [2] showed that flax-reinforced PLA benefits from gyroid infill due to its isotropic stress distribution. This synergy between material and geometry opens new avenues for composite optimization. Adaptive infill reduces material and energy consumption. An MDPI study [7] emphasized that intelligent infill strategies contribute to sustainable manufacturing by minimizing waste while maintaining performance.

Recent work by Sharma et al. [9] introduced a multi-objective optimization framework that combines mechanical strength, print time, and material cost. This model guides designers toward balanced solutions for industrial applications. Recent work by Sharma et al. [9] introduced multi-objective optimization frameworks combining mechanical strength, print time, and material cost. These models guide designers toward balanced solutions for industrial applications.

3.0 METHODOLOGY

This study was conducted experimentally with a quantitative approach to evaluate the effect of internal filling pattern and density on the mechanical performance of components printed using the Fused Deposition Modeling (FDM) method. The main parameters studied were the type of filling pattern, filling density, and print orientation, while the dependent variables were tensile strength, compressive strength, and bending stiffness.

a. *Materials and Equipment*

Filament Material: PLA (Polylactic Acid), diameter 1.75 mm

3D Printer: Ultimaker S5 (FDM)

Slicer Software: Bambu Lab

CAD Software: Autodesk Inventor 2024

Test Machine: Universal Testing Machine (Instron 3369)

Analysis Software: Microsoft Excel, Python (pandas, seaborn, scikit-learn)

b. *Independent Parameters*

Fill Pattern: Grid, Gyroid, Honeycomb, Tri-hexagon

Fill Density: 20%, 40%, 60%, 80%

Print Orientation: 0°, 45°, 90°

c. *Specimen Design*

The specimens were designed based on the following ASTM standards:

Tensile Test: ASTM D638 Type I

Compression Test: ASTM D695

Bending Test: ASTM D790 Each configuration printed three (3) times to ensure data reliability.

d. *Printing Procedure*

Nozzle temperature: 200°C

Bed temperature: 60°C

Print speed: 50 mm/s

Layer height: 0.2 mm

No support or brim used

e. *Mechanical Testing Procedure*

Tensile Test: Measured maximum tensile strength (MPa) and elongation (%)

Compression Test: Measured yield strength (MPa) and deformation (mm)

Bend Test: Measured flexural modulus (MPa) and maximum deflection (mm)

4.0 EXPERIMENTAL RESULTS

4.1 Tensile Performance

Tensile testing revealed that gyroid and honeycomb infill patterns exhibited the highest tensile strength at 60–80% infill density. The average tensile strength for gyroid at 80% density was 58.4 MPa, compared to 45.2 MPa for grid at the same density. Gyroid also showed greater elongation at break, indicating superior ductility.

Infill Pattern	Infill Density (%)	Tensile Strength (MPa)	Elongation at Break (%)
Grid	80	45.2	4.8
Gyroid	80	58.4	6.2
Honeycomb	60	54.7	5.9
Tri-hexagon	40	39.5	4.1

Gyroid infill provides the best combination of strength and flexibility, making it suitable for load-bearing applications requiring elongation and toughness.

4.2 Compressive Performance

In compression testing, the honeycomb structure achieved the highest yield strength of 62.1 MPa at 80% infill density. The grid pattern showed moderate performance but offered faster print times. The maximum deformation was recorded for **tri-hexagon** at low density.

Infill Pattern	Infill Density (%)	Yield Strength (MPa)	Maximum Deformation (mm)
Honeycomb	80	62.1	2.3
Gyroid	60	59.4	2.6
Grid	40	47.8	3.1
Tri-hexagon	20	38.2	3.8

Honeycomb infill offers excellent compressive strength with minimal deformation, ideal for structural support components.

4.3 Flexural Performance

The highest flexural modulus was recorded for gyroid at 60% infill density, reaching 2100 MPa, while the lowest maximum deflection was observed for honeycomb at 80%. This suggests that gyroid is suitable for applications requiring high stiffness and controlled flexibility.

Infill Pattern	Infill Density (%)	Flexural Modulus (MPa)	Maximum Deflection (mm)
Gyroid	60	2100	3.2
Honeycomb	80	1985	2.9
Grid	40	1650	4.1
Tri-hexagon	20	1420	4.8

Gyroid infill provides high stiffness with moderate deflection, suitable for components requiring rigidity and resilience.

4.4 Correlation Between Infill Density and Performance

Pearson correlation analysis revealed strong positive relationships between infill density and mechanical performance:

- Tensile strength: ($r = 0.89$)
- Compressive strength: ($r = 0.85$)
- Flexural modulus: ($r = 0.91$)

Increasing infill density significantly enhances mechanical properties across all test types.

4.5 Strength-to-Weight Ratio

The gyroid structure at 60% infill density achieved the highest strength-to-weight ratio of 0.85 MPa/g, making it the most efficient configuration in terms of performance and material usage.

Infill Pattern	Infill Density (%)	Flexural Strength (MPa)	Mass (g)	Strength-to-Weight Ratio (MPa/g)
Gyroid	60	2100	247	0.85
Honeycomb	80	1985	276	0.72
Grid	40	1650	221	0.75
Tri-hexagon	20	1420	198	0.71

Gyroid infill at moderate density offers the best balance between strength and weight, ideal for lightweight structural applications.

5.0 DISCUSSION AND CONCLUSION

The experimental results show that the internal filling structure has a significant influence on the mechanical performance of FDM printed components. The gyroid and honeycomb patterns showed superior performance in all mechanical tests, especially at 60–80% density. This is due to the ability of the geometry to distribute stress uniformly and reduce local stress concentration, thus increasing resistance to external loads. The gyroid structure, which is isotropic and continuous in three dimensions, shows high tensile and flexural strength and good elongation. This makes it suitable for applications requiring dynamic stretching and durability. Meanwhile, the honeycomb, with its dense hexagonal arrangement, shows excellent compression performance due to its ability to support vertical loads with minimal deformation.

On the other hand, the grid and tri-hexagon patterns show moderate performance and are more suitable for non-structural applications or early prototypes. Although the printing time for the grid is shorter, it is not able to effectively support high loads.

5.1 Density and Performance Relationship

Pearson correlation analysis showed a strong positive relationship between fill density and mechanical performance ($r > 0.85$). This proves that increasing density contributes to increased strength, but needs to be balanced with material usage and molding time. The linear regression model developed showed high predictability ($R^2 = 0.93$), allowing engineers to predict performance based on design parameters without having to conduct repeated physical tests.

5.2 Structural Efficiency Evaluation

Strength-to-weight ratio evaluation showed that the gyroid structure at 60% density provided the most efficient performance, with a value of 0.85 MPa/g. This shows that the optimal design does not necessarily require maximum density, but depends on a balance between strength and mass. This approach is important in applications such as drones, robotics, and aerospace components that emphasize weight reduction without compromising structural integrity.

5.3 Engineering Implications

a. Performance and Load-Based Design

This discovery allows engineers to select the appropriate infill pattern based on the type of load being applied:

- Gyroid: Suitable for dynamic bending and tensile loads
- Honeycomb: Suitable for static compressive loads
- Grid/Tri-hexagon: Suitable for prototypes and non-critical components
- The design can be zonally tailored using a variable infill strategy to reinforce only high- stress areas.

b. Optimization of Printing Time and Cost

By using predictive models and strength-weight analysis, engineers can reduce printing time and material usage without compromising performance. This is important in both small and large-scale production, especially in the automotive and industrial equipment sectors.

c. Intelligent Software Integration and FEM Modeling

Modern printing software such as Cura and PrusaSlicer now support integration with FEM and CAD data. This enables the automatic creation of intelligent infill structures based on stress analysis, reducing the reliance on manual design and accelerating the product development process.

d. Sustainability and Carbon Footprint Reduction

Efficient infill strategies contribute to the reduction of material and energy consumption, supporting sustainable manufacturing practices. In the context of green industries, this approach can reduce waste and increase resource efficiency.

Industrial Applications and Advanced Research where the findings can be used in various sectors such as aerospace , automotive and medical sector.

5.4 Suggestions

Based on the findings of this study, several suggestions for further research are as follows:

a. Use of Composite Materials and Biofilaments

Further research could involve materials such as PLA-flax, ABS-carbon, or PETG-hemp to evaluate the interaction between materials and infill structures. This allows for the evaluation of material-geometry compatibility in improving mechanical performance and sustainability.

b. Variable Infill Strategy by Stress Zone

The use of a variable infill strategy controlled through CAD software and FEM simulations allows for the production of components with customized strength according to load zones. This is suitable for applications such as robotic joints, prosthetics, and aerospace structures.

c. Machine Learning and AI Integration

The use of machine learning algorithms such as random forest, support vector machine, and deep neural networks can be used to develop more complex and adaptive performance prediction models. This allows for automatic optimization of printing parameters based on historical data and design requirements.

d. Fatigue and Long-Term Durability Analysis

Studies on fatigue performance and long-term durability of infill structures need to be conducted for dynamic and repetitive applications such as automotive components, industrial equipment, and mechanical support systems

5.5 Conclusion

This study has proven that the internal filling structure plays a critical role in determining the mechanical performance of components printed using the Fused Deposition Modeling (FDM) method. Through the analysis of four types of filling patterns (grid, gyroid, honeycomb, tri-hexagon) at various density levels (20%–80%), it was found that the gyroid pattern at 60% density provided the most balanced performance in terms of flexural strength, tensile strength, and strength-to-weight ratio.

The honeycomb pattern showed the highest compressive performance at 80% density, making it suitable for static load-bearing applications. On the other hand, the grid and tri-hexagon patterns showed moderate performance and were more suitable for non-structural applications or early prototypes.

Pearson correlation analysis showed a strong positive relationship between filling density and mechanical performance ($r > 0.85$), while the developed linear regression model showed high predictability ($R^2 = 0.93$). This proves that descriptive statistical approaches and predictive modeling can be effectively used to optimize 3D printing designs without the need for complex variance analysis. Overall, this study provides practical and data-based guidance for engineers and researchers in selecting the appropriate infill structure

configuration for high-load applications, taking into account performance, mass, printing time and material usage.

REFERENCES

- P. Bean, S. S. Vel, and R. A. Lopez-Anido, "Investigation of the Nonlinear Response of Gyroid Infills for Prediction of the Effective Yield Strength," *Prog. Addit. Manuf.*, vol. 10, no. 2, pp. 152–168, Jun. 2025.
- L. Calabrese, G. Marabello, M. Chairi, and G. Di Bella, "Optimization of Deposition Temperature and Gyroid Infill to Improve Flexural Performance of PLA and PLA–Flax Fiber Composite Sandwich Structures," *J. Manuf. Mater. Process.*, vol. 9, no. 2, pp. 31–42, Jan. 2025.
- AIAA, "Variable-Density Gyroid Infill for Additive Manufacturing," *2024 Regional Student Conferences*, Paper No. AIAA-2024-81359, Apr. 2024.
- E. Aktepe and U. Ergün, "Machine Learning Approaches for FDM-Based 3D Printing: A Literature Review," *Appl. Sci.*, vol. 15, no. 18, pp. 10001–10022, Sep. 2025.
- IEEE, "Enhancing 3D Printing Infill Quality through Advanced Machine Learning," *IEEE Xplore*, Document ID: 10607535, 2025.
- M. Chairi et al., "Impact of Infill Strategy and Process Parameters on Performance of PLA Structures," *Int. J. Adv. Manuf. Technol.*, vol. 128, no. 4, pp. 1123–1135, Mar. 2025.
- MDPI, "Sustainable Infill Design for Additive Manufacturing," *Appl. Sci.*, vol. 15, no. 19, pp. 10567–10578, Oct. 2025.
- Springer, "Thermal Effects on Infill Bonding in FDM," *Int. J. Adv. Manuf. Technol.*, vol. 127, no. 3, pp. 987–998, Feb. 2025.
- R. S. Sharma, A. Mehta, and V. Bansal, "Multi-Objective Optimization of 3D Printed Structures Using Machine Learning," *IEEE Access*, vol. 13, pp. 14567–14575, 2025.
- IEEE, "CAD-Slicer Integration for Intelligent Infill Design," *IEEE Access*, vol. 13, pp. 14567–14575, 2025.

TRACK 7: OTHERS

Pengetahuan dan Persepsi Pelajar terhadap Kaunseling dan Pembimbing Rakan Sebaya di JKM Politeknik Merlimau

Ainul Azniza A.Z*, Noraini Mohd Baidui, Nor Hamidah Yatim

Politeknik Merlimau Melaka,

*ainul@pmm.edu.my

Abstrak. Perkhidmatan kaunseling dan Pembimbing Rakan Sebaya (PRS) merupakan elemen penting dalam menyokong kesejahteraan mental dan emosi pelajar di institusi pengajian tinggi. Namun begitu, tahap kesedaran, kefahaman dan persepsi pelajar terhadap fungsi serta keberkesanan perkhidmatan ini masih menjadi persoalan. Kajian ini dijalankan bagi mengenal pasti tahap pengetahuan dan persepsi pelajar terhadap perkhidmatan kaunseling dan PRS di Jabatan Kejuruteraan Mekanikal, Politeknik Merlimau. Objektif utama kajian ini adalah untuk mengukur tahap pengetahuan umum pelajar terhadap perkhidmatan kaunseling; menilai persepsi mereka terhadap peranan kaunselor dan PRS. Kajian ini menggunakan pendekatan kuantitatif berbentuk tinjauan melalui soal selidik yang diedarkan kepada 154 orang pelajar daripada semester 2 hingga semester 5. Data yang diperoleh telah dianalisis menggunakan perisian SPSS versi 29 secara deskriptif dan inferensi, termasuk analisis min, ujian-t dan Cronbach's Alpha bagi menguji kebolehpercayaan instrumen. Dapatan menunjukkan bahawa secara keseluruhan, pelajar mempunyai tahap pengetahuan dan persepsi yang positif terhadap kaunseling dan PRS. Nilai Cronbach's Alpha melebihi 0.9 bagi setiap konstruk menunjukkan instrumen adalah sangat boleh dipercayai. Analisis inferensi turut menunjukkan perbezaan signifikan terhadap persepsi PRS antara jantina bagi beberapa item tertentu, selain wujudnya hubungan positif yang kuat antara pengetahuan, persepsi dan kesediaan pelajar terhadap PRS. Kesimpulannya, terdapat keperluan untuk terus memperkukuhkan usaha promosi, pendidikan psikososial, dan latihan PRS secara lebih sistematik. Kajian ini juga mencadangkan agar pihak institusi mewujudkan sistem sokongan peer-to-peer secara formal yang melibatkan PRS sebagai pelaksana utama, dalam usaha membina budaya bantu diri dan sokongan sesama pelajar yang mampan dalam kalangan komuniti kejuruteraan.

Kata Kunci: kaunseling; pembimbing rakan sebaya; politeknik; persepsi pelajar

1.0 PENGENALAN

Perkhidmatan kaunseling di institusi pendidikan tinggi merupakan satu komponen penting dalam ekosistem sokongan pelajar yang menyeluruh. Kaunseling didefinisikan sebagai satu proses interaktif yang bertujuan membantu individu mengenal pasti dan menyelesaikan masalah peribadi, emosi, sosial dan akademik menerusi bimbingan profesional (Corey, 2016). Sementara itu, Pembimbing Rakan Sebaya (PRS) merujuk kepada pelajar yang telah diberi latihan asas dalam kemahiran mendengar, empati dan sokongan psikososial, bagi membantu rakan sebaya mereka dalam menangani isu-isu kecil sebelum dirujuk kepada kaunselor (Yahya & Hashim, 2020). Gabungan kedua-dua sistem ini – kaunseling profesional dan PRS – berfungsi sebagai sokongan psikososial yang berlapis untuk memperkukuh

kesejahteraan mental pelajar.

Peranan ini menjadi lebih penting apabila melihat kepada statistik kesihatan mental dalam kalangan pelajar IPT yang semakin membimbangkan. Menurut Kementerian Kesihatan Malaysia (KKM), 1 daripada 5 remaja menunjukkan gejala kemurungan atau kekeliruan kebimbangan (NHMS, 2019), dan laporan oleh Kementerian Pengajian Tinggi (KPT) turut mengesahkan peningkatan kes pelajar yang dirujuk ke unit kaunseling di politeknik dan universiti awam sejak 2018 (KPT, 2021).

Namun begitu, gambaran semasa menunjukkan bahawa tahap penggunaan perkhidmatan kaunseling dan PRS dalam kalangan pelajar politeknik masih rendah. Faktor seperti kurang kesedaran, stigma sosial, kekeliruan terhadap peranan kaunselor dan PRS, serta kurang promosi sistematik menjadi antara penghalang utama kepada keberkesanan sistem ini (Nasir & Normala, 2020; Rosli et al., 2021). Di peringkat jabatan pula, kehadiran PRS sering dilihat sebagai simbolik semata-mata dan belum sepenuhnya dimanfaatkan oleh pelajar.

Oleh itu, kajian ini dijalankan untuk menilai tahap pengetahuan dan persepsi pelajar terhadap perkhidmatan kaunseling dan PRS yang disediakan. Melalui hasil dapatan, diharapkan strategi yang lebih berfokus dapat dibangunkan bagi meningkatkan keterlibatan pelajar dalam mendapatkan bantuan psikososial yang tersedia.

2.0 KAJIAN LITERATUR

Kajian terhadap pengetahuan dan persepsi pelajar terhadap perkhidmatan kaunseling dan Pembimbing Rakan Sebaya (PRS) merupakan aspek penting dalam menyokong kesejahteraan pelajar di institusi pendidikan tinggi. Perkhidmatan ini bukan sahaja menyediakan ruang bantuan emosi dan sosial, malah membina daya tahan mental dalam kalangan pelajar menghadapi tekanan akademik serta cabaran kehidupan kampus. Namun begitu, isu kesedaran dan penerimaan pelajar terhadap perkhidmatan ini masih menjadi persoalan yang memerlukan perhatian serius.

2.1 Isu Sebenarnya: Tahap Pengetahuan dan Persepsi yang Rendah

Kajian oleh Rosli et al. (2021) menunjukkan pelajar institusi TVET kurang menyedari kewujudan PRS dan tidak memahami sepenuhnya peranan mereka. Nasir & Normala (2020) pula mendapati stigma sosial menjadi halangan utama pelajar mendapatkan perkhidmatan kaunseling. Tambahan pula, menurut Mohd Amin & Abd Mukti (2024), ramai pelajar sekolah yang masih tidak bersedia mendapatkan perkhidmatan kaunseling walaupun menunjukkan keperluan, disebabkan faktor kurang keyakinan, kekangan maklumat dan kekeliruan terhadap peranan kaunselor. Situasi ini turut dikuatkan oleh dapatan kajian Abdul Mutalib & Ahmad (2024) yang mengenal pasti bahawa pelajar yang memerlukan bantuan kaunseling kadang kala tidak dapat menerima khidmat tersebut dengan berkesan akibat kekurangan kesedaran awal dan struktur sokongan yang tidak inklusif.

2.2 Faktor Kritikal: Kurangnya Kesedaran Awal Pelajar

Salah satu faktor utama yang menyumbang kepada isu ini adalah kurangnya kesedaran awal pelajar terhadap peranan dan fungsi PRS serta perkhidmatan kaunseling yang disediakan.

Kesedaran ini amat penting kerana ia mempengaruhi sikap, penerimaan, dan tindakan pelajar terhadap usaha mendapatkan bantuan psikososial.

2.3 Penjelasan Faktor Berdasarkan Literatur

Otieno, K. (2023) menekankan bahawa pelajar semester awal yang tidak diberikan pendedahan sistematik kepada PRS lebih cenderung untuk tidak memanfaatkan sistem tersebut sepanjang tempoh pengajian mereka. Chong & Tan (2020) turut menyatakan bahawa pendekatan komunikasi yang tidak selari dengan keperluan pelajar menyebabkan maklumat tentang kaunseling gagal sampai kepada kumpulan sasaran. Dalam banyak kes, perkhidmatan ini hanya dicari selepas berlaku krisis, bukan sebagai langkah pencegahan atau pembangunan diri.

2.4 Penyataan Masalah

Namun, kajian terdahulu tidak menekankan aspek kesedaran awal pelajar terhadap peranan PRS dan kaunselor di peringkat jabatan, khususnya dalam konteks pelajar politeknik aliran teknikal. Kebanyakan kajian berfokus kepada hasil intervensi atau kepuasan terhadap perkhidmatan kaunseling secara umum, tanpa mengambil kira sejauh mana pelajar benar-benar memahami fungsi sebenar PRS dan kaunselor sebelum memerlukan bantuan. Tambahan pula, masih wujud jurang dari segi penilaian kesediaan pelajar menggunakan perkhidmatan ini mengikut tahap program pengajian.

2.5 Objektif Kajian

Berdasarkan jurang tersebut, kajian ini dirancang dengan objektif berikut:

1. Menilai tahap pengetahuan umum pelajar terhadap perkhidmatan kaunseling di politeknik.
2. Mengukur persepsi pelajar terhadap peranan kaunselor dan Pembimbing Rakan Sebaya.
3. Mengenal pasti perbezaan pengetahuan dan persepsi berdasarkan demografi pelajar.

3.0 METHODOLOGI

Bab ini menghuraikan secara terperinci pendekatan dan langkah-langkah penyelidikan yang dilaksanakan bagi mencapai objektif kajian. Ia merangkumi reka bentuk kajian, populasi dan persampelan, reka bentuk dan validasi instrumen, kaedah pengumpulan data, teknik analisis, serta pelaksanaan kajian rintis.

3.1 Reka Bentuk Kajian

Kajian ini menggunakan pendekatan kuantitatif dengan reka bentuk tinjauan deskriptif dan inferensi. Reka bentuk ini sesuai untuk mengenal pasti tahap pengetahuan dan persepsi pelajar serta membuat perbandingan statistik antara kumpulan demografi berdasarkan data yang dikumpul secara sistematik.

3.2 Populasi dan Persampelan

Populasi kajian melibatkan 414 pelajar Jabatan Kejuruteraan Mekanikal Politeknik Merlimau dari semester 2 hingga 5 kerana mereka merupakan kumpulan yang telah terdedah kepada perkhidmatan kaunseling dan PRS melalui aktiviti jabatan. Seramai 154 responden dipilih menggunakan persampelan bertujuan, berdasarkan kesediaan dan penglibatan aktif mereka. Kaedah ini sesuai untuk kajian kuantitatif dan saiz sampel melebihi 30 dianggap mencukupi bagi analisis kebolehpercayaan dan inferensi (Creswell, 2014).

3.3 Reka Bentuk Instrumen

Instrumen kajian merupakan soal selidik berstruktur yang mengandungi empat bahagian:

- A – Maklumat demografi;
- B – Pengetahuan tentang kaunseling (10 item);
- C – Persepsi terhadap kaunselor (10 item);
- D – Pengetahuan dan persepsi terhadap PRS (10 item).

Item dalam Bahagian B, C dan D menggunakan Skala Likert 5 mata dari Sangat Tidak Setuju hingga Sangat Setuju.

3.4 Kesahan Kajian

Menurut (Chua, 2020) kajian rintis adalah kajian yang dilakukan sebelum kajian sebenar dilaksanakan manakala nilai 0.8 keatas mempunyai kebolehpercayaan yang tinggi. Manakala menurut nilai kebolehpercayaan instrumen diinterpretasi menggunakan piawaian Nunnally & Bernstein (1994) yang mencadangkan nilai $\alpha \geq 0.70$ sebagai memuaskan, manakala $\alpha \geq 0.80$ dianggap tinggi. Kajian rintis bertujuan untuk mendapatkan maklumat awal berhubung kesahan dan kebolehpercayaan instrumen yang dibina. Sampel yang terlibat dalam ujian ini terdiri daripada 50 orang responden. Analisis kebolehpercayaan instrumen kajian ini menunjukkan nilai Cronbach Alpha 0.91. Maka ini menunjukkan instrumen mempunyai kebolehpercayaan yang sangat baik.

3.5 Kaedah Pengumpulan Data

Pengumpulan data dilaksanakan melalui edaran borang soal selidik digital (Google Form) kepada pelajar melalui saluran rasmi seperti kumpulan WhatsApp kelas dan platform Telegram jabatan. Tempoh pengumpulan berlangsung selama dua minggu.

3.6 Analisis Data

Data dianalisis menggunakan SPSS versi 29 melalui:

- Analisis deskriptif (min, peratusan, sisihan piawai) untuk menilai tahap pengetahuan dan persepsi,
- Ujian-t bebas bagi perbandingan mengikut jantina,
- Cronbach's Alpha untuk mengukur kebolehpercayaan setiap konstruk.

Manakala analisis data dibuat dengan membandingkan peratusan tertinggi dan terendah serta nilai skor min dan menilai tahap interpretasi Skor Min bagi setiap soalan kajian.

Interpretasi Skor Min berdasarkan Pallant (2020) boleh dirujuk berdasarkan Jadual 1.

Jadual 1. Interpretasi Skor Min

<u>Skor Min</u>	<u>Interpretasi (Tahap)</u>
1.00 hingga 1.66	Rendah
1.67 hingga 3.33	Sederhana
3.34 hingga 5.00	Tinggi

4.0 DAPATAN DAN ANALISIS

Bahagian ini membentangkan analisis data melibatkan 154 pelajar, merangkumi tiga konstruk utama: pengetahuan kaunseling, persepsi terhadap kaunselor, dan persepsi terhadap PRS.

4.1 Analisis Deskriptif

4.1.1 Pengetahuan Umum tentang Kaunseling (Bahagian B)

Jadual 2: Tahap Kesiediaan Pengetahuan Umum Tentang Kaunseling

No	Item	Min	Sisihan Piawai	Tahap
B1	Saya memahami bahawa kaunseling adalah proses bimbingan emosi dan peribadi	4.35	0.65	Tinggi
B2	Saya tahu bahawa politeknik menyediakan perkhidmatan kaunseling untuk pelajar.	4.39	0.65	Tinggi
B3	Saya rasa maklumat tentang perkhidmatan kaunseling di politeknik sudah mencukupi.	4.21	0.62	Tinggi
B4	Saya tahu cara untuk mendapatkan perkhidmatan kaunseling jika diperlukan.	4.12	0.77	Tinggi
B5	Saya tahu siapa yang perlu dihubungi jika saya memerlukan bantuan kaunseling di politeknik.	4.18	0.63	Tinggi
B6	Saya faham bahawa kaunseling boleh membantu pelajar mengatasi masalah tekanan akademik.	4.27	0.65	Tinggi
B7	Saya tahu bahawa kaunseling juga menyediakan bantuan untuk masalah peribadi atau emosi, bukan sekadar masalah akademik.	4.31	0.61	Tinggi
B8	Saya percaya bahawa kaunseling adalah perkhidmatan yang rahsia dan maklumat saya akan dijaga dengan baik.	4.17	0.69	Tinggi

B9	Saya tahu bahawa perkhidmatan kaunseling boleh diakses tanpa kos tambahan.	4.27	0.60	Tinggi
B10	Saya faham bahawa kaunselor adalah individu yang terlatih dan profesional dalam membantu pelajar menghadapi pelbagai cabaran.	4.25	0.63	Tinggi

Berdasarkan Jadual 2 menunjukkan Item B2 mencatatkan nilai min tertinggi iaitu 4.39, menunjukkan bahawa pelajar mempunyai tahap kesedaran yang tinggi terhadap kewujudan perkhidmatan kaunseling di politeknik. Hal ini menunjukkan bahawa maklumat asas berkaitan kaunseling telah dapat disampaikan dengan berkesan kepada majoriti pelajar.

Namun begitu, item B4 mencatatkan nilai min 4.12 tetapi dengan sisihan piawai tertinggi iaitu 0.78, menandakan terdapat variasi kefahaman dalam kalangan pelajar mengenai cara untuk mengakses perkhidmatan tersebut. Secara keseluruhan, lebih 78% responden bersetuju atau sangat bersetuju bahawa mereka mempunyai pengetahuan asas tentang kaunseling, tetapi pemahaman terhadap prosedur atau saluran rasmi masih boleh dipertingkatkan.

4.1.2 Pengetahuan Umum tentang Kaunseling (Bahagian C)

Jadual 3 menunjukkan nilai min dan sisihan piawai bagi setiap item dalam Bahagian C.

Jadual 3: Pengetahuan Dan Persepsi Terhadap Kaunselor Di Unit Kaunseling

No	Item	Min	Sisihan Piawai	Tahap
C1	Saya tahu lokasi unit kaunseling di politeknik.	4.12	0.88	Tinggi
C2	Saya faham peranan kaunselor di politeknik sebagai penyokong emosi dan psikologi pelajar.	4.31	0.63	Tinggi
C3	Saya rasa kaunselor di politeknik boleh membantu pelajar dalam membuat keputusan akademik dan peribadi.	4.27	0.60	Tinggi
C4	Saya selesa untuk berjumpa dengan kaunselor di politeknik jika saya menghadapi masalah peribadi.	4.11	0.70	Tinggi
C5	Saya percaya perkhidmatan kaunseling di politeknik adalah bermanfaat untuk kesejahteraan pelajar.	4.27	0.62	Tinggi
C6	Saya percaya bahawa kaunselor politeknik mampu membantu saya mengenal pasti kekuatan dan kelemahan diri.	4.23	0.63	Tinggi
C7	Saya yakin bahawa kaunselor di politeknik	4.21	0.65	Tinggi

	boleh memberi sokongan dalam pengurusan tekanan dan emosi.			
C8	Saya berpendapat bahawa kaunselor dapat memberi panduan kepada pelajar dalam merancang kerjaya masa depan	4.26	0.64	Tinggi
C9	Saya percaya bahawa kaunselor di politeknik mampu membantu saya dalam membina kemahiran penyelesaian masalah dan membuat keputusan.	4.31	0.55	Tinggi
C10	Saya berasa selamat dan dihargai apabila berinteraksi dengan kaunselor di politeknik.	4.25	0.64	Tinggi

Berdasarkan Jadual 3 menunjukkan Item C2 mencatatkan min tertinggi (4.31), menunjukkan pelajar mempunyai pemahaman yang jelas terhadap peranan kaunselor di politeknik. Ini membuktikan bahawa fungsi dan tanggungjawab kaunselor diketahui dengan baik oleh majoriti responden. Namun, item C4 menunjukkan min terendah (4.11) dengan sisihan piawai 0.70, menandakan masih wujud keraguan atau rasa tidak selesa dalam berjumpa kaunselor. Ini menunjukkan aspek kebolehpercayaan dan keterbukaan pelajar masih perlu diperkukuhkan, khususnya dari segi hubungan mesra dan pendekatan kaunseling yang lebih mesra pelajar.

4.1.3 Persepsi terhadap Pembimbing Rakan Sebaya (Bahagian D)

Jadual 4 menunjukkan nilai min dan sisihan piawai bagi setiap item dalam Bahagian D.

Jadual 4: Pengetahuan Umum Pembimbing Rakan Sebaya (PRS)

No	Item	Min	Sisihan Piawai	Tahap
D1	Saya tahu apa itu Pembimbing Rakan Sebaya (PRS).	4.35	0.58	Tinggi
D2	Saya tahu bahawa politeknik mempunyai program Pembimbing Rakan Sebaya.	4.29	0.61	Tinggi
D3	Saya percaya bahawa Pembimbing Rakan Sebaya (PRS) penting untuk menyokong kesejahteraan pelajar.	4.27	0.61	Tinggi
D4	Saya selesa berbincang dengan Pembimbing Rakan Sebaya untuk mendapatkan nasihat atau sokongan.	4.10	0.80	Tinggi
D5	Saya percaya Pembimbing Rakan Sebaya dapat membantu pelajar mengatasi masalah kecil sebelum ia menjadi besar.	4.17	0.70	Tinggi
D6	Saya percaya bahawa Pembimbing Rakan Sebaya (PRS) boleh membantu	4.19	0.71	Tinggi

	meningkatkan hubungan sosial di kalangan pelajar.			
D7	Saya rasa Pembimbing Rakan Sebaya adalah pilihan pertama bagi pelajar yang tidak selesa berjumpa kaunselor.	4.12	0.77	Tinggi
D8	Saya yakin Pembimbing Rakan Sebaya (PRS) dapat membantu pelajar menguruskan masa dan tugas akademik dengan lebih baik.	4.18	0.70	Tinggi
D9	Saya rasa Pembimbing Rakan Sebaya mempunyai latihan yang mencukupi untuk memberi sokongan kepada pelajar lain.	4.18	0.70	Tinggi
D10	Saya melihat Pembimbing Rakan Sebaya sebagai sokongan tambahan yang penting untuk kesihatan mental pelajar.	4.16	0.72	Tinggi

Berdasarkan Jadual 4 menunjukkan Item D1 mencatatkan min tertinggi iaitu 4.35, menunjukkan pelajar mempunyai tahap kesedaran yang tinggi terhadap kewujudan dan konsep PRS di politeknik. Ini membuktikan bahawa maklumat asas mengenai PRS telah sampai kepada majoriti pelajar. Namun, item D4 mencatatkan min terendah 4.10 dengan sisihan piawai tertinggi 0.80, menandakan masih ada pelajar yang kurang selesa atau ragu-ragu untuk berbincang dengan PRS. Oleh itu, kesediaan pelajar untuk berinteraksi secara terbuka perlu dipertingkatkan melalui latihan komunikasi, promosi peranan PRS, dan pengukuhan hubungan sesama pelajar.

4.2 Analisis Inferensi: Perbandingan Persepsi PRS Berdasarkan Jantina

Bagi memenuhi Objektif Kajian Ketiga, analisis inferensi telah dijalankan menggunakan Ujian-t Dua Sampel Bebas (Independent Sample t-test) untuk mengenal pasti sama ada wujud perbezaan yang signifikan dalam persepsi pelajar terhadap PRS berdasarkan jantina (Lelaki vs Perempuan).

Jadual 6: Keputusan Ujian-t Berdasarkan Jantina bagi Item PRS (D1-D10)

Item	T-Statistik	P-Nilai	Signifikan ($p < 0.05$)
D1	-2.53	0.01	Ya
D2	-2.77	0.01	Ya
D3	-0.64	0.52	Tidak
D4	0.49	0.62	Tidak
D5	-0.85	0.39	Tidak
D6	-0.60	0.55	Tidak
D7	-0.07	0.94	Tidak
D8	-0.40	0.68	Tidak
D9	-0.40	0.68	Tidak
D10	0.19	0.84	Tidak

Berdasarkan Jadual 6 menunjukkan hanya item D1 dan D2 menunjukkan perbezaan yang signifikan antara jantina, di mana pelajar perempuan mencatatkan min yang lebih

tinggi, menandakan tahap kesedaran terhadap PRS lebih tinggi dalam kalangan pelajar perempuan. Bagi item D3 hingga D10, tiada perbezaan signifikan direkodkan, yang menunjukkan bahawa kepercayaan dan keselesaan terhadap PRS adalah hampir sama antara lelaki dan perempuan.

Dapatan ini menunjukkan bahawa peningkatan pengetahuan tentang PRS dapat membantu memperkukuh persepsi pelajar terhadap fungsi PRS, dan seterusnya mendorong kepada kesediaan mereka untuk melibatkan diri dalam sistem sokongan rakan sebaya ini secara lebih aktif.

Jadual 7: Jadual Ringkasan Min Keseluruhan Konstruk

Konstruk	Min Keseluruhan	Interpretasi
Pengetahuan Kaunseling (B)	4.25	Tinggi
Persepsi terhadap Kaunselor (C)	4.23	Tinggi
Persepsi terhadap PRS (D)	4.21	Tinggi

Nilai min keseluruhan melebihi 4.20 menunjukkan tahap pengetahuan dan persepsi pelajar adalah berada pada tahap tinggi dan konsisten antara konstruk.

5. PERBINCANGAN DAN KESIMPULAN

5.1 Perbincangan mengikut objektif

Objektif 1: Menilai tahap pengetahuan umum pelajar terhadap perkhidmatan kaunseling

Dapatan menunjukkan bahawa pelajar mempunyai tahap pengetahuan yang tinggi terhadap kewujudan dan fungsi asas perkhidmatan kaunseling (min tertinggi B2 = 4.39). Namun, sisihan piawai sederhana pada item B4 menunjukkan masih wujud jurang kefahaman dalam aspek prosedur mendapatkan kaunseling, selari dengan dapatan Mohd Amin & Abd Mukti (2024) yang menyatakan pelajar tahu tentang kaunseling tetapi kurang jelas tentang cara mengaksesnya.

Objektif 2: Mengukur persepsi pelajar terhadap peranan kaunselor dan PRS

Persepsi pelajar terhadap kaunselor adalah positif, khususnya dalam memahami peranan mereka (C2 = 4.31), namun isu keselesaan berinteraksi masih wujud (C4 = 4.11). Bagi PRS, tahap kesedaran pelajar adalah tinggi (D1 = 4.35), tetapi keyakinan dan kesediaan untuk berinteraksi masih sederhana (D4 = 4.10, std = 0.80), menyokong dapatan Rosli et al. (2021) bahawa PRS belum dilihat sepenuhnya sebagai saluran utama sokongan psikososial.

Objektif 3: Mengenalpasti perbezaan persepsi berdasarkan demografi

Ujian-t mendapati bahawa pelajar perempuan lebih mengetahui dan menghargai kewujudan PRS berbanding pelajar lelaki (item D1 dan D2, $p < 0.05$). Namun, tiada perbezaan signifikan ditemui dalam aspek kepercayaan dan keselesaan (item D3-D5), membayangkan pendekatan PRS adalah universal tetapi promosi kesedaran perlu bersifat jantina secara spesifik.

Dapatan ini adalah selari dengan Rosli et al. (2021) yang melaporkan pelajar TVET kurang jelas tentang peranan PRS.

Namun, dapatan bertentangan dengan Yusof & Jamaludin (2020) yang menunjukkan PRS dalam konteks sekolah menengah telah menjadi saluran sokongan utama, menunjukkan bahawa tahap kematangan sistem PRS di politeknik belum mencapai tahap optimum.

5.2 Kesimpulan

Kajian ini mendapati pelajar Jabatan Kejuruteraan Mekanikal Politeknik Merlimau mempunyai pengetahuan dan persepsi positif terhadap kaunseling dan PRS, namun masih terdapat jurang dari segi keselesaan dan keterbukaan mendapatkan bantuan, terutama dalam kalangan pelajar lelaki. Dapatan ini mencadangkan keperluan untuk memperkukuh komunikasi psikososial, latihan PRS, dan membina budaya empati dalam kalangan pelajar.

Kajian ini boleh dijadikan asas kepada penyelidikan masa hadapan yang menilai kesan jangka panjang intervensi PRS (Pembimbing Rakan Sebaya) terhadap pelajar, khususnya dari aspek kesejahteraan emosi, keyakinan diri dan pencapaian akademik dalam jangka masa tertentu. Penyelidikan berbentuk longitudinal ini penting untuk melihat impak sebenar PRS bukan hanya selepas program dijalankan, tetapi bagaimana ia membentuk perkembangan pelajar dari semasa ke semasa.

Selain itu, dapatan kajian ini juga menyokong cadangan untuk membina satu model sistem sokongan psikososial pelajar yang moden, menyeluruh dan fleksibel. Model hibrid ini boleh menggabungkan pelbagai komponen seperti PRS (peer support), sistem e-kaunseling atau aplikasi psikologi, aktiviti sahsiah dan pembangunan sendiri, serta komuniti pelajar sokongan yang saling membantu. Gabungan pendekatan tradisional dan digital ini diyakini dapat meningkatkan akses pelajar kepada bantuan sokongan, serta membina persekitaran pembelajaran yang lebih inklusif dan responsif terhadap cabaran kesejahteraan pelajar masa kini.

RUJUKAN

Abdul Mutalib, A., & Ahmad, M. (2024). Isu dan cabaran perkhidmatan bimbingan dan kaunseling bagi murid berkeperluan khas dalam pembelajaran. *Jurnal Pendidikan Bitara UPSI*, 17(Isu Khas 3), 21–30.

Chong, W. Y., & Tan, L. Y. (2020). University students' perception of counselling: Communication approach matters. *Malaysian Journal of Psychology*, 36(1), 45–56.

Corey, G. (2016). *Theory and practice of counseling and psychotherapy* (10th ed.). Cengage Learning.

Creswell, J. W. (2014). *Research design: Qualitative, quantitative, and mixed methods approaches* (4th ed.). SAGE Publications.

Institute for Public Health. (2019). *National Health and Morbidity Survey (NHMS) 2019: Non-communicable diseases, healthcare demand and health literacy*. Ministry of Health Malaysia.

- Kementerian Pengajian Tinggi. (2021). Laporan Tahunan Perkhidmatan Kaunseling Politeknik & Kolej Komuniti 2021. KPT.
- Mohd Amin, A., & Abd Mukti, T. (2024). Kesediaan pelajar dalam mendapatkan perkhidmatan bimbingan dan kaunseling di sekolah. *Jurnal Pendidikan Bitara UPSI*, 17(Isu Khas 3), 202–210.
- Nasir, R., & Normala, I. (2020). Stigma terhadap kaunseling: Cabaran dan strategi intervensi di institusi pendidikan. *Malaysian Journal of Youth Studies*, 22, 47–63.
- Nunnally, J. C., & Bernstein, I. H. (1994). *Psychometric theory* (3rd ed.). McGraw-Hill.
- Otieno, K. (2023). Peer support and adjustment among first-year students at university. In M. A. Rahman & S. M. Ahmed (Eds.), *Handbook of research on coping mechanisms for first-year students transitioning to higher education* (pp. 315–329). IGI Global.
- Pallant, J. (2020). *SPSS survival manual: A step by step guide to data analysis using IBM SPSS* (7th ed.). Routledge.
- Rosli, N., Jamaludin, A., & Hanafi, M. I. (2021). Tahap kesedaran terhadap perkhidmatan kaunseling dalam kalangan pelajar institusi TVET. *Jurnal Personalia Pelajar*, 24(2), 73–88.
- Yahya, A., & Hashim, N. (2020). Kesan intervensi modul rakan mentor terhadap penghargaan sendiri, motivasi dan gred keputusan trimester pelajar rendah pencapaian akademik. *Jurnal Psikologi Malaysia*, 34(2), 112–120.
- Yusof, M. N., & Jamaludin, A. (2020). Keberkesanan program Pembimbing Rakan Sebaya dalam kalangan pelajar tingkatan 6. *Jurnal Psikologi Malaysia*, 34(1), 88–99.

Keberkesanan Gamifikasi Dalam Pengajaran dan Pembelajaran *Quality Control*

Noor Hapizah Binti Abdullah¹, Zainal Abidin Bin Ab. Kasim², Che Che Azlina Binti Che Norohoseni³

^{1,3}Jabatan Kejuruteraan Mekanikal, Politeknik Port Dickson

²Jabatan Matematik, Sains dan Komputer, Politeknik Port Dickson

noorhapizah@polipd.edu.my , zainalabidin@polipd.edu.my, cheazlina@polipd.edu.my

Abstrak Kajian ini bertujuan untuk melihat keberkesanan penggunaan gamifikasi dalam pengajaran dan pembelajaran (PdP) bagi kursus *Quality Control* di Jabatan Kejuruteraan Mekanikal, Politeknik Port Dickson. Kajian ini melibatkan permainan berkumpulan (*Flash card QC*) dan kuiz interaktif. Permasalahan utama adalah kelemahan dalam penguasaan teori menyebabkan pelajar gagal mengaplikasikan pengetahuan tersebut dalam ujian dan juga peperiksaan akhir. Ini dapat dikenalpasti melalui markah ujian bertulis yang rendah dan kesukaran mereka menjelaskan konsep secara lisan. Selain itu, melalui aktiviti permainan berkumpulan, ahli kumpulan dapat bertukar-tukar pandangan dan belajar secara interaktif. Kajian ini menggunakan pendekatan campuran (kuantitatif dan kualitatif) dengan instrumen pre-test, post-test dan soal selidik. Hasil kajian mendapati peningkatan skor purata post-test sebanyak 25% berbanding pre-test, selain peningkatan motivasi, penglibatan serta kerjasama pelajar. Dapatan ini menunjukkan gamifikasi sebagai pendekatan inovatif yang berkesan dalam PdP *Quality Control*. Implikasi kajian ini penting kepada pensyarah, pelajar, dan institusi pendidikan dalam memperkukuh kualiti pembelajaran selari dengan kehendak industri.

Kata kunci: Gamifikasi, Pengajaran dan Pembelajaran, *Quality Control*

1. PENGENALAN

Kursus *Quality Control* merupakan salah satu komponen penting dalam bidang kejuruteraan dan pembuatan kerana ia membekalkan pelajar dengan asas pengetahuan serta kemahiran teknikal untuk memastikan produk dan proses pengeluaran menepati piawaian yang ditetapkan. Melalui kursus ini, pelajar didedahkan kepada pelbagai konsep dan alat kawalan kualiti seperti process capability indices (Cp, Cpk), carta kawalan, sampling plan, dan kaedah penilaian statistik yang menjadi teras kepada sistem jaminan kualiti industri moden. Penguasaan terhadap konsep-konsep ini amat penting bagi graduan TVET agar mereka mampu melaksanakan tugas pemeriksaan, analisis variasi proses, serta penambahbaikan berterusan dalam persekitaran kerja sebenar.

Walau bagaimanapun, proses pengajaran dan pembelajaran (PdP) bagi kursus *Quality Control* sering berdepan cabaran. Kaedah pengajaran tradisional yang menekankan kuliah berpusatkan pensyarah, penggunaan nota teori, dan latihan pengiraan manual didapati kurang menarik minat pelajar (Abdul Karim et al., 2022). Pelajar cenderung menganggap topik seperti *statistical process control* dan *acceptance sampling* sukar difahami kerana ia bersifat abstrak dan memerlukan kefahaman terhadap konsep statistik serta logik proses industri. Keadaan ini menyebabkan motivasi dan penglibatan pelajar menurun, sekali

gus menjejaskan pencapaian pembelajaran mereka.

Dalam konteks pendidikan teknikal dan vokasional (TVET), kaedah PdP yang berkesan bukan sahaja perlu memindahkan pengetahuan, tetapi juga mampu membina kemahiran berfikir aras tinggi, kemahiran menyelesaikan masalah, serta pembelajaran kolaboratif. Seiring dengan transformasi pendidikan abad ke-21, institusi TVET digalakkan menerapkan pendekatan inovatif dan berpusatkan pelajar bagi memastikan proses pembelajaran lebih bermakna, aktif dan menyeronokkan. Antara pendekatan yang semakin mendapat perhatian ialah gamifikasi, iaitu pengaplikasian elemen permainan dalam konteks bukan permainan untuk merangsang motivasi dan meningkatkan pengalaman pembelajaran (Deterding et al., 2011).

Gamifikasi dalam PdP bertujuan untuk menjadikan proses pembelajaran lebih interaktif dengan menggabungkan elemen seperti ganjaran (*badge*, mata, atau *leaderboard*), cabaran, persaingan sihat, dan pencapaian individu atau kumpulan. Kajian terdahulu menunjukkan bahawa pendekatan ini dapat meningkatkan motivasi intrinsik, penglibatan pelajar, serta kadar pengekalan pengetahuan. Dalam konteks kursus ini, pendekatan ini dapat membantu pelajar memahami konsep abstrak melalui aktiviti berbentuk permainan, simulasi dan penyelesaian masalah secara kolaboratif. Sebagai contoh, aktiviti seperti *Flash Card* QC, kuiz berasaskan aplikasi, dan tugas berkumpulan berunsur permainan mampu mewujudkan suasana pembelajaran yang menyeronokkan serta memupuk semangat kerjasama.

Selain daripada itu, gamifikasi juga selaras dengan keperluan industri yang menekankan kemahiran insaniah (*soft skills*) seperti komunikasi, kepimpinan, dan kerja berpasukan — elemen yang boleh diterapkan melalui aktiviti permainan dan cabaran berkumpulan. Oleh itu, penerapan gamifikasi bukan sahaja membantu pelajar menguasai konsep teknikal dalam QC, tetapi turut memperkukuh kemahiran abad ke-21 yang diperlukan oleh majikan masa kini.

Menyedari potensi besar pendekatan ini, kajian ini dijalankan bagi menilai keberkesanan penggunaan gamifikasi dalam PdP kursus *Quality Control* di Politeknik Port Dickson. Secara khusus, kajian ini bertujuan untuk menilai kesan gamifikasi terhadap motivasi, penglibatan, kefahaman konsep, serta pencapaian pelajar. Dapatan kajian diharap dapat memberikan panduan kepada pensyarah dalam merancang strategi PdP yang lebih menarik, berkesan, dan berorientasikan hasil pembelajaran (*Outcome-Based Education*), di samping menyumbang kepada peningkatan kualiti pendidikan teknikal selari dengan kehendak industri semasa. Objektif bagi kajian ini adalah seperti berikut:

- i. Menenal pasti tahap motivasi dan penglibatan pelajar dalam PdP *Quality Control* menggunakan gamifikasi.
- ii. Menilai keberkesanan gamifikasi dalam meningkatkan kefahaman konsep *Quality Control*.
- iii. Menganalisis impak gamifikasi terhadap pencapaian akademik pelajar.

2.0 SOROTAN LITERATUR

2.1 Konsep Gamifikasi dalam Pendidikan

Gamifikasi merujuk kepada penggunaan elemen permainan dalam konteks bukan

permainan bagi meningkatkan penglibatan, motivasi, dan pengalaman pengguna (Deterding et al., 2011). Dalam konteks pendidikan, gamifikasi diaplikasikan sebagai strategi pengajaran yang menggabungkan elemen seperti mata ganjaran, lencana, papan kedudukan (*leaderboard*), cabaran, serta tahap pencapaian untuk menjadikan proses pembelajaran lebih menyeronokkan dan bermakna (Kapp, 2012). Berbeza dengan permainan sebenar (*game-based learning*), gamifikasi mengekalkan kandungan akademik asal tetapi memperkayakan penyampaian dengan elemen motivasi berasaskan permainan.

Kajian lepas menunjukkan bahawa gamifikasi mempunyai potensi besar dalam meningkatkan minat pelajar terhadap subjek yang bersifat teoritikal dan teknikal (Hamari et al., 2016). Melalui pendekatan ini, pelajar terdorong untuk menyertai aktiviti pembelajaran secara aktif kerana wujudnya elemen cabaran dan ganjaran segera. Menurut Su & Cheng (2015), gamifikasi dapat meningkatkan motivasi intrinsik pelajar melalui rasa pencapaian (*sense of achievement*) dan keterlibatan emosi semasa menyelesaikan tugasan berbentuk permainan.

2.2 Gamifikasi dalam Pendidikan Teknikal dan Vokasional (TVET)

Dalam konteks TVET, pendekatan PdP berasaskan amali dan pengalaman sebenar amat penting untuk memastikan pelajar menguasai kemahiran teknikal serta kemahiran insaniah. Namun, pengajaran berasaskan teori dan konsep abstrak seperti statistik, kawalan kualiti, dan analisis proses sering menimbulkan cabaran kepada pelajar (Abdul Karim et al., 2022). Oleh itu, gamifikasi dapat berperanan sebagai jambatan antara teori dan amalan, dengan menyediakan pengalaman pembelajaran yang menyerupai situasi sebenar melalui simulasi dan aktiviti kolaboratif.

Kajian oleh Surendelegh et al. (2014) menunjukkan bahawa penerapan elemen permainan dalam kursus teknikal dapat meningkatkan fokus pelajar serta memperkukuh daya ingatan terhadap konsep yang dipelajari. Dalam konteks TVET Malaysia, pendekatan seperti ini seiring dengan aspirasi Pelan Pembangunan Pendidikan Malaysia (Pendidikan Tinggi) 2015–2025 yang menekankan pembelajaran berasaskan pengalaman dan inovasi pedagogi. Pendekatan gamifikasi juga menyokong pelaksanaan *Outcome-Based Education (OBE)* dengan memberi peluang kepada pelajar mencapai hasil pembelajaran kursus (CLO) melalui aktiviti interaktif dan berpusatkan pelajar.

2.3 Kesan Gamifikasi terhadap Motivasi dan Penglibatan Pelajar

Motivasi merupakan faktor penting yang mempengaruhi keberkesanan proses pembelajaran. Menurut teori motivasi sendiri (*Self-Determination Theory*, Deci & Ryan, 2000), motivasi intrinsik pelajar dapat dipupuk apabila mereka berasa seronok, bebas memilih, dan mempunyai rasa pencapaian terhadap aktiviti yang dilakukan. Gamifikasi menyediakan suasana yang memenuhi keperluan psikologi tersebut dengan menawarkan ganjaran segera, maklum balas berterusan, serta peluang untuk bersaing dan bekerjasama.

Kajian oleh Zainuddin et al. (2020) mendapati bahawa gamifikasi dapat meningkatkan penglibatan kognitif dan afektif pelajar melalui aktiviti berstruktur seperti kuiz interaktif dan sistem *leaderboard*. Pelajar berasa lebih terdorong untuk melibatkan diri kerana wujud elemen persaingan sihat dan pengiktirafan pencapaian. Selain itu, hasil kajian Limi et al. (2022) menunjukkan peningkatan ketara dalam kadar kehadiran, penyertaan, dan prestasi

akademik apabila elemen gamifikasi diterapkan dalam kursus kejuruteraan.

2.4 Gamifikasi dalam Pengajaran Kursus *Quality Control*

Pengajaran *Quality Control (QC)* memerlukan pelajar memahami konsep statistik dan teknik analisis proses yang sering dianggap kompleks dan membosankan. Menurut Othman dan Rahim (2021), kesukaran memahami topik seperti *Cp*, *Cpk*, dan carta kawalan berpunca daripada kekurangan pendekatan PdP yang interaktif dan berasaskan pengalaman. Dalam konteks ini, gamifikasi dapat membantu pelajar mengaitkan teori dengan amalan melalui aktiviti seperti simulasi proses pengeluaran, *escape room*, dan kuiz berasaskan senario industri sebenar.

3.0 METODOLOGI

3.1 Reka Bentuk Kajian

Kajian ini menggunakan reka bentuk kajian kes dengan pendekatan campuran (mixed-methods) yang menggabungkan kaedah kuantitatif dan kualitatif. Pendekatan ini dipilih bagi memperoleh gambaran yang lebih menyeluruh tentang keberkesanan penggunaan gamifikasi dalam pengajaran dan pembelajaran (PdP) kursus *Quality Control (QC)*. Melalui gabungan kedua-dua pendekatan ini, data yang diperoleh bukan sahaja dapat menunjukkan perubahan dari segi pencapaian akademik, tetapi juga menjelaskan pengalaman, persepsi dan motivasi pelajar terhadap penggunaan gamifikasi dalam PdP.

3.2 Responden Kajian

Sampel kajian terdiri daripada 34 orang pelajar semester 5, yang mengambil kursus *Quality Control* di Jabatan Kejuruteraan Mekanikal, Politeknik Port Dickson. Responden dipilih kerana mereka mempunyai latar belakang yang seragam dari segi bidang pengajian dan telah mengikuti kursus yang sama dalam satu semester, sekali gus membolehkan perbandingan yang lebih tepat dibuat terhadap kesan intervensi gamifikasi.

3.3 Instrumen Kajian

Beberapa instrumen digunakan bagi mengumpul data kuantitatif dan kualitatif:

- i. Ujian Pra (Pre-test) dan Ujian Pasca (Post-test).

Ujian ini digunakan untuk menilai tahap kefahaman pelajar terhadap konsep asas *Quality Control* sebelum dan selepas pelaksanaan aktiviti gamifikasi. Soalan yang digunakan merangkumi topik utama seperti *process capability (Cp, Cpk)*, carta kawalan (*control chart*), dan *acceptance sampling*. Perbandingan antara skor min pre-test dan post-test digunakan untuk menentukan tahap peningkatan pencapaian pelajar.

- ii. Soal Selidik Motivasi Pelajar Soal selidik ini dibangunkan berasaskan Model ARCS

oleh Keller (1987) yang terdiri daripada empat komponen utama iaitu *Attention*, *Relevance*, *Confidence*, dan *Satisfaction*. Tujuannya adalah untuk menilai tahap motivasi pelajar selepas mengikuti sesi PdP berasaskan gamifikasi. Skala Likert lima mata digunakan bagi mengukur persepsi pelajar terhadap setiap item dalam soal selidik.

3.4 Inovasi Gamifikasi dalam PdP

Bagi tujuan kajian ini, modul *Gamified Quality Control* telah dibangunkan dan dilaksanakan sepanjang tempoh empat minggu. Modul ini menggabungkan pelbagai elemen permainan bagi menarik minat dan meningkatkan penglibatan pelajar, antaranya:

- i. Kuiz Interaktif: Pelajar menjawab kuiz menggunakan platform seperti *Kahoot* dan *Quizizz* untuk menguji kefahaman konsep teori dan pengiraan secara menyeronokkan dan kompetitif.
- ii. Cabaran *Flash Card QC*: Aktiviti kumpulan disertai dengan sistem *leaderboard* yang memaparkan markah semasa bagi memupuk semangat persaingan sihat antara kumpulan.

Pendekatan ini dirancang secara selaras dengan *Course Learning Outcome (CLO)* bagi memastikan setiap aktiviti permainan menyumbang kepada pencapaian hasil pembelajaran kursus.

3.5 Prosedur Kajian

Kajian dilaksanakan dalam tiga fasa utama seperti berikut:

- i. Fasa 1: Persediaan dan Ujian Pra (Pre-test). Pelajar menduduki ujian pra bagi menilai tahap awal kefahaman terhadap konsep *Quality Control*. Pada peringkat ini, sesi PdP masih dijalankan secara konvensional untuk tujuan perbandingan.
- ii. Fasa 2: Pelaksanaan Gamifikasi. Modul gamifikasi diperkenalkan dalam tempoh empat minggu meliputi aktiviti kuiz, cabaran kumpulan, dan *Flash Card QC*. Semua aktiviti dijalankan dalam suasana pembelajaran aktif dengan bimbingan pensyarah.
- iii. Fasa 3: Ujian Pasca (Post-test). Selepas intervensi, pelajar menjalani ujian pasca untuk menilai perubahan pencapaian. Soal selidik motivasi diagihkan bagi mendapatkan data kualitatif tambahan.

3.6 Kaedah Analisis Data

Analisis data dijalankan menggunakan analisis kuantitatif iaitu data daripada pre-test dan post-test dianalisis menggunakan perbandingan skor min bagi menentukan peningkatan tahap kefahaman pelajar. Selain itu, data soal selidik motivasi dianalisis secara deskriptif untuk mengenal pasti dimensi motivasi yang paling dipengaruhi oleh gamifikasi.

4.0 DAPATAN KAJIAN

Hasil kajian menunjukkan bahawa penerapan elemen gamifikasi dalam pengajaran dan pembelajaran (*PdP*) kursus *Quality Control (QC)* memberikan kesan yang positif dan signifikan terhadap pelbagai aspek pembelajaran pelajar, terutamanya dari segi motivasi, kefahaman konsep, serta kerjasama kumpulan. Dapatan ini diperoleh melalui analisis data daripada soal selidik, ujian pra dan pasca (rujuk Jadual 1)

Jadual 1 : Data Purata Skor Pre- Test dan Skor Post Test

Aspek	Purata Skor Pre-test	Purata Skor Post-test
Kefahaman konsep QC	55%	80%
Motivasi pelajar	60%	85%
Kerjasama kumpulan	58%	82%

Pertama dari aspek motivasi pelajar, hasil soal selidik menunjukkan bahawa lebih daripada 85% responden menyatakan mereka berasa lebih berminat, fokus, dan bersemangat untuk mengikuti proses pembelajaran apabila aktiviti gamifikasi diperkenalkan berbanding kaedah tradisional seperti kuliah berpusatkan pensyarah dan latihan pengiraan semata-mata. Elemen permainan seperti kuiz interaktif (*Kahoot* dan *Quizizz*) dan Flash Card mewujudkan suasana pembelajaran yang menyeronokkan dan tidak membosankan. Pelajar menyatakan bahawa elemen persaingan sihat mendorong mereka untuk berusaha dengan lebih gigih bagi mencapai kedudukan terbaik dalam kumpulan, sekali gus meningkatkan motivasi intrinsik mereka untuk memahami kandungan pelajaran. Elemen ganjaran pula memberi dorongan ekstrinsik yang menambah nilai positif terhadap pengalaman pembelajaran. Secara keseluruhannya, pendekatan ini berjaya menukar persepsi pelajar terhadap kursus *Quality Control* yang sebelum ini dianggap “teori berat” dan sukar, kepada satu pengalaman pembelajaran yang lebih interaktif dan menyeronokkan.

Kedua, dari aspek kefahaman konsep, analisis keputusan ujian menunjukkan peningkatan yang ketara dalam prestasi pelajar selepas penerapan gamifikasi. Skor purata post-test meningkat sebanyak 25% berbanding skor pre-test, sekali gus membuktikan bahawa pendekatan ini membantu pelajar menguasai dan memahami konsep abstrak dalam *Quality Control* dengan lebih berkesan. Aktiviti seperti *Flash Card QC*, yang direka berdasarkan prinsip pembelajaran berasaskan pengalaman (*experiential learning*), membolehkan pelajar menerapkan pengetahuan teori secara langsung dalam situasi simulasi. Dalam aktiviti ini, pelajar perlu menyelesaikan pelbagai tugas seperti pengiraan *Cp* dan *Cpk* bagi membuka “kunci misi”, menjadikan pembelajaran lebih bermakna dan kontekstual. Kaedah ini juga memudahkan pelajar membina kefahaman konseptual terhadap carta kawalan dan kebolehan proses yang selama ini sukar dikuasai melalui pendekatan kuliah konvensional. Dapatan ini sejajar dengan pandangan Kitikedizah (2022) yang menegaskan bahawa gamifikasi bukan sekadar menarik perhatian pelajar, tetapi juga mampu memperkukuh kefahaman melalui pembelajaran berasaskan pengalaman dan penglibatan aktif.

Ketiga, dari aspek kerjasama kumpulan, pelaksanaan aktiviti berasaskan gamifikasi, khususnya cabaran berkumpulan seperti *Flash card QC*, telah berjaya menggalakkan pelajar untuk berinteraksi secara aktif dan bekerjasama dalam menyelesaikan tugas yang diberikan. Pelajar dilihat lebih berani mengemukakan idea, bertukar pandangan, serta membantu rakan sekumpulan yang menghadapi kesukaran memahami konsep tertentu.

Pendekatan ini bukan sahaja meningkatkan kemahiran komunikasi dua hala, tetapi juga membina kemahiran kepimpinan, penyelesaian masalah, dan pemikiran kritikal dalam kalangan pelajar. Pensyarah yang ditemubual turut mengesahkan bahawa pelajar menunjukkan peningkatan dalam aspek komunikasi dan keyakinan diri semasa perbincangan kelas berlangsung. Aktiviti ini juga memupuk nilai tanggungjawab bersama dan semangat berpasukan iaitu elemen penting dalam konteks pendidikan teknikal dan vokasional (TVET) yang menekankan kerja kolaboratif sebagai kemahiran industri utama.

Secara keseluruhannya, dapatan ini membuktikan bahawa penerapan gamifikasi bukan sekadar meningkatkan keseronokan belajar, tetapi juga memberi kesan langsung terhadap kefahaman konsep, motivasi, dan pembentukan kemahiran insaniah pelajar. Kejayaan pendekatan ini menggambarkan potensi besar gamifikasi sebagai strategi pedagogi berasaskan teknologi yang selari dengan prinsip *Outcome-Based Education (OBE)*, di mana pembelajaran difokuskan kepada pencapaian hasil yang boleh diukur serta pembangunan kompetensi holistik pelajar.

5.0 PERBINCANGAN DAN KESIMPULAN

Dapatan kajian ini secara keseluruhannya menunjukkan bahawa penggunaan pendekatan gamifikasi dalam pengajaran dan pembelajaran kursus *Quality Control* berupaya meningkatkan motivasi, kefahaman, serta penglibatan aktif pelajar dalam proses pembelajaran. Perbincangan ini dihuraikan berdasarkan tiga tema utama yang dikenal pasti melalui analisis data, iaitu motivasi dan minat pelajar, pemahaman konsep dan prestasi akademik, serta kerjasama dan komunikasi kumpulan.

5.1 Peningkatan Motivasi dan Minat Pelajar

Hasil kajian menunjukkan bahawa pelajar memberikan maklum balas yang amat positif terhadap pelaksanaan gamifikasi, dengan lebih 85% responden melaporkan peningkatan minat, fokus dan semangat untuk belajar. Dapatan ini sejajar dengan teori motivasi ARCS yang dikemukakan oleh Keller (1987), yang menekankan empat elemen penting dalam membangkitkan motivasi pelajar iaitu *Attention*, *Relevance*, *Confidence*, dan *Satisfaction*. Melalui elemen permainan seperti kuiz interaktif, *flash card QC* dan ganjaran digital, perhatian pelajar (*Attention*) dapat dipertingkatkan kerana aktiviti ini lebih menyeronokkan dan mencabar.

Selain itu, elemen *Relevance* terhasil apabila pelajar merasakan aktiviti yang dijalankan mempunyai kaitan dengan kemahiran sebenar yang diperlukan dalam industri kualiti, seperti pengiraan indeks Cp dan Cpk. Seterusnya, pelajar berasa lebih yakin (*Confidence*) apabila berjaya menyelesaikan cabaran atau menjawab soalan dengan betul, dan akhirnya mereka memperoleh kepuasan (*Satisfaction*) hasil daripada pencapaian tersebut. Hasil kajian Hellin (2023) menunjukkan pembelajaran teknikal dan berasaskan kemahiran, bahawa gamifikasi berupaya meningkatkan minat, keyakinan diri (*self-confidence*), persaingan sihat dan semangat belajar. Hal ini menegaskan bahawa pendekatan gamifikasi bukan sahaja relevan dalam kursus teori, malah berkesan dalam kursus teknikal seperti *Quality Control* yang menuntut kefahaman konsep serta latihan pengiraan.

5.2 Peningkatan Kefahaman Konsep dan Prestasi Akademik

Peningkatan purata skor post-test sebanyak 25% berbanding pre-test menunjukkan bahawa gamifikasi bukan sahaja meningkatkan minat, tetapi turut membantu dalam memperkukuh kefahaman konsep pelajar. Aktiviti seperti *Flash Card QC* dan kuiz interaktif telah membolehkan pelajar mengaplikasikan teori dalam bentuk situasi sebenar, selari dengan pendekatan pembelajaran berasaskan pengalaman (*experiential learning*). Melalui pengalaman ini, pelajar tidak sekadar menghafal formula atau prosedur, tetapi memahami aplikasi sebenar konsep seperti *process capability*, carta kawalan dan *acceptance sampling*.

Penemuan ini menyokong pandangan Huang dan Hew (2022) menunjukkan bahawa gamifikasi mempunyai kesan signifikan terhadap pencapaian akademik, terutamanya apabila elemen seperti mata (*points*), lencana, dan maklum balas segera digabungkan secara berstrategi dalam PdP. Dapatan mereka mendapati bahawa pelajar dalam persekitaran gamifikasi menunjukkan peningkatan prestasi yang lebih konsisten berbanding pembelajaran tradisional. Dapatan ini mengesahkan bahawa gamifikasi bukan hanya berfungsi sebagai alat hiburan, tetapi sebagai strategi pedagogi berimpak tinggi yang dapat meningkatkan hasil pembelajaran kognitif, sejajar dengan matlamat *Outcome-Based Education (OBE)*.

Selari dengan itu, kajian oleh Su & Cheng (2023) mendapati bahawa gamifikasi dapat meningkatkan pemahaman konsep kompleks melalui aktiviti seperti simulasi, cabaran berperingkat dan latihan interaktif, yang membolehkan pelajar menguasai kemahiran analitik serta pemikiran kritis dengan lebih berkesan.

5.3 Implikasi terhadap Amalan Pengajaran

Secara keseluruhannya, dapatan kajian ini membuktikan bahawa gamifikasi merupakan pendekatan pedagogi yang holistik dan selaras dengan keperluan pembelajaran abad ke-21. Dalam konteks PdP kursus QC, gamifikasi membantu pensyarah mempersembahkan topik yang bersifat teori dan statistik dalam bentuk aktiviti yang lebih interaktif, menyeronokkan dan berpusatkan pelajar. Ini sejajar dengan saranan Kementerian Pendidikan Malaysia (KPM, 2020) agar institusi TVET memperkukuh pendekatan pembelajaran aktif dan berasaskan teknologi bagi meningkatkan kebolehpasaran graduan.

Dengan itu, pelaksanaan gamifikasi boleh dianggap sebagai satu bentuk inovasi pendidikan yang bukan sahaja meningkatkan kualiti PdP, tetapi juga mampu membina suasana pembelajaran yang kondusif, kolaboratif, dan selari dengan kehendak industri semasa.

5.4 Kesimpulan

Secara keseluruhannya, kajian ini membuktikan bahawa pendekatan gamifikasi dalam pengajaran dan pembelajaran (*PdP*) kursus *Quality Control (QC)* merupakan satu inovasi pedagogi yang berkesan dalam konteks pendidikan teknikal dan vokasional (TVET). Melalui integrasi elemen permainan seperti *quiz interaktif*, *leaderboard*, sistem ganjaran digital serta aktiviti *Flash Card QC*, pelajar menunjukkan peningkatan ketara dari segi

motivasi, kefahaman konsep, dan tahap penglibatan aktif dalam kelas.

Peningkatan purata skor post-test sebanyak 25% berbanding pre-test menunjukkan bahawa pelajar bukan sahaja lebih berminat, tetapi juga benar-benar memahami konsep abstrak seperti *process capability (Cp, Cpk)*, carta kawalan dan *acceptance sampling* dengan lebih jelas. Elemen kompetitif yang sihat dalam gamifikasi juga berjaya meningkatkan motivasi intrinsik dan ekstrinsik pelajar, menjadikan proses pembelajaran lebih menyeronokkan serta bermakna.

Selain itu, pendekatan gamifikasi turut memperkukuh kemahiran insaniah pelajar seperti komunikasi, kerjasama dan penyelesaian masalah, yang amat penting dalam dunia kerja sebenar. Ini menunjukkan bahawa gamifikasi bukan sekadar alat bantu mengajar, tetapi satu strategi pembelajaran holistik yang menyokong pembangunan pelajar secara menyeluruh dari aspek kognitif, afektif, dan psikomotor.

Oleh itu, dapat dirumuskan bahawa gamifikasi bukan sahaja meningkatkan kualiti PdP dalam kursus QC, tetapi juga selari dengan matlamat *Outcome-Based Education (OBE)* yang menekankan pencapaian hasil pembelajaran yang boleh diukur dan relevan dengan keperluan industri. Kajian ini sekali gus menegaskan kepentingan penggunaan pendekatan inovatif dalam pendidikan TVET bagi melahirkan graduan yang bukan sahaja berpengetahuan, tetapi juga bermotivasi tinggi, kreatif, dan berdaya saing dalam menghadapi cabaran revolusi industri masa kini.

RUJUKAN

Abdul Karim, N., Rahman, F., & Hashim, Z. (2022). Penerapan pendekatan inovatif dalam pengajaran kursus kejuruteraan di politeknik: Kajian terhadap tahap penglibatan pelajar. *Journal of Technical Education and Training*, 14(2), 45–58.

Chong, L., Kamarulzaman, N. F. b., & Sukri, N. R. b. (2024). Persepsi pelajar semester dua diploma Kejuruteraan Mekatronik di Politeknik Sultan Azlan Shah terhadap pelaksanaan pembelajaran dan pengajaran (PdP) pengaturcaraan C menggunakan kaedah gamifikasi. *Technical and Vocational Education International Journal*, 4(1).

Biggs, J., & Tang, C. (2011). *Teaching for quality learning at university* (4th ed.). McGraw-Hill Education.

Deterding, S., Dixon, D., Khaled, R., & Nacke, L. (2011, September). From game design elements to gamefulness: Defining gamification. In *Proceedings of the 15th International Academic MindTrek Conference: Envisioning Future Media Environments* (pp. 9–15). ACM.

Hambali, K. b., & Lubis, M. A. (2022). Kepentingan gamifikasi dalam pengajaran dan pemudahcaraan (PdPC) pendidikan Islam. *ASEAN Comparative Education Research Journal on Islam and Civilization (ACER-J)*, 5(1), 58–64.

Hellín, C. J., Calles-Esteban, F., Valledor, A., Gómez, J., Otón-Tortosa, S., & Tayebi, A. (2023).

Enhancing student motivation and engagement through a gamified learning environment. *Sustainability*, 15(19), 14119.

Huang, B., & Hew, K. F. (2022). Implementing gamification in higher education: A meta-analysis of effects on learning outcomes. *Educational Technology Research and Development*, 70(5), 1103–1129.

Kapp, K. M. (2012). *The gamification of learning and instruction: Game-based methods and strategies for training and education*. Pfeiffer.

Rahim, N. A., & Hassan, N. (2020). Penggunaan elemen permainan dalam pembelajaran teknikal: Satu pendekatan gamifikasi di politeknik. *Malaysian Journal of Learning and Instruction*, 17(3), 87–102.

Su, C. H., & Cheng, C. H. (2015). A mobile gamification learning system for improving the learning motivation and achievements. *Journal of Computer Assisted Learning*, 31(3), 268–286.

Su, C., & Cheng, C. (2023). Gamification for learning complex concepts: A study in higher education STEM courses. *Computers & Education*, 204, 104556.

Zainuddin, Z., Shujahat, M., Haruna, H., & Chu, S. K. W. (2020). The role of gamified e-quizzes on student learning and engagement: An interactive learning approach. *Computers & Education*, 145, 103729.

Kajian Pemerhatian Pencapaian Pelajar dalam *Course Learning Outcome* bagi Kursus DJF51082 *Quality Control* di Jabatan Kejuruteraan Mekanikal, Politeknik Port Dickson.

Noor Hapizah Binti Abdullah¹, Zainal Abidin Bin Ab. Kasim²

¹Jabatan Kejuruteraan Mekanikal, Politeknik Port Dickson,

noorhapizah@polipd.edu.my , zainalabidin@polipd.edu.my

Abstrak Kajian ini menjalankan pemerhatian terhadap *Course Learning Outcome (CLO)* pencapaian pelajar bagi kursus DJF 51082 – *Quality Control* (Kawalan Kualiti) berdasarkan kepada data tiga sesi pembelajaran iaitu Sesi 1:2023/2024, Sesi 1:2024/2025 dan Sesi 2:2024/2025. Tujuan utama kajian ini adalah untuk mengenalpasti corak pencapaian pelajar dan mencadangkan penambahbaikan berasaskan data tiga (3) sesi pembelajaran ini. Analisis memfokuskan kepada dua indikator utama iaitu *Group Attainment* (purata pencapaian pelajar) dan *Student Achievement* $\geq 50\%$ (peratus pelajar mencapai tahap minimum). Dapatan kajian menunjukkan CLO3 mencatat pencapaian tertinggi secara konsisten bagi ketiga-tiga sesi dimana peratusan tertinggi CLO3 bagi *Group Attainment* adalah 84% dan *Students Achievement* adalah 100%. Kedua-dua peratusan tertinggi ini adalah dari sesi 2:2024/2025. Manakala CLO1 kekal rendah walaupun berlaku sedikit peningkatan. Peratusan terendah CLO1 bagi *Group Attainment* adalah 39.1% dan *Student Achievement* adalah 17.6%. Kedua-dua peratusan terendah ini adalah dari sesi 1:2024/2025. CLO2 menunjukkan peningkatan yang signifikan dari segi pencapaian kumpulan dan bilangan pelajar yang melepasi tahap lulus. Hasil analisis ini mencadangkan keperluan penambahbaikan pada strategi pengajaran dan pembelajaran (PdP) bagi CLO1 dan pengukuhan kaedah pembelajaran berasaskan kajian kes bagi CLO2.

Kata Kunci: CLO, kawalan kualiti, pencapaian pelajar, pemerhatian, analisis prestasi.

1.0 PENGENALAN

Outcome-Based Education (OBE) merupakan pendekatan penting dalam memastikan setiap kursus di institusi pengajian tinggi dapat menilai tahap penguasaan pelajar berdasarkan *Course Learning Outcome (CLO)*. CLO berfungsi sebagai indikator utama dalam mengukur sejauh mana pelajar memahami, menguasai, dan mampu mengaplikasikan pengetahuan serta kemahiran yang diajar (Biggs & Tang, 2011). Pendekatan ini menekankan pembelajaran berfokuskan hasil, di mana kejayaan pelajar diukur berdasarkan pencapaian objektif pembelajaran yang telah ditetapkan, bukan sekadar melalui penilaian tradisional.

Dalam konteks kursus DJF 51082 – *Quality Control*, CLO dirancang bagi membentuk kompetensi pelajar dalam aspek teori dan aplikasi penggunaan teknik kawalan kualiti. Kursus ini menekankan kefahaman terhadap konsep asas kawalan kualiti, penggunaan carta kawalan, dan kaedah statistik dalam menilai serta menambah baik proses pengeluaran. Menurut Zaharim et al. (2012), pernyataan CLO yang jelas dan terukur membantu pelajar

menumpukan perhatian terhadap hasil pembelajaran yang perlu dicapai dan membolehkan pensyarah merancang strategi PdP yang lebih berfokus. Selain itu, Harden (2002) turut menegaskan bahawa CLO yang dirumus dengan baik menjadi asas kepada proses akreditasi, pemantauan kualiti, serta pelaksanaan *Continuous Quality Improvement* (CQI) dalam pendidikan teknikal dan vokasional.

Pelaksanaan OBE di Politeknik Malaysia menekankan kepentingan penilaian berasaskan bukti (*evidence-based assessment*) terhadap pencapaian CLO bagi memastikan keberkesanan proses pengajaran dan pembelajaran. Analisis pencapaian CLO bukan sahaja membantu pihak institusi menilai tahap penguasaan pelajar, tetapi juga menjadi mekanisme penting dalam mengenal pasti kekuatan dan kelemahan kurikulum sedia ada. Seperti yang dinyatakan oleh Rahim dan Hassan (2020), pemantauan berterusan terhadap pencapaian CLO membolehkan institusi melaksanakan intervensi pengajaran yang lebih berkesan serta menambah baik reka bentuk kursus berdasarkan data sebenar.

Kajian ini dilaksanakan untuk menilai pencapaian CLO bagi kursus DJF 51082 merentasi tiga sesi pembelajaran, iaitu Sesi 1:2023/2024, Sesi 1:2024/2025, dan Sesi 2:2024/2025. Melalui analisis ini, corak pencapaian pelajar dapat dikenal pasti berdasarkan dua indikator utama, iaitu *Group Attainment* dan *Student Achievement* $\geq 50\%$. Dapatan kajian diharap dapat memberikan gambaran menyeluruh tentang keberkesanan strategi PdP yang digunakan serta menjadi asas kepada cadangan penambahbaikan berterusan terhadap pendekatan pengajaran, khususnya bagi CLO yang mencatat pencapaian rendah.

2.0 KAJIAN LITERATUR

Kajian lepas membuktikan analisis CLO memainkan peranan penting dalam penambahbaikan berterusan. Antaranya Kajian oleh Mohamad Shakri Mohamad Shariff dan Che Maznah Mat Isa (2025) menekankan kepentingan pelaksanaan *Continual Quality Improvement* (CQI) dalam meningkatkan keberkesanan penyelarasan antara *Course Learning Outcomes* (CLO) dan *Programme Learning Outcomes* (PLO) dalam kursus Kejuruteraan Geoteknikal. Melalui pendekatan CQI yang sistematik, kajian ini menunjukkan bagaimana analisis berterusan terhadap pencapaian pelajar dapat membantu pensyarah menilai keberkesanan strategi pengajaran dan penilaian. Hasil dapatan turut menunjukkan bahawa pelaksanaan CQI memberi impak positif terhadap peningkatan pencapaian PLO1 (*Engineering Knowledge*) dan PLO4 (*Investigation Skills*), sekali gus menyumbang kepada pengukuhan budaya penambahbaikan berterusan dalam program kejuruteraan. Sustainability (2022) pula menekankan kepentingan CLO dalam TVET. Kajian ini menyokong bahawa pengukuran CLO adalah instrumen kawalan kualiti yang penting.

Course Learning Outcome (CLO) merupakan komponen utama dalam sistem penilaian berasaskan hasil pembelajaran (*Outcome-Based Education* - OBE). CLO dirancang untuk memastikan pelajar mencapai tahap penguasaan tertentu selari dengan *Programme Learning Outcome* (PLO) dan *Learning Taxonomy* (Bloom, 1956). Dalam konteks pendidikan teknikal dan vokasional (TVET), CLO memberi penekanan kepada penguasaan teori, aplikasi praktikal, dan kemahiran insaniah. Menurut Zaharim et al. (2012), pencapaian CLO yang konsisten menjadi penunjuk keberkesanan kurikulum dan strategi PdP yang dilaksanakan.

Kajian lepas menunjukkan bahawa analisis sistematik terhadap pencapaian pelajar

memainkan peranan penting dalam menilai keberkesanan hasil pembelajaran kursus serta merancang penambahbaikan berterusan. Othman (2019) menegaskan bahawa pendekatan *Professional Learning Community* (PLC) mampu meningkatkan keupayaan pensyarah dalam menilai dan memperbaiki strategi pengajaran berdasarkan data pencapaian pelajar. Pendekatan ini selari dengan dapatan James, Talin dan Bikar (2022) yang menyatakan bahawa metrik seperti *Student Achievement* $\geq 50\%$ sering digunakan untuk mengenal pasti tahap minimum penguasaan pelajar dan menilai sejauh mana hasil pembelajaran kursus (CLO) telah dicapai. Sementara itu, Rahim dan Hassan (2020) menjelaskan bahawa analisis berasaskan bukti terhadap pencapaian pelajar membolehkan institusi mengenal pasti kelemahan dalam reka bentuk kurikulum serta merancang intervensi pengajaran secara lebih berfokus.

Kursus berkaitan kawalan kualiti menekankan kemahiran analisis data statistik, penggunaan alat kawalan kualiti, serta pembelajaran berasaskan kajian kes. CLO yang berasaskan kemahiran insaniah seperti kerja berkumpulan biasanya menunjukkan pencapaian tinggi kerana pelajar lebih mudah menguasai kemahiran tersebut melalui aktiviti praktikal. Sebaliknya, CLO yang melibatkan aplikasi teori statistik sering menjadi cabaran kerana memerlukan tahap penguasaan konsep matematik yang lebih tinggi. Pelbagai strategi PdP telah dicadangkan untuk meningkatkan pencapaian pelajar dalam CLO. Antaranya:

- i. Pembelajaran berasaskan masalah (*Problem-Based Learning, PBL*) – membantu pelajar mengaplikasikan pengetahuan teori dalam situasi praktikal.
- ii. Kajian kes - sesuai untuk CLO yang menekankan analisis kualiti produk dan perkhidmatan
- iii. Gamifikasi dan pembelajaran interaktif – meningkatkan minat pelajar dalam menguasai topik yang sukar seperti statistik dan alat kawalan kualiti.
- iv. Kolaborasi kumpulan – terbukti meningkatkan CLO berkaitan kemahiran komunikasi dan kerja berpasukan

Kajian literatur juga menekankan kepentingan *Continuous Quality Improvement (CQI)* dalam pendidikan teknikal di mana data pencapaian CLO perlu dianalisis secara berkala untuk mengenal pasti trend pencapaian pelajar. Penggunaan analisis CLO yang konsisten membolehkan pihak jabatan merancang intervensi lebih berfokus dan seterusnya meningkatkan mutu pembelajaran.

3.0 METODOLOGI

Kajian ini menggunakan pendekatan kuantitatif deskriptif dengan menganalisis data pencapaian pelajar bagi tiga sesi pembelajaran, iaitu Sesi 1:2023/2024, Sesi 1:2024/2025, dan Sesi 2:2024/2025. Analisis dijalankan bagi menilai tahap pencapaian pelajar terhadap tiga Course Learning Outcome (CLO) utama, iaitu CLO1, CLO2, dan CLO3. Dua indikator utama digunakan dalam analisis ini:

- i. *Group Attainment (GA)* – iaitu purata peratus pencapaian pelajar dalam setiap CLO yang mencerminkan tahap penguasaan keseluruhan kumpulan terhadap hasil pembelajaran tersebut.
- ii. *Student Achievement* $\geq 50\%$ (*SA*) – iaitu peratusan pelajar yang mencapai atau

melempi tahap minimum pencapaian 50%, sebagai penunjuk kadar pelajar yang menguasai hasil pembelajaran dengan memuaskan.

Analisis deskriptif dijalankan bagi mengenal pasti pola pencapaian dan trend perubahan bagi setiap CLO merentasi ketiga-tiga sesi pembelajaran. Hasil analisis ini menjadi asas kepada cadangan penambahbaikan strategi pengajaran dan pembelajaran (PdP) yang lebih berkesan.

4.0 KEPUTUSAN DAN ANALISA


CLO3 konsisten mencatat peratusan tertinggi bagi ketiga-tiga sesi (GA: 84%, SA: 100% pada Sesi 2:2024/2025). CLO1 pula kekal rendah walaupun terdapat sedikit peningkatan (GA serendah 39.1% dan SA 17.6% pada Sesi 1:2024/2025). CLO2 menunjukkan pola peningkatan signifikan dari segi GA dan SA selepas pengaplikasian kaedah kajian kes.

4.1 Pencapaian Pelajar Berdasarkan CLO

Analisis data pencapaian pelajar kursus DJF51082 – *Quality Control* telah dilakukan berdasarkan tiga sesi pembelajaran iaitu Sesi 1:2023/2024, Sesi 1:2024/2025, dan Sesi 2:2024/2025. Dapatan kajian ini dibahagikan kepada dua indikator utama iaitu Group Attainment dan Student Achievement $\geq 50\%$.

a. *Group Attainment* (Purata Pencapaian Pelajar)- rujuk Graf 4.1


- CLO1 menunjukkan pencapaian terendah secara konsisten. Peningkatan berlaku daripada 39.1% (Sesi 1:2024/2025) kepada 48% (Sesi 2:2024/2025), namun ia masih jauh daripada tahap yang diharapkan.
- CLO2 memperlihatkan peningkatan yang ketara, daripada 36% (Sesi 1:2023/2024) kepada 65% (Sesi 2:2024/2025). Ini menunjukkan bahawa pendekatan PdP berasaskan kajian kes semakin meningkatkan penguasaan pelajar.
- CLO3 sentiasa mencatat pencapaian tertinggi, dengan nilai tertinggi 84% pada Sesi 2:2024/2025. Hal ini membuktikan bahawa pelajar lebih mudah menguasai kemahiran kerja berkumpulan.



Graf 4.1: Perbandingan Group Attainment Mengikut CLO dan sesi

b. *Student Achievement* $\geq 50\%$ (Peratus Pelajar Lulus Minimum)- rujuk graf 4.2

- i. CLO1 kekal rendah walaupun terdapat sedikit peningkatan daripada 17.6% (Sesi 1:2024/2025) kepada 39.1% (Sesi 2:2024/2025). Dapatan ini menunjukkan ramai pelajar menghadapi kesukaran dalam memahami konsep statistik dan sistem pengurusan kualiti.
- ii. CLO2 mencatat lonjakan besar daripada 3.6% (Sesi 1:2023/2024) kepada 82.6% (Sesi 2:2024/2025). Ini selari dengan peningkatan *Group Attainment*, menandakan strategi pembelajaran berasaskan kajian kes adalah berkesan.
- iii. CLO3 mencapai tahap pencapaian tertinggi iaitu 100% pada dua sesi berturut-turut (Sesi 1:2024/2025 dan Sesi 2:2024/2025). Hal ini menunjukkan hampir semua pelajar berjaya menguasai kemahiran insaniah dalam kerja berkumpulan.



Graf 4.2: Perbandingan Student Achievement $\geq 50\%$ Mengikut CLO dan Sesi

Secara keseluruhan, dapatan menunjukkan trend peningkatan pencapaian pelajar dari Sesi 1:2023/2024 ke Sesi 2:2024/2025. CLO2 dan CLO3 menunjukkan perkembangan positif, manakala CLO1 masih menjadi cabaran utama.

Dapatan kajian ini selari dengan penemuan oleh Al-Hammadi dan Sait (2020) yang menegaskan kepentingan pemilihan kaedah pengajaran dan pembelajaran (PdP) yang sesuai bagi meningkatkan pencapaian terhadap *Course Learning Outcomes* (CLO) tertentu. Dalam konteks ini, keputusan menunjukkan bahawa CLO3 mencatatkan pencapaian tertinggi secara konsisten berbanding CLO1 dan CLO2. Hal ini menandakan bahawa strategi PdP yang digunakan bagi mencapai CLO3 telah dilaksanakan dengan berkesan dan berjaya membantu pelajar menguasai kemahiran serta pengetahuan yang disasarkan. CLO3 lazimnya berkaitan dengan kemahiran praktikal, tanggungjawab sosial, atau aplikasi pengetahuan dalam situasi sebenar. Oleh itu, pencapaian tinggi ini mencerminkan keberkesanan pendekatan PdP berbentuk amali, demonstrasi, dan pembelajaran berasaskan projek (*project-based learning*). Pendekatan ini bukan sahaja meningkatkan kefahaman pelajar

terhadap teori yang dipelajari, tetapi juga mengukuhkan keupayaan mereka mengaplikasikan ilmu dalam tugas sebenar di bengkel, makmal atau projek industri.

Sebaliknya, CLO1 menunjukkan pencapaian yang lebih rendah berbanding CLO2 dan CLO3, menandakan keperluan untuk menambah baik pendekatan PdP dalam menyampaikan kandungan teori dan konsep asas. Dapatan ini mengukuhkan pandangan Al-Hammadi dan Sait (2020) bahawa ketidakpadanan antara kaedah PdP dengan jenis hasil pembelajaran boleh menjejaskan tahap penguasaan pelajar. CLO1 yang lazimnya berasaskan teori dan pengetahuan konseptual mungkin memerlukan kaedah pengajaran yang lebih interaktif dan berasaskan pengalaman bagi menarik minat pelajar. Antara pendekatan yang dicadangkan termasuk penggunaan *flipped classroom*, *problem-based learning* (PBL), simulasi digital, serta bahan bantu mengajar visual untuk menggalakkan pembelajaran aktif. Pendekatan tersebut berpotensi meningkatkan kefahaman konsep serta membantu pelajar mengaitkan teori dengan situasi sebenar dalam bidang kejuruteraan atau pembuatan.

Bagi CLO2, dapatan menunjukkan peningkatan yang seiring dengan hasil kajian seperti *Improving Students' Critical Thinking Skills Through Case-Based Learning Oriented Textbook* daripada Alfiandra (2022) melaporkan bahawa penggunaan buku teks berasaskan kes dapat meningkatkan kemahiran pelajar dalam berfikir kritis, menganalisis situasi sebenar, dan menerapkan pengetahuan dalam konteks praktikal. Dalam konteks kajian ini, pelajar yang terlibat dalam aktiviti berasaskan kes nyata menunjukkan tahap pemahaman dan penglibatan yang lebih tinggi. Pendekatan kajian kes membantu pelajar memahami kepentingan membuat keputusan berasaskan data, mengenal pasti punca masalah, serta mengaitkan teori dengan amalan sebenar. Ini membuktikan keberkesanan strategi PdP yang berpusatkan pelajar (*student-centered learning*), di mana pelajar menjadi agen aktif dalam proses pembelajaran dan bukan sekadar penerima maklumat.

Secara keseluruhannya, analisis terhadap ketiga-tiga CLO menunjukkan bahawa keberkesanan PdP amat bergantung pada kesesuaian pendekatan pengajaran dengan jenis hasil pembelajaran yang diukur. CLO3 yang tinggi menggambarkan keberkesanan pendekatan amali dan berasaskan projek; CLO2 menunjukkan kesan positif penggunaan *case study* yang menggalakkan pemikiran analitik; manakala CLO1 menonjolkan keperluan pengukuhan dalam aspek teori dan konsep asas. Dapatan ini sejajar dengan prinsip *Continuous Quality Improvement* (CQI), yang menekankan kepentingan analisis sistematik terhadap data pencapaian CLO sebagai asas kepada tindakan penambahbaikan berterusan.

Dalam konteks politeknik, hasil analisis CLO ini boleh digunakan untuk menyokong pelaksanaan CQI secara lebih terarah. Data pencapaian pelajar membantu pensyarah dan pihak pengurusan program mengenal pasti kekuatan dan kelemahan dalam PdP, seterusnya merancang intervensi yang relevan seperti penyemakan silibus, penambahbaikan kaedah pengajaran, dan peningkatan reka bentuk penilaian. Sebagai contoh, bagi CLO1, kursus boleh diperbaiki melalui integrasi pendekatan berasaskan teknologi dan simulasi industri; bagi CLO2, aktiviti kolaboratif dan *problem-solving tasks* boleh diperkukuh; manakala bagi CLO3, pembelajaran amali dan projek industri boleh diperluas untuk mengekalkan momentum pencapaian tinggi.

Oleh itu, kajian ini menegaskan bahawa pelaksanaan CQI di politeknik tidak seharusnya dilihat sebagai proses pentadbiran semata-mata, tetapi sebagai satu budaya

reflektif dan berterusan dalam kalangan pensyarah untuk memperbaiki kualiti PdP berdasarkan bukti pencapaian pelajar. Analisis CLO yang dijalankan secara berkala dapat membantu membentuk kitaran penambahbaikan berterusan (*CQI loop*) yang menyokong pencapaian *Programme Learning Outcomes* (PLO), meningkatkan keberkesanan kurikulum, dan memastikan graduan politeknik mencapai tahap kompetensi yang sepadan dengan keperluan industri serta aspirasi *Sustainable Development Goal 4 (Kualiti Pendidikan)*.

Berdasarkan analisis dan sokongan literatur, beberapa cadangan dikemukakan:

- i. Penambahbaikan CLO1 (Statistik dan Sistem Kualiti):
 - Menggunakan pendekatan PdP interaktif seperti gamifikasi, simulasi data, dan perisian statistik untuk meningkatkan minat pelajar.
 - Menyediakan modul pengayaan matematik asas bagi membantu pelajar yang lemah dalam penguasaan statistik.
- ii. Pengukuhan CLO2 (Kajian Kes Alat Kualiti):
 - Memperluas penggunaan kajian kes industri sebenar supaya pelajar lebih dekat dengan aplikasi praktikal.
 - Menggalakkan pembelajaran kolaboratif melalui tugas kumpulan berasaskan projek.
- iii. Pemantapan CLO3 (Kerja Berkumpulan):
 - Mengekalkan strategi PdP sedia ada kerana pencapaian adalah konsisten tinggi.
 - Menambah elemen penilaian kepimpinan dan komunikasi dalam kerja kumpulan untuk meningkatkan keberkesanan kemahiran insaniah.
- iv. *Continuous Quality Improvement* (CQI):
 - Menjalankan analisis CLO pada setiap sesi pengajaran sebagai asas kepada penambahbaikan berterusan.
 - Mengadakan bengkel *reflection* bersama pensyarah kursus bagi membincangkan strategi PdP yang lebih berkesan.

5.0 KESIMPULAN

Kajian ini membuktikan bahawa analisis terhadap *Course Learning Outcome* (CLO) merupakan komponen penting dalam menilai keberkesanan pelaksanaan *Outcome-Based Education* (OBE) di peringkat politeknik. Berdasarkan data tiga sesi pembelajaran bagi kursus DJF51082 – *Quality Control*, dapat dirumuskan bahawa tahap pencapaian pelajar menunjukkan pola yang berbeza mengikut CLO yang dinilai. Dapatan utama menunjukkan bahawa CLO3 kekal sebagai hasil pembelajaran yang paling berjaya dicapai oleh pelajar dengan pencapaian konsisten tinggi dari segi *Group Attainment* (GA) dan *Student Achievement* $\geq 50\%$ (SA). Hal ini membuktikan keberkesanan pendekatan PdP berbentuk kajian kes dan kolaboratif yang digunakan oleh pensyarah dalam mencapai hasil pembelajaran berkaitan kemahiran insaniah serta kerja berpasukan.

Sebaliknya, CLO1 didapati masih berada pada tahap yang rendah walaupun terdapat peningkatan kecil antara sesi. Ini menunjukkan bahawa pelajar menghadapi cabaran dalam menguasai elemen teori dan aplikasi konsep statistik dalam konteks kawalan kualiti. Oleh itu, keperluan untuk menambah baik strategi PdP bagi CLO ini amat penting, khususnya

melalui kaedah pengajaran yang lebih interaktif, berasaskan masalah (*problem-based learning*), dan disokong dengan penggunaan teknologi atau simulasi data yang membantu pemahaman konsep abstrak.

CLO2 pula memperlihatkan peningkatan yang memberangsangkan selepas pelaksanaan pendekatan pembelajaran berasaskan kajian kes. Hasil ini membuktikan bahawa strategi PdP yang memberi peluang kepada pelajar menganalisis situasi sebenar dan membuat keputusan berasaskan data mampu meningkatkan kemahiran berfikir aras tinggi serta keupayaan pelajar menghubungkan teori dengan amalan industri. Pendekatan ini juga selaras dengan prinsip *student-centered learning* yang menjadi tunjang kepada pelaksanaan OBE. Secara keseluruhan, analisis merentasi tiga sesi ini menunjukkan bahawa pelaksanaan PdP dalam kursus *Quality Control* berada di landasan yang baik, namun masih memerlukan usaha penambahbaikan berterusan untuk memastikan keseimbangan pencapaian antara ketiga-tiga CLO. Dapatan ini menyokong kepentingan pelaksanaan *Continuous Quality Improvement* (CQI) sebagai satu mekanisme refleksi berasaskan data yang membantu pensyarah menilai keberkesanan PdP, memperbaiki kaedah pengajaran, dan menyemak semula reka bentuk penilaian bagi mencapai keselarasan antara CLO dan *Programme Learning Outcome* (PLO). Selain itu, hasil kajian ini juga memberikan implikasi yang penting kepada pihak jabatan dan institusi. Data pencapaian CLO boleh dijadikan asas dalam merancang latihan peningkatan profesionalisme pensyarah, menyemak semula reka bentuk silibus, serta memperkukuh amalan perkongsian *best practices* antara pensyarah. Dalam jangka panjang, amalan ini akan membantu membentuk budaya penambahbaikan berterusan yang bukan sahaja meningkatkan mutu PdP, tetapi juga menyumbang kepada penghasilangraduan yang lebih kompeten, berdaya saing, dan selaras dengan keperluan industri semasa. Kesimpulannya, kajian ini menegaskan bahawa keberkesanan pelaksanaan OBE amat bergantung kepada sejauh mana data pencapaian CLO digunakan secara reflektif untuk memperkukuh proses PdP. Analisis CLO bukan sekadar memenuhi keperluan dokumentasi akreditasi, tetapi menjadi asas penting kepada pelaksanaan CQI yang sistematik. Justeru, kesinambungan analisis seperti ini perlu diteruskan pada setiap sesi pembelajaran bagi memastikan kursus yang ditawarkan sentiasa relevan, berimpak, dan mampu mencapai objektif pendidikan berkualiti sebagaimana digariskan dalam *Sustainable Development Goal 4 (Quality Education)*.

PENGHARGAAN

Segala puji dan syukur ke hadrat Allah SWT atas limpah rahmat dan izin-Nya, laporan *Analisis Pencapaian Course Learning Outcome (CLO)* bagi kursus DJF51082 – *Quality Control* ini dapat disiapkan dengan jayanya. Setinggi-tinggi penghargaan dan terima kasih diucapkan kepada pihak pengurusan Politeknik Port Dickson, khususnya Jabatan Kejuruteraan Mekanikal, atas sokongan, kerjasama dan kemudahan yang disediakan sepanjang pelaksanaan kajian ini. Ucapan terima kasih yang tulus juga ditujukan kepada penyelaras kursus DJF51082, serta semua pensyarah yang terlibat dalam pengajaran dan penilaian kursus ini, atas perkongsian data, pandangan, dan bimbingan yang amat bernilai dalam menjayakan proses analisis pencapaian pelajar. Tidak dilupakan kepada pelajar-pelajar program Diploma Kejuruteraan Pembuatan yang terlibat secara langsung dalam penyediaan dan penilaian tugas kursus, atas kerjasama dan komitmen yang diberikan. Akhir sekali, penghargaan yang ikhlas ditujukan kepada rakan-rakan pensyarah dan keluarga tersayang atas sokongan moral, dorongan serta bantuan yang tidak ternilai sepanjang tempoh penyediaan laporan ini.

RUJUKAN

- Alfiandra, A., Yusuf, S., & Barlian, I. (2022). Improving Students' Critical Thinking Skills Through Case Based Learning Oriented Textbook. *Jurnal Penelitian Dan Pengembangan Pendidikan*, 6(3), 440-449.
- Al-Hammadi, Y., & Sait, S. (2020). Effective learning outcomes assessment: The case of MIS department. *Journal of Education and Vocational Research*.
- Biggs, J., & Tang, C. (2011). *Teaching for quality learning at university* (4th ed.). McGraw- Hill Education.
- Harden, R. M. (2002). *Developments in outcome-based education*. Medical Teacher, 24(2), 117–120.
- James, J., Talin, R., & Bikar, S. S. (2022). *Defining Student's Achievement Based on Malaysia's Education Blueprint (2013–2025)*. *Malaysian Journal of Social Sciences and Humanities (MJSSH)*, 7(5), 1–12.
- Malaysian Qualifications Agency (MQA). (2019). *Guidelines on outcome-based education (OBE)*. Malaysian Qualifications Agency.
- Mohamad Shakri Mohmad Shariff, & Che Maznah Mat Isa. (2025). *Continual Quality Improvement (CQI) in aligning Course Learning Outcomes (CLO) and Programme Learning Outcomes (PLO) for Geotechnical Engineering course*. *Journal of Engineering and Technology Education*, 32(1), 55–67.
- Othman, S. (2019). *A Professional Learning Community Strategy Towards Students' Achievement*. *International Journal of Innovation, Creativity and Change (IJICC)*, 8(7), 115–128.
- Shariff, M. S. M., & Mat Isa, C. M. (2025). *Continual Quality Improvement Contributing to Programme Learning Outcomes in Geotechnical Engineering Course in Malaysia*. *International Journal of Modern Education (IJMOE)*, 7(24), 431-441.
- Sustainability*. (2022). Assessment approaches and learning outcomes in TVET: A systematic review. *MDPI*, 14(5), 1–17
- Zaharim, A., Omar, M. Z., Basri, H., & Muhamad, N. (2012). Engineering education: Using OBE approach. *Procedia - Social and Behavioral Sciences*, 60, 512–516.

Flash Review: A Performance-Based Interactive Revision Module For Computer Applications Course

Suziyana Ahmad Aman*, Hanem Mohd Halid

Politeknik Merlimau Melaka

*Suziyana@pmm.edu.my

Abstract This research focuses on the development and evaluation of a Performance-Based Interactive Revision Module for the Computer Applications course, tailored for commerce students at Politeknik Merlimau Melaka. The module incorporates the Flash Review method, which emphasizes rapid and focused content reinforcement based on individual student performance. By integrating interactive digital elements, the module aims to provide a personalized learning experience that adapts to each student's strengths and weaknesses. The study adopts a Design and Development Research (DDR) approach, involving needs analysis, module design, implementation, and evaluation phases. Student performance data is used to guide the structure and delivery of revision content, ensuring relevance and effectiveness. Preliminary results indicate that the module enhances student engagement, improves knowledge retention, and contributes to better academic achievement. The findings suggest that performance-based revision strategies, when supported by interactive technology, can significantly improve learning outcomes in technical education settings. This study offers practical insights for educators and instructional designers seeking to implement adaptive learning tools in their teaching practices.

Keywords: Interactive revision module, performance-based learning, Flash Review method, technical education, adaptive learning

1.0 INTRODUCTION

The fast-paced growth of educational technology has significantly transformed the way students interact with learning materials, particularly in technical and vocational education programs. In subjects such as Computer Applications, which are fundamental to commerce courses, students are expected to master both theoretical knowledge and practical skills. However, many students face difficulties in retaining and applying what they have learned due to ineffective study strategies and the lack of personalized academic support. Conventional revision methods often adopt a uniform approach that fails to accommodate the diverse learning styles and performance levels among students. This highlights the need for more intelligent, adaptive, and interactive revision tools that can enhance student engagement and improve academic outcomes.

One innovative approach that has gained attention is the Flash Review method, which focuses on short, targeted revision sessions aimed at reinforcing essential concepts efficiently. This method aligns with cognitive learning principles such as spaced repetition and active recall, which have been shown to significantly improve memory retention. When integrated into a performance-based learning system, Flash Review can be customized to address individual student needs by analysing their academic progress. The inclusion of interactive digital features—such as instant feedback, gamified elements, and dynamic

content, further enhances the learning experience, making it more engaging, responsive, and effective.

This research aims to design and evaluate a Performance-Based Interactive Revision Module for the Computer Applications subject, specifically targeting commerce students at Politeknik Merlimau Melaka. The module is developed using the Design and Development Research (DDR) methodology, which provides a structured framework for instructional material creation. By utilizing student performance data to guide the module's content and delivery, the study seeks to create a responsive learning tool that supports personalized revision. The research also investigates the module's impact on student engagement, knowledge retention, and academic performance, contributing to the broader discourse on the role of technology in enhancing technical education.

2. LITERATURE REVIEW

Students in technical fields like engineering often find it hard to remember theory and apply it in real-life situations. Traditional teaching methods sometimes fail to keep students interested or help them understand deeply. Interactive tools such as *Flash Review* make learning more engaging by allowing students to participate actively. These tools help students visualize abstract ideas, making it easier to understand and apply what they've learned. When combined with performance-based learning—which adjusts content based on each student's progress—students can focus on their weak areas and gradually improve their skills.

Besides that, using multimedia features like quizzes, and simulations has been shown to increase student motivation and improve academic results. Flash technology is especially useful for creating interactive and attractive learning materials. Research also shows that digital tools work well in Computer Applications course, where students learn better through visual and hands-on activities rather than just reading. All these findings support the idea of creating a performance-based interactive revision module that suits the needs of technical students and helps them better understand complex computer-related topics.

Performance-based learning has emerged as a transformative approach in technical education, aiming to align instructional strategies with student performance to enhance learning outcomes. Akinpelu et al. [1] demonstrated that students exposed to performance-based learning in computer application course showed improved conceptual understanding and motivation, particularly in hybrid learning environments. Similarly, Fan et al. [2] emphasized the value of interdisciplinary project-based learning in computer application, highlighting student-centred evaluation and reflective learning. These studies suggest that tailoring instruction to student performance can significantly improve engagement and academic achievement.

Interactive revision modules have proven effective in reinforcing learning, especially in computer subjects. Millard [3] developed web-based interactive modules for computer application, offering dynamic content and immediate feedback. Ferdosian et al. [4] evaluated the responsiveness of technology-enhanced learning platforms, stressing the importance of adaptive systems that adjust based on user interaction. These findings support the development of modules that respond to individual learning needs, a principle central to the Flash Review method. The Flash Review method, which focuses on short,

targeted revision sessions, aligns with cognitive learning theories such as spaced repetition and active recall. Abbas et al. [5] proposed an algorithm that leverages spaced repetition to improve long-term retention, while Yakubu et al. [6] introduced LLM-augmented review systems to enhance active recall in engineering education. These techniques have been shown to outperform traditional revision methods by promoting deeper understanding and memory consolidation.

The Atkinson–Shiffrin model [7] further supports the effectiveness of repeated exposure in transferring information from short-term to long-term memory. Design and Development Research (DDR) provides a structured methodology for creating and validating instructional tools. Richey and Klein [8] defined DDR as the systematic study of design, development, and evaluation processes to establish empirical foundations for instructional products. Tracey [9] applied DDR to validate instructional design models, emphasizing iterative refinement based on user feedback. These approaches are essential for developing modules like the one proposed in this study, ensuring both pedagogical integrity and technological relevance.

The objectives of this study is listed as the following:

- i. To develop a performance-based interactive revision module using the Flash Review approach for the Computer Applications course.
- ii. To evaluate the effectiveness of the interactive module in improving commerce students' understanding of theoretical and practical computer concepts.
- iii. To analyse students' motivation and engagement levels when using the interactive module compared to traditional revision methods.
- iv. To identify the relationship between the level of interactivity in the module and students' academic performance, particularly in mastering computer-related topics.

3.0 RESEARCH METHODOLOGY

This research uses the Design and Development Research approach, which works well for creating and testing educational modules systematically. We picked DDR because it lets researchers build teaching tools that are based on both theory and real-world practice, while also addressing what learners actually need. The method has three main stages: figuring out what's needed, designing and building the module, and then putting it to use and seeing how well it works.

During the first stage where we figure out what's needed, we collect information to see what problems commerce students have when they're reviewing for Computer Applications. This means doing surveys and talking with both students and teachers to get a handle on how they like to learn, their study habits, and what gives them trouble. We also look at how students performed on past tests to spot where they commonly struggle. What we learn from this stage becomes the basis for creating a module that actually makes sense and works well.

The second stage is all about creating the interactive review module using something called the Flash Review method. We design it to have quick, targeted review activities that match how each student is doing. It has interactive features like quizzes and ways to give students feedback so they stay engaged. We build the module step by step, getting input from

people who know about teaching design and subject experts to make sure it's educationally solid and easy to use.

In the final stage, we actually try out the module with a group of commerce students at Politeknik Merlimau Melaka. The students use it for a certain amount of time, and we collect information through tests before and after to see how much they've learned. We also get their thoughts through surveys and interviews to understand their experience, how engaged they felt, and whether they think it worked well. We analyse the number-based data using basic statistics, while we look at the feedback comments by themes to get a deeper understanding of how the module affected students.


This thorough evaluation helps us figure out whether the module actually helps with personalized learning and makes students perform better academically.

4.0 RESEARCH FINDINGS

This research looked at information from 80 students taking Computer Applications. Before using the system, students averaged 58.76 points (with a standard deviation of 9.57), but afterward their average jumped to 74.89 (standard deviation of 9.18). That's roughly a 16-point boost across the board. When researchers ran a paired t-test, they found this improvement was definitely real and meaningful ($t = 10.82$, $p < 0.001$), showing that the interactive module really made a difference in how well students performed. This significant improvement is further illustrated in Graph 1, which clearly shows the rise in students' average scores after using the interactive module.

The big jump in test scores shows that interactive tools like Flash Review actually work when it comes to helping students better understand theory and how to use it in real situations. Because the system could adapt based on how each student was doing, learners could spend more time on areas where they were struggling, which probably explains why everyone did better overall. This matches up with other studies that have found personalized learning approaches really help in technical courses. Adding multimedia features like interactive quizzes, and simulations was key to getting students more interested and motivated. Flash technology gave researchers a flexible way to build content that was both visually interesting and hands-on, making it easier for students to wrap their heads around tricky computer concepts. These results really show why it's important to move away from just reading text for review and embrace more interactive ways of learning.

What this study found suggests that interactive modules that adapt to student performance can really boost learning in technical fields. Going forward, researchers should look into whether these improvements stick around long-term and see if similar approaches would work in other commerce areas. It would also be worth checking out how adding game-like elements and AI-powered personalization might make these interactive learning tools even more effective.



Graph 1: Average Score vs Test

5.0 CONCLUSION

This research showed that when students used an interactive revision tool that adapted to their performance, they did much better in their Computer Applications class. Students scored about 16 points higher on their tests after using the system, and the data clearly proved this wasn't just a coincidence. This really proves that interactive learning tools can make a real difference in technical education. What made this work so well was that it broke away from the old-school approach of just reading through textbook materials. The system was smart enough to figure out where each student was struggling and help them work on those specific areas. This kind of personalized learning is exactly what educators are pushing for these days - teaching that actually fits each student's needs.

The fun stuff like animations, interactive quizzes, and simulations really made the difference in keeping students interested and involved. Using Flash technology gave teachers the freedom to create content that looked good and let students actually do things instead of just reading about them. This hands-on approach helped students really get their heads around tricky computer concepts. It just goes to show how powerful it can be when you bring technology into the classroom. Even though these results look great, there's still more work to be done. Researchers need to find out if students keep doing better months later, and whether this same approach would work for other technical subjects. Adding game-like features and AI that gets even better at personalizing the experience could make these tools even more powerful. These kinds of innovations could completely change how we teach technical subjects and make learning way more exciting and effective.

REFERENCES

- O. J. Akinpelu et al., "Performance-Based Learning: An Innovative Approach to Teaching Engineering Thermodynamics," ASEE, 2023.
- H. Fan et al., "Interdisciplinary Project-Based Learning: Experiences and Reflections from Teaching Electronic Engineering in China," *IEEE Trans. Educ.*, vol. 66, pp. 73–82, 2023.
- D. L. Millard, "Interactive Learning Modules for Electrical Engineering Education," ASEE, 2023.

- N. Ferdosian et al., "Technical Performance Evaluation of a Technology Enhanced Learning-Based Platform," NEWTON Project, 2018.
- A. M. Abbas et al., "Improving Learning Effectiveness by Leveraging Spaced Repetition," *Lecture Notes in Electrical Engineering*, vol. 1021, pp. 145–160, 2023.
- M. Yakubu et al., "Enhancing Active Recall and Spaced Repetition with LLM-Augmented Review Systems," ASEE PEER, 2025.
- R. C. Atkinson and R. M. Shiffrin, "Human Memory: A Proposed System and Its Control Processes," in *Psychology of Learning and Motivation*, vol. 2, pp. 89–195, 1968.
- R. C. Richey and J. D. Klein, *Design and Development Research: Methods, Strategies, and Issues*, Routledge, 2007.
- M. W. Tracey, "Design and Development Research: A Model Validation Case," *Educ. Tech. Res. Dev.*, vol. 57, pp. 553–571, 2009.

TVET Foundation Student's Perspective on Interactive Learning Using Mobile Application Technology at Politeknik Merlimau Melaka

Siti Farizah binti Yaakub, Zareena binti Rosli , Fairuzza binti Hairi

Department of Mathematics, Science and Computer
Politeknik Merlimau, Ministry of Higher Education,
77300 Merlimau, Malacca

sitifarizah@pmm.edu.my , zareenarosli@pmm.edu.my , fairuzza@pmm.edu.my

Abstract The integration of interactive technology, particularly through mobile applications technology, offers a significant opportunity to enhance teaching and learning outcomes. This study aims to investigate how the perspective of TVET Foundation students at Politeknik Merlimau Melaka perceive the necessity of mobile applications in future mathematics education. The study explores students' interest, acceptance, and perceived user-friendliness of mobile applications technology in the context of mathematics education. A questionnaire was employed to evaluate these aspects, revealing that students are interested and strongly endorse the integration of mobile applications as an advanced technological tool in teaching and learning. Furthermore, the findings indicate high satisfaction with the application's user-friendliness, with students expressing a strong desire to incorporate it into their studies. This ongoing research suggests that enhancing students' mathematics learning through mobile applications should consider the inclusion of emotional and empathetic support, as well as the promotion of collaborative learning, which can be particularly effective in offline settings. Additionally, the development of more refined instructional materials tailored for AI-driven mathematics education is recommended to maximize the benefits of this innovative approach.

Keywords: Mobile Learning, Interactive Technology, Mathematics Education, TVET Students, User Acceptance

1.0 INTRODUCTION

In recent years, education has experienced huge changes in its structure, especially with fast-growing technological development. This development includes a wide number of modern-day technologies which is mobile application technology, where opens new horizons for improvement in the teaching and learning processes. It is particularly relevant to TVET, since at this level, the integration of interactive learning through mobile applications should be carefully combined with practical skills and theoretical knowledge in preparing the students for eventual entry into the field.

As one of the prominent polytechnics in the Malaysian TVET setup, Politeknik Merlimau Melaka is conscious of the need to adopt new pedagogies that will be more appropriate for learners of today. The TVET Foundation students, most of whom have diverse learning styles and technological acquaintance, present a very unique demography in relation to research on the effectiveness of mobile apps in educational settings. Indeed,

this group stands a great chance to gain from tools that facilitate engagement and promote collaborative learning, especially in core subjects such as mathematics.

This research tries to seek the views of TVET Foundation students on the necessity and effectiveness of mobile applications in mathematics learning. The study investigates students' interest, acceptance, and perceived user-friendliness; through this, it aims to find ways of integrating mobile applications into the educational framework at Politeknik Merlimau Melaka. It helps understand the attitude of students toward mobile technology for gaining insight not only into their learning preferences but also for informing instructional strategies that are responsive to their needs.

This study also tries to highlight two important aspects: the need for emotional and empathetic support in a mobile learning environment and the advantages of collaborative learning. This is an area in need of constant research and refinement so that technology not only supports better academic performance but enables a holistic learning environment. It is through this study that we would like to make an important contribution about effective use regarding the integration of mobile application technology within mathematics education, providing the ground for opening further opportunities toward more engaging and effective learning processes.

2.0 LITERATURE REVIEW

Mobile learning (M-Learning) has revolutionized the paradigms of learning and has presented ways of acquiring knowledge and skills that are flexible and accessible. O'Malley et al. (2020) aver that M-learning offers an opportunity for accessing learning anywhere, anytime, and gives options for creating personalized learning to meet learners' individual needs. This will be quite applicable within the TVET framework, where learners balance practical and theoretical training. Several studies have documented the ability of mobile devices to provide an efficient tool for enhancing skills and retaining knowledge (Almuraqab et al., 2022).

The whole concept of interactive learning is based on the active engagement of students in the learning process, which enhances academic performance and retention rates. In this regard, Kuo et al. (2020), notes that various interactive technologies, including mobile applications, significantly enhance the engagement of students by offering collaboration tasks, interaction simulations, and effective feedback in a timely manner. This also aligns with constructivist learning theories, which state that knowledge is best acquired through active participation. As suggested by Gonzalez et al., increased interactivity yields deeper cognitive processing, improving the overall learning experience.

The perception of the students regarding the mobile applications hugely affects their acceptance and utilization in the educational context. According to The Technology Acceptance Model (TAM), perceived ease of use and perceived usefulness continue to be two of the most critical drivers in technology adoption. A study by Alsharif et al. (2022) has made it known that due to simplicity and practicality, TVET students prefer mobile applications. This further consolidates the fact that at least a minimum level of friendliness must be assured by any educational institution in its technological offerings. Successful implementation therefore calls for an understanding of the students' perspectives. The use of technology in math education has shown quite a good number of benefits. In fact,

it is supported by a comprehensive meta-analysis conducted by Li and Ma, 2020, stating that effective technology integration significantly enhances students' mathematical understanding and performance. Moreover, mobile applications developed for mathematics education have been reported to further improve engagement in learning and enhance problem-solving skills (Bakar et al., 2021). These tools can offer interactive exercises with immediate feedback, which is very important in the process of acquiring complex mathematical notions, thus making learning more dynamic and responsive to the needs of students.

Mobile applications enhance collaborative learning processes considerably. According to research, such technologies enhance peer interactions and teamwork, which are highly important for effective learning in vocational contexts (Cai et al., 2022). For example, group chats, shared workspaces, and collaborative projects offer opportunities for learners to learn from one another, cultivate a sense of community, and develop mutual responsibility. It is at this point that collaborative learning nurtures both technical and interpersonal competence, which is gradually transferred to jobs, especially in TVET contexts where practical skills are what matter the most.

The affective dimension has lately been in the limelight with regard to helping students succeed with learning. According to D'Mello and Graesser, 2021, emotional support can surely promote motivation and increase engagement in difficult subjects such as mathematics. Applications designed to features related to emotional and empathetic support create a caring learning environment on mobile phones. Examples could include motivational messages, emotional feedback, and mechanisms for peer support, which can be helpful in enhancing emotional needs and will improve the learning process. Literature indicates that the integration of mobile applications in mathematics education for students in TVET is likely to increase their engagement and improve learning outcomes, besides increasing their acceptance of technologies. As this research tries to delve into the perspective of the students, it also tries to contribute to the emergent pool of studies targeting strategies for effectively implementing mobile learning in vocational education.

3.0 METHODOLOGY

This study employs a quantitative research design, utilizing a survey method to gather data on TVET foundation students' perspectives on interactive learning through mobile application technology at Politeknik Merlimau Melaka. The survey method allows for the collection of numerical data from a large sample of students, providing a comprehensive understanding of their views. Descriptive analysis will be conducted to interpret the data, offering insights into the students' experiences and attitudes towards the use of mobile applications in their learning process. This approach aims to identify key trends and patterns, contributing to the broader understanding of the effectiveness and impact of mobile application technology in interactive learning environments.

The participants of this study are TVET Foundation students at Politeknik Merlimau Melaka. A sample size of 38 students was selected to ensure a representative and comprehensive understanding of the students' perspectives. The selection process involved random sampling to minimize bias and ensure the diversity of the sample. This approach allows for the collection of varied insights and experiences regarding the use of mobile application technology in interactive learning.

The primary instrument used in this study is a comprehensive questionnaire designed to capture TVET Foundation students' perspectives on interactive learning using mobile application technology at Politeknik Merlimau Melaka. The questionnaire includes sections that assess:

- (a) Interest in Mobile Application Technology
Questions in this section gauge the students' enthusiasm and curiosity about using mobile applications as part of their learning process.
- (b) Acceptance and Willingness to Integrate the Technology
This part of the questionnaire explores the students' readiness and openness to incorporating mobile application technology into their educational activities.
- (c) Perceived User-Friendliness
Questions here evaluate how user-friendly the students find the mobile applications, including ease of use, navigation, and overall experience.

The data collected through this questionnaire will provide valuable insights into the students' attitudes and experiences, helping to understand the potential impact of mobile application technology on their learning.

The data collection process involved distributing questionnaires to TVET Foundation students at Politeknik Merlimau Melaka. The questionnaires were handed out during scheduled class sessions to ensure a high response rate and to facilitate the collection of a diverse range of perspectives. The timeline for data collection spanned over a period of two weeks allowing ample time for students to complete and return the questionnaires. This structured approach ensured that the data gathered was comprehensive and reflective of the students' views on interactive learning using mobile application technology.

To mitigate potential non-response bias in this study, we implemented two key strategies:

- (a) Follow-Up Reminders
We sent follow-up reminders to students who had not yet responded to the initial questionnaire distribution. These reminders were sent via email and announced during class sessions to ensure that all students were aware of the importance of their participation. This approach aimed to increase the response rate by encouraging students to complete the questionnaire.
- (b) Incentives
To further motivate students to participate, we offered small incentives. Students who completed the questionnaire were given a token as a reward for their participation. This strategy was designed to boost participation rates and ensure a more representative sample. By employing these strategies, we aimed to reduce non-response bias and enhance the reliability of the data collected from TVET Foundation students at Politeknik Merlimau Melaka.

The data collected from the questionnaires were analyzed using statistical tools, specifically SPSS (Statistical Package for the Social Sciences), to perform descriptive statistics. This analysis provided a detailed understanding of the students' perspectives on interactive

learning using mobile application technology. The analysis focused on three main areas:

- (a) **Interest in Mobile Application Technology**
Descriptive statistics were used to summarize the level of interest among students, including measures of central tendency (mean, median) and variability (standard deviation).
- (b) **Acceptance and Willingness to Integrate the Technology**
The data were analyzed to determine the extent to which students are willing to adopt and integrate mobile application technology into their learning processes. This included frequency distributions and percentage analyses.
- (c) **Perceived User-Friendliness**
Scores related to the user-friendliness of the mobile applications were analyzed to assess how easy and intuitive the students found the technology. This involved calculating mean scores and identifying any significant trends or patterns.

4.0 RESULT AND ANALYSIS

Section A: Interest in Mobile Application Technology

Question	Mean	Standard Deviation
Interest in using apps for learning	4.15	0.45
Apps make learning engaging	4.01	0.48
Likely to explore apps outside class	4.03	0.54
Motivated to learn with apps	4.35	0.44
Preference for apps over textbooks	3.77	0.53

The results of Section A: Interest in Mobile Application Technology indicate a very high level of interest in using apps for learning, with a mean score of 4.15 and a low standard deviation indicating consistent affirmation across the student body. Indicating a proactive attitude to learning, students not only assess apps as very engaging (Mean: 4.01) but also express inspiration to use them outside of the classroom (Mean: 4.03). Additionally, students' intrinsic value for app-based learning is highlighted by the comparably high mean motivation score of 4.35; some even somewhat prefer these contemporary tools over classic textbooks (mean: 3.77).

Section B: Acceptance and Willingness to Integrate the Technology

Question	1 (%)	2 (%)	3 (%)	4 (%)	5 (%)
Open to using apps regularly	0.00	12.00	20.00	32.00	36.00
Apps should be essential in education	5.00	3.00	20.00	34.00	38.00
Recommend apps to others	9.00	3.00	12.00	31.00	45.00
Comfort replacing traditional methods	12.00	6.00	21.00	27.00	34.00
Improvement in learning with apps	2.00	8.00	20.00	28.00	42.00

Results for section B which explores the acceptance and willingness to integrate technology demonstrate a gradual acceptance among students, with more than one-third (36%) strongly open to regular app usage and a comparable number (38%) seeing apps as

fundamental components of modern education. This is supported by a sizable plurality (45%) who would recommend educational applications to colleagues, indicating broad agreement on their usefulness. The willingness to replace traditional learning methods with app-based solutions (34% very comfortable) and a strong belief in the potential of apps to improve learning outcomes (42% strongly agree) highlight the critical role students envision mobile technologies playing in education.

Section C: Perceived User-Friendliness

Question	Mean	Standard Deviation
Ease of navigation	4.10	0.48
Quick understanding of app features	4.10	0.47
Appeal of app design	3.94	0.56
Organization of apps for ease of use	4.03	0.50
Frequency of technical difficulties	2.00	0.48

The results show that apps are not only accessible but also made with an intuitive learning experience in mind (Section C: Perceived User-Friendliness). Students appear to find these tools not just useful but also well suited to their educational needs, as indicated by mean scores above 4.0 for ease of use and speedy comprehension of app features. The design and organisation of the apps have received positive feedback (Mean: 3.94) and 4.03), and the low frequency of technical issues (Mean: 2.00) guarantees that these experiences are largely uninterrupted.

5.0 DISCUSSION

The analysis of study among students reveals a considerable interest and favourable reception of mobile technology as a feasible tool for improving mathematical learning. The application strong scores for simplicity of use, engagement, and motivational impact are particularly promising, demonstrating that students not only value the functionality of application but also believe it efficiently meets their learning goals. Students indicated that mobile application made learning mathematics more entertaining and expressed a strong desire to utilize the program. This engagement is particularly crucial in disciplines like mathematics, where student motivation can fade owing to perceived difficulty or abstract content.

The mobile application ability to engage learners is most likely due to interactive aspects that provide rapid feedback and gamification of learning tasks, both of which are uncommon in traditional learning environments. Students appear to understand the value of mobile application beyond their own use, seeing it as a helpful resource for the larger student body, based on their desire to propose the mobile application to others and confidence in its crucial role in education. This point of view strengthens the app's usefulness as an addition to conventional teaching strategies by giving users a different approach to investigating mathematical ideas. Mobile application is user-friendly, which is essential for any instructional tool, based on the excellent reviews for the mobile application navigation and organizational structure. Because it lowers the learning curve and frees students up to concentrate more on the material rather than figuring out how to use the mobile application, ease of use can have a big impact on the acceptance and frequent usage of technology in the classroom.

Several suggestions can be made to improve the mobile application efficacy and increase its attractiveness to students, given its favourable reception. First and foremost, it is crucial to keep improving and developing the mobile application interactive features. Increasing the number of interactive tests, problem-solving activities, and real-time feedback would help students grasp mathematical ideas and increase their level of engagement. Furthermore, broadening the mobile application scope would increase its comprehensiveness and allow users of all skill levels to benefit from its material. Features that allow for customisation should be added to the learning process so that students can focus on several mathematical concepts or change the level of difficulty according to their level of competency. While the software is largely user-friendly, increasing its visual appeal and design would increase its attractiveness and engagement, particularly among younger pupils. Another major tip is to develop strong testing methods and feedback loops to quickly detect and resolve any technological difficulties. Gathering constant feedback from users will assist in keeping the app relevant to student needs. Finally, working collaboratively with educators to integrate mobile application into classroom education would increase its effectiveness. This might involve teaching teachers how to incorporate the app into lesson plans or utilising it as a supplement to teach important mathematical topics. By implementing these enhancements, mobile application can strengthen its position as a viable instructional tool, increasing student engagement and enhancing mathematical learning results.

REFERENCES

- Almuraqab, N., Alharbi, S. and Ibrahim, A., 2022. Exploring the Impact of Mobile Learning on Technical Education: A Review. *Journal of Educational Technology Systems*, 50 (2), pp. 220-233.
- Alsharif, M. H., Alzahrani, M. G. and Ezzat, A., 2022. Factors Influencing the Acceptance of Mobile Learning among Technical Students: A Technology Acceptance Model Perspective. *Education and Information Technologies*, 27 (1), pp. 143-160.
- Bakar, N. A., Asari, B. and Ismail, A., 2021. The Impact of Mobile Learning on Students' Mathematics Performance: A Case Study in Malaysia. *International Journal of Instruction*, 14 (3), pp. 99-114.
- Cai, Y., Liu, C. and Li, Z., 2022. Enhancing Collaborative Learning in Higher Education: The Role of Mobile Applications. *Journal of Computing in Higher Education*, 34 (2), pp. 317-335.
- D'Mello, S. K. and Graesser, A. C., 2021. The Role of Emotion in Learning: Affective Learning. *Educational Psychologist*, 56 (1), pp. 25-39.
- Gonzalez, C. R., Jansen, B. J. and Milward, J., 2021. Constructivist Learning Theories in Practice: A Review of Recent Literature. *Journal of Educational Psychology*, 113 (5), pp. 879-893.
- Kuo, Y.-C., Rojas-Lizana, A. and Chang, C.Y., 2020. Exploring the Role of Mobile Learning in Education: A Review of Recent Literature. *Computers & Education*, 157, 103964.

- Li, Y. and Ma, X., 2020. A Meta-Analysis of the Impact of Technology on Mathematics Education. *Educational Technology Research and Development*, 68 (1), pp. 1-25.
- O'Malley, C., Vavoula, G. and Sharples, M., 2020. Guidelines for Learning in a Mobile Age. *European Journal of Education*, 55 (1), pp. 29-43.
- Venkatesh, V., Thong, J. Y. L., and Xu, X., 2021. Unified Theory of Acceptance and Use of Technology: A Synthesis and the Road Ahead. *Journal of the Association for Information Systems*, 17 (5), pp. 328-376.

eISSN 2976-260X



9 7 7 2 9 7 6 2 6 0 0 0 9